



Yreka Shasta River Bridge Rehab

CALIFORNIA DEPARTMENT OF TRANSPORTATION

SISKIYOU - INTERSTATE 5 BRIDGE REHABILITATION

FACT SHEET- JANUARY 2010

The Project

The Yreka Shasta River Bridge Rehabilitation Project proposes to replace the bridge decks and rails on bridge numbers 02-0148 L/R, which are located on Interstate 5, just north of Yreka. Additional work includes seismic retrofit of both structures and replacement of the approach slabs. Construction staging will require temporary detours using median crossovers, construction of construction access roads and a temporary river crossing. Construction is anticipated to begin during the 2012 construction season and complete in 2014.

The Need

I-5 is the north/south transportation backbone for the State of California, providing service for vital goods movement as well as regional and interregional travelers. The bridge decks have reached the end of their serviceable life and will be replaced.

Jobs/Benefits

This project will provide an estimated 70 jobs related to the construction trades and materials industry.

Partnerships

This project has been developed through a partnership between the California Department of Transportation (Caltrans) and the Federal Highway Administration (FHWA).

Project Status

The project preliminary engineering and environmental studies are scheduled to be complete in April 2010. Final engineering, contract preparation, and bid opening are scheduled to be complete in July 2011

Project Costs

SHOPP estimated \$10.1 million

Project Schedule

Start Construction: June 2012

Project Completion: July 2013

Contacts

Carl Anderson, Project Manager 530-225-2154

Media Inquiries 530-225-3260

