STATE OF CALIFORNIA
BUSINESS, TRANSPORTATION AND HOUSING AGENCY
DEPARTMENT OF TRANSPORTATION

2009
CONTRACT COST DATA

A SUMMARY OF COST BY ITEMS FOR HIGHWAY CONSTRUCTION PROJECTS

Caltrans

2009
CONTRACT COST DATA

The *Contract Cost Data* book is published annually by the Department of Transportation, Division of Engineering Services - Office Engineer, Office of Contract Awards and Services. This book includes standard contract items for major highway contracts for which bids were *awarded in 2009.* Some of the units of measure for these items were in U.S. Customary Units (English) and were converted to International System of Units (SI) for this publication. The conversion factors used for this purpose are listed in *Appendix A*. For those who wish to convert back to English units, the appropriate conversion factors are listed in *Appendix B*.

Advertised item quantities have been used as source information. Item quantities may vary from the final quantities incorporated into the completed contract. Prices shown in this tabulation are the mechanically weighted average of the awarded bidders' prices and are affected by location, time, quantity in the job and size of the item (relative to the size of the job). In this book, a six-digit item code has been assigned to each standard contract item and the items are listed numerically.

For assistance, contact Division of Engineering Services - Office Engineer, Office of Contract Awards and Services by e-mail at this address: DES-OE_Contract_Service @dot.ca.gov. The Web site address to download this book is http://www.dot.ca.gov/hq/esc/oe/awards.

TABLE OF CONTENTS

INDEX OF ITEM DESCRIPTION ……..A1

CONTRACT ITEM COST DATA……1

APPENDIX A……363
(CONVERSION FACTORS FROM ENGLISH UNITS TO SI UNITS)

APPENDIX B……363
(CONVERSION FACTORS FROM SI UNITS TO ENGLISH UNITS)

Index of Item Description

ITEM DESCRIPTION	ITEM CODE
0 - 9	
0.9 M CHAIN LINK GATE (TYPE CL-1.8)	802584
1 1/2" BACKFLOW PREVENTER ASSEMBLY	208425
1 1/2" ELECTRIC REMOTE CONTROL VALVE	206604
1 1/2" GATE VALVE	208574
1 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208265
1 1/2" WYE STRAINER	208628
1 1/4" BACKFLOW PREVENTER ASSEMBLY	208424
1 1/4" ELECTRIC REMOTE CONTROL VALVE	206603
1 1/4" GALVANIZED STEEL PIPE (SUPPLY LINE)	208004
1 1/4" GATE VALVE	208573
1 1/4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208264
1 1/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208596
1" ELECTRIC REMOTE CONTROL VALVE	206602
1" GATE VALVE	208572
1" MANUAL CONTROL VALVE	208618
1" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208263
1" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208595
1" WYE STRAINER	208626
1.2 M CAST-IN-DRILLED-HOLE CONCRETE PILING	490661
1.2 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	490677
1.2 M CHAIN LINK GATE (TYPE CL-1.8)	802585
1.2 M CHAIN LINK GATE (TYPE CL-1.8, VINYL-CLAD)	802586
1.2 M CHAIN LINK GATE (TYPE CL-2.4)	802943
1.5 M CAST-IN-DRILLED-HOLE CONCRETE PILING	490663
1.5 M CHAIN LINK GATE (TYPE CL-1.8)	802589
1.8 M CAST-IN-DRILLED-HOLE CONCRETE PILING	490665
1.8 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	490679
1.8 M CHAIN LINK GATE (TYPE CL-1.8)	802590

ITEM DESCRIPTION	ITEM CODE
0 - 9	
1.8 M METAL GATE	801365
1/2" PLASTIC PIPE (IRRIGATION LINE)	208211
10' CHAIN LINK GATE (TYPE CL-6)	802560
10" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208739
10" WELDED STEEL PIPE CONDUIT (.250" THICK)	208809
100 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208256
100 MM THERMOPLASTIC TRAFFIC STRIPE	840561
100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 1.83 M - 0.30 M)	840567
100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	840570
100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M)	840568
100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 5.18 M - 2.14 M)	840571
100 MM TWO-COMPONENT PAINT TRAFFIC STRIPE	840575
100 MM WELDED STEEL PIPE CONDUIT (6.02 MM THICK)	208796
1050 MM ALTERNATIVE FLARED END SECTION	705340
1050 MM ALTERNATIVE PIPE CULVERT	620930
1050 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK)	690290
1050 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	664037
1050 MM REINFORCED CONCRETE PIPE	650081
1050 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650131
1050 MM STEEL FLARED END SECTION	705049
1050 MM TEMPORARY CULVERT	073032
1050 MM X 725 MM ALTERNATIVE FLARED END PIPE ARCH SECTION	705349
1050 MM X 725 MM ALTERNATIVE PIPE ARCH CULVERT	625392
108" CAST-IN-DRILLED-HOLE CONCRETE PILING	490620
108" PERMANENT STEEL CASING	490595
12' CHAIN LINK GATE (TYPE CL-4)	802180

ITEM DESCRIPTION	ITEM CODE
0 - 9	
12' CHAIN LINK GATE (TYPE CL-6)	802580
12 SINGLEMODE FIBER OPTIC CABLE	867014
12 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	206751
12" ALTERNATIVE FLARED END SECTION	705307
12" ALTERNATIVE PIPE CULVERT	620060
12" ANCHOR ASSEMBLY	692305
12" CONCRETE FLARED END SECTION	705201
12" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208740
12" CORRUGATED STEEL PIPE	665010
12" CORRUGATED STEEL PIPE (.064" THICK)	665011
12" CORRUGATED STEEL PIPE (.079" THICK)	665012
12" CORRUGATED STEEL PIPE DOWNDRAIN	690110
12" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690112
12" DOWNDRAIN SLIP JOINT	692205
12" ENTRANCE TAPER	692005
12" PERFORATED STEEL PIPE UNDERDRAIN (.079" THICK)	680412
12" PLASTIC PIPE	641101
12" REINFORCED CONCRETE PIPE	650010
12" STEEL FLARED END SECTION	705007
12" TEMPORARY CULVERT	073004
12" WELDED STEEL PIPE (.250" THICK)	703533
12" WELDED STEEL PIPE CONDUIT (.250" THICK)	208812
1200 MM ALTERNATIVE PIPE CULVERT	620933
1200 MM CORRUGATED STEEL PIPE (2.77 MM THICK)	664044
1200 MM CORRUGATED STEEL PIPE RISER (2.01 MM THICK)	703287
1200 MM PRECAST CONCRETE PIPE MANHOLE	707247
1200 MM REINFORCED CONCRETE PIPE	650084
1200 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650132
1200 MM STEEL FLARED END SECTION	705050
1350 MM ALTERNATIVE FLARED END SECTION	705342

ITEM DESCRIPTION	ITEM CODE
0 - 9	
1350 MM ALTERNATIVE PIPE CULVERT	620938
1350 MM REINFORCED CONCRETE PIPE	650086
1372 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561013
14' CHAIN LINK GATE (TYPE CL-6)	802601
15" ALTERNATIVE PIPE CULVERT	620080
15" CORRUGATED STEEL PIPE (.109" THICK)	665015
15" PLASTIC PIPE	641104
15" REINFORCED CONCRETE PIPE	650012
15" STEEL FLARED END SECTION	705009
150 MM ALTERNATIVE PIPE CULVERT	620901
150 MM CORRUGATED STEEL PIPE CONDUIT (1.63 MM THICK)	208741
150 MM NON-PERFORATED PLASTIC PIPE UNDERDRAIN	680932
150 MM PERFORATED PLASTIC PIPE UNDERDRAIN	680931
150 MM PLASTIC PIPE	681066
150 MM SEWER PIPE	717073
150 MM THERMOPLASTIC TRAFFIC STRIPE	840562
150 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	208797
1500 MM ALTERNATIVE PIPE CULVERT	620940
1500 MM CORRUGATED STEEL PIPE (2.77 MM THICK)	664052
1500 MM PRECAST CONCRETE PIPE MANHOLE	707249
1500 MM REINFORCED CONCRETE PIPE	650089
1524 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561015
16' CHAIN LINK GATE (TYPE CL-6)	802620
16' WIRE MESH GATE	801230
16" CAST-IN-DRILLED-HOLE CONCRETE PILING	490601
16" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	498016
1650 MM REINFORCED CONCRETE PIPE	650091
18" ALTERNATIVE FLARED END SECTION	705311
18" ALTERNATIVE PIPE CULVERT	620100
18" ALTERNATIVE PIPE CULVERT (TYPE A)	620101

ITEM DESCRIPTION	ITEM CODE
0 - 9	
18" ANCHOR ASSEMBLY	692307
18" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	665117
18" BITUMINOUS COATED CORRUGATED STEEL PIPE (.109" THICK)	665118
18" BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (.079" THICK)	703317
18" CAST-IN-DRILLED-HOLE CONCRETE PILING	490615
18" CONCRETE FLARED END SECTION	705204
18" CORRUGATED STEEL PIPE (.064" THICK)	665016
18" CORRUGATED STEEL PIPE (.079" THICK)	665017
18" CORRUGATED STEEL PIPE (.109" THICK)	665018
18" CORRUGATED STEEL PIPE (.138" THICK)	665075
18" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	690116
18" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690117
18" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	690118
18" DOWNDRAIN SLIP JOINT	692207
18" PLASTIC PIPE	641107
18" REINFORCED CONCRETE PIPE	650014
18" REINFORCED CONCRETE PIPE (CLASS III)	650311
18" REINFORCED CONCRETE PIPE (CLASS IV)	650411
18" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650105
18" SLOTTED CORRUGATED STEEL PIPE (.079" THICK)	665717
18" STEEL FLARED END SECTION	705011
18" TAPERED INLET	692107
18" TEMPORARY CULVERT	073006
1800 MM PRECAST CONCRETE PIPE MANHOLE	707252
2 1/2" GATE VALVE	208576
2 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208267
2 1/2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208277
2" BACKFLOW PREVENTER ASSEMBLY	208426
2" ELECTRIC REMOTE CONTROL VALVE	206605

ITEM DESCRIPTION	ITEM CODE
0 - 9	
2" GALVANIZED STEEL PIPE (SUPPLY LINE)	208006
2" GATE VALVE	208575
2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208266
2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208276
2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208598
2.0 M CAST-IN-DRILLED-HOLE CONCRETE PILING	490667
2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING	490669
2.1 M PERMANENT STEEL CASING	493486
2.4 M CAST-IN-DRILLED-HOLE CONCRETE PILING	490671
2.4 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	490681
2.4 M CHAIN LINK GATE (TYPE CL-1.8)	802592
2.4 M WIRE MESH GATE	801194
20 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208249
200 MM ALTERNATIVE CONDUIT	208724
200 MM ALTERNATIVE PIPE UNDERDRAIN	685067
200 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208731
200 MM CORRUGATED STEEL PIPE DOWNDRAIN	690154
200 MM CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK)	690155
200 MM DOWNDRAIN SLIP JOINT	692244
200 MM ENTRANCE TAPER	692086
200 MM PERFORATED PLASTIC PIPE UNDERDRAIN	680933
200 MM PERFORATED STEEL PIPE UNDERDRAIN (1.63 MM THICK)	680465
200 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208295
200 MM THERMOPLASTIC TRAFFIC STRIPE	840563
200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	840574
200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M)	840564
200 MM TWO-COMPONENT PAINT TRAFFIC STRIPE	840577
200 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	208798
21" ALTERNATIVE PIPE CULVERT	620120

ITEM DESCRIPTION	ITEM CODE
0 - 9	
21" X 15" CORRUGATED STEEL PIPE ARCH (.109" THICK)	667006
21" X 15" STEEL FLARED END PIPE ARCH SECTION	705403
2100 MM CORRUGATED STEEL PIPE (4.27 MM THICK)	664064
2100 MM REINFORCED CONCRETE PIPE	650094
24 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	206753
24" ALTERNATIVE FLARED END SECTION	705315
24" ALTERNATIVE PIPE CULVERT	620140
24" ANCHOR ASSEMBLY	692309
24" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561003
24" CAST-IN-DRILLED-HOLE CONCRETE PILING	490603
24" CAST-IN-DRILLED-HOLE CONCRETE PILING (RETAINING WALL)	499010
24" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	490683
24" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	498022
24" CONCRETE FLARED END SECTION	705206
24" CORRUGATED STEEL PIPE (.079" THICK)	665023
24" CORRUGATED STEEL PIPE (.109" THICK)	665024
24" CORRUGATED STEEL PIPE (.138" THICK)	665025
24" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690123
24" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	690124
24" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	690125
24" CORRUGATED STEEL PIPE ENERGY DISSIPATOR (.064" THICK)	702616
24" PLASTIC PIPE	641113
24" REINFORCED CONCRETE PIPE	650018
24" REINFORCED CONCRETE PIPE (CLASS II, RUBBER GASKET JOINT)	652215
24" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650107
24" STEEL FLARED END SECTION	705015
24" WELDED STEEL PIPE (.250" THICK)	703575
24" WELDED STEEL PIPE CASING (BRIDGE)	703460

ITEM DESCRIPTION	ITEM CODE
0 - 9	
25 MM ELECTRIC REMOTE CONTROL VALVE	206611
25 MM GATE VALVE	208488
25 MM MANUAL CONTROL VALVE	208505
25 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208250
25 MM WYE STRAINER	208509
250 MM BITUMINOUS COATED STEEL PIPE CONDUIT (1.63 MM THICK)	208747
250 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208732
250 MM CORRUGATED STEEL PIPE CONDUIT (1.63 MM THICK)	208743
250 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	208799
27" REINFORCED CONCRETE PIPE	650019
3" BACKFLOW PREVENTER ASSEMBLY	208428
3" ELECTRIC REMOTE CONTROL VALVE	206607
3" GALVANIZED STEEL PIPE (SUPPLY LINE)	208008
3" GATE VALVE	208588
3" PLASTIC PIPE	680207
3" PLASTIC PIPE (EDGE DRAIN OUTLET)	681107
3" PLASTIC PIPE (EDGE DRAIN)	681103
3" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208268
3" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208278
3.0 M CHAIN LINK GATE (TYPE CL-1.8)	802595
3.7 M CHAIN LINK GATE (TYPE CL-1.8)	802596
3/4" GALVANIZED STEEL PIPE (SUPPLY LINE)	208002
3/4" PLASTIC PIPE (IRRIGATION LINE)	208213
3/4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208262
3/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208594
3/4" QUICK COUPLING VALVE	208645
30" ALTERNATIVE PIPE CULVERT	620180
30" ANCHOR ASSEMBLY	692311
30" BITUMINOUS COATED STEEL FLARED END SECTION	705069
30" CAST-IN-DRILLED-HOLE CONCRETE PILING	490604

ITEM DESCRIPTION	ITEM CODE
0 - 9	
30" CORRUGATED STEEL PIPE (.079" THICK)	665031
30" CORRUGATED STEEL PIPE (.109" THICK)	665032
30" CORRUGATED STEEL PIPE (.138" THICK)	665033
30" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690131
30" PLASTIC PIPE	641119
30" REINFORCED CONCRETE PIPE	650022
30" REINFORCED CONCRETE PIPE (CLASS II)	650220
30" STEEL FLARED END SECTION	705019
30" WELDED STEEL PIPE (.250" THICK)	703598
300 MM ALTERNATIVE FLARED END SECTION	705334
300 MM ALTERNATIVE PIPE CULVERT	620904
300 MM ALTERNATIVE PIPE CULVERT (TYPE A)	620905
300 MM ALTERNATIVE PIPE CULVERT (TYPE B)	620906
300 MM ALTERNATIVE PIPE DOWNDRAIN	698091
300 MM ANCHOR ASSEMBLY	692383
300 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (1.63 MM THICK)	664084
300 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	690273
300 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208733
300 MM CORRUGATED STEEL PIPE	664008
300 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664010
300 MM CORRUGATED STEEL PIPE CONDUIT (1.63 MM THICK)	208744
300 MM CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK)	690159
300 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	690160
300 MM CORRUGATED STEEL PIPE RISER (1.63 MM THICK)	703267
300 MM DOWNDRAIN SLIP JOINT	692245
300 MM ENTRANCE TAPER	692088
300 MM GATE VALVE	705954
300 MM PERFORATED STEEL PIPE UNDERDRAIN (2.01 MM THICK)	680469

ITEM DESCRIPTION	ITEM CODE
0 - 9	
300 MM PLASTIC PIPE	641132
300 MM REINFORCED CONCRETE PIPE	650067
300 MM STEEL FLARED END SECTION	705042
300 MM TEMPORARY CULVERT	073026
300 MM WELDED STEEL PIPE (2.67 MM THICK)	703542
300 MM WELDED STEEL PIPE (3.40 MM THICK)	703543
300 MM WELDED STEEL PIPE (6.35 MM THICK)	703545
300 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	208800
32 MM ELECTRIC REMOTE CONTROL VALVE	206612
32 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208251
32 MM WYE STRAINER	208510
33" REINFORCED CONCRETE PIPE	650024
36" ALTERNATIVE PIPE CULVERT	620220
36" ALTERNATIVE PIPE RISER	708050
36" ANCHOR ASSEMBLY	692313
36" BITUMINOUS COATED CORRUGATED STEEL PIPE (.109" THICK)	665137
36" BITUMINOUS COATED STEEL FLARED END SECTION	705073
36" CORRUGATED STEEL PIPE (.079" THICK)	665036
36" CORRUGATED STEEL PIPE (.109" THICK)	665037
36" CORRUGATED STEEL PIPE (.138" THICK)	665038
36" CORRUGATED STEEL PIPE (.168" THICK)	665039
36" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	690137
36" CORRUGATED STEEL PIPE INLET (.079" THICK)	700638
36" CORRUGATED STEEL PIPE INLET (.109" THICK)	700639
36" CORRUGATED STEEL PIPE INLET (.138" THICK)	700640
36" CORRUGATED STEEL PIPE INLET (.168" THICK)	700641
36" CORRUGATED STEEL PIPE RISER (.109" THICK)	703239
36" DEBRIS RACK CAGE (H=4')	706605
36" PRECAST CONCRETE PIPE INLET	707117

ITEM DESCRIPTION	ITEM CODE
0 - 9	
36" PRECAST CONCRETE PIPE MANHOLE	707217
36" PRECAST CONCRETE PIPE RISER	707417
36" REINFORCED CONCRETE PIPE	650026
36" REINFORCED CONCRETE PIPE (CLASS II)	650224
36" REINFORCED CONCRETE PIPE RISER	707467
36" STEEL FLARED END SECTION	705023
36" TEMPORARY INLET	073051
365 MM X 575 MM OVAL SHAPED REINFORCED CONCRETE PIPE (CLASS III, RUBBER GASKET JOINT)	657343
375 MM ALTERNATIVE FLARED END SECTION	705335
375 MM ALTERNATIVE PIPE CULVERT	620908
375 MM PLASTIC PIPE	641133
375 MM REINFORCED CONCRETE PIPE	650068
39" REINFORCED CONCRETE PIPE	650028
4' CHAIN LINK GATE (TYPE CL-3)	801901
4' CHAIN LINK GATE (TYPE CL-6)	802501
4" GALVANIZED STEEL PIPE (SUPPLY LINE)	208009
4" GATE VALVE	208589
4" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208279
4" PLASTIC PIPE UNDERDRAIN	680285
4" POLYVINYL CHLORIDE SEWER PIPE	717001
4" THERMOPLASTIC TRAFFIC STRIPE	840504
4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	840523
4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 17-7)	840526
4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	840525
4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 6-1)	840521
4" THERMOPLASTIC TRAFFIC STRIPE (DASHED WHITE)	840511
4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED)	840581
4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED) (BROKEN 17-7)	840580
4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED, BROKEN 36-12)	840545

ITEM DESCRIPTION	ITEM CODE
0 - 9	
4" TWO-COMPONENT PAINT TRAFFIC STRIPE	840582
4.3 M CHAIN LINK GATE (TYPE CL-1.8)	802671
4.9 M CHAIN LINK GATE (TYPE CL-1.8)	802672
40 MM ELECTRIC REMOTE CONTROL VALVE	206613
40 MM GATE VALVE	208490
40 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208252
40 MM WYE STRAINER	208511
400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490655
400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	498027
400 MM PLASTIC PIPE-LINER	152666
42" ALTERNATIVE PIPE CULVERT	620260
42" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561006
42" REINFORCED CONCRETE PIPE	650030
42" X 29" ALTERNATIVE PIPE ARCH CULVERT	625299
450 MM ALTERNATIVE FLARED END SECTION	705336
450 MM ALTERNATIVE PIPE CULVERT	620909
450 MM ALTERNATIVE PIPE CULVERT (TYPE A)	620910
450 MM ALTERNATIVE PIPE CULVERT (TYPE B)	620911
450 MM ALTERNATIVE PIPE DOWNDRAIN	698162
450 MM ANCHOR ASSEMBLY	692385
450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK)	664091
450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	690276
450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK)	690277
450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (3.51 MM THICK)	690297
450 MM CONCRETE FLARED END SECTION	705222
450 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	664014
450 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664015

ITEM DESCRIPTION	ITEM CODE
0 - 9	
450 MM CORRUGATED STEEL PIPE (2.77 MM THICK)	664016
450 MM CORRUGATED STEEL PIPE (3.51 MM THICK)	664068
450 MM CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK)	690165
450 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	690166
450 MM ENTRANCE TAPER	692090
450 MM PLASTIC PIPE	641134
450 MM REINFORCED CONCRETE PIPE	650069
450 MM REINFORCED CONCRETE PIPE (CLASS IV)	650470
450 MM REINFORCED CONCRETE PIPE (CLASS V)	650574
450 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650127
450 MM SLIDE HEADGATE	705648
450 MM SLOTTED CORRUGATED STEEL PIPE (1.63 MM THICK)	665732
450 MM SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK)	665733
450 MM STEEL FLARED END SECTION	705044
450 MM TEMPORARY CULVERT	073028
48 SINGLEMODE FIBER OPTIC CABLE	867017
48" ALTERNATIVE PIPE CULVERT	620300
48" BITUMINOUS COATED STEEL FLARED END SECTION	705081
48" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561011
48" CAST-IN-DRILLED-HOLE CONCRETE PILING	490607
48" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	490684
48" CORRUGATED STEEL PIPE (.079" THICK)	665046
48" CORRUGATED STEEL PIPE (.109" THICK)	665047
48" CORRUGATED STEEL PIPE (.168" THICK)	665049
48" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	690148
48" DEBRIS RACK CAGE (H=4')	706607
48" PRECAST CONCRETE PIPE INLET	707125
48" REINFORCED CONCRETE PIPE	650034
48" TEMPORARY CULVERT	073013

ITEM DESCRIPTION	ITEM CODE
0 - 9	
48" WELDED STEEL PIPE (.375" THICK)	703656
49" X 33" ALTERNATIVE PIPE ARCH CULVERT	625319
5' CHAIN LINK GATE (TYPE CL-6)	802510
5.5 M CHAIN LINK GATE (TYPE CL-2.1)	802841
50 MM BACKFLOW PREVENTER ASSEMBLY	208435
50 MM ELECTRIC REMOTE CONTROL VALVE	206614
50 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	208021
50 MM GATE VALVE	208491
50 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208253
50 MM PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208502
525 MM PLASTIC PIPE-LINER	152668
525 MM X 375 MM ALTERNATIVE FLARED END PIPE ARCH SECTION	705346
525 MM X 375 MM ALTERNATIVE PIPE ARCH CULVERT	625382
54" ALTERNATIVE PIPE CULVERT	620340
54" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561014
54" CAST-IN-DRILLED-HOLE CONCRETE PILING	490608
54" REINFORCED CONCRETE PIPE	650038
6' CHAIN LINK GATE (TYPE CL-6)	802520
6" NON-PERFORATED PLASTIC PIPE UNDERDRAIN	680903
6" PERFORATED PLASTIC PIPE UNDERDRAIN	680902
6" PLASTIC PIPE	681023
6" PLASTIC PIPE (EDGE DRAIN OUTLET)	681113
6" PLASTIC PIPE (EDGE DRAIN)	681108
6" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208280
6" THERMOPLASTIC TRAFFIC STRIPE	840505
6.1 M CHAIN LINK GATE (TYPE CL-1.8)	802675
60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561016
60" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	490685
60" REINFORCED CONCRETE PIPE (CLASS IV)	650440

ITEM DESCRIPTION	ITEM CODE
0 - 9	
600 MM ALTERNATIVE FLARED END SECTION	705337
600 MM ALTERNATIVE PIPE CULVERT	620913
600 MM ALTERNATIVE PIPE CULVERT (TYPE A)	620914
600 MM ALTERNATIVE PIPE CULVERT (TYPE B)	620915
600 MM ALTERNATIVE PIPE CULVERT (TYPE C)	620916
600 MM ALTERNATIVE PIPE DOWNDRAIN	698169
600 MM ANCHOR ASSEMBLY	692386
600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK)	664097
600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK)	690281
600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (3.51 MM THICK)	690282
600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490657
600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	490676
600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	498030
600 MM CONCRETE FLARED END SECTION	705224
600 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	664019
600 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664020
600 MM CORRUGATED STEEL PIPE (2.77 MM THICK)	664021
600 MM CORRUGATED STEEL PIPE (3.51 MM THICK)	664022
600 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	690170
600 MM CORRUGATED STEEL PIPE DOWNDRAIN (3.51 MM THICK)	690172
600 MM DOWNDRAIN SLIP JOINT	692247
600 MM ENTRANCE TAPER	692091
600 MM PLASTIC PIPE	641136
600 MM REINFORCED CONCRETE PIPE	650075
600 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650128
600 MM REINFORCED CONCRETE PIPE (SPECIAL)	650073
600 MM STEEL FLARED END SECTION	705045

ITEM DESCRIPTION	ITEM CODE
0 - 9	
600 MM TEMPORARY CULVERT	073029
600 MM WELDED STEEL PIPE CASING (BRIDGE)	703481
65 MM BACKFLOW PREVENTER ASSEMBLY	208436
65 MM ELECTRIC REMOTE CONTROL VALVE	206615
65 MM GATE VALVE	208492
65 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208254
66" CAST-IN-DRILLED-HOLE CONCRETE PILING	490610
675 MM PLASTIC PIPE-LINER	152669
7.3 M CHAIN LINK GATE (TYPE CL-1.8)	802676
75 MM GATE VALVE	208493
75 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208255
750 MM ALTERNATIVE FLARED END SECTION	705338
750 MM ALTERNATIVE PIPE CULVERT	620919
750 MM ALTERNATIVE PIPE CULVERT (TYPE A)	620920
750 MM ALTERNATIVE PIPE CULVERT (TYPE B)	620921
750 MM ALTERNATIVE PIPE DOWNDRAIN	698176
750 MM ANCHOR ASSEMBLY	692387
750 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (3.51 MM THICK)	690294
750 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490658
750 MM CONCRETE FLARED END SECTION	705226
750 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664028
750 MM DOWNDRAIN SLIP JOINT	692248
750 MM REINFORCED CONCRETE PIPE	650077
750 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650129
750 MM STEEL FLARED END SECTION	705047
750 MM TEMPORARY CULVERT	073030
760 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561008
8' CHAIN LINK GATE (TYPE CL-6)	802540
8" ALTERNATIVE PIPE CULVERT	620020

ITEM DESCRIPTION	ITEM CODE
0 - 9	
8" ALTERNATIVE PIPE UNDERDRAIN	685020
8" ANCHOR ASSEMBLY	692303
8" BITUMINOUS COATED CORRUGATED STEEL PIPE CONDUIT (.064" THICK)	208765
8" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208738
8" CORRUGATED STEEL FLUME DOWNDRAIN	691003
8" CORRUGATED STEEL PIPE (.079" THICK)	665006
8" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690106
8" GATE VALVE	208591
8" PERFORATED PLASTIC PIPE UNDERDRAIN	680905
8" PERFORATED STEEL PIPE UNDERDRAIN	680404
8" PERFORATED STEEL PIPE UNDERDRAIN (.064" THICK)	680405
8" THERMOPLASTIC TRAFFIC STRIPE	840506
8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	840508
8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	840550
8" WELDED STEEL PIPE CONDUIT (.250" THICK)	208808
80 MM PLASTIC PIPE (EDGE DRAIN OUTLET)	681137
80 MM PLASTIC PIPE (EDGE DRAIN)	681134
80 MM SLOTTED PLASTIC PIPE	680259
875 MM X 600 MM ALTERNATIVE FLARED END PIPE ARCH SECTION	705348
875 MM X 600 MM ALTERNATIVE PIPE ARCH CULVERT	625391
875 MM X 600 MM CORRUGATED STEEL PIPE ARCH (3.51 MM THICK)	667059
875 MM X 600 MM STEEL FLARED END PIPE ARCH SECTION	705477
900 MM ALTERNATIVE FLARED END SECTION	705339
900 MM ALTERNATIVE PIPE CULVERT	620924
900 MM ALTERNATIVE PIPE CULVERT (TYPE A)	620925
900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK)	664110
900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE INLET (2.77 MM THICK)	700858

ITEM DESCRIPTION	ITEM CODE
0 - 9	
900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE INLET (3.51 MM THICK)	700859
900 MM CONCRETE FLARED END SECTION	705227
900 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664033
900 MM CORRUGATED STEEL PIPE (2.77 MM THICK)	664034
900 MM CORRUGATED STEEL PIPE INLET (2.01 MM THICK)	700658
900 MM CORRUGATED STEEL PIPE INLET (2.77 MM THICK)	700659
900 MM CORRUGATED STEEL PIPE INLET (3.51 MM THICK)	700660
900 MM CORRUGATED STEEL PIPE RISER (2.77 MM THICK)	703284
900 MM CORRUGATED STEEL PIPE RISER (3.51 MM THICK)	703285
900 MM DEBRIS RACK CAGE (H = 1.8 M)	706652
900 MM PRECAST CONCRETE PIPE INLET	707133
900 MM PRECAST CONCRETE PIPE MANHOLE	707244
900 MM PRECAST CONCRETE PIPE RISER	707471
900 MM REINFORCED CONCRETE PIPE	650079
900 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650130
900 MM REINFORCED CONCRETE PIPE RISER	707479
900 MM STEEL FLARED END SECTION	705048
920 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561009
A	
ABANDON CULVERT	150206
ABANDON DECK DRAIN	150208
ABANDON INLET	150221
ABANDON MANHOLE	150224
ABANDON PIPELINE	150227
ABANDON REINFORCED CONCRETE BOX	150205
ABANDON SEWER	150241
ABANDON WATER WELL	150229
ACCESS OPENING, SOFFIT	153531
ADJUST FRAME AND COVER TO GRADE	152438

ITEM DESCRIPTION	ITEM CODE
A	
ADJUST FRAME AND GRATE TO GRADE	152439
ADJUST INLET	152430
ADJUST MANHOLE	152432
ADJUST MANHOLE TO GRADE	152440
ADJUST METAL BEAM GUARD RAILING	152500
ADJUST MONUMENT COVER	152422
ADJUST MONUMENT TO GRADE	152423
ADJUST PIPE INLET TO GRADE	152443
ADJUST PULL BOX	869042
ADJUST SEWER CLEANOUT TO GRADE	152400
ADJUST SEWER MANHOLE	152475
ADJUST UTILITY COVER TO GRADE	152469
ADJUST VALVE BOX	152453
ADJUST VALVE BOX FRAME AND COVER TO GRADE	152441
ADJUST WATER METER	152450
ADJUST WATER METER BOX TO GRADE	152403
ADJUST WATER METER TO GRADE	152401
ADJUST WATER VALVE	152451
ADJUST WATER VALVE COVER TO GRADE	152402
AGGREGATE BASE	260200
AGGREGATE BASE (APPROACH SLAB)	260210
ALTERNATIVE FLARED TERMINAL SYSTEM	839585
ALTERNATIVE IN-LINE TERMINAL SYSTEM	839584
ANCHOR ASSEMBLY	692301
ANTI-GRAFFITI COATING	511047
ARCHITECTURAL TREATMENT	511035
ASBESTOS COMPLIANCE PLAN	190113
ASBESTOS COMPLIANCE PLAN (NATURALLY OCCURING ASBESTOS)	190115
ASPHALT BINDER (POLYMER MODIFIED)	370125
ASPHALT CONCRETE	390104
ASPHALT CONCRETE (LEVELING)	390107
ASPHALT CONCRETE (OPEN GRADED)	390106

ITEM DESCRIPTION	ITEM CODE
A	
ASPHALT CONCRETE (TYPE A)	390102
ASPHALT MEMBRANE WATERPROOFING	540101
ASPHALT TREATED PERMEABLE BASE	290201
ASPHALTIC EMULSION (CURING SEAL)	270065
ASPHALTIC EMULSION (FOG SEAL COAT)	374002
ASPHALTIC EMULSION (PAINT BINDER)	397001
ASPHALTIC EMULSION (POLYMER MODIFIED)	374492
ASPHALTIC EMULSION MEMBRANE (BONDED WEARING COURSE)	390149
ASPHALT-RUBBER BINDER	370120
B	
BACKFLOW PREVENTER ASSEMBLY	208420
BACKFLOW PREVENTER ASSEMBLY ENCLOSURE	208421
BALL VALVE	208683
BAR REINFORCING STEEL	520101
BAR REINFORCING STEEL (BOX CULVERT)	520107
BAR REINFORCING STEEL (BRIDGE)	520102
BAR REINFORCING STEEL (EPOXY COATED)	520106
BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	520110
BAR REINFORCING STEEL (PUMPING PLANT)	520113
BAR REINFORCING STEEL (RETAINING WALL)	520103
BAR REINFORCING STEEL (SOUND WALL)	520105
BARRICADE (LEFT IN PLACE)	120140
BENCH	994425
BICYCLE LOCKER	994922
BICYCLE PARKING RACK	994920
BLANK WELL CASING	760030
BOOSTER PUMP ELECTRICAL SYSTEM	860798
BOOSTER PUMP SYSTEM	209503
BRIDGE DECK DRAINAGE SYSTEM	750505
BRIDGE REMOVAL	157550

ITEM DESCRIPTION	ITEM CODE
B	
BRIDGE REMOVAL (PORTION)	157560
BRIDGE REMOVAL (PORTION), LOCATION A	157561
BRIDGE REMOVAL (PORTION), LOCATION B	157562
BRIDGE REMOVAL (PORTION), LOCATION C	157563
BRIDGE REMOVAL (PORTION), LOCATION D	157564
BRIDGE REMOVAL (PORTION), LOCATION E	157565
BRIDGE REMOVAL (PORTION), LOCATION F	157566
BRIDGE REMOVAL (PORTION), LOCATION G	157567
BRIDGE REMOVAL, LOCATION A	157551
BRIDGE REMOVAL, LOCATION B	157552
BRIDGE REMOVAL, LOCATION C	157553
BRIDGE REMOVAL, LOCATION D	157554
BRIDGE REMOVAL, LOCATION E	157555
BRIDGE REMOVAL, LOCATION F	157556
BRIDGE REMOVAL, LOCATION G	157557
BRIDGE REMOVAL, LOCATION H	157558
BROKEN CONCRETE SLOPE PROTECTION	722002
BUILDING WORK	994650
BURIED POST ANCHOR	839528
BUS SHELTER	995000
C	
CABLE ANCHORAGE SYSTEM	692409
CABLE RAILING	839521
CABLE RAILING (MODIFIED)	839527
CAM COUPLER ASSEMBLY	208562
CAP INLET	155003
CAP MANHOLE	155007
CAP RISER	155006
CEMENT TREATED BASE (PLANT-MIXED, CLASS A)	270011
CEMENT TREATED PERMEABLE BASE	290301
CHAIN LINK FENCE (TYPE CL-0.9)	800381

ITEM DESCRIPTION	ITEM CODE
C	
CHAIN LINK FENCE (TYPE CL-0.9, VINYL-CLAD)	800382
CHAIN LINK FENCE (TYPE CL-1.2)	800385
CHAIN LINK FENCE (TYPE CL-1.2, VINYL-CLAD)	800386
CHAIN LINK FENCE (TYPE CL-1.8)	800391
CHAIN LINK FENCE (TYPE CL-1.8, SLATTED)	800395
CHAIN LINK FENCE (TYPE CL-1.8, VINYL-CLAD)	800392
CHAIN LINK FENCE (TYPE CL-2.4)	800423
CHAIN LINK FENCE (TYPE CL-3, VINYL-CLAD)	800302
CHAIN LINK FENCE (TYPE CL-3.0, VINYL-CLAD)	800428
CHAIN LINK FENCE (TYPE CL-6)	800360
CHAIN LINK FENCE (TYPE CL-6, EXTENSION ARM)	800363
CHAIN LINK FENCE (TYPE CL-6, SLATTED)	800365
CHAIN LINK FENCE (TYPE CL-6, VINYL-CLAD)	800361
CHAIN LINK RAILING	833020
CHAIN LINK RAILING (TYPE 7 MODIFIED)	833033
CHAIN LINK RAILING (TYPE 7)	833032
CHAIN LINK RAILING (TYPE 7L)	833034
CHANGEABLE MESSAGE SIGN SYSTEM	860530
CHANNEL EXCAVATION	190151
CHANNELIZER (SURFACE MOUNTED)	120165
CHANNELIZER (SURFACE MOUNTED) (LEFT IN PLACE)	120166
CHECK VALVE	208670
CLASS 1 AGGREGATE SUBBASE	250101
CLASS 1 CONCRETE (BACKFILL)	510414
CLASS 1 CONCRETE (BOX CULVERT)	510413
CLASS 1 CONCRETE (MINOR STRUCTURE)	510409
CLASS 1 CONCRETE (RETAINING WALL)	510408
CLASS 1 CONCRETE (STRUCTURE)	510410
CLASS 1 PERMEABLE MATERIAL	682020
CLASS 1 PERMEABLE MATERIAL (STABILIZATION)	682021

ITEM DESCRIPTION	ITEM CODE
C	
CLASS 2 AGGREGATE BASE	260201
CLASS 2 AGGREGATE SUBBASE	250201
CLASS 2 CONCRETE (BOX CULVERT)	510129
CLASS 2 CONCRETE (HEADWALL)	510135
CLASS 2 CONCRETE (MINOR STRUCTURE)	510126
CLASS 2 CONCRETE (RETAINING WALL FOOTING)	510132
CLASS 2 CONCRETE (STRUCTURE)	510127
CLASS 2 CONCRETE (WINGWALLS)	510138
CLASS 2 PERMEABLE MATERIAL (UNDERDRAIN)	682041
CLASS 3 AGGREGATE BASE	260301
CLASS 3 AGGREGATE SUBBASE	250301
CLASS 3 CONCRETE	510217
CLASS 3 CONCRETE (BACKFILL)	510220
CLASS 3 PERMEABLE MATERIAL	682045
CLASS 3 PERMEABLE MATERIAL (BLANKET)	682049
CLASS 3 PERMEABLE MATERIAL (UNDERDRAIN)	682048
CLASS 4 AGGREGATE SUBBASE	250401
CLASS 4 CONCRETE (BACKFILL)	510314
CLASS 4 CONCRETE (BACKFILL)	719598
CLEAN AND PAINT STRUCTURAL STEEL	590115
CLEAN AND PAINT STRUCTURAL STEEL (EXISTING BRIDGE)	590116
CLEAN BRIDGE DECK	153235
CLEAN EXPANSION JOINT	511118
CLEAN STRUCTURAL STEEL (EXISTING BRIDGE)	590106
CLEANOUT ASSEMBLY (EDGE DRAIN)	681111
CLEARING AND GRUBBING	160101
CLOSED CIRCUIT TELEVISION SYSTEM	860990
COLD PLANE ASPHALT CONCRETE PAVEMENT	153103
COLD PLANE ASPHALT CONCRETE PAVEMENT (.08' MAXIMUM)	153109
COLUMN CASING	550110
COMMERCIAL FERTILIZER	202018

ITEM DESCRIPTION	ITEM CODE
C	
COMMERCIAL FERTILIZER (PACKET)	202033
COMMERCIAL FERTILIZER (SLOW RELEASE)	202031
COMMUNICATION CONDUIT	860791
COMMUNICATION CONDUIT (BRIDGE)	860792
COMPOST, INCORPORATE	203025
CONCRETE (CHANNEL LINING)	721430
CONCRETE (CONCRETED-ROCK SLOPE PROTECTION)	721501
CONCRETE (DITCH LINING)	721420
CONCRETE (SLOPE PROTECTION)	721400
CONCRETE BACKFILL	193118
CONCRETE BACKFILL (SOLDIER PILE WALL)	193116
CONCRETE BACKFILL FAST SETTING	193117
CONCRETE BARRIER (SPECIAL)	839402
CONCRETE BARRIER (TYPE 25 MODIFIED)	833128
CONCRETE BARRIER (TYPE 25)	833125
CONCRETE BARRIER (TYPE 25A MODIFIED)	833129
CONCRETE BARRIER (TYPE 25B)	833127
CONCRETE BARRIER (TYPE 25R)	833138
CONCRETE BARRIER (TYPE 26 MODIFIED)	833142
CONCRETE BARRIER (TYPE 26)	833140
CONCRETE BARRIER (TYPE 26A MODIFIED)	833143
CONCRETE BARRIER (TYPE 26A)	833141
CONCRETE BARRIER (TYPE 27B MODIFIED)	833165
CONCRETE BARRIER (TYPE 50)	839481
CONCRETE BARRIER (TYPE 60)	839701
CONCRETE BARRIER (TYPE 60A)	839702
CONCRETE BARRIER (TYPE 60C)	839703
CONCRETE BARRIER (TYPE 60D)	839704
CONCRETE BARRIER (TYPE 60E)	839705
CONCRETE BARRIER (TYPE 60G)	839706
CONCRETE BARRIER (TYPE 60GC)	839708
CONCRETE BARRIER (TYPE 60GE)	839709

ITEM DESCRIPTION	ITEM CODE
C	
CONCRETE BARRIER (TYPE 60S)	839710
CONCRETE BARRIER (TYPE 60SC)	839712
CONCRETE BARRIER (TYPE 60SE)	839713
CONCRETE BARRIER (TYPE 732 MODIFIED)	839717
CONCRETE BARRIER (TYPE 732)	839720
CONCRETE BARRIER (TYPE 732A)	839721
CONCRETE BARRIER (TYPE 732B)	839723
CONCRETE BARRIER (TYPE 732R)	839718
CONCRETE BARRIER (TYPE 736 MODIFIED)	839727
CONCRETE BARRIER (TYPE 736)	839725
CONCRETE BARRIER (TYPE 736A)	839726
CONCRETE BARRIER (TYPE 736B)	839731
CONCRETE BARRIER (TYPE 736R)	839728
CONCRETE BARRIER (TYPE 736SV)	839734
CONCRETE BARRIER (TYPE 742)	839735
CONCRETE BARRIER (TYPE 742A)	839736
CONCRETE BARRIER (TYPE 742B)	839737
CONCRETE BARRIER (TYPE 80)	839714
CONCRETE BARRIER (TYPE K)	833080
CONCRETE BLOCK WALL	513570
CONCRETE CLOSURE WALL	513501
CONCRETE PAVEMENT	401000
CONCRETE PAVEMENT (RAMP TERMINI)	401066
CONCRETE PAVEMENT (WEIGH-IN-MOTION)	401102
CONCRETE SEWER MANHOLE	719210
CONCRETED-ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	721607
CONCRETED-ROCK SLOPE PROTECTION (1T, METHOD A)	721518
CONCRETED-ROCK SLOPE PROTECTION (COBBLE, METHOD B)	721616
CONCRETED-ROCK SLOPE PROTECTION (FACING, METHOD A)	721509
CONDUCTOR CASING	760025
CONSTRUCTION AREA SIGNS	120090

ITEM DESCRIPTION	ITEM CODE
C	
CONSTRUCTION SITE MANAGEMENT	074016
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT	400050
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT)	400060
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE E)	400065
CONTOUR GRADING	197003
CONTROL AND NEUTRAL CONDUCTORS	206560
CORE CONCRETE (0 - 50 MM)	515072
CORE CONCRETE (1 1/2")	515160
CORE CONCRETE (1")	515060
CORE CONCRETE (101 MM - 150 MM)	515074
CORE CONCRETE (151 MM - 200 MM)	515075
CORE CONCRETE (201 MM - 250 MM)	515076
CORE CONCRETE (251 MM - 300 MM)	515077
CORE CONCRETE (8")	515067
CRACK EXISTING CONCRETE PAVEMENT	415101
CRASH CUSHION (ADIEM)	839603
CRASH CUSHION (REACT 9CBB)	839604
CRASH CUSHION (REACT 9SCBS)	839605
CRASH CUSHION (TYPE CAT)	839601
CRASH CUSHION (TYPE CAT) BACKUP	839602
CRASH CUSHION MODULE, SAND FILLED	839631
CRASH CUSHION, SAND FILLED	839591
CULTIVATE	200120
CULTIVATE (SOIL AMENDMENT)	200121
CURB RAMP DETECTABLE WARNING SURFACE	731656
D	
DATA CORE	394060
DEBRIS RACK	706500
DELINEATOR (CLASS 1)	820107
DELINEATOR (CLASS 2)	820108
DELINEATOR (SPECIAL)	820105

ITEM DESCRIPTION	ITEM CODE
D	
DETECTOR LOOP	860811
DEVELOP WATER SUPPLY	170101
DIAPHRAGM BOLSTER	510805
DITCH EXCAVATION	194001
DOUBLE METAL BEAM GUARD RAILING (WOOD POST)	839220
DOUBLE THRIE BEAM BARRIER	839310
DOUBLE THRIE BEAM BARRIER (STEEL POST)	839312
DOUBLE THRIE BEAM BARRIER (WOOD POST)	839311
DOWEL BAR (DRILL AND BOND)	406050
DOWEL BAR RETROFIT	406100
DRAINAGE INLET MARKER	700617
DRAINAGE PUMPING EQUIPMENT	740500
DRILL AND BOND DOWEL	511106
DRILL AND BOND DOWEL (CHEMICAL ADHESIVE)	511110
DRILL AND BOND DOWEL (EPOXY CARTRIDGE)	511109
DRILL HOLE (HORIZONTAL DRAIN)	681502
DRILL PILOT HOLE	760021
DRINKING FOUNTAIN	994900
DRIVE 16" CAST-IN-STEEL SHELL CONCRETE PILE	495104
DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (1524 MM)	499055
DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (914 MM)	499043
DRIVE PILE (CLASS 140) (ALTERNATIVE V)	490745
DRIVE PILE (CLASS 400)	491008
DRIVE PILE (CLASS 400) (ALTERNATIVE W)	491013
DRIVE PILE (CLASS 625) (ALTERNATIVE V)	490771
DRIVE PILE (CLASS 625) (ALTERNATIVE W)	490773
DRIVE PILE (CLASS 90)	490737
DRIVE PILE (CLASS 90) (ALTERNATIVE V)	490741
DRIVE PILE (CLASS 900) (ALTERNATIVE W)	490701
DRIVE STEEL PILE (HP 12 X 84)	490521
DRIVE STEEL PILE (HP 14 X 117)	490539

ITEM DESCRIPTION	ITEM CODE
D	
DRIVE STEEL PILE (HP 250 X 62)	490506
DRIVE STEEL PILE (HP 250 X 85)	490512
DRIVE STEEL PILE (HP 360 X 132)	490567
DUFF	202007
DUST CONTROL PLAN (NATURALLY OCCURRING ASBESTOS)	190116
E	
EARTH RETAINING STRUCTURE	197020
ELECTRIC SERVICE (IRRIGATION)	860797
ELECTRICAL WORK	991061
END ANCHOR ASSEMBLY (TYPE CA)	839582
END ANCHOR ASSEMBLY (TYPE SFT)	839581
END CAP	839555
END CAP (TYPE A)	839576
END CAP (TYPE TA)	839577
END CAP (TYPE TC)	839578
END SECTION	839553
ENTRANCE TAPER	692001
ERECT PRECAST PRESTRESSED CONCRETE BOX GIRDER	512502
ERECT PRECAST PRESTRESSED CONCRETE DECK UNIT	512510
ERECT PRECAST PRESTRESSED CONCRETE GIRDER	512500
ERECT STRUCTURAL STEEL (BRIDGE)	550204
EROSION CONTROL (BFM)	203019
EROSION CONTROL (BLANKET)	203001
EROSION CONTROL (BONDED FIBER MATRIX) (SQFT)	203027
EROSION CONTROL (COMPOST BLANKET)	203002
EROSION CONTROL (DRILL SEED)	203012
EROSION CONTROL (HYDRAULIC MATRIX)	203017
EROSION CONTROL (HYDROSEED) (ACRE)	203032
EROSION CONTROL (HYDROSEED) (SQFT)	203031
EROSION CONTROL (NETTING)	203018
EROSION CONTROL (TYPE C)	203011

ITEM DESCRIPTION	ITEM CODE
E	
EROSION CONTROL (TYPE D)	203016
EROSION CONTROL HYDRAULIC MULCH (BONDED FIBER MATRIX)	203020
EROSION CONTROL HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	203022
ESTABLISH EXISTING PLANTING	204100
EXPANSION DAM	519050
EXPOSED AGGREGATE FINISH	511045
EXTEND 10" CONDUIT	208907
EXTEND 150 MM CONDUIT	208908
EXTEND 200 MM CONDUIT	208909
EXTEND 250 MM CONDUIT	208910
EXTEND 8" CONDUIT	208906
EXTINGUISHABLE MESSAGE SIGN	860503
EXTINGUISHABLE MESSAGE SIGN SYSTEM	860504
F	
FENCE (TYPE BW, 4-STRAND, METAL POST)	800008
FENCE (TYPE BW, 5 STRAND, METAL POST)	800007
FENCE (TYPE BW, METAL POST)	800001
FENCE (TYPE BW, WOOD POST)	800002
FENCE (TYPE WM, METAL POST)	800051
FIBER OPTIC SPLICE CLOSURE	867130
FIBER ROLLS	203021
FILTER ASSEMBLY UNIT	208560
FILTER FABRIC	681990
FILTER FABRIC	729000
FILTER FABRIC (GABION)	729002
FILTER FABRIC (UNDERDRAIN)	681988
FINISHING ROADWAY	220101
FLASHING BEACON	860601
FLASHING BEACON (PORTABLE)	120200
FLASHING BEACON AND LIGHTING	860603
FLUME ANCHOR ASSEMBLY	692361

ITEM DESCRIPTION	ITEM CODE
F	
FLUME DOWNDRAIN	691900
FOLIAGE PROTECTOR	205051
FRACTURED FIN TEXTURE	511063
FRACTURED RIB TEXTURE	511064
FRAME AND COVER	750008
FRAME AND GRATE	750007
FURNISH 16" CAST-IN-STEEL SHELL CONCRETE PILING	495103
FURNISH AND INSTALL DRAIN PIPE (HORIZONTAL DRAIN)	681501
FURNISH BRIDGE DECK TREATMENT MATERIAL	540108
FURNISH BRIDGE DECK TREATMENT MATERIAL (LOW ODOR)	540109
FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (1524 MM)	499054
FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (914 MM)	499042
FURNISH FIBERGLASS REINFORCED PLASTIC PANEL SIGN (3.4 MM)	560243
FURNISH FORMED PANEL SIGN (OVERHEAD)	560233
FURNISH LAMINATED PANEL SIGN (1"-TYPE A)	560244
FURNISH LAMINATED PANEL SIGN (1"-TYPE B)	560245
FURNISH LAMINATED PANEL SIGN (2 1/2"-TYPE B)	560246
FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE A)	560234
FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE B)	560235
FURNISH LAMINATED PANEL SIGN (63.5 MM-TYPE B)	560236
FURNISH LAMINATED PANEL SIGN (63.5 MM-TYPE H)	560237
FURNISH PILING (CLASS 140) (ALTERNATIVE V)	490744
FURNISH PILING (CLASS 400)	491007
FURNISH PILING (CLASS 400) (ALTERNATIVE W)	491012
FURNISH PILING (CLASS 625) (ALTERNATIVE V)	490770
FURNISH PILING (CLASS 625) (ALTERNATIVE W)	490772
FURNISH PILING (CLASS 90)	490736
FURNISH PILING (CLASS 90) (ALTERNATIVE V)	490740

ITEM DESCRIPTION	ITEM CODE
F	
FURNISH PILING (CLASS 900) (ALTERNATIVE W)	490700
FURNISH POLYESTER CONCRETE OVERLAY	515041
FURNISH PRECAST PRESTRESSED CONCRETE BOX GIRDER (80'-90')	512225
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (110'-120')	512280
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (120'-130')	512281
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (60'-70')	512290
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (70'-80')	512291
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (10 M - 15 M)	512230
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (15 M - 20 M)	512231
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (20 M - 25 M)	512232
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (35 M - 40 M)	512235
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (5 M - 10 M)	512229
FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	560203
FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY)	560223
FURNISH SIGN STRUCTURE (LIGHTWEIGHT)	560213
FURNISH SIGN STRUCTURE (TRUSS)	560218
FURNISH SIGN STRUCTURE (TUBULAR)	560208
FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED)	560251
FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	560248
FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED)	560252
FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED)	560249
FURNISH SINGLE SHEET ALUMINUM SIGN (0.125"-UNFRAMED)	560250
FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-FRAMED)	560241
FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-UNFRAMED)	560238
FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-FRAMED)	560242
FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-UNFRAMED)	560239
FURNISH STEEL PILING (HP 12 X 84)	490520

ITEM DESCRIPTION	ITEM CODE
F	
FURNISH STEEL PILING (HP 14 X 117)	490538
FURNISH STEEL PILING (HP 250 X 62)	490505
FURNISH STEEL PILING (HP 250 X 85)	490511
FURNISH STEEL PILING (HP 360 X 132)	490566
FURNISH STRUCTURAL STEEL (BRIDGE)	550203
G	
GABION	722020
GEOCOMPOSITE DRAIN	681132
GEOSYNTHETIC PAVEMENT INTERLAYER	393003
GEOSYNTHETIC REINFORCEMENT	198250
GRATED LINE DRAIN	703233
GRIND EXISTING CONCRETE PAVEMENT	420201
GROOVE EXISTING CONCRETE PAVEMENT	420102
GUARD RAILING DELINEATOR	820118
H	
HANDRAILING	839514
HEADED BAR REINFORCEMENT	520120
HEALTH AND SAFETY PLAN	074018
HEAVY BLAST TEXTURE	511046
HIGHWAY ADVISORY RADIO SYSTEM	860520
HIGHWAY LIGHTING	860403
HIGHWAY PLANTING	200001
HORIZONTAL DRAIN CONNECTOR UNIT	681510
HOT MIX ASPHALT	390130
HOT MIX ASPHALT	390131
HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	390141
HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	390142
HOT MIX ASPHALT (BONDED WEARING COURSE-OPEN GRADED)	390158
HOT MIX ASPHALT (LEVELING)	390135
HOT MIX ASPHALT (OPEN GRADED)	390134
HOT MIX ASPHALT (TYPE A)	390132

ITEM DESCRIPTION	ITEM CODE
H	
HOT MIX ASPHALT (TYPE B)	390133
I	
IMPERMEABLE MEMBRANE	682007
IMPORTED BORROW	198001
IMPORTED MATERIAL (SHOULDER BACKING)	198007
IMPORTED ROCKY MATERIAL	198021
IMPORTED TOPSOIL	200101
INDUCTIVE LOOP DETECTOR	860810
INLET FRAME AND GRATE	750030
INLET GRATE	750050
INSTALL MEDIAN MILEAGE PANEL	820180
INSTALL ROADSIDE SIGN (LAMINATED WOOD BOX POST)	568023
INSTALL ROADSIDE SIGN PANEL ON EXISTING POST	568017
INSTALL SIGN (MAST-ARM HANGER METHOD)	568015
INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	568001
INSTALL SIGN OVERLAY	568007
INSTALL SIGN PANEL ON EXISTING FRAME	568016
INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	560204
INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY)	560224
INSTALL SIGN STRUCTURE (LIGHTWEIGHT)	560214
INSTALL SIGN STRUCTURE (TRUSS)	560219
INSTALL SIGN STRUCTURE (TUBULAR)	560209
INSTALL STUD CONNECTORS	515010
INTERCONNECTION CONDUIT AND CABLE	860703
INTERCONNECTION CONDUIT AND CONDUCTOR	860701
IRON SULFATE	202003
IRRIGATION CONTROLLER (BATTERY)	206929
IRRIGATION CONTROLLER ENCLOSURE CABINET	208301
IRRIGATION SLEEVE	208310
IRRIGATION SYSTEM	208000

ITEM DESCRIPTION	ITEM CODE
I	
ISOLATION CASING	750041
J	
JACKED 12" WELDED STEEL PIPE (.250" THICK)	704133
JACKED 18" REINFORCED CONCRETE PIPE (CLASS III)	655311
JACKED 24" REINFORCED CONCRETE PIPE (CLASS II)	655212
JACKED 24" REINFORCED CONCRETE PIPE (CLASS V)	655516
JACKED 24" WELDED STEEL PIPE (.250" THICK)	704175
JACKED 30" WELDED STEEL PIPE (.239" THICK)	704196
JACKED 450 MM REINFORCED CONCRETE PIPE (CLASS III)	655365
JACKED 48" REINFORCED CONCRETE PIPE (CLASS IV)	655432
JACKED 600 MM REINFORCED CONCRETE PIPE (CLASS II)	655256
JACKED 600 MM REINFORCED CONCRETE PIPE (CLASS V)	655574
JACKED 750 MM REINFORCED CONCRETE PIPE (CLASS II)	655257
JOINT SEAL (ASPHALTIC PLUG)	519133
JOINT SEAL (MR 1 1/2")	519091
JOINT SEAL (MR 1")	519088
JOINT SEAL (MR 1/2")	519081
JOINT SEAL (MR 15 MM)	519120
JOINT SEAL (MR 2")	519100
JOINT SEAL (MR 30 MM)	519117
JOINT SEAL (MR 40 MM)	519142
JOINT SEAL (MR 50 MM)	519144
JOINT SEAL (TYPE AL)	519102
JOINT SEAL ASSEMBLY (MR 100 MM)	519128
JOINT SEAL ASSEMBLY (MR 101 MM - 160 MM)	519129
JOINT SEAL ASSEMBLY (MR 161 MM - 240 MM)	519130
JOINT SEAL ASSEMBLY (MR 2 1/2")	519092
JOINT SEAL ASSEMBLY (MR 241 MM - 320 MM)	519131
JOINT SEAL ASSEMBLY (MR 3 1/2")	519094

ITEM DESCRIPTION	ITEM CODE
J	
JOINT SEAL ASSEMBLY (MR 3")	519093
JOINT SEAL ASSEMBLY (MR 321 MM - 400 MM)	519132
JOINT SEAL ASSEMBLY (MR 4")	519095
JOINT SEAL ASSEMBLY (MR 60 MM)	519124
JOINT SEAL ASSEMBLY (MR 70 MM)	519125
JOINT SEAL ASSEMBLY (MR 80 MM)	519126
JOINT SEAL ASSEMBLY (MR 90 MM)	519127
JOINTED PLAIN CONCRETE PAVEMENT	401050
JUTE MESH	203561
L	
LEAD COMPLIANCE PLAN	190110
LEAN CONCRETE BACKFILL	193119
LEAN CONCRETE BASE	280000
LIGHTING	860401
LIGHTING (CITY STREET)	860402
LIGHTING (PARKING LOT)	860407
LIGHTING (STAGE CONSTRUCTION)	860415
LIGHTING (TEMPORARY)	860400
LIGHTING (TUNNEL)	860420
LIGHTING AND SIGN ILLUMINATION	860460
LIGHTING AND SIGN ILLUMINATION (LOCATION 1)	860551
LIGHTING AND SIGN ILLUMINATION (LOCATION 2)	860552
LIGHTING AND SIGN ILLUMINATION (LOCATION 3)	860553
LIGHTWEIGHT CONCRETE	511001
LIME	240100
LIQUID ASPHALT (PRIME COAT)	395000
LIQUID ASPHALT, MC-70 (PRIME COAT)	395501
M	
MAINTAIN EXISTING IRRIGATION FACILITIES	206401
MAINTAIN EXISTING PLANTED AREAS	204096

ITEM DESCRIPTION	ITEM CODE
M	
MAINTAIN EXISTING PLANTS	204098
MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	860090
MAINTENANCE VEHICLE PULLOUT	209801
MANHOLE (TYPE A)	719305
MANHOLE FRAME AND COVER	750010
MARKER	820101
MARKER (CULVERT)	820112
MASONRY BLOCK WALL	518201
METAL (BARRIER MOUNTED SIGN)	562002
METAL (RAIL MOUNTED SIGN)	562004
METAL (ROADSIDE SIGN)	562001
METAL BEAM GUARD RAILING	832001
METAL BEAM GUARD RAILING (7' WOOD POST)	832012
METAL BEAM GUARD RAILING (SPECIAL)	832004
METAL BEAM GUARD RAILING (STEEL POST)	832002
METAL BEAM GUARD RAILING (WOOD POST)	832003
METAL GATE	801340
METAL TUBE BRIDGE RAILING	833092
MICRO-SURFACING	378000
MICROWAVE VEHICLE DETECTION SYSTEM	860812
MILEPOST MARKER	820110
MINOR CONCRETE	510501
MINOR CONCRETE (BACKFILL)	510526
MINOR CONCRETE (BACKFILL)	719589
MINOR CONCRETE (BRUSHED CONCRETE)	731518
MINOR CONCRETE (CHANNEL LINING)	727905
MINOR CONCRETE (COBBLESTONE TEXTURED PAVING)	731524
MINOR CONCRETE (CONCRETE MOW STRIP)	731509
MINOR CONCRETE (CURB AND CURB RAMP)	731626
MINOR CONCRETE (CURB AND GUTTER)	731504

ITEM DESCRIPTION	ITEM CODE
M	
MINOR CONCRETE (CURB AND SIDEWALK)	731505
MINOR CONCRETE (CURB RAMP)	731623
MINOR CONCRETE (CURB)	731501
MINOR CONCRETE (CURB, GUTTER, SIDEWALK AND DRIVEWAY)	731510
MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP)	731627
MINOR CONCRETE (DITCH LINING)	727901
MINOR CONCRETE (DRIVEWAY)	731516
MINOR CONCRETE (EXPOSED AGGREGATE SIDEWALK)	731512
MINOR CONCRETE (GUTTER DEPRESSION)	731507
MINOR CONCRETE (GUTTER LINING)	727906
MINOR CONCRETE (GUTTER)	731517
MINOR CONCRETE (INVERT PAVING)	510510
MINOR CONCRETE (ISLAND PAVING)	731511
MINOR CONCRETE (MINOR STRUCTURE)	510502
MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	731502
MINOR CONCRETE (PIPE ENCASEMENT)	719569
MINOR CONCRETE (SIDEWALK)	731521
MINOR CONCRETE (SLOPE PROTECTION)	727902
MINOR CONCRETE (SOUND WALL)	510524
MINOR CONCRETE (STAMPED CONCRETE)	731519
MINOR CONCRETE (TEXTURED PAVING)	731530
MINOR HOT MIX ASPHALT	390136
MISCELLANEOUS IRON AND STEEL	750001
MISCELLANEOUS IRON AND STEEL (SEWER SYSTEM)	750002
MISCELLANEOUS METAL (BRIDGE)	750501
MISCELLANEOUS METAL (RESTRAINER - BAR TYPE)	750497
MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE)	750498
MISCELLANEOUS METAL (RESTRAINER - PIPE TYPE)	750496
MOBILIZATION	999990
MOBILIZATION, DEMOBILIZATION, AND FINAL CLEANUP	760090

ITEM DESCRIPTION	ITEM CODE
M	
MODIFY CONCRETE BARRIER	159110
MODIFY DRAINAGE FACILITY	152600
MODIFY ELECTRICAL EQUIPMENT	152594
MODIFY FLASHING BEACON	860615
MODIFY INLET	152604
MODIFY INLET TO MANHOLE	152609
MODIFY LIGHTING	861503
MODIFY LIGHTING AND SIGN ILLUMINATION	861504
MODIFY MANHOLE	152610
MODIFY METAL BEAM GUARD RAILING	152632
MODIFY RAMP METERING SYSTEM	861088
MODIFY SIGN ILLUMINATION	860508
MODIFY SIGNAL	861502
MODIFY SIGNAL (LOCATION 1)	861491
MODIFY SIGNAL (LOCATION 2)	861492
MODIFY SIGNAL (LOCATION 3)	861493
MODIFY SIGNAL (LOCATION 4)	861494
MODIFY SIGNAL (LOCATION 5)	861495
MODIFY SIGNAL AND LIGHTING	861501
MODIFY SIGNAL AND LIGHTING (LOCATION 1)	861497
MODIFY SIGNAL AND LIGHTING (LOCATION 2)	861498
MODIFY SIGNAL AND LIGHTING (LOCATION 3)	861499
MODIFY SIGNAL AND LIGHTING (LOCATION 4)	861500
MODIFY SIGNAL AND LIGHTING (LOCATION 5)	861505
MODIFY SIGNAL AND LIGHTING (LOCATION 6)	861506
MODIFY SIGNAL AND LIGHTING (LOCATION 7)	861507
MODIFY SIGNAL AND LIGHTING (LOCATION 8)	861508
MODIFY SIGNAL AND LIGHTING (LOCATION 9)	861509
MODIFY TRAFFIC MONITORING STATION	860889
MODIFY TRAFFIC MONITORING STATION (COUNT)	860890

ITEM DESCRIPTION	ITEM CODE
M	
MOVE-IN/MOVE-OUT (EROSION CONTROL)	203026
MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)	074037
MULCH	202011
N	
NO. 5 PULL BOX	869035
NOISE MONITORING	148005
NPS 2 SUPPLY LINE (BRIDGE)	208036
NPS 3 SUPPLY LINE (BRIDGE)	208038
O	
OBJECT MARKER	820130
OBJECT MARKER (TYPE K)	820131
OBJECT MARKER (TYPE K-1)	820141
OBJECT MARKER (TYPE K-2)	820143
OBJECT MARKER (TYPE L)	820132
OBJECT MARKER (TYPE L-1)	820151
OBJECT MARKER (TYPE L-2)	820152
OBJECT MARKER (TYPE N)	820133
OBJECT MARKER (TYPE P)	820134
OBJECT MARKER (TYPE R)	820135
OBLITERATE SURFACING	150305
P	
PAINT CONCRETE SURFACES	590280
PAINT CURB (2-COAT)	597401
PAINT PAVEMENT MARKING	840660
PAINT PAVEMENT MARKING (2-COAT)	840666
PAINT STRUCTURAL STEEL (EXISTING BRIDGE)	590111
PAINT TRAFFIC STRIPE	840653
PAINT TRAFFIC STRIPE (1-COAT)	840655
PAINT TRAFFIC STRIPE (2-COAT)	840656
PAINTED STALL LINES AND PAVEMENT MARKINGS	840651

ITEM DESCRIPTION	ITEM CODE
P	
PAINTED TRAFFIC STRIPE	840600
PARKING BUMPER (PRECAST CONCRETE)	842000
PAVEMENT MARKER (NON-REFLECTIVE)	850101
PAVEMENT MARKER (REFLECTIVE)	850102
PAVEMENT MARKER (REFLECTIVE-RECESSED)	850120
PAVEMENT MARKER (REFLECTIVE-SPECIAL TYPE H)	850104
PAVEMENT MARKER (RETROREFLECTIVE)	850111
PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	850122
PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE G)	850112
PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE H)	850113
PAVEMENT REINFORCING FABRIC	393001
PAVEMENT TRANSITION TAPER	416101
PAVING ASPHALT (BINDER, GEOSYNTHETIC PAVEMENT INTERLAYER)	391007
PAVING ASPHALT (BINDER-PAVEMENT REINFORCING FABRIC)	391005
PAVING ASPHALT (PAINT BINDER)	391003
PAVING NOTCH EXTENSION	510800
PEDESTRIAN BARRICADE	833077
PERMEABLE MATERIAL	682001
PERMEABLE MATERIAL (BLANKET)	682008
PERVIOUS BACKFILL MATERIAL	193030
PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	193031
PICNIC TABLE WITH BENCHES	994420
PIPE HANDRAILING	833085
PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	394002
PLACE ASPHALT CONCRETE DIKE (TYPE A)	394040
PLACE ASPHALT CONCRETE DIKE (TYPE C)	394044
PLACE ASPHALT CONCRETE DIKE (TYPE D)	394046
PLACE ASPHALT CONCRETE DIKE (TYPE E)	394048
PLACE ASPHALT CONCRETE DIKE (TYPE F)	394049
PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	394090

ITEM DESCRIPTION	ITEM CODE
P	
PLACE HOT MIX ASPHALT DIKE	394071
PLACE HOT MIX ASPHALT DIKE (TYPE A)	394073
PLACE HOT MIX ASPHALT DIKE (TYPE C)	394074
PLACE HOT MIX ASPHALT DIKE (TYPE D)	394075
PLACE HOT MIX ASPHALT DIKE (TYPE E)	394076
PLACE HOT MIX ASPHALT DIKE (TYPE F)	394077
PLACE POLYESTER CONCRETE OVERLAY	515042
PLANT (GROUP A)	204001
PLANT (GROUP A)	204035
PLANT (GROUP B)	204002
PLANT (GROUP B)	204036
PLANT (GROUP E)	204005
PLANT (GROUP F)	204006
PLANT (GROUP G)	204007
PLANT (GROUP H)	204008
PLANT (GROUP I)	204009
PLANT (GROUP K)	204011
PLANT (GROUP M)	204013
PLANT (GROUP O)	204010
PLANT (GROUP S)	204015
PLANT (GROUP U)	204021
PLANT (GROUP U)	204038
PLANT (GROUP W)	204017
PLANT (GROUP Z)	204022
PLANT ESTABLISHMENT WORK	204099
PLASTIC PIPE LINER	152659
PLASTIC PIPE LINER (21.50" O.D.)	152664
PLUG PIPE	155002
PORTABLE CHANGEABLE MESSAGE SIGN	128650
PORTABLE DELINEATOR	120182
PORTLAND CEMENT CONCRETE BASE	405030
POWER AND TELEPHONE SERVICE	869070

ITEM DESCRIPTION	ITEM CODE
P	
PREPARE AND PAINT CONCRETE	597600
PREPARE AND STAIN CONCRETE	597601
PREPARE CONCRETE BRIDGE DECK SURFACE	153225
PREPARE HOLE	200110
PREPARE HOLE (SOIL AMENDMENT)	200108
PREPARE STORM WATER POLLUTION PREVENTION PLAN	074019
PREPARE WATER POLLUTION CONTROL PROGRAM	074017
PRESTRESSING	500010
PRESTRESSING CAST-IN-PLACE CONCRETE	500001
PROGRESS SCHEDULE (CRITICAL PATH METHOD)	070012
PROGRESS SCHEDULE (CRITICAL PATH)	070010
PRUNE EXISTING PLANTS	200052
PTFE BEARING	518050
PTFE SPHERICAL BEARING	518051
PULL BOX	869040
PUMPING PLANT ELECTRICAL EQUIPMENT	741001
PUMPING PLANT METAL WORK	750520
Q	
QUICK COUPLING VALVE	208649
R	
RAIL TENSIONING ASSEMBLY	839561
RAMP METERING SYSTEM	861100
RAMP METERING SYSTEM (LOCATION 1)	861101
RAMP METERING SYSTEM (LOCATION 2)	861102
RAMP METERING SYSTEM (LOCATION 3)	861103
RAMP METERING SYSTEM (LOCATION 4)	861104
RAPID SETTING CONCRETE (PATCH)	511124
REAMING WATER WELL	760022
RECONSTRUCT CHAIN LINK FENCE	151540
RECONSTRUCT CHAIN LINK RAILING	151538

ITEM DESCRIPTION	ITEM CODE
R	
RECONSTRUCT DOUBLE THRIE BEAM BARRIER	151570
RECONSTRUCT FENCE (TYPE BW)	151536
RECONSTRUCT FENCE (TYPE WM)	151537
RECONSTRUCT INLET	151512
RECONSTRUCT METAL BEAM GUARD RAILING	151572
RECONSTRUCT METAL BEAM GUARD RAILING (2.1 M POST)	151624
RECONSTRUCT METAL BEAM GUARD RAILING (7' POST)	151623
RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST)	151625
RECONSTRUCT METAL RAILING (BRIDGE)	159010
RECONSTRUCT WOOD FENCE	151534
RECYCLED WATER WARNING SIGNS	209202
REFINISH BRIDGE DECK	515020
REINFORCED CONCRETE CRIB WALL (TYPE A)	513601
REINFORCED CONCRETE CRIB WALL (TYPE B)	513602
REINFORCED CONCRETE CRIB WALL (TYPE C)	513603
REINFORCED CONCRETE CRIB WALL (TYPE D)	513604
RELAY CONCRETE FLARED END SECTION	152045
RELAY ENTRANCE TAPER	152039
RELOCATE CONCRETE BARRIER (TYPE K)	152372
RELOCATE CRASH CUSHION	152388
RELOCATE FENCE	152379
RELOCATE FLASHING BEACON	861303
RELOCATE GATE	152381
RELOCATE HYDRANT	152351
RELOCATE MAILBOX	152370
RELOCATE ROADSIDE SIGN	152390
RELOCATE ROADSIDE SIGN (METAL POST)	152391
RELOCATE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)	152393
RELOCATE ROADSIDE SIGN (WOOD POST)	152392
RELOCATE ROADSIDE SIGN-ONE POST	152386

ITEM DESCRIPTION	ITEM CODE
R	
RELOCATE ROADSIDE SIGN-TWO POST	152387
RELOCATE SIGN PANEL	152396
RELOCATE SIGN STRUCTURE	152394
REMODEL INLET	152703
REMOVABLE BARRIER POST	839522
REMOVE ASPHALT CONCRETE	150769
REMOVE ASPHALT CONCRETE DIKE	150771
REMOVE ASPHALT CONCRETE OVERSIDE DRAIN	150859
REMOVE ASPHALT CONCRETE SURFACING	150857
REMOVE BARRICADE	150645
REMOVE BARRIER RAILING	156577
REMOVE BASE AND SURFACING	150860
REMOVE BOX CULVERT	156535
REMOVE BRIDGE MOUNTED SIGN	150767
REMOVE BRIDGE RAILING	156579
REMOVE CABLE RAILING	150676
REMOVE CATCH BASIN	150827
REMOVE CHAIN LINK FENCE	150608
REMOVE CHANNELIZERS	150730
REMOVE CONCRETE	153210
REMOVE CONCRETE (CHANNEL)	153220
REMOVE CONCRETE (CURB AND GUTTER)	153215
REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK)	153239
REMOVE CONCRETE (MISCELLANEOUS)	153246
REMOVE CONCRETE (STRUCTURE)	153213
REMOVE CONCRETE BARRIER	153221
REMOVE CONCRETE BARRIER (TYPE 50)	153230
REMOVE CONCRETE BARRIER (TYPE K)	153229
REMOVE CONCRETE CURB	153214
REMOVE CONCRETE CURB AND SIDEWALK	153216
REMOVE CONCRETE DECK SURFACE	150870
REMOVE CONCRETE FLARED END SECTION	153219

ITEM DESCRIPTION	ITEM CODE
R	
REMOVE CONCRETE ISLAND (PORTIONS)	153222
REMOVE CONCRETE PAVEMENT	150846
REMOVE CONCRETE PAVEMENT AND BASE	150847
REMOVE CONCRETE SIDEWALK	153218
REMOVE CONCRETE SIDEWALK AND DRIVEWAY	153211
REMOVE CONTRAST TREATMENT	150720
REMOVE CRASH CUSHION	156585
REMOVE CRASH CUSHION (SAND FILLED)	156590
REMOVE CULVERT	150805
REMOVE CURB	150772
REMOVE DELINEATOR	151224
REMOVE DOUBLE METAL BEAM BARRIER	150667
REMOVE DOWNDRAIN	150823
REMOVE DRAINAGE FACILITY	150804
REMOVE ENTRANCE TAPER	150615
REMOVE EXISTING SIGNAL SYSTEM	861349
REMOVE FENCE	150605
REMOVE FENCE (TYPE BW)	150606
REMOVE FENCE (TYPE WM)	150607
REMOVE FLARED END SECTION	150668
REMOVE GATE	150620
REMOVE GUTTER DRAIN	150780
REMOVE HEADWALL	150821
REMOVE INLET	150820
REMOVE IRRIGATION FACILITY	150685
REMOVE IRRIGATION SYSTEM	150686
REMOVE JUNCTION BOX	150828
REMOVE LIGHTING STANDARD	868007
REMOVE MANHOLE	150826
REMOVE MARKER	150630
REMOVE METAL BEAM BARRIER	150666
REMOVE METAL BEAM GUARD RAILING	150662

ITEM DESCRIPTION	ITEM CODE
R	
REMOVE METAL POST	150749
REMOVE METAL RAILING	156576
REMOVE OVERSIDE DRAIN	150801
REMOVE PAINTED PAVEMENT MARKING	150712
REMOVE PAINTED TRAFFIC STRIPE	150711
REMOVE PAVEMENT	150855
REMOVE PAVEMENT MARKER	150722
REMOVE PAVEMENT MARKING	150713
REMOVE PIPE	150806
REMOVE RAILING	156572
REMOVE REINFORCED CONCRETE BOX CULVERT	150825
REMOVE RETAINING WALL	150829
REMOVE RETAINING WALL (PORTION)	150830
REMOVE ROADSIDE SIGN	150742
REMOVE ROADSIDE SIGN (METAL POST)	150745
REMOVE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)	150747
REMOVE ROADSIDE SIGN (WOOD POST)	150744
REMOVE ROADSIDE SIGN MOUNTED ON MAST ARM	150741
REMOVE ROADSIDE SIGN PANEL	150748
REMOVE SEWER MANHOLE	150824
REMOVE SEWER PIPE	150841
REMOVE SIGN OVERLAY	150764
REMOVE SIGN PANEL	150763
REMOVE SIGN STRUCTURE	150760
REMOVE SOUND WALL	153250
REMOVE TERMINAL SECTION	150659
REMOVE THERMOPLASTIC PAVEMENT MARKING	150715
REMOVE THERMOPLASTIC TRAFFIC STRIPE	150714
REMOVE THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING	150718
REMOVE TRAFFIC STRIPE	150710
REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING	150717

ITEM DESCRIPTION	ITEM CODE
R	
REMOVE TREE	160120
REMOVE TREE STUMP	160121
REMOVE UNSOUND CONCRETE	153223
REMOVE UNSUITABLE MATERIAL	190167
REMOVE WOOD FENCE	150604
REMOVE YELLOW PAINTED PAVEMENT MARKING	150702
REMOVE YELLOW PAINTED TRAFFIC STRIPE	150701
REMOVE YELLOW PAINTED TRAFFIC STRIPE (HAZARDOUS WASTE)	141101
REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING	150705
REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING (HAZARDOUS WASTE)	141104
REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	150704
REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	141103
REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING	150706
REPAIR SPALLED JOINTS	413111
REPAIR SPALLED SURFACE AREA	515028
REPLACE ASPHALT CONCRETE SURFACING	390095
REPLACE BEARING PAD	518040
REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	401108
REPLACE PULL BOX	862065
REPLACE VALVE BOX COVER	208565
RESET GATE	152291
RESET MAILBOX	152255
RESET MARKER	152301
RESET MARKERS AND DELINEATORS	152303
RESET MILEPOST MARKER	152299
RESET ROADSIDE SIGN	152320
RESET ROADSIDE SIGN (ONE POST)	152316
RESET ROADSIDE SIGN (TWO POST)	152317
RESET ROADSIDE SIGN (WOOD POST)	152322
RESET TEMPORARY RAILING (TYPE K)	158210

ITEM DESCRIPTION	ITEM CODE
R	
RETAINING WALL STEM (TYPE 6)	513551
RETURN CAP	839571
RETURN CAP (TYPE TA)	839572
ROADSIDE CLEARING	200002
ROADSIDE PAVING (MISCELLANEOUS AREAS)	394095
ROADSIDE SIGN - ONE POST	566011
ROADSIDE SIGN - TWO POST	566012
ROADWAY EXCAVATION	190101
ROADWAY EXCAVATION (DETOUR REMOVAL)	190138
ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS)	190109
ROADWAY EXCAVATION (SLIDE REMOVAL)	190130
ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	190107
ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	190108
ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	190105
ROADWAY EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD)	190106
ROADWAY EXCAVATION (UNSUITABLE MATERIAL)	190139
ROCK BLANKET	200114
ROCK SLOPE PROTECTION (1 TON, METHOD A)	720104
ROCK SLOPE PROTECTION (1 TON, METHOD B)	721004
ROCK SLOPE PROTECTION (1/2 TON, METHOD A)	720106
ROCK SLOPE PROTECTION (1/2 TON, METHOD B)	721006
ROCK SLOPE PROTECTION (1/2T, METHOD A)	720120
ROCK SLOPE PROTECTION (1/2T, METHOD B)	721023
ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	721007
ROCK SLOPE PROTECTION (1/4T, METHOD B)	721024
ROCK SLOPE PROTECTION (1T, METHOD A)	720119
ROCK SLOPE PROTECTION (1T, METHOD B)	721022
ROCK SLOPE PROTECTION (2 TON, METHOD A)	720103
ROCK SLOPE PROTECTION (2T, METHOD A)	720118

ITEM DESCRIPTION	ITEM CODE
R	
ROCK SLOPE PROTECTION (2T, METHOD B)	721025
ROCK SLOPE PROTECTION (4T, METHOD A)	720117
ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B)	721010
ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	721011
ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B)	721012
ROCK SLOPE PROTECTION (FACING, METHOD B)	721009
ROCK SLOPE PROTECTION (LIGHT, METHOD B)	721008
ROCK SLOPE PROTECTION FABRIC	729010
ROLLED EROSION CONTROL PRODUCT (NETTING)	203034
ROOT PROTECTOR	205061
RUBBERIZED ASPHALT CONCRETE (TYPE G)	390126
RUBBERIZED ASPHALT CONCRETE (TYPE O)	390127
RUBBERIZED HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	390156
RUBBERIZED HOT MIX ASPHALT (BONDED WEARING COURSE-OPEN GRADED)	390159
RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	390137
RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	390140
RUBBERIZED HOT MIX ASPHALT (OPEN GRADED HIGH BINDER)	390139
RUBBERIZED HOT MIX ASPHALT (OPEN GRADED)	390138
RUMBLE STRIP	394050
S	
SALVAGE CONCRETE BARRIER (TYPE K)	151274
SALVAGE CRASH CUSHION MODULES	158101
SALVAGE DOUBLE THRIE BEAM BARRIER	151266
SALVAGE METAL BEAM GUARD RAILING	151272
SALVAGE METAL BRIDGE RAILING	151270
SALVAGE SINGLE THRIE BEAM BARRIER	151265
SAMPLING AND ANALYSIS PLAN (NATURALLY OCCURRING ASBESTOS)	190117
SAND BACKFILL	193114
SAND BEDDING	192502

ITEM DESCRIPTION	ITEM CODE
S	
SAND COVER	365001
SCREENINGS (COARSE)	375023
SCREENINGS (HOT-APPLIED)	375030
SCREENINGS (MEDIUM FINE)	375021
SCREENINGS (MEDIUM)	375022
SEAL COURSE CONCRETE	510000
SEAL JOINT (EXISTING CONCRETE PAVEMENT)	413115
SEAL LONGITUDINAL ISOLATION JOINT	404094
SEAL LONGITUDINAL JOINT	414091
SEAL PAVEMENT JOINT	404092
SEAL RANDOM CRACKS	374206
SEEDING	204051
SEISMIC MONITORING SYSTEM	869072
SEWER MANHOLE	719200
SEWER MANHOLE FRAME AND COVER	719190
SEWER TERMINAL CLEANOUT	719110
SHEET PILING	490380
SHOTCRETE	530100
SHOULDER BACKING	190185
SHOULDER RUMBLE STRIP (AC, GROUND-IN INDENTATIONS)	394054
SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	394053
SHOULDER RUMBLE STRIP (HMA,ROLLED-IN INDENTATIONS)	394051
SHOULDER RUMBLE STRIP (PCC, GROUND-IN INDENTATIONS)	401082
SIGN ILLUMINATION	860501
SIGNAL AND LIGHTING	860201
SIGNAL AND LIGHTING	860301
SIGNAL AND LIGHTING (CITY STREET LOCATION 3)	860303
SIGNAL AND LIGHTING (CITY STREET LOCATION 5)	860305
SIGNAL AND LIGHTING (CITY STREET LOCATION 6)	860306
SIGNAL AND LIGHTING (CITY)	860297
SIGNAL AND LIGHTING (LOCATION 1)	860251

ITEM DESCRIPTION	ITEM CODE
S	
SIGNAL AND LIGHTING (LOCATION 2)	860252
SIGNAL AND LIGHTING (LOCATION 3)	860253
SIGNAL AND LIGHTING (LOCATION 4)	860254
SIGNAL AND LIGHTING (LOCATION 5)	860255
SIGNAL AND LIGHTING (LOCATION 6)	860256
SIGNAL AND LIGHTING (LOCATION 7)	860257
SIGNAL AND LIGHTING (LOCATION 8)	860258
SIGNAL AND LIGHTING (LOCATION 9)	860259
SIGNAL AND LIGHTING (STAGE CONSTRUCTION)	860298
SIGNAL AND LIGHTING (TEMPORARY LOCATION 1)	860151
SIGNAL AND LIGHTING (TEMPORARY)	860150
SINGLE THRIE BEAM BARRIER	839301
SINGLE THRIE BEAM BARRIER (STEEL POST)	839303
SIZE 53 CONDUIT	860764
SLOPE PAVING (CONCRETE)	721810
SLURRY SEAL	377501
SMALL BUSINESS UTILIZATION REPORT	070013
SNOWPLOW DEFLECTOR	519078
SOIL AMENDMENT	202006
SOIL NAIL ASSEMBLY	197060
SOUND WALL (BARRIER) (MASONRY BLOCK)	517961
SOUND WALL (MASONRY BLOCK)	518002
SPLICE VAULT	869047
SPOT BLAST CLEAN AND PAINT UNDERCOAT	590135
SPOT BLAST CLEAN AND PAINT UNDERCOAT (LOCATION A)	590136
SPOT BLAST CLEAN AND PAINT UNDERCOAT (LOCATION B)	590137
SPRINKLER (TYPE A-1)	208461
SPRINKLER (TYPE A-5)	208465
SPRINKLER (TYPE A-6)	208466
SPRINKLER (TYPE A-7)	208467
SPRINKLER (TYPE A-8)	208468

ITEM DESCRIPTION	ITEM CODE
S	
SPRINKLER (TYPE B-1)	208471
SPRINKLER (TYPE B-2)	208472
SPRINKLER (TYPE B-4)	208474
SPRINKLER (TYPE B-6)	208476
SPRINKLER (TYPE C-1)	208481
SPRINKLER (TYPE C-2 MOD)	208480
SPRINKLER (TYPE C-2)	208482
SPRINKLER (TYPE D-1)	208526
SPRINKLER CONTROL CONDUIT (BRIDGE)	860796
STEEL COVER	750005
STEEL FLARED END SECTION	705001
STREET SWEEPING	074041
STRUCTURAL CONCRETE	510050
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ)	510085
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N MODIFIED)	510088
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	510086
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	510087
STRUCTURAL CONCRETE, BARRIER SLAB	510072
STRUCTURAL CONCRETE, BRIDGE	510053
STRUCTURAL CONCRETE, BRIDGE FOOTING	510051
STRUCTURAL CONCRETE, RETAINING WALL	510060
STRUCTURAL STEEL (BRIDGE)	550102
STRUCTURE BACKFILL	193001
STRUCTURE BACKFILL (BRIDGE)	193003
STRUCTURE BACKFILL (CRIB WALL)	193012
STRUCTURE BACKFILL (CULVERT)	193004
STRUCTURE BACKFILL (PUMPING PLANT)	192027
STRUCTURE BACKFILL (RETAINING WALL)	193013
STRUCTURE BACKFILL (SLURRY CEMENT)	193006
STRUCTURE BACKFILL (SOIL NAIL WALL)	193028
STRUCTURE BACKFILL (SOLDIER PILE WALL)	193029

ITEM DESCRIPTION	ITEM CODE
S	
STRUCTURE BACKFILL (SOUND WALL)	193014
STRUCTURE BACKFILL (TIEBACK WALL)	193026
STRUCTURE CONCRETE (PUMPING PLANT)	510069
STRUCTURE EXCAVATION	192001
STRUCTURE EXCAVATION (BRIDGE)	192003
STRUCTURE EXCAVATION (CRIB WALL)	192036
STRUCTURE EXCAVATION (NATURALLY OCCURRING ASBESTOS)	192009
STRUCTURE EXCAVATION (PUMPING PLANT)	192026
STRUCTURE EXCAVATION (RETAINING WALL)	192037
STRUCTURE EXCAVATION (ROCK SLOPE PROTECTION)	192032
STRUCTURE EXCAVATION (ROCK)	192035
STRUCTURE EXCAVATION (SOIL NAIL WALL)	192055
STRUCTURE EXCAVATION (SOLDIER PILE WALL)	192049
STRUCTURE EXCAVATION (SOUND WALL)	192038
STRUCTURE EXCAVATION (TIEBACK WALL)	192050
STRUCTURE EXCAVATION (TYPE A)	192008
STRUCTURE EXCAVATION (TYPE D)	192020
STRUCTURE EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	192057
STRUCTURE EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	192058
STRUCTURE EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	192053
STRUCTURE EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD)	192054
SUBGRADE ENHANCEMENT FABRIC	198200
SUBGRADE ENHANCEMENT GEOTEXTILE	198205
SURVEY MONUMENT	810110
SURVEY MONUMENT (TYPE A)	810111
SURVEY MONUMENT (TYPE B)	810112
SURVEY MONUMENT (TYPE D)	810116
SYSTEM TESTING AND DOCUMENTATION	869075
T	
TACK COAT	397005

ITEM DESCRIPTION	ITEM CODE
T	
TAPERED INLET	692101
TEMPORARY ACTIVE TREATMENT SYSTEM	074015
TEMPORARY CHECK DAM	074035
TEMPORARY CONCRETE WASHOUT (PORTABLE)	074042
TEMPORARY CONCRETE WASHOUT BIN	074043
TEMPORARY CONCRETE WASHOUT FACILITY	074032
TEMPORARY CONSTRUCTION ENTRANCE	074033
TEMPORARY CONSTRUCTION ROADWAY	074044
TEMPORARY COVER	074034
TEMPORARY CRASH CUSHION	129110
TEMPORARY CRASH CUSHION MODULE	129100
TEMPORARY CULVERT	073000
TEMPORARY DECK BRIDGING	072009
TEMPORARY DELINEATOR (CLASS 1)	128201
TEMPORARY DELINEATOR (CLASS 2)	128202
TEMPORARY DRAINAGE INLET PROTECTION	074038
TEMPORARY EROSION CONTROL	074023
TEMPORARY EROSION CONTROL BLANKET	074027
TEMPORARY FENCE	071301
TEMPORARY FENCE (TYPE BW)	071302
TEMPORARY FENCE (TYPE CL-1.8)	071322
TEMPORARY FENCE (TYPE CL-6)	071321
TEMPORARY FENCE (TYPE ESA)	071325
TEMPORARY FIBER ROLL	074028
TEMPORARY FLASHING BEACON	128660
TEMPORARY GRAVEL BAG BERM	074031
TEMPORARY HYDRAULIC MULCH	074051
TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	074040
TEMPORARY HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	074039
TEMPORARY LARGE SEDIMENT BARRIER	074045
TEMPORARY MARKER	120154

ITEM DESCRIPTION	ITEM CODE
T	
TEMPORARY MULCH	074026
TEMPORARY PAVEMENT MARKER	120300
TEMPORARY PAVEMENT MARKING (PAINT)	120149
TEMPORARY PAVEMENT MARKING (TAPE)	120152
TEMPORARY RAILING (TYPE K)	129000
TEMPORARY REINFORCED SILT FENCE	071324
TEMPORARY RETAINING WALL	129510
TEMPORARY SHORING	072008
TEMPORARY SIGNAL AND LIGHTING	128605
TEMPORARY SIGNAL SYSTEM	128601
TEMPORARY SILT FENCE	074029
TEMPORARY SOIL BINDER	074055
TEMPORARY SOIL STABILIZER	074025
TEMPORARY STRAW BALE BARRIER	074036
TEMPORARY SUPPORT	072006
TEMPORARY TACKED STRAW	074054
TEMPORARY TERMINAL SECTION (TYPE K)	121161
TEMPORARY TRAFFIC SCREEN	129150
TEMPORARY TRAFFIC STRIPE (PAINT)	120159
TEMPORARY TRAFFIC STRIPE (TAPE)	120151
TERMINAL ANCHOR ASSEMBLY (TYPE SFT)	839568
TERMINAL CONNECTOR (THRIE BEAM BARRIER)	839547
TERMINAL SYSTEM (TYPE CAT)	839566
TERMINAL SYSTEM (TYPE CAT) BACKUP	839567
TERMINAL SYSTEM (TYPE ET)	839559
TERMINAL SYSTEM (TYPE SKT)	839539
TERMINAL SYSTEM (TYPE SRT)	839565
TESTING WELL	760012
THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING	840519
THERMOPLASTIC PAVEMENT MARKING	840515
THERMOPLASTIC TRAFFIC STRIPE	840501
THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	840560

ITEM DESCRIPTION	ITEM CODE
T	
TIE BAR	406001
TIE BAR (DRILL AND BOND)	406003
TIEBACK ANCHOR	500050
TIMBER LAGGING	575004
TIME-RELATED OVERHEAD	070018
TRAFFIC CONE	120119
TRAFFIC CONTROL SURVEILLANCE	120102
TRAFFIC CONTROL SYSTEM	120100
TRAFFIC MONITORING STATION	860930
TRAFFIC MONITORING STATION (COUNT)	860925
TRAFFIC MONITORING STATION (LOCATION 1)	860931
TRAFFIC MONITORING STATION (LOCATION 2)	860932
TRAFFIC MONITORING STATION (LOCATION 3)	860933
TRAFFIC MONITORING STATION (LOCATION 4)	860934
TRAFFIC MONITORING STATION (LOCATION 5)	860935
TRAFFIC PLASTIC DRUM	120199
TRAINING	869080
TRANSITION RAILING (TYPE DTB)	839542
TRANSITION RAILING (TYPE STB)	839540
TRANSITION RAILING (TYPE WB)	839541
TRANSPLANT PALM TREE	204031
TRASH RECEPTACLE	994901
TREAT BRIDGE DECK	540102
TUBULAR HANDRAILING	833088
TWO-COMPONENT PAINT PAVEMENT MARKING	840661
TYPE II BARRICADE	120116
TYPE III BARRICADE	120120
U	
UNDERDRAIN MARKER	820111
V	

ITEM DESCRIPTION	ITEM CODE	ITEM DESCRIPTION	ITEM CODE
V			
VEGETATION CONTROL (MINOR CONCRETE)	832070		
W			
WATER METER	208304		
WATER POLLUTION CONTROL	074020		
WATER SUPPLY SYSTEM	760080		
WELDED STEEL PIPE CASING (BRIDGE)	703450		
WELL DEVELOPMENT	760011		
WELL SCREEN	760035		
WILD FLOWER SEEDING	204053		
WILD FLOWER SEEDING (SQYD)	204055		
WILDLIFE PASSAGE WAY (TYPE S)	833072		
WIRE MESH AND WOOD FENCE	800705		
WOOD FENCE	800701		
WORK AREA MONITORING	590301		

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
070010	PROGRESS SCHEDULE (CRITICAL PATH)	LS	12	1	1.00	$800.00	$800.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$800.00**	**$800.00**
	Item Code 070010 Total No. of Proj.			**1**		**Total Amount**	**$800.00**
070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	1	3	3.00	$6,666.67	$20,000.00
		LS	2	4	4.00	$4,509.25	$18,037.00
		LS	3	15	15.00	$3,180.00	$47,700.00
		LS	4	21	21.00	$11,363.33	$238,630.00
		LS	5	5	5.00	$6,861.20	$34,306.00
		LS	6	7	7.00	$6,177.86	$43,245.00
		LS	7	9	9.00	$7,261.11	$65,350.00
		LS	8	4	4.00	$7,437.50	$29,750.00
		LS	9	1	1.00	$2,500.00	$2,500.00
		LS	10	4	4.00	$2,500.00	$10,000.00
		LS	11	5	5.00	$13,000.00	$65,000.00
		LS	12	3	3.00	$4,850.00	$14,550.00
	Unit Sub Total	**LS**		**81**	**81.00**	**$7,272.44**	**$589,068.00**
	Item Code 070012 Total No. of Proj.			**81**		**Total Amount**	**$589,068.00**
070013	SMALL BUSINESS UTILIZATION REPORT	EA	1	32	61.00	$250.00	$15,250.00
		EA	2	33	76.00	$250.00	$19,000.00
		EA	3	39	112.00	$250.00	$28,000.00
		EA	4	56	204.00	$248.53	$50,700.00
		EA	5	27	102.00	$250.00	$25,500.00
		EA	6	39	81.00	$250.00	$20,250.00
		EA	7	44	162.00	$250.00	$40,500.00
		EA	8	44	70.00	$253.57	$17,750.00
		EA	9	8	12.00	$250.00	$3,000.00
		EA	10	34	73.00	$250.00	$18,250.00
		EA	11	24	83.00	$250.00	$20,750.00
		EA	12	27	77.00	$250.00	$19,250.00
	Unit Sub Total	**EA**		**407**	**1,113.00**	**$249.96**	**$278,200.00**
	Item Code 070013 Total No. of Proj.			**407**		**Total Amount**	**$278,200.00**
070018	TIME-RELATED OVERHEAD	LS	1	1	1.00	$810,000.00	$810,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
070018	TIME-RELATED OVERHEAD		LS	3	1	1.00	$2,340,000.00	$2,340,000.00
			LS	4	11	11.00	$2,696,363.64	$29,660,000.00
			LS	6	1	1.00	$262,500.00	$262,500.00
			LS	11	1	1.00	$150,000.00	$150,000.00
			LS	12	1	1.00	$730,000.00	$730,000.00
		Unit Sub Total	**LS**		**16**	**16.00**	**$2,122,031.25**	**$33,952,500.00**
070018	TIME-RELATED OVERHEAD		WDAY	1	2	745.00	$1,252.68	$933,250.00
			WDAY	2	3	1,600.00	$8,237.50	$13,180,000.00
			WDAY	3	10	2,160.00	$1,036.34	$2,238,500.00
			WDAY	4	6	2,870.00	$2,567.39	$7,368,420.00
			WDAY	5	4	1,860.00	$1,604.03	$2,983,500.00
			WDAY	6	5	1,660.00	$1,094.31	$1,816,550.00
			WDAY	7	9	3,885.00	$2,342.86	$9,102,000.00
			WDAY	8	5	1,825.00	$2,648.60	$4,833,700.00
			WDAY	9	1	115.00	$1,000.00	$115,000.00
			WDAY	10	4	1,370.00	$1,188.32	$1,628,000.00
			WDAY	11	4	1,925.00	$2,434.16	$4,685,750.00
			WDAY	12	2	270.00	$68.33	$18,450.00
		Unit Sub Total	**WDAY**		**55**	**20,285.00**	**$2,410.80**	**$48,903,120.00**
	Item Code 070018	**Total No. of Proj.**			**71**		**Total Amount**	**$82,855,620.00**
071301	TEMPORARY FENCE		LF	1	1	150.00	$10.00	$1,500.00
		Unit Sub Total	**LF**		**1**	**150.00**	**$10.00**	**$1,500.00**
071301	TEMPORARY FENCE		M	10	1	4,920.00	$4.00	$19,680.00
		Unit Sub Total	**M**		**1**	**4,920.00**	**$4.00**	**$19,680.00**
	Item Code 071301	**Total No. of Proj.**			**2**		**Total Amount**	**$21,180.00**
071302	TEMPORARY FENCE (TYPE BW)		M	4	1	3,670.00	$8.20	$30,094.00
			M	9	1	250.00	$10.00	$2,500.00
		Unit Sub Total	**M**		**2**	**3,920.00**	**$8.31**	**$32,594.00**
	Item Code 071302	**Total No. of Proj.**			**2**		**Total Amount**	**$32,594.00**
071321	TEMPORARY FENCE (TYPE CL-6)		LF	3	1	16,000.00	$5.00	$80,000.00
			LF	4	3	1,530.00	$4.97	$7,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
071321	TEMPORARY FENCE (TYPE CL-6)	LF	5	1	170.00	$3.32	$564.40
		LF	7	1	14,600.00	$8.69	$126,874.00
		LF	11	1	300.00	$3.60	$1,080.00
		LF	12	1	600.00	$7.30	$4,380.00
	Unit Sub Total	**LF**		**8**	**33,200.00**	**$6.64**	**$220,498.40**
	Item Code 071321 Total No. of Proj.			**8**		**Total Amount**	**$220,498.40**
071322	TEMPORARY FENCE (TYPE CL-1.8)	LF	7	1	200.00	$10.00	$2,000.00
	Unit Sub Total	**LF**		**1**	**200.00**	**$10.00**	**$2,000.00**
071322	TEMPORARY FENCE (TYPE CL-1.8)	M	3	3	1,300.00	$18.15	$23,595.00
		M	4	4	4,770.00	$24.60	$117,350.00
		M	7	2	2,601.00	$20.41	$53,085.00
		M	8	1	170.00	$22.00	$3,740.00
		M	11	1	510.00	$25.00	$12,750.00
	Unit Sub Total	**M**		**11**	**9,351.00**	**$22.51**	**$210,520.00**
	Item Code 071322 Total No. of Proj.			**12**		**Total Amount**	**$212,520.00**
071324	TEMPORARY REINFORCED SILT FENCE	LF	4	2	340.00	$3.53	$1,200.00
	Unit Sub Total	**LF**		**2**	**340.00**	**$3.53**	**$1,200.00**
	Item Code 071324 Total No. of Proj.			**2**		**Total Amount**	**$1,200.00**
071325	TEMPORARY FENCE (TYPE ESA)	LF	1	16	9,440.00	$3.79	$35,774.00
		LF	2	9	13,460.00	$2.94	$39,537.50
		LF	3	11	27,010.00	$3.06	$82,589.00
		LF	4	14	9,887.00	$4.07	$40,277.27
		LF	5	10	22,660.00	$2.61	$59,119.50
		LF	6	5	12,542.00	$3.22	$40,362.00
		LF	7	2	7,030.00	$2.40	$16,840.00
		LF	8	7	12,150.00	$3.19	$38,784.00
		LF	9	1	700.00	$2.00	$1,400.00
		LF	10	4	5,730.00	$4.07	$23,338.20
		LF	11	1	800.00	$4.00	$3,200.00
		LF	12	1	17,100.00	$4.50	$76,950.00
	Unit Sub Total	**LF**		**81**	**138,509.00**	**$3.31**	**$458,171.47**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
071325	TEMPORARY FENCE (TYPE ESA)	M	1	3	900.00	$11.39	$10,250.00
		M	2	1	2,160.00	$16.00	$34,560.00
		M	3	5	6,735.00	$7.59	$51,117.00
		M	4	10	25,803.00	$7.52	$194,062.00
		M	5	1	620.00	$15.00	$9,300.00
		M	6	3	1,170.00	$10.85	$12,700.00
		M	8	2	3,740.00	$13.29	$49,700.00
		M	9	2	1,800.00	$13.54	$24,372.00
		M	10	6	3,795.00	$7.22	$27,385.00
		M	11	3	22,399.00	$8.98	$201,044.00
	Unit Sub Total	**M**		**36**	**69,122.00**	**$8.89**	**$614,490.00**
	Item Code 071325 Total No. of Proj.			**117**		**Total Amount**	**$1,072,661.47**
072006	TEMPORARY SUPPORT	EA	10	1	22.00	$8,225.00	$180,950.00
	Unit Sub Total	**EA**		**1**	**22.00**	**$8,225.00**	**$180,950.00**
072006	TEMPORARY SUPPORT	LS	1	1	1.00	$250,000.00	$250,000.00
		LS	4	4	4.00	$78,250.00	$313,000.00
		LS	6	1	1.00	$49,000.00	$49,000.00
		LS	7	1	1.00	$27,000.00	$27,000.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$91,285.71**	**$639,000.00**
	Item Code 072006 Total No. of Proj.			**8**		**Total Amount**	**$819,950.00**
072008	TEMPORARY SHORING	M2	4	1	760.00	$137.00	$104,120.00
	Unit Sub Total	**M2**		**1**	**760.00**	**$137.00**	**$104,120.00**
072008	TEMPORARY SHORING	SQFT	4	1	1,350.00	$1.00	$1,350.00
	Unit Sub Total	**SQFT**		**1**	**1,350.00**	**$1.00**	**$1,350.00**
	Item Code 072008 Total No. of Proj.			**2**		**Total Amount**	**$105,470.00**
072009	TEMPORARY DECK BRIDGING	LS	3	1	1.00	$61,000.00	$61,000.00
		LS	4	1	1.00	$40,000.00	$40,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$50,500.00**	**$101,000.00**
	Item Code 072009 Total No. of Proj.			**2**		**Total Amount**	**$101,000.00**
073000	TEMPORARY CULVERT	LF	2	1	6.00	$350.00	$2,100.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**1**	**6.00**	**$350.00**	**$2,100.00**
	Item Code 073000	**Total No. of Proj.**			**1**		**Total Amount**	**$2,100.00**
073004	12" TEMPORARY CULVERT		LF	4	1	200.00	$65.00	$13,000.00
		Unit Sub Total	**LF**		**1**	**200.00**	**$65.00**	**$13,000.00**
	Item Code 073004	**Total No. of Proj.**			**1**		**Total Amount**	**$13,000.00**
073006	18" TEMPORARY CULVERT		LF	4	1	350.00	$25.00	$8,750.00
		Unit Sub Total	**LF**		**1**	**350.00**	**$25.00**	**$8,750.00**
	Item Code 073006	**Total No. of Proj.**			**1**		**Total Amount**	**$8,750.00**
073013	48" TEMPORARY CULVERT		LF	6	1	400.00	$95.00	$38,000.00
			LF	8	1	130.00	$120.00	$15,600.00
		Unit Sub Total	**LF**		**2**	**530.00**	**$101.13**	**$53,600.00**
	Item Code 073013	**Total No. of Proj.**			**2**		**Total Amount**	**$53,600.00**
073026	300 MM TEMPORARY CULVERT		M	3	1	18.00	$100.00	$1,800.00
			M	4	3	713.00	$91.75	$65,415.00
		Unit Sub Total	**M**		**4**	**731.00**	**$91.95**	**$67,215.00**
	Item Code 073026	**Total No. of Proj.**			**4**		**Total Amount**	**$67,215.00**
073028	450 MM TEMPORARY CULVERT		M	3	1	63.00	$200.00	$12,600.00
			M	4	3	400.00	$115.45	$46,180.00
			M	5	1	170.00	$200.00	$34,000.00
		Unit Sub Total	**M**		**5**	**633.00**	**$146.57**	**$92,780.00**
	Item Code 073028	**Total No. of Proj.**			**5**		**Total Amount**	**$92,780.00**
073029	600 MM TEMPORARY CULVERT		M	2	1	130.00	$375.00	$48,750.00
			M	4	1	3.00	$279.00	$837.00
		Unit Sub Total	**M**		**2**	**133.00**	**$372.83**	**$49,587.00**
	Item Code 073029	**Total No. of Proj.**			**2**		**Total Amount**	**$49,587.00**
073030	750 MM TEMPORARY CULVERT		M	4	1	4.00	$200.00	$800.00
		Unit Sub Total	**M**		**1**	**4.00**	**$200.00**	**$800.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 073030 Total No. of Proj.			**1**		**Total Amount**	**$800.00**
073032	1050 MM TEMPORARY CULVERT	M	2	1	3.00	$1,600.00	$4,800.00
	Unit Sub Total	**M**		**1**	**3.00**	**$1,600.00**	**$4,800.00**
	Item Code 073032 Total No. of Proj.			**1**		**Total Amount**	**$4,800.00**
073051	36" TEMPORARY INLET	EA	2	1	1.00	$2,999.00	$2,999.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$2,999.00**	**$2,999.00**
	Item Code 073051 Total No. of Proj.			**1**		**Total Amount**	**$2,999.00**
074015	TEMPORARY ACTIVE TREATMENT SYSTEM	LS	2	1	1.00	$510,000.00	$510,000.00
		LS	4	2	2.00	$11,500.00	$23,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$177,666.67**	**$533,000.00**
	Item Code 074015 Total No. of Proj.			**3**		**Total Amount**	**$533,000.00**
074016	CONSTRUCTION SITE MANAGEMENT	LS	1	46	46.00	$2,457.80	$113,059.00
		LS	2	44	44.00	$3,297.45	$145,088.00
		LS	3	61	61.00	$7,175.73	$437,719.42
		LS	4	87	87.00	$11,686.37	$1,016,714.17
		LS	5	36	36.00	$5,361.49	$193,013.62
		LS	6	60	60.00	$4,929.34	$295,760.10
		LS	7	91	91.00	$8,856.22	$805,916.26
		LS	8	66	66.00	$5,875.12	$387,757.76
		LS	9	11	11.00	$2,915.45	$32,070.00
		LS	10	40	40.00	$3,304.38	$132,175.00
		LS	11	34	34.00	$18,784.59	$638,676.08
		LS	12	37	37.00	$11,115.46	$411,272.00
	Unit Sub Total	**LS**		**613**	**613.00**	**$7,519.12**	**$4,609,221.41**
	Item Code 074016 Total No. of Proj.			**613**		**Total Amount**	**$4,609,221.41**
074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	1	33	33.00	$2,078.61	$68,594.00
		LS	2	29	29.00	$1,034.86	$30,011.00
		LS	3	44	44.00	$1,721.58	$75,749.62
		LS	4	65	65.00	$930.17	$60,461.22
		LS	5	23	23.00	$1,127.48	$25,932.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	6	45	45.00	$1,278.96	$57,553.14
		LS	7	77	77.00	$1,908.50	$146,954.81
		LS	8	44	44.00	$1,703.49	$74,953.51
		LS	9	8	8.00	$1,268.75	$10,150.00
		LS	10	27	27.00	$1,191.67	$32,175.00
		LS	11	24	24.00	$1,215.90	$29,181.70
		LS	12	30	30.00	$1,203.38	$36,101.33
	Unit Sub Total	**LS**		**449**	**449.00**	**$1,442.80**	**$647,817.33**
	Item Code 074017 Total No. of Proj.			**449**		**Total Amount**	**$647,817.33**
074018	HEALTH AND SAFETY PLAN	LS	1	1	1.00	$1,000.00	$1,000.00
		LS	3	1	1.00	$850.00	$850.00
		LS	4	6	6.00	$3,324.17	$19,945.00
		LS	8	1	1.00	$5,500.00	$5,500.00
		LS	11	2	2.00	$1,225.00	$2,450.00
		LS	12	1	1.00	$500.00	$500.00
	Unit Sub Total	**LS**		**12**	**12.00**	**$2,520.42**	**$30,245.00**
	Item Code 074018 Total No. of Proj.			**12**		**Total Amount**	**$30,245.00**
074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	1	13	13.00	$2,915.00	$37,895.00
		LS	2	15	15.00	$1,847.67	$27,715.00
		LS	3	17	17.00	$2,970.93	$50,505.80
		LS	4	22	22.00	$3,248.64	$71,470.00
		LS	5	13	13.00	$1,986.87	$25,829.35
		LS	6	15	15.00	$1,915.38	$28,730.65
		LS	7	14	14.00	$2,726.07	$38,165.00
		LS	8	22	22.00	$2,534.42	$55,757.33
		LS	9	3	3.00	$773.33	$2,320.00
		LS	10	13	13.00	$1,674.31	$21,766.00
		LS	11	10	10.00	$2,601.25	$26,012.50
		LS	12	7	7.00	$3,110.71	$21,775.00
	Unit Sub Total	**LS**		**164**	**164.00**	**$2,487.45**	**$407,941.63**
	Item Code 074019 Total No. of Proj.			**164**		**Total Amount**	**$407,941.63**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074020	WATER POLLUTION CONTROL		LS	4	1	1.00	$2,500.00	$2,500.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$2,500.00**	**$2,500.00**
	Item Code 074020	**Total No. of Proj.**			**1**		**Total Amount**	**$2,500.00**
074023	TEMPORARY EROSION CONTROL		SQYD	1	1	1,420.00	$4.20	$5,964.00
		Unit Sub Total	**SQYD**		**1**	**1,420.00**	**$4.20**	**$5,964.00**
	Item Code 074023	**Total No. of Proj.**			**1**		**Total Amount**	**$5,964.00**
074025	TEMPORARY SOIL STABILIZER		SQYD	8	1	200.00	$10.00	$2,000.00
		Unit Sub Total	**SQYD**		**1**	**200.00**	**$10.00**	**$2,000.00**
	Item Code 074025	**Total No. of Proj.**			**1**		**Total Amount**	**$2,000.00**
074026	TEMPORARY MULCH		CY	2	1	4.50	$240.00	$1,080.00
		Unit Sub Total	**CY**		**1**	**4.50**	**$240.00**	**$1,080.00**
074026	TEMPORARY MULCH		M2	10	1	3,200.00	$3.65	$11,680.00
		Unit Sub Total	**M2**		**1**	**3,200.00**	**$3.65**	**$11,680.00**
074026	TEMPORARY MULCH		SQYD	2	2	545.00	$17.65	$9,620.00
		Unit Sub Total	**SQYD**		**2**	**545.00**	**$17.65**	**$9,620.00**
	Item Code 074026	**Total No. of Proj.**			**4**		**Total Amount**	**$22,380.00**
074027	TEMPORARY EROSION CONTROL BLANKET		M2	3	1	1,700.00	$2.00	$3,400.00
			M2	7	1	9,000.00	$4.00	$36,000.00
			M2	8	1	5,130.00	$1.45	$7,438.50
		Unit Sub Total	**M2**		**3**	**15,830.00**	**$2.96**	**$46,838.50**
074027	TEMPORARY EROSION CONTROL BLANKET		SQYD	1	1	1,500.00	$3.00	$4,500.00
			SQYD	3	1	5,000.00	$2.00	$10,000.00
			SQYD	4	1	10,600.00	$3.00	$31,800.00
			SQYD	5	1	200.00	$6.25	$1,250.00
			SQYD	7	3	21,000.00	$2.11	$44,320.00
			SQYD	8	1	350.00	$10.00	$3,500.00
		Unit Sub Total	**SQYD**		**8**	**38,650.00**	**$2.47**	**$95,370.00**
	Item Code 074027	**Total No. of Proj.**			**11**		**Total Amount**	**$142,208.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074028	TEMPORARY FIBER ROLL		LF	1	23	25,770.00	$3.92	$101,025.00
			LF	2	22	22,130.00	$3.51	$77,775.00
			LF	3	13	85,635.00	$2.27	$194,170.00
			LF	4	2	2,580.00	$3.49	$9,000.00
			LF	5	10	14,860.00	$3.25	$48,228.40
			LF	6	5	13,780.00	$2.53	$34,800.00
			LF	7	13	41,960.00	$2.76	$115,975.00
			LF	8	14	22,230.00	$2.75	$61,117.50
			LF	9	4	12,584.00	$3.03	$38,081.50
			LF	10	5	4,740.00	$2.62	$12,420.00
			LF	11	6	29,970.00	$2.24	$67,135.50
			LF	12	4	21,760.00	$3.58	$77,880.00
		Unit Sub Total	**LF**		**121**	**297,999.00**	**$2.81**	**$837,607.90**
074028	TEMPORARY FIBER ROLL		M	1	3	1,610.00	$12.67	$20,400.00
			M	2	4	3,640.00	$12.74	$46,389.00
			M	3	6	33,580.00	$5.85	$196,536.00
			M	4	3	5,660.00	$7.62	$43,120.00
			M	5	3	5,620.00	$5.72	$32,146.40
			M	6	2	1,050.00	$8.99	$9,440.00
			M	7	3	7,090.00	$8.47	$60,080.00
			M	8	3	31,920.00	$6.16	$196,490.00
			M	9	2	21,000.00	$6.26	$131,400.00
			M	10	7	15,890.00	$8.29	$131,718.00
			M	11	3	304,280.00	$3.91	$1,188,310.00
		Unit Sub Total	**M**		**39**	**431,340.00**	**$4.77**	**$2,056,029.40**
	Item Code 074028	**Total No. of Proj.**			**160**		**Total Amount**	**$2,893,637.30**
074029	TEMPORARY SILT FENCE		LF	1	12	4,230.00	$5.01	$21,189.00
			LF	2	2	3,250.00	$1.68	$5,460.00
			LF	3	4	14,160.00	$2.32	$32,820.00
			LF	4	17	13,262.00	$3.67	$48,610.17
			LF	5	3	1,500.00	$4.90	$7,350.00
			LF	6	1	1,000.00	$1.45	$1,450.00
			LF	7	6	7,850.00	$2.66	$20,870.00
			LF	8	17	31,180.00	$2.32	$72,355.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074029	TEMPORARY SILT FENCE		LF	10	2	250.00	$7.40	$1,850.00
			LF	12	2	18,360.00	$3.06	$56,140.00
		Unit Sub Total	**LF**		**66**	**95,042.00**	**$2.82**	**$268,094.17**
074029	TEMPORARY SILT FENCE		M	1	5	1,092.00	$13.93	$15,215.00
			M	2	1	1,350.00	$38.00	$51,300.00
			M	3	4	12,390.00	$4.27	$52,904.00
			M	4	13	36,910.00	$6.95	$256,582.50
			M	5	3	3,525.00	$5.58	$19,673.00
			M	6	1	20,000.00	$3.00	$60,000.00
			M	7	3	2,170.00	$13.88	$30,130.00
			M	8	2	8,980.00	$6.28	$56,435.00
			M	10	4	18,260.00	$5.02	$91,609.00
			M	11	1	56,400.00	$2.00	$112,800.00
		Unit Sub Total	**M**		**37**	**161,077.00**	**$4.64**	**$746,648.50**
	Item Code 074029	**Total No. of Proj.**			**103**		**Total Amount**	**$1,014,742.67**
074031	TEMPORARY GRAVEL BAG BERM		LF	1	14	3,805.00	$8.12	$30,881.00
			LF	2	6	1,570.00	$7.20	$11,300.00
			LF	3	1	60.00	$20.00	$1,200.00
			LF	4	3	3,490.00	$10.92	$38,100.00
			LF	5	4	660.00	$10.93	$7,213.50
			LF	7	13	3,250.00	$4.02	$13,063.20
			LF	8	7	10,010.00	$2.36	$23,593.00
			LF	9	1	96.00	$2.10	$201.60
			LF	11	1	270.00	$2.50	$675.00
			LF	12	16	11,319.00	$2.60	$29,436.00
		Unit Sub Total	**LF**		**66**	**34,530.00**	**$4.51**	**$155,663.30**
074031	TEMPORARY GRAVEL BAG BERM		M	1	4	328.00	$32.83	$10,768.00
			M	2	3	860.00	$47.82	$41,125.00
			M	3	4	594.00	$11.20	$6,650.00
			M	4	4	5,140.00	$12.12	$62,320.00
			M	7	3	3,270.00	$7.58	$24,790.00
			M	8	2	2,650.00	$14.26	$37,791.00
			M	10	1	200.00	$8.00	$1,600.00
		Unit Sub Total	**M**		**21**	**13,042.00**	**$14.19**	**$185,044.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 074031 Total No. of Proj.			**87**		**Total Amount**	**$340,707.30**
074032	TEMPORARY CONCRETE WASHOUT FACILITY	EA	1	9	20.00	$2,101.50	$42,030.00
		EA	2	3	3.00	$2,481.33	$7,444.00
		EA	3	4	7.00	$1,314.29	$9,200.00
		EA	4	10	67.00	$1,036.25	$69,428.80
		EA	5	5	14.00	$1,763.01	$24,682.10
		EA	6	9	26.00	$2,124.04	$55,225.00
		EA	7	5	33.00	$1,851.52	$61,100.00
		EA	8	4	52.00	$1,002.88	$52,150.00
		EA	9	5	5.00	$1,101.00	$5,505.00
		EA	10	2	5.00	$2,140.00	$10,700.00
		EA	11	6	39.00	$1,506.15	$58,740.00
		EA	12	3	6.00	$11,479.17	$68,875.00
	Unit Sub Total	**EA**		**65**	**277.00**	**$1,678.99**	**$465,079.90**
074032	TEMPORARY CONCRETE WASHOUT FACILITY	LS	4	1	1.00	$750.00	$750.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$750.00**	**$750.00**
	Item Code 074032 Total No. of Proj.			**66**		**Total Amount**	**$465,829.90**
074033	TEMPORARY CONSTRUCTION ENTRANCE	EA	1	10	20.00	$2,798.00	$55,960.00
		EA	2	5	26.00	$1,902.12	$49,455.01
		EA	3	9	70.00	$2,267.14	$158,700.00
		EA	4	19	99.00	$2,381.82	$235,800.00
		EA	5	11	33.00	$1,787.38	$58,983.41
		EA	6	11	41.00	$3,152.29	$129,244.00
		EA	7	8	51.00	$3,471.76	$177,060.00
		EA	8	13	59.00	$1,903.93	$112,332.00
		EA	9	1	1.00	$1,475.00	$1,475.00
		EA	10	9	34.00	$1,894.12	$64,400.00
		EA	11	11	108.00	$4,986.14	$538,503.50
		EA	12	2	7.00	$1,621.43	$11,350.00
	Unit Sub Total	**EA**		**109**	**549.00**	**$2,902.12**	**$1,593,262.92**
	Item Code 074033 Total No. of Proj.			**109**		**Total Amount**	**$1,593,262.92**
074034	TEMPORARY COVER	M2	2	1	21,000.00	$2.35	$49,350.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074034	TEMPORARY COVER		M2	3	2	13,500.00	$2.67	$36,000.00
			M2	4	12	55,440.00	$2.73	$151,182.00
			M2	5	2	13,600.00	$2.35	$32,000.00
			M2	6	1	2,500.00	$2.00	$5,000.00
			M2	7	3	4,450.00	$4.85	$21,600.00
			M2	8	2	9,410.00	$2.73	$25,708.50
			M2	10	1	3,000.00	$1.00	$3,000.00
		Unit Sub Total	**M2**		**24**	**122,900.00**	**$2.63**	**$323,840.50**
074034	TEMPORARY COVER		SQFT	1	1	1,440.00	$0.50	$720.00
		Unit Sub Total	**SQFT**		**1**	**1,440.00**	**$0.50**	**$720.00**
074034	TEMPORARY COVER		SQYD	1	4	2,430.00	$2.30	$5,600.00
			SQYD	2	1	430.00	$10.00	$4,300.00
			SQYD	3	2	20,200.00	$4.95	$100,000.00
			SQYD	4	11	10,690.00	$3.17	$33,934.80
			SQYD	5	6	8,830.00	$1.29	$11,366.00
			SQYD	6	1	1,340.00	$9.45	$12,663.00
			SQYD	7	7	4,195.00	$1.93	$8,095.00
			SQYD	8	7	2,846.00	$6.21	$17,679.20
			SQYD	11	3	4,850.00	$2.14	$10,369.20
			SQYD	12	1	4,450.00	$1.00	$4,450.00
		Unit Sub Total	**SQYD**		**43**	**60,261.00**	**$3.46**	**$208,457.20**
	Item Code 074034	**Total No. of Proj.**			**68**		**Total Amount**	**$533,017.70**
074035	TEMPORARY CHECK DAM		EA	8	1	10.00	$45.00	$450.00
		Unit Sub Total	**EA**		**1**	**10.00**	**$45.00**	**$450.00**
074035	TEMPORARY CHECK DAM		LF	1	11	1,355.00	$5.84	$7,917.50
			LF	2	11	2,000.00	$8.28	$16,550.00
			LF	3	3	23,200.00	$2.49	$57,800.00
			LF	4	8	2,258.00	$5.31	$12,000.71
			LF	5	10	3,284.00	$7.99	$26,252.40
			LF	7	5	415.00	$7.71	$3,200.00
			LF	8	3	313.00	$6.90	$2,159.98
			LF	10	1	54.00	$63.00	$3,402.00
			LF	11	2	1,080.00	$8.11	$8,760.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**54**	**33,959.00**	**$4.06**	**$138,042.59**
074035	TEMPORARY CHECK DAM		LS	10	1	1.00	$1,500.00	$1,500.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$1,500.00**	**$1,500.00**
074035	TEMPORARY CHECK DAM		M	1	2	320.00	$27.73	$8,875.00
			M	2	1	310.00	$51.00	$15,810.00
			M	3	4	760.00	$7.75	$5,890.00
			M	4	7	1,525.00	$17.86	$27,229.00
			M	5	2	4,300.00	$7.09	$30,500.00
			M	8	1	970.00	$8.25	$8,002.50
			M	9	1	450.00	$35.00	$15,750.00
			M	10	1	54.00	$37.85	$2,043.90
			M	11	3	36,464.00	$5.73	$208,790.00
		Unit Sub Total	**M**		**22**	**45,153.00**	**$7.15**	**$322,890.40**
	Item Code 074035	**Total No. of Proj.**			**78**		**Total Amount**	**$462,882.99**
074036	TEMPORARY STRAW BALE BARRIER		LF	1	2	126.00	$18.79	$2,368.00
			LF	2	1	32.00	$7.00	$224.00
			LF	5	1	360.00	$32.00	$11,520.00
		Unit Sub Total	**LF**		**4**	**518.00**	**$27.24**	**$14,112.00**
074036	TEMPORARY STRAW BALE BARRIER		M	1	1	15.00	$40.00	$600.00
			M	9	1	4.00	$500.00	$2,000.00
		Unit Sub Total	**M**		**2**	**19.00**	**$136.84**	**$2,600.00**
	Item Code 074036	**Total No. of Proj.**			**6**		**Total Amount**	**$16,712.00**
074037	MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)		EA	1	3	15.00	$333.33	$5,000.00
			EA	2	1	15.00	$1,000.00	$15,000.00
			EA	3	6	53.00	$301.51	$15,980.00
			EA	4	8	63.00	$672.22	$42,350.00
			EA	5	1	8.00	$250.00	$2,000.00
			EA	6	1	8.00	$435.00	$3,480.00
			EA	7	2	9.00	$833.33	$7,500.00
			EA	8	2	3.00	$750.00	$2,250.00
			EA	10	2	6.00	$833.33	$5,000.00
			EA	11	4	50.00	$484.40	$24,220.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**30**	**230.00**	**$533.83**	**$122,780.00**
074037	MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)	LS	3	1	1.00	$850.00	$850.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$850.00**	**$850.00**
	Item Code 074037 Total No. of Proj.			**31**		**Total Amount**	**$123,630.00**
074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	1	16	85.00	$181.28	$15,409.00
		EA	2	12	153.00	$340.47	$52,092.00
		EA	3	17	717.00	$182.57	$130,902.00
		EA	4	55	1,786.00	$187.70	$335,230.78
		EA	5	18	208.00	$204.27	$42,487.68
		EA	6	18	179.00	$313.91	$56,189.00
		EA	7	24	619.00	$195.47	$120,997.00
		EA	8	14	426.00	$184.01	$78,387.40
		EA	9	5	199.00	$114.59	$22,804.00
		EA	10	11	244.00	$128.48	$31,349.50
		EA	11	16	1,103.00	$140.62	$155,105.70
		EA	12	36	1,191.00	$138.75	$165,249.00
	Unit Sub Total	**EA**		**242**	**6,910.00**	**$174.56**	**$1,206,203.06**
074038	TEMPORARY DRAINAGE INLET PROTECTION	LS	4	1	1.00	$2,000.00	$2,000.00
		LS	6	1	1.00	$3,500.00	$3,500.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$2,750.00**	**$5,500.00**
	Item Code 074038 Total No. of Proj.			**244**		**Total Amount**	**$1,211,703.06**
074039	TEMPORARY HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	M2	1	2	12,800.00	$0.56	$7,200.00
		M2	2	1	54,900.00	$1.20	$65,880.00
		M2	3	2	22,000.00	$0.74	$16,200.00
		M2	5	1	2,400.00	$0.85	$2,040.00
		M2	11	1	1,140,000.00	$0.35	$399,000.00
	Unit Sub Total	**M2**		**7**	**1,232,100.00**	**$0.40**	**$490,320.00**
074039	TEMPORARY HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	SQYD	3	1	3,000.00	$1.25	$3,750.00
	Unit Sub Total	**SQYD**		**1**	**3,000.00**	**$1.25**	**$3,750.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 074039 Total No. of Proj.			**8**		**Total Amount**	**$494,070.00**
074040	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	M2	3	1	12,400.00	$0.85	$10,540.00
		M2	4	8	149,180.00	$0.98	$145,930.00
		M2	5	1	231,000.00	$0.50	$115,500.00
		M2	7	1	17,500.00	$1.00	$17,500.00
		M2	10	2	145,000.00	$0.71	$102,430.00
	Unit Sub Total	**M2**		**13**	**555,080.00**	**$0.71**	**$391,900.00**
074040	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	SQYD	1	1	1,380.00	$2.50	$3,450.00
		SQYD	3	2	19,840.00	$1.07	$21,260.00
		SQYD	4	2	14,850.00	$1.21	$17,900.00
		SQYD	12	1	48.00	$28.00	$1,344.00
	Unit Sub Total	**SQYD**		**6**	**36,118.00**	**$1.22**	**$43,954.00**
	Item Code 074040 Total No. of Proj.			**19**		**Total Amount**	**$435,854.00**
074041	STREET SWEEPING	LS	1	22	22.00	$5,881.59	$129,395.00
		LS	2	6	6.00	$52,416.67	$314,500.00
		LS	3	23	23.00	$21,821.52	$501,894.91
		LS	4	77	77.00	$15,964.46	$1,229,263.23
		LS	5	17	17.00	$8,429.44	$143,300.40
		LS	6	36	36.00	$15,058.31	$542,099.00
		LS	7	81	81.00	$8,696.28	$704,398.43
		LS	8	22	22.00	$11,099.32	$244,185.00
		LS	9	4	4.00	$9,537.50	$38,150.00
		LS	10	36	36.00	$7,403.69	$266,533.00
		LS	11	21	21.00	$14,331.48	$300,961.12
		LS	12	34	34.00	$8,116.76	$275,970.00
	Unit Sub Total	**LS**		**379**	**379.00**	**$12,376.39**	**$4,690,650.09**
	Item Code 074041 Total No. of Proj.			**379**		**Total Amount**	**$4,690,650.09**
074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	EA	1	1	2.00	$500.00	$1,000.00
		EA	3	4	6.00	$1,080.67	$6,484.00
		EA	4	3	102.00	$338.24	$34,500.00
		EA	6	1	2.00	$1,070.00	$2,140.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	EA	8	2	2.00	$1,100.00	$2,200.00
		EA	10	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**EA**		**12**	**115.00**	**$411.51**	**$47,324.00**
074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	1	25	25.00	$1,199.00	$29,975.00
		LS	2	28	28.00	$2,225.43	$62,312.00
		LS	3	31	31.00	$2,720.26	$84,328.08
		LS	4	17	17.00	$8,639.59	$146,873.00
		LS	5	20	20.00	$1,409.30	$28,185.92
		LS	6	20	20.00	$2,081.55	$41,631.00
		LS	7	62	62.00	$5,127.84	$317,926.00
		LS	8	34	34.00	$6,671.41	$226,828.00
		LS	9	1	1.00	$1,000.00	$1,000.00
		LS	10	24	24.00	$1,141.88	$27,405.00
		LS	11	18	18.00	$1,635.36	$29,436.54
		LS	12	27	27.00	$1,989.56	$53,718.00
	Unit Sub Total	**LS**		**307**	**307.00**	**$3,418.95**	**$1,049,618.54**
	Item Code 074042 Total No. of Proj.			**319**		**Total Amount**	**$1,096,942.54**
074043	TEMPORARY CONCRETE WASHOUT BIN	EA	2	1	40.00	$1,500.00	$60,000.00
		EA	4	10	281.00	$752.88	$211,560.00
		EA	7	2	6.00	$1,000.00	$6,000.00
		EA	11	1	37.00	$700.00	$25,900.00
		EA	12	2	5.00	$380.60	$1,903.00
	Unit Sub Total	**EA**		**16**	**369.00**	**$827.54**	**$305,363.00**
	Item Code 074043 Total No. of Proj.			**16**		**Total Amount**	**$305,363.00**
074044	TEMPORARY CONSTRUCTION ROADWAY	CY	8	1	260.00	$60.00	$15,600.00
	Unit Sub Total	**CY**		**1**	**260.00**	**$60.00**	**$15,600.00**
074044	TEMPORARY CONSTRUCTION ROADWAY	M3	4	2	1,280.00	$70.58	$90,340.00
	Unit Sub Total	**M3**		**2**	**1,280.00**	**$70.58**	**$90,340.00**
	Item Code 074044 Total No. of Proj.			**3**		**Total Amount**	**$105,940.00**
074045	TEMPORARY LARGE SEDIMENT BARRIER	M	11	1	1,500.00	$6.00	$9,000.00
	Unit Sub Total	**M**		**1**	**1,500.00**	**$6.00**	**$9,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 074045	**Total No. of Proj.**			**1**		**Total Amount**	**$9,000.00**
074051	TEMPORARY HYDRAULIC MULCH		M2	11	2	902,800.00	$0.29	$265,860.00
		Unit Sub Total	**M2**		**2**	**902,800.00**	**$0.29**	**$265,860.00**
074051	TEMPORARY HYDRAULIC MULCH		SQYD	1	1	2,900.00	$0.90	$2,610.00
			SQYD	11	1	19,800.00	$0.30	$5,940.00
		Unit Sub Total	**SQYD**		**2**	**22,700.00**	**$0.38**	**$8,550.00**
	Item Code 074051	**Total No. of Proj.**			**4**		**Total Amount**	**$274,410.00**
074054	TEMPORARY TACKED STRAW		M2	10	1	30,000.00	$0.35	$10,500.00
		Unit Sub Total	**M2**		**1**	**30,000.00**	**$0.35**	**$10,500.00**
	Item Code 074054	**Total No. of Proj.**			**1**		**Total Amount**	**$10,500.00**
074055	TEMPORARY SOIL BINDER		M2	2	1	175,000.00	$0.12	$21,000.00
			M2	8	1	170,000.00	$0.25	$42,500.00
		Unit Sub Total	**M2**		**2**	**345,000.00**	**$0.18**	**$63,500.00**
074055	TEMPORARY SOIL BINDER		SQYD	1	1	4,840.00	$0.30	$1,452.00
			SQYD	2	3	339,000.00	$0.07	$22,050.00
			SQYD	3	1	145,000.00	$0.10	$14,500.00
			SQYD	6	2	815,000.00	$0.25	$201,702.00
			SQYD	8	7	33,620.00	$0.74	$24,772.70
		Unit Sub Total	**SQYD**		**14**	**1,337,460.00**	**$0.20**	**$264,476.70**
	Item Code 074055	**Total No. of Proj.**			**16**		**Total Amount**	**$327,976.70**
120090	CONSTRUCTION AREA SIGNS		LS	1	43	43.00	$5,709.19	$245,495.00
			LS	2	39	39.00	$16,244.28	$633,527.00
			LS	3	44	44.00	$7,273.43	$320,030.70
			LS	4	86	86.00	$9,017.18	$775,477.66
			LS	5	36	36.00	$8,078.14	$290,812.88
			LS	6	57	57.00	$7,036.09	$401,057.03
			LS	7	84	84.00	$6,974.59	$585,865.86
			LS	8	65	65.00	$8,625.42	$560,652.17
			LS	9	11	11.00	$20,711.91	$227,831.00
			LS	10	40	40.00	$5,392.60	$215,704.00
			LS	11	32	32.00	$12,244.06	$391,809.92

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
120090	CONSTRUCTION AREA SIGNS		LS	12	36	36.00	$6,608.89	$237,920.00
		Unit Sub Total	**LS**		**573**	**573.00**	**$8,527.37**	**$4,886,183.22**
	Item Code 120090	**Total No. of Proj.**			**573**		**Total Amount**	**$4,886,183.22**
120100	TRAFFIC CONTROL SYSTEM		LS	1	45	45.00	$50,060.84	$2,252,738.00
			LS	2	42	42.00	$66,148.03	$2,778,217.27
			LS	3	57	57.00	$86,936.74	$4,955,394.20
			LS	4	82	82.00	$67,050.42	$5,498,134.53
			LS	5	35	35.00	$78,449.94	$2,745,747.77
			LS	6	56	56.00	$80,458.10	$4,505,653.71
			LS	7	87	87.00	$62,109.41	$5,403,518.68
			LS	8	60	60.00	$61,894.82	$3,713,689.18
			LS	9	11	11.00	$95,172.56	$1,046,898.20
			LS	10	39	39.00	$49,126.71	$1,915,941.50
			LS	11	32	32.00	$77,556.00	$2,481,791.87
			LS	12	36	36.00	$44,724.81	$1,610,093.00
		Unit Sub Total	**LS**		**582**	**582.00**	**$66,851.92**	**$38,907,817.91**
	Item Code 120100	**Total No. of Proj.**			**582**		**Total Amount**	**$38,907,817.91**
120102	TRAFFIC CONTROL SURVEILLANCE		LS	2	1	1.00	$1,500.00	$1,500.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$1,500.00**	**$1,500.00**
120102	TRAFFIC CONTROL SURVEILLANCE		WDAY	2	1	180.00	$1,150.00	$207,000.00
		Unit Sub Total	**WDAY**		**1**	**180.00**	**$1,150.00**	**$207,000.00**
	Item Code 120102	**Total No. of Proj.**			**2**		**Total Amount**	**$208,500.00**
120116	TYPE II BARRICADE		EA	4	2	67.00	$90.45	$6,060.00
			EA	5	2	43.00	$72.33	$3,110.00
			EA	6	1	2.00	$15.00	$30.00
			EA	7	1	2.00	$80.00	$160.00
			EA	8	5	24.00	$110.00	$2,640.00
		Unit Sub Total	**EA**		**11**	**138.00**	**$86.96**	**$12,000.00**
	Item Code 120116	**Total No. of Proj.**			**11**		**Total Amount**	**$12,000.00**
120119	TRAFFIC CONE		EA	12	1	6.00	$15.00	$90.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**6.00**	**$15.00**	**$90.00**
	Item Code 120119	**Total No. of Proj.**			**1**		**Total Amount**	**$90.00**
120120	TYPE III BARRICADE		EA	1	3	22.00	$63.64	$1,400.00
			EA	2	5	55.00	$76.36	$4,200.00
			EA	3	6	199.00	$60.70	$12,080.00
			EA	4	9	220.00	$63.91	$14,060.00
			EA	5	4	386.00	$45.60	$17,600.00
			EA	6	7	1,680.00	$51.62	$86,718.00
			EA	7	8	270.00	$101.44	$27,389.00
			EA	8	7	121.00	$93.74	$11,343.00
			EA	9	2	71.00	$41.69	$2,960.00
			EA	10	5	96.00	$53.02	$5,090.00
			EA	11	5	249.00	$103.13	$25,680.00
			EA	12	5	38.00	$128.16	$4,870.00
		Unit Sub Total	**EA**		**66**	**3,407.00**	**$62.63**	**$213,390.00**
	Item Code 120120	**Total No. of Proj.**			**66**		**Total Amount**	**$213,390.00**
120140	BARRICADE (LEFT IN PLACE)		EA	11	1	6.00	$500.00	$3,000.00
		Unit Sub Total	**EA**		**1**	**6.00**	**$500.00**	**$3,000.00**
	Item Code 120140	**Total No. of Proj.**			**1**		**Total Amount**	**$3,000.00**
120149	TEMPORARY PAVEMENT MARKING (PAINT)		M2	1	2	18.20	$123.02	$2,239.00
			M2	2	1	47.00	$65.00	$3,055.00
			M2	3	3	469.00	$20.96	$9,830.00
			M2	4	6	1,424.00	$29.91	$42,585.00
			M2	7	2	8.00	$96.88	$775.00
			M2	8	1	43.00	$20.00	$860.00
			M2	9	1	96.00	$23.25	$2,232.00
			M2	10	2	40.00	$34.31	$1,372.50
			M2	11	2	820.00	$9.76	$8,000.00
		Unit Sub Total	**M2**		**20**	**2,965.20**	**$23.93**	**$70,948.50**
120149	TEMPORARY PAVEMENT MARKING (PAINT)		SQFT	1	6	940.00	$10.80	$10,151.00
			SQFT	2	3	308.00	$3.18	$978.00
			SQFT	3	3	6,350.00	$1.66	$10,530.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
120149	TEMPORARY PAVEMENT MARKING (PAINT)	SQFT	4	2	1,650.00	$1.12	$1,842.00
		SQFT	7	1	290.00	$3.00	$870.00
		SQFT	8	2	610.00	$3.65	$2,225.80
		SQFT	10	1	1,810.00	$3.80	$6,878.00
		SQFT	11	1	3,330.00	$1.60	$5,328.00
		SQFT	12	2	9,800.00	$1.13	$11,039.00
	Unit Sub Total	**SQFT**		**21**	**25,088.00**	**$1.99**	**$49,841.80**
	Item Code 120149 Total No. of Proj.			**41**		**Total Amount**	**$120,790.30**
120151	TEMPORARY TRAFFIC STRIPE (TAPE)	LF	1	3	38,530.00	$1.13	$43,531.00
		LF	2	3	39,850.00	$1.01	$40,296.00
		LF	3	1	5,250.00	$2.00	$10,500.00
		LF	4	2	2,460.00	$2.86	$7,027.00
		LF	5	1	450.00	$1.50	$675.00
		LF	6	3	16,270.00	$1.83	$29,720.00
		LF	7	2	2,800.00	$2.19	$6,125.00
		LF	10	1	270.00	$6.00	$1,620.00
		LF	12	1	6,620.00	$0.50	$3,310.00
	Unit Sub Total	**LF**		**17**	**112,500.00**	**$1.27**	**$142,804.00**
120151	TEMPORARY TRAFFIC STRIPE (TAPE)	M	3	3	959.00	$6.05	$5,803.00
		M	4	5	50,890.00	$4.59	$233,480.00
		M	6	2	7,150.00	$2.40	$17,171.00
		M	10	3	5,880.00	$6.74	$39,652.00
	Unit Sub Total	**M**		**13**	**64,879.00**	**$4.56**	**$296,106.00**
	Item Code 120151 Total No. of Proj.			**30**		**Total Amount**	**$438,910.00**
120152	TEMPORARY PAVEMENT MARKING (TAPE)	M2	1	1	16.00	$30.00	$480.00
		M2	2	1	12.00	$86.00	$1,032.00
		M2	3	2	91.00	$55.82	$5,080.00
		M2	4	5	73.00	$100.68	$7,350.00
		M2	6	2	74.00	$77.16	$5,710.00
		M2	10	1	47.00	$44.00	$2,068.00
	Unit Sub Total	**M2**		**12**	**313.00**	**$69.39**	**$21,720.00**
120152	TEMPORARY PAVEMENT MARKING (TAPE)	SQFT	1	2	54.00	$18.44	$996.00
		SQFT	2	3	1,170.00	$7.61	$8,902.40

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
120152	TEMPORARY PAVEMENT MARKING (TAPE)	SQFT	3	2	142.00	$17.18	$2,440.00
		SQFT	4	1	24.00	$102.50	$2,460.00
		SQFT	5	1	26.00	$30.00	$780.00
		SQFT	6	2	223.00	$7.50	$1,672.00
	Unit Sub Total	**SQFT**		**11**	**1,639.00**	**$10.52**	**$17,250.40**
	Item Code 120152 Total No. of Proj.			**23**		**Total Amount**	**$38,970.40**
120154	TEMPORARY MARKER	EA	4	1	42.00	$4.00	$168.00
		EA	6	1	1.00	$27.00	$27.00
	Unit Sub Total	**EA**		**2**	**43.00**	**$4.53**	**$195.00**
	Item Code 120154 Total No. of Proj.			**2**		**Total Amount**	**$195.00**
120159	TEMPORARY TRAFFIC STRIPE (PAINT)	LF	1	7	40,860.00	$0.93	$38,134.50
		LF	2	5	606,520.00	$0.21	$129,875.00
		LF	3	3	603,580.00	$0.13	$75,506.00
		LF	4	3	66,400.00	$0.32	$21,130.00
		LF	5	3	28,420.00	$0.70	$19,846.00
		LF	7	5	1,375,740.00	$0.26	$352,149.00
		LF	8	5	167,160.00	$0.77	$128,611.00
		LF	10	2	60,600.00	$0.21	$12,710.00
		LF	11	4	88,030.00	$0.28	$24,989.00
		LF	12	5	977,110.00	$0.13	$130,069.00
	Unit Sub Total	**LF**		**42**	**4,014,420.00**	**$0.23**	**$933,019.50**
120159	TEMPORARY TRAFFIC STRIPE (PAINT)	M	1	3	20,350.00	$1.86	$37,899.00
		M	2	1	35,200.00	$2.40	$84,480.00
		M	3	5	135,200.00	$0.42	$56,795.00
		M	4	6	242,670.00	$0.58	$140,840.00
		M	6	1	27,700.00	$0.30	$8,310.00
		M	7	1	280.00	$16.00	$4,480.00
		M	8	1	46,100.00	$0.39	$17,979.00
		M	9	1	43,900.00	$0.20	$8,780.00
		M	10	3	15,910.00	$0.73	$11,603.00
		M	11	2	61,087.00	$0.70	$42,760.90
	Unit Sub Total	**M**		**24**	**628,397.00**	**$0.66**	**$413,926.90**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 120159 Total No. of Proj.			**66**		**Total Amount**	**$1,346,946.40**
120165	CHANNELIZER (SURFACE MOUNTED)	EA	1	13	1,925.00	$26.95	$51,883.00
		EA	2	10	2,138.00	$36.55	$78,148.00
		EA	3	9	3,211.00	$27.83	$89,359.00
		EA	4	18	3,046.00	$31.63	$96,332.00
		EA	5	8	1,250.00	$31.27	$39,082.30
		EA	6	10	2,144.00	$30.90	$66,252.80
		EA	7	18	1,985.00	$28.17	$55,910.00
		EA	8	13	2,959.00	$44.20	$130,779.00
		EA	9	2	1,231.00	$25.33	$31,182.50
		EA	10	11	816.00	$32.31	$26,366.00
		EA	11	3	47.00	$35.72	$1,679.00
		EA	12	11	7,180.00	$23.39	$167,970.00
	Unit Sub Total	**EA**		**126**	**27,932.00**	**$29.89**	**$834,943.60**
	Item Code 120165 Total No. of Proj.			**126**		**Total Amount**	**$834,943.60**
120166	CHANNELIZER (SURFACE MOUNTED) (LEFT IN PLACE)	EA	4	1	24.00	$35.00	$840.00
		EA	8	3	53.00	$48.87	$2,590.00
		EA	11	2	49.00	$40.00	$1,960.00
		EA	12	1	990.00	$22.00	$21,780.00
	Unit Sub Total	**EA**		**7**	**1,116.00**	**$24.35**	**$27,170.00**
	Item Code 120166 Total No. of Proj.			**7**		**Total Amount**	**$27,170.00**
120182	PORTABLE DELINEATOR	EA	2	3	32.00	$21.54	$689.31
		EA	8	1	13.00	$50.00	$650.00
		EA	10	1	10.00	$34.00	$340.00
	Unit Sub Total	**EA**		**5**	**55.00**	**$30.53**	**$1,679.31**
	Item Code 120182 Total No. of Proj.			**5**		**Total Amount**	**$1,679.31**
120199	TRAFFIC PLASTIC DRUM	EA	1	3	110.00	$140.05	$15,406.00
		EA	3	6	656.00	$41.56	$27,266.00
		EA	4	3	137.00	$52.19	$7,150.00
		EA	11	9	1,413.00	$35.41	$50,033.00
	Unit Sub Total	**EA**		**21**	**2,316.00**	**$43.12**	**$99,855.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 120199 Total No. of Proj.			**21**		**Total Amount**	**$99,855.00**
120200	FLASHING BEACON (PORTABLE)	EA	1	1	2.00	$1,200.00	$2,400.00
		EA	4	2	18.00	$502.78	$9,050.00
		EA	6	1	2.00	$300.00	$600.00
		EA	8	5	49.00	$588.69	$28,846.00
		EA	9	1	8.00	$450.00	$3,600.00
		EA	10	1	3.00	$200.00	$600.00
	Unit Sub Total	**EA**		**11**	**82.00**	**$549.95**	**$45,096.00**
	Item Code 120200 Total No. of Proj.			**11**		**Total Amount**	**$45,096.00**
120300	TEMPORARY PAVEMENT MARKER	EA	1	4	784.00	$6.22	$4,876.00
		EA	2	1	6,400.00	$3.00	$19,200.00
		EA	3	6	64,190.00	$3.23	$207,606.80
		EA	4	13	53,958.00	$3.44	$185,649.00
		EA	5	1	130.00	$4.00	$520.00
		EA	6	4	1,386.00	$4.54	$6,286.00
		EA	7	5	30,900.00	$3.67	$113,541.00
		EA	8	5	9,920.00	$4.12	$40,868.00
		EA	10	5	4,522.00	$2.97	$13,443.50
		EA	11	5	15,045.00	$3.52	$52,922.50
		EA	12	2	676.00	$3.09	$2,092.00
	Unit Sub Total	**EA**		**51**	**187,911.00**	**$3.44**	**$647,004.80**
120300	TEMPORARY PAVEMENT MARKER	M	1	1	470.00	$3.00	$1,410.00
	Unit Sub Total	**M**		**1**	**470.00**	**$3.00**	**$1,410.00**
	Item Code 120300 Total No. of Proj.			**52**		**Total Amount**	**$648,414.80**
121161	TEMPORARY TERMINAL SECTION (TYPE K)	EA	2	1	1.00	$2,500.00	$2,500.00
		EA	4	2	4.00	$2,500.00	$10,000.00
		EA	7	6	12.00	$1,266.67	$15,200.00
		EA	10	1	2.00	$3,000.00	$6,000.00
	Unit Sub Total	**EA**		**10**	**19.00**	**$1,773.68**	**$33,700.00**
	Item Code 121161 Total No. of Proj.			**10**		**Total Amount**	**$33,700.00**
128201	TEMPORARY DELINEATOR (CLASS 1)	EA	2	1	26.00	$35.00	$910.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
128201	TEMPORARY DELINEATOR (CLASS 1)	EA	10	2	46.00	$31.85	$1,465.00
	Unit Sub Total	**EA**		**3**	**72.00**	**$32.99**	**$2,375.00**
	Item Code 128201 Total No. of Proj.			**3**		**Total Amount**	**$2,375.00**
128202	TEMPORARY DELINEATOR (CLASS 2)	EA	9	1	140.00	$15.00	$2,100.00
	Unit Sub Total	**EA**		**1**	**140.00**	**$15.00**	**$2,100.00**
	Item Code 128202 Total No. of Proj.			**1**		**Total Amount**	**$2,100.00**
128601	TEMPORARY SIGNAL SYSTEM	LS	1	6	6.00	$105,666.67	$634,000.00
		LS	2	2	2.00	$119,000.00	$238,000.00
		LS	4	3	3.00	$110,608.33	$331,825.00
		LS	5	3	3.00	$95,166.67	$285,500.00
		LS	7	1	1.00	$87,120.00	$87,120.00
	Unit Sub Total	**LS**		**15**	**15.00**	**$105,096.33**	**$1,576,445.00**
	Item Code 128601 Total No. of Proj.			**15**		**Total Amount**	**$1,576,445.00**
128605	TEMPORARY SIGNAL AND LIGHTING	LS	3	1	1.00	$75,000.00	$75,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$75,000.00**	**$75,000.00**
	Item Code 128605 Total No. of Proj.			**1**		**Total Amount**	**$75,000.00**
128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	1	25	64.00	$3,180.47	$203,550.00
		EA	2	23	52.00	$3,000.13	$156,006.94
		EA	4	20	79.00	$5,400.05	$426,604.00
		EA	8	51	148.00	$3,273.75	$484,514.40
		EA	11	32	132.00	$5,067.24	$668,875.36
	Unit Sub Total	**EA**		**151**	**475.00**	**$4,083.26**	**$1,939,550.70**
128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	1	20	20.00	$6,768.00	$135,360.00
		LS	2	17	17.00	$24,954.35	$424,224.00
		LS	3	58	58.00	$10,495.69	$608,750.23
		LS	4	60	60.00	$10,290.18	$617,410.69
		LS	5	34	34.00	$8,721.64	$296,535.86
		LS	6	56	56.00	$9,029.28	$505,639.84
		LS	7	2	2.00	$4,500.00	$9,000.00
		LS	8	6	6.00	$7,050.00	$42,300.00
		LS	9	8	8.00	$9,262.50	$74,100.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	10	37	37.00	$6,618.95	$244,901.00
		LS	12	30	30.00	$7,257.10	$217,713.00
	Unit Sub Total	**LS**		**328**	**328.00**	**$9,682.73**	**$3,175,934.62**
	Item Code 128650 Total No. of Proj.			**479**		**Total Amount**	**$5,115,485.32**
128660	TEMPORARY FLASHING BEACON	LS	2	4	4.00	$3,875.00	$15,500.00
		LS	3	1	1.00	$7,000.00	$7,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$4,500.00**	**$22,500.00**
	Item Code 128660 Total No. of Proj.			**5**		**Total Amount**	**$22,500.00**
129000	TEMPORARY RAILING (TYPE K)	LF	1	13	20,850.00	$14.61	$304,610.00
		LF	2	9	79,870.00	$10.16	$811,200.00
		LF	3	8	117,870.00	$21.58	$2,543,330.00
		LF	4	8	45,430.00	$15.14	$687,770.00
		LF	5	5	5,810.00	$39.32	$228,430.00
		LF	6	5	20,530.00	$11.19	$229,780.00
		LF	7	15	95,530.00	$10.16	$970,580.00
		LF	8	9	22,380.00	$16.44	$367,992.00
		LF	10	3	26,120.00	$6.54	$170,930.00
		LF	11	6	51,340.00	$8.79	$451,140.00
		LF	12	8	73,120.00	$12.54	$917,062.50
	Unit Sub Total	**LF**		**89**	**558,850.00**	**$13.75**	**$7,682,824.50**
129000	TEMPORARY RAILING (TYPE K)	M	1	3	11,230.00	$29.81	$334,800.00
		M	2	3	8,264.00	$71.75	$592,958.15
		M	3	5	42,620.00	$21.21	$903,860.00
		M	4	12	151,765.00	$27.15	$4,120,290.00
		M	5	3	4,340.00	$49.52	$214,924.00
		M	6	4	3,990.00	$39.22	$156,480.00
		M	7	4	62,680.00	$29.49	$1,848,700.00
		M	8	3	89,040.00	$24.84	$2,212,000.00
		M	10	7	15,260.00	$33.92	$517,610.00
		M	11	3	37,020.00	$18.36	$679,650.00
	Unit Sub Total	**M**		**47**	**426,209.00**	**$27.17**	**$11,581,272.15**
	Item Code 129000 Total No. of Proj.			**136**		**Total Amount**	**$19,264,096.65**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
129100	TEMPORARY CRASH CUSHION MODULE	EA	1	9	320.00	$262.32	$83,942.00
		EA	2	7	592.00	$276.08	$163,440.00
		EA	3	11	3,657.00	$77.60	$283,780.00
		EA	4	19	3,684.00	$202.33	$745,396.00
		EA	5	3	884.00	$98.31	$86,908.20
		EA	6	8	601.00	$144.83	$87,040.00
		EA	7	20	2,683.00	$220.40	$591,330.00
		EA	8	7	1,638.00	$261.49	$428,320.00
		EA	10	7	857.00	$127.15	$108,966.00
		EA	11	7	1,117.00	$264.73	$295,700.00
		EA	12	7	896.00	$278.64	$249,660.00
	Unit Sub Total	**EA**		**105**	**16,929.00**	**$184.56**	**$3,124,482.20**
	Item Code 129100 Total No. of Proj.			**105**		**Total Amount**	**$3,124,482.20**
129110	TEMPORARY CRASH CUSHION	EA	5	1	4.00	$2,100.00	$8,400.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$2,100.00**	**$8,400.00**
	Item Code 129110 Total No. of Proj.			**1**		**Total Amount**	**$8,400.00**
129150	TEMPORARY TRAFFIC SCREEN	LF	3	1	50,300.00	$2.00	$100,600.00
		LF	4	2	14,250.00	$2.06	$29,350.00
		LF	5	1	420.00	$5.00	$2,100.00
		LF	8	2	9,280.00	$2.19	$20,300.00
		LF	10	1	23,300.00	$3.20	$74,560.00
		LF	12	6	70,570.00	$3.55	$250,565.00
	Unit Sub Total	**LF**		**13**	**168,120.00**	**$2.84**	**$477,475.00**
129150	TEMPORARY TRAFFIC SCREEN	M	3	1	7,200.00	$13.50	$97,200.00
		M	4	4	17,500.00	$14.77	$258,400.00
		M	7	1	250.00	$11.00	$2,750.00
		M	8	2	80,200.00	$9.09	$729,200.00
		M	10	1	910.00	$9.00	$8,190.00
	Unit Sub Total	**M**		**9**	**106,060.00**	**$10.33**	**$1,095,740.00**
	Item Code 129150 Total No. of Proj.			**22**		**Total Amount**	**$1,573,215.00**
129510	TEMPORARY RETAINING WALL	M2	4	2	8,730.00	$84.83	$740,590.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M2**		**2**	**8,730.00**	**$84.83**	**$740,590.00**
	Item Code 129510 Total No. of Proj.			**2**		**Total Amount**	**$740,590.00**
141101	REMOVE YELLOW PAINTED TRAFFIC STRIPE (HAZARDOUS WASTE)	LF	4	1	5,700.00	$1.00	$5,700.00
		LF	5	1	1,400.00	$2.50	$3,500.00
		LF	10	1	23,700.00	$0.40	$9,480.00
	Unit Sub Total	**LF**		**3**	**30,800.00**	**$0.61**	**$18,680.00**
	Item Code 141101 Total No. of Proj.			**3**		**Total Amount**	**$18,680.00**
141103	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	LF	3	2	4,340.00	$1.00	$4,340.00
		LF	4	3	8,340.00	$2.29	$19,074.00
		LF	5	1	8,310.00	$2.50	$20,775.00
		LF	7	1	15,300.00	$0.33	$5,049.00
		LF	10	1	23,700.00	$0.88	$20,856.00
		LF	12	1	6,010.00	$0.83	$4,988.30
	Unit Sub Total	**LF**		**9**	**66,000.00**	**$1.14**	**$75,082.30**
	Item Code 141103 Total No. of Proj.			**9**		**Total Amount**	**$75,082.30**
141104	REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING (HAZARDOUS WASTE)	SQFT	7	1	250.00	$2.75	$687.50
		SQFT	12	1	620.00	$4.35	$2,697.00
	Unit Sub Total	**SQFT**		**2**	**870.00**	**$3.89**	**$3,384.50**
	Item Code 141104 Total No. of Proj.			**2**		**Total Amount**	**$3,384.50**
148005	NOISE MONITORING	LS	4	1	1.00	$475.00	$475.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$475.00**	**$475.00**
	Item Code 148005 Total No. of Proj.			**1**		**Total Amount**	**$475.00**
150205	ABANDON REINFORCED CONCRETE BOX	EA	3	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$2,000.00**	**$2,000.00**
	Item Code 150205 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
150206	ABANDON CULVERT	EA	1	4	4.00	$1,450.00	$5,800.00
		EA	2	6	18.00	$4,052.72	$72,949.04

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150206	ABANDON CULVERT		EA	3	3	22.00	$1,165.45	$25,640.00
			EA	4	6	74.00	$621.62	$46,000.00
			EA	5	1	2.00	$700.00	$1,400.00
			EA	6	2	10.00	$1,510.00	$15,100.00
			EA	9	1	4.00	$800.00	$3,200.00
			EA	10	2	3.00	$933.33	$2,800.00
			EA	11	2	10.00	$1,096.00	$10,960.00
		Unit Sub Total	**EA**		**27**	**147.00**	**$1,250.67**	**$183,849.04**
150206	ABANDON CULVERT		LF	1	1	26.00	$20.00	$520.00
			LF	4	3	2,772.00	$15.33	$42,484.00
			LF	6	1	32.00	$100.00	$3,200.00
			LF	7	1	5,100.00	$16.00	$81,600.00
		Unit Sub Total	**LF**		**6**	**7,930.00**	**$16.12**	**$127,804.00**
150206	ABANDON CULVERT		M	4	4	3,890.00	$29.63	$115,270.00
			M	5	2	213.00	$77.70	$16,550.00
			M	6	1	42.00	$60.00	$2,520.00
			M	8	2	600.00	$68.17	$40,900.00
			M	10	1	51.00	$210.00	$10,710.00
			M	11	1	420.00	$100.00	$42,000.00
		Unit Sub Total	**M**		**11**	**5,216.00**	**$43.70**	**$227,950.00**
	Item Code 150206	**Total No. of Proj.**			**44**		**Total Amount**	**$539,603.04**
150208	ABANDON DECK DRAIN		EA	7	1	7.00	$500.00	$3,500.00
		Unit Sub Total	**EA**		**1**	**7.00**	**$500.00**	**$3,500.00**
	Item Code 150208	**Total No. of Proj.**			**1**		**Total Amount**	**$3,500.00**
150221	ABANDON INLET		EA	4	6	51.00	$860.29	$43,875.00
			EA	10	1	1.00	$250.00	$250.00
			EA	11	1	7.00	$440.00	$3,080.00
		Unit Sub Total	**EA**		**8**	**59.00**	**$800.08**	**$47,205.00**
	Item Code 150221	**Total No. of Proj.**			**8**		**Total Amount**	**$47,205.00**
150224	ABANDON MANHOLE		EA	10	1	2.00	$600.00	$1,200.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$600.00**	**$1,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150224	**Total No. of Proj.**			**1**		**Total Amount**	**$1,200.00**
150227	ABANDON PIPELINE		EA	7	2	4.00	$1,100.00	$4,400.00
		Unit Sub Total	**EA**		**2**	**4.00**	**$1,100.00**	**$4,400.00**
150227	ABANDON PIPELINE		LF	7	1	100.00	$10.00	$1,000.00
		Unit Sub Total	**LF**		**1**	**100.00**	**$10.00**	**$1,000.00**
150227	ABANDON PIPELINE		M	7	1	45.00	$67.00	$3,015.00
		Unit Sub Total	**M**		**1**	**45.00**	**$67.00**	**$3,015.00**
	Item Code 150227	**Total No. of Proj.**			**4**		**Total Amount**	**$8,415.00**
150229	ABANDON WATER WELL		EA	6	1	12.00	$5,500.00	$66,000.00
		Unit Sub Total	**EA**		**1**	**12.00**	**$5,500.00**	**$66,000.00**
	Item Code 150229	**Total No. of Proj.**			**1**		**Total Amount**	**$66,000.00**
150241	ABANDON SEWER		EA	4	1	1.00	$1,000.00	$1,000.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$1,000.00**	**$1,000.00**
150241	ABANDON SEWER		LF	11	1	420.00	$17.00	$7,140.00
		Unit Sub Total	**LF**		**1**	**420.00**	**$17.00**	**$7,140.00**
150241	ABANDON SEWER		M	4	1	420.00	$23.00	$9,660.00
			M	11	1	390.00	$35.00	$13,650.00
		Unit Sub Total	**M**		**2**	**810.00**	**$28.78**	**$23,310.00**
	Item Code 150241	**Total No. of Proj.**			**4**		**Total Amount**	**$31,450.00**
150305	OBLITERATE SURFACING		M2	3	3	26,960.00	$1.87	$50,468.00
			M2	4	4	14,196.00	$1.47	$20,900.00
			M2	8	1	3,130.00	$4.00	$12,520.00
		Unit Sub Total	**M2**		**8**	**44,286.00**	**$1.89**	**$83,888.00**
150305	OBLITERATE SURFACING		SQYD	7	1	4,160.00	$1.75	$7,280.00
			SQYD	8	1	110.00	$5.00	$550.00
		Unit Sub Total	**SQYD**		**2**	**4,270.00**	**$1.83**	**$7,830.00**
	Item Code 150305	**Total No. of Proj.**			**10**		**Total Amount**	**$91,718.00**
150604	REMOVE WOOD FENCE		LF	7	1	90.00	$19.50	$1,755.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**1**	**90.00**	**$19.50**	**$1,755.00**
150604	REMOVE WOOD FENCE		M	9	1	20.00	$8.00	$160.00
		Unit Sub Total	**M**		**1**	**20.00**	**$8.00**	**$160.00**
	Item Code 150604	**Total No. of Proj.**			**2**		**Total Amount**	**$1,915.00**
150605	REMOVE FENCE		LF	1	1	210.00	$12.00	$2,520.00
			LF	2	1	7,140.00	$2.10	$14,994.00
			LF	3	2	21,440.00	$3.14	$67,400.00
			LF	4	1	520.00	$5.00	$2,600.00
			LF	6	1	340.00	$4.00	$1,360.00
			LF	10	1	15.00	$10.00	$150.00
		Unit Sub Total	**LF**		**7**	**29,665.00**	**$3.00**	**$89,024.00**
150605	REMOVE FENCE		M	1	1	22.00	$66.00	$1,452.00
			M	2	2	26.00	$49.40	$1,284.27
			M	3	2	4,680.00	$3.31	$15,480.00
			M	4	1	5,950.00	$5.00	$29,750.00
			M	6	4	2,652.00	$5.40	$14,330.00
			M	8	1	1,350.00	$12.00	$16,200.00
			M	10	2	574.00	$24.39	$14,000.40
		Unit Sub Total	**M**		**13**	**15,254.00**	**$6.06**	**$92,496.67**
	Item Code 150605	**Total No. of Proj.**			**20**		**Total Amount**	**$181,520.67**
150606	REMOVE FENCE (TYPE BW)		LF	2	2	920.00	$2.72	$2,500.00
			LF	3	1	160.00	$2.76	$441.60
			LF	5	1	80.00	$10.00	$800.00
			LF	10	1	2,110.00	$2.00	$4,220.00
		Unit Sub Total	**LF**		**5**	**3,270.00**	**$2.43**	**$7,961.60**
150606	REMOVE FENCE (TYPE BW)		M	5	1	2,230.00	$3.00	$6,690.00
			M	9	2	1,390.00	$6.18	$8,590.00
			M	10	1	2,170.00	$5.10	$11,067.00
		Unit Sub Total	**M**		**4**	**5,790.00**	**$4.55**	**$26,347.00**
	Item Code 150606	**Total No. of Proj.**			**9**		**Total Amount**	**$34,308.60**
150607	REMOVE FENCE (TYPE WM)		M	3	1	2,230.00	$1.00	$2,230.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150607	REMOVE FENCE (TYPE WM)		M	10	1	510.00	$15.00	$7,650.00
		Unit Sub Total	**M**		**2**	**2,740.00**	**$3.61**	**$9,880.00**
	Item Code 150607	**Total No. of Proj.**			**2**		**Total Amount**	**$9,880.00**
150608	REMOVE CHAIN LINK FENCE		LF	4	2	1,360.00	$4.00	$5,440.00
			LF	5	3	461.00	$7.71	$3,555.30
			LF	6	1	1,010.00	$2.00	$2,020.00
			LF	7	2	15,120.00	$5.39	$81,516.00
			LF	8	4	5,570.00	$2.64	$14,726.00
			LF	11	5	12,105.00	$2.03	$24,570.00
			LF	12	2	6,020.00	$4.17	$25,100.00
		Unit Sub Total	**LF**		**19**	**41,646.00**	**$3.77**	**$156,927.30**
150608	REMOVE CHAIN LINK FENCE		M	2	1	560.00	$22.00	$12,320.00
			M	3	1	1,890.00	$5.50	$10,395.00
			M	4	7	15,760.00	$9.96	$156,906.00
			M	5	2	810.00	$16.42	$13,300.00
			M	7	3	4,835.00	$14.91	$72,090.00
			M	8	1	1,260.00	$10.00	$12,600.00
			M	11	3	1,870.00	$12.22	$22,850.00
		Unit Sub Total	**M**		**18**	**26,985.00**	**$11.13**	**$300,461.00**
	Item Code 150608	**Total No. of Proj.**			**37**		**Total Amount**	**$457,388.30**
150615	REMOVE ENTRANCE TAPER		EA	4	1	8.00	$850.00	$6,800.00
			EA	6	2	3.00	$180.00	$540.00
		Unit Sub Total	**EA**		**3**	**11.00**	**$667.27**	**$7,340.00**
	Item Code 150615	**Total No. of Proj.**			**3**		**Total Amount**	**$7,340.00**
150620	REMOVE GATE		EA	2	1	1.00	$225.00	$225.00
			EA	4	2	2.00	$225.00	$450.00
			EA	5	1	1.00	$100.00	$100.00
			EA	6	1	1.00	$500.00	$500.00
			EA	10	1	2.00	$1,000.00	$2,000.00
			EA	11	1	2.00	$80.00	$160.00
		Unit Sub Total	**EA**		**7**	**9.00**	**$381.67**	**$3,435.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150620	**Total No. of Proj.**			**7**		**Total Amount**	**$3,435.00**
150630	REMOVE MARKER		EA	1	1	7.00	$50.00	$350.00
			EA	2	7	60.00	$38.85	$2,331.00
			EA	3	1	1.00	$32.01	$32.01
			EA	8	1	17.00	$46.00	$782.00
			EA	10	1	1.00	$75.00	$75.00
			EA	11	1	4.00	$50.00	$200.00
		Unit Sub Total	**EA**		**12**	**90.00**	**$41.89**	**$3,770.01**
	Item Code 150630	**Total No. of Proj.**			**12**		**Total Amount**	**$3,770.01**
150645	REMOVE BARRICADE		M	11	1	14.00	$57.00	$798.00
		Unit Sub Total	**M**		**1**	**14.00**	**$57.00**	**$798.00**
	Item Code 150645	**Total No. of Proj.**			**1**		**Total Amount**	**$798.00**
150659	REMOVE TERMINAL SECTION		EA	3	1	1.00	$425.00	$425.00
			EA	4	1	1.00	$500.00	$500.00
			EA	6	1	1.00	$800.00	$800.00
		Unit Sub Total	**EA**		**3**	**3.00**	**$575.00**	**$1,725.00**
	Item Code 150659	**Total No. of Proj.**			**3**		**Total Amount**	**$1,725.00**
150662	REMOVE METAL BEAM GUARD RAILING		LF	1	5	1,848.00	$6.76	$12,496.50
			LF	2	12	17,273.00	$8.64	$149,295.50
			LF	3	9	51,435.00	$5.14	$264,491.55
			LF	4	12	58,934.00	$6.81	$401,233.30
			LF	5	7	11,760.00	$6.11	$71,856.00
			LF	6	6	17,830.00	$5.43	$96,790.00
			LF	7	8	6,392.00	$9.25	$59,115.00
			LF	8	11	7,221.00	$9.04	$65,254.96
			LF	9	1	80.00	$40.00	$3,200.00
			LF	10	2	740.00	$6.95	$5,140.00
			LF	11	8	9,137.00	$8.05	$73,589.00
			LF	12	8	30,897.00	$7.04	$217,550.00
		Unit Sub Total	**LF**		**89**	**213,547.00**	**$6.65**	**$1,420,011.81**
150662	REMOVE METAL BEAM GUARD RAILING		M	1	2	157.00	$47.13	$7,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150662	REMOVE METAL BEAM GUARD RAILING	M	2	1	610.00	$30.00	$18,300.00
		M	3	4	2,534.00	$18.72	$47,444.00
		M	4	11	7,855.00	$22.80	$179,095.00
		M	5	3	1,517.00	$20.90	$31,705.80
		M	6	2	106.00	$61.52	$6,521.00
		M	7	4	3,716.00	$28.32	$105,220.00
		M	8	2	2,790.00	$42.35	$118,160.00
		M	10	3	640.00	$22.01	$14,085.00
		M	11	2	1,620.00	$21.98	$35,600.00
	Unit Sub Total	**M**		**34**	**21,545.00**	**$26.16**	**$563,530.80**
	Item Code 150662 Total No. of Proj.			**123**		**Total Amount**	**$1,983,542.61**
150666	REMOVE METAL BEAM BARRIER	LF	7	1	8,870.00	$4.14	$36,721.80
		LF	10	1	11,600.00	$4.00	$46,400.00
	Unit Sub Total	**LF**		**2**	**20,470.00**	**$4.06**	**$83,121.80**
	Item Code 150666 Total No. of Proj.			**2**		**Total Amount**	**$83,121.80**
150667	REMOVE DOUBLE METAL BEAM BARRIER	LF	7	1	27,100.00	$4.85	$131,435.00
	Unit Sub Total	**LF**		**1**	**27,100.00**	**$4.85**	**$131,435.00**
	Item Code 150667 Total No. of Proj.			**1**		**Total Amount**	**$131,435.00**
150668	REMOVE FLARED END SECTION	EA	1	3	4.00	$127.50	$510.00
		EA	2	3	8.00	$450.00	$3,600.00
		EA	3	8	83.00	$320.06	$26,565.00
		EA	4	7	27.00	$352.96	$9,530.00
		EA	5	1	4.00	$100.00	$400.00
		EA	6	5	39.00	$377.18	$14,710.00
		EA	7	2	2.00	$200.00	$400.00
		EA	8	1	2.00	$100.00	$200.00
		EA	9	1	2.00	$400.00	$800.00
	Unit Sub Total	**EA**		**31**	**171.00**	**$331.67**	**$56,715.00**
	Item Code 150668 Total No. of Proj.			**31**		**Total Amount**	**$56,715.00**
150676	REMOVE CABLE RAILING	LF	7	1	560.00	$10.00	$5,600.00
	Unit Sub Total	**LF**		**1**	**560.00**	**$10.00**	**$5,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150676 Total No. of Proj.			**1**		**Total Amount**	**$5,600.00**
150685	REMOVE IRRIGATION FACILITY	EA	9	1	8.00	$150.00	$1,200.00
		EA	10	1	2.00	$1,000.00	$2,000.00
	Unit Sub Total	**EA**		**2**	**10.00**	**$320.00**	**$3,200.00**
150685	REMOVE IRRIGATION FACILITY	LS	4	1	1.00	$8,000.00	$8,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$8,000.00**	**$8,000.00**
	Item Code 150685 Total No. of Proj.			**3**		**Total Amount**	**$11,200.00**
150686	REMOVE IRRIGATION SYSTEM	LS	3	2	2.00	$4,275.00	$8,550.00
		LS	8	1	1.00	$400.00	$400.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$2,983.33**	**$8,950.00**
	Item Code 150686 Total No. of Proj.			**3**		**Total Amount**	**$8,950.00**
150701	REMOVE YELLOW PAINTED TRAFFIC STRIPE	LF	1	1	190.00	$8.00	$1,520.00
		LF	4	1	37,800.00	$0.52	$19,656.00
		LF	7	1	560.00	$0.85	$476.00
		LF	10	3	4,470.00	$1.62	$7,231.00
		LF	11	14	162,390.00	$0.96	$155,637.00
		LF	12	1	200.00	$6.60	$1,320.00
	Unit Sub Total	**LF**		**21**	**205,610.00**	**$0.90**	**$185,840.00**
150701	REMOVE YELLOW PAINTED TRAFFIC STRIPE	M	3	1	5,000.00	$1.50	$7,500.00
		M	4	3	13,660.00	$2.87	$39,230.00
		M	5	2	3,690.00	$1.42	$5,235.00
		M	6	1	18,200.00	$1.00	$18,200.00
		M	7	1	13,600.00	$0.80	$10,880.00
		M	8	1	14.00	$1.25	$17.50
		M	9	1	1,240.00	$4.30	$5,332.00
		M	10	1	1,190.00	$8.00	$9,520.00
		M	11	3	4,470.00	$2.96	$13,243.00
	Unit Sub Total	**M**		**14**	**61,064.00**	**$1.79**	**$109,157.50**
	Item Code 150701 Total No. of Proj.			**35**		**Total Amount**	**$294,997.50**
150702	REMOVE YELLOW PAINTED PAVEMENT MARKING	M2	10	1	17.00	$180.00	$3,060.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M2**		**1**	**17.00**	**$180.00**	**$3,060.00**
150702	REMOVE YELLOW PAINTED PAVEMENT MARKING		SQFT	4	1	190.00	$2.09	$397.10
		Unit Sub Total	**SQFT**		**1**	**190.00**	**$2.09**	**$397.10**
	Item Code 150702	**Total No. of Proj.**			**2**		**Total Amount**	**$3,457.10**
150704	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE		LF	1	13	46,780.00	$1.79	$83,943.00
			LF	2	5	24,410.00	$1.15	$28,100.00
			LF	3	6	86,410.00	$0.82	$70,973.90
			LF	4	30	630,888.00	$0.57	$361,218.80
			LF	5	14	351,380.00	$0.50	$174,189.50
			LF	6	4	179,730.00	$0.38	$67,735.50
			LF	7	30	389,360.00	$0.52	$203,816.60
			LF	8	14	275,180.00	$0.42	$114,263.00
			LF	10	6	80,640.00	$0.46	$37,049.00
			LF	12	17	621,840.00	$0.42	$263,592.80
		Unit Sub Total	**LF**		**139**	**2,686,618.00**	**$0.52**	**$1,404,882.10**
150704	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE		M	1	2	8,370.00	$2.59	$21,640.00
			M	3	1	3,010.00	$6.30	$18,963.00
			M	4	10	43,200.00	$1.78	$76,997.50
			M	5	2	7,960.00	$0.57	$4,549.00
			M	6	2	1,110.00	$1.63	$1,810.00
			M	7	5	32,050.00	$1.67	$53,394.00
			M	8	2	23,900.00	$1.10	$26,290.00
			M	10	6	6,910.00	$2.87	$19,806.50
		Unit Sub Total	**M**		**30**	**126,510.00**	**$1.77**	**$223,450.00**
	Item Code 150704	**Total No. of Proj.**			**169**		**Total Amount**	**$1,628,332.10**
150705	REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING		SQFT	1	1	170.00	$15.00	$2,550.00
			SQFT	2	1	810.00	$8.50	$6,885.00
			SQFT	4	5	9,290.00	$1.02	$9,463.30
			SQFT	5	1	70.00	$2.00	$140.00
			SQFT	6	2	140.00	$6.75	$945.00
			SQFT	7	2	2,030.00	$2.58	$5,232.80

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150705	REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING	SQFT	8	3	720.00	$3.18	$2,289.00
		SQFT	9	2	280.00	$6.00	$1,680.00
		SQFT	10	2	1,170.00	$2.17	$2,542.50
		SQFT	11	2	690.00	$9.46	$6,524.20
		SQFT	12	1	100.00	$4.00	$400.00
	Unit Sub Total	**SQFT**		**22**	**15,470.00**	**$2.50**	**$38,651.80**
	Item Code 150705 Total No. of Proj.			**22**		**Total Amount**	**$38,651.80**
150706	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING	SQFT	7	1	13,900.00	$0.60	$8,340.00
	Unit Sub Total	**SQFT**		**1**	**13,900.00**	**$0.60**	**$8,340.00**
	Item Code 150706 Total No. of Proj.			**1**		**Total Amount**	**$8,340.00**
150710	REMOVE TRAFFIC STRIPE	LF	1	1	2,430.00	$1.30	$3,159.00
		LF	2	2	108,550.00	$0.31	$34,075.00
		LF	3	4	259,770.00	$0.23	$58,965.00
		LF	4	2	182,500.00	$0.03	$5,405.00
		LF	5	1	910.00	$0.75	$682.50
		LF	6	4	84,440.00	$0.39	$32,845.00
		LF	7	3	27,080.00	$0.85	$23,085.00
		LF	8	6	39,260.00	$0.43	$16,716.00
		LF	9	2	1,630.00	$4.87	$7,936.00
		LF	11	2	78,900.00	$0.39	$31,150.00
		LF	12	1	900.00	$1.10	$990.00
	Unit Sub Total	**LF**		**28**	**786,370.00**	**$0.27**	**$215,008.50**
150710	REMOVE TRAFFIC STRIPE	M	3	3	40,490.00	$1.15	$46,390.00
		M	7	1	560.00	$2.20	$1,232.00
		M	8	1	222,000.00	$0.95	$210,900.00
		M	9	1	29,500.00	$1.55	$45,725.00
		M	11	3	143,170.00	$0.63	$90,353.00
	Unit Sub Total	**M**		**9**	**435,720.00**	**$0.91**	**$394,600.00**
	Item Code 150710 Total No. of Proj.			**37**		**Total Amount**	**$609,608.50**
150711	REMOVE PAINTED TRAFFIC STRIPE	LF	1	1	220.00	$5.00	$1,100.00
		LF	2	3	18,820.00	$0.71	$13,370.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150711	REMOVE PAINTED TRAFFIC STRIPE	LF	3	1	1,920.00	$1.00	$1,920.00
		LF	4	4	77,060.00	$0.42	$32,513.00
		LF	5	8	163,580.00	$0.28	$45,340.00
		LF	7	2	107,650.00	$0.37	$40,050.00
		LF	10	3	15,270.00	$0.53	$8,153.00
		LF	12	2	114,390.00	$0.42	$47,702.00
	Unit Sub Total	**LF**		**24**	**498,910.00**	**$0.38**	**$190,148.00**
150711	REMOVE PAINTED TRAFFIC STRIPE	M	1	2	820.00	$9.27	$7,600.00
		M	3	1	8,540.00	$2.10	$17,934.00
		M	4	5	24,210.00	$2.02	$48,885.00
		M	5	2	5,910.00	$1.48	$8,723.00
		M	6	2	9,880.00	$1.21	$11,986.00
		M	7	3	64,100.00	$1.33	$85,335.00
		M	8	1	40.00	$1.25	$50.00
		M	9	1	2,520.00	$3.40	$8,568.00
		M	10	2	5,740.00	$1.16	$6,631.00
	Unit Sub Total	**M**		**19**	**121,760.00**	**$1.61**	**$195,712.00**
	Item Code 150711 **Total No. of Proj.**			**43**		**Total Amount**	**$385,860.00**
150712	REMOVE PAINTED PAVEMENT MARKING	M2	4	2	76.00	$20.00	$1,520.00
		M2	5	1	110.00	$20.00	$2,200.00
		M2	6	1	300.00	$20.00	$6,000.00
		M2	7	1	24.00	$21.60	$518.40
		M2	9	1	4.10	$75.00	$307.50
		M2	10	2	19.00	$72.74	$1,382.00
		M2	11	1	87.00	$30.00	$2,610.00
	Unit Sub Total	**M2**		**9**	**620.10**	**$23.44**	**$14,537.90**
150712	REMOVE PAINTED PAVEMENT MARKING	SQFT	1	1	80.00	$11.00	$880.00
		SQFT	2	2	24.00	$17.50	$420.00
		SQFT	3	1	84.00	$2.00	$168.00
		SQFT	4	3	5,640.00	$2.22	$12,494.40
		SQFT	8	1	120.00	$5.50	$660.00
		SQFT	10	1	550.00	$1.80	$990.00
		SQFT	12	1	330.00	$2.00	$660.00
	Unit Sub Total	**SQFT**		**10**	**6,828.00**	**$2.38**	**$16,272.40**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150712	**Total No. of Proj.**			**19**		**Total Amount**	**$30,810.30**
150713	REMOVE PAVEMENT MARKING		M2	1	1	24.00	$3.00	$72.00
			M2	2	1	47.00	$32.00	$1,504.00
			M2	3	3	413.00	$7.06	$2,915.00
			M2	4	1	42.00	$30.00	$1,260.00
			M2	6	2	40.00	$26.00	$1,040.00
			M2	8	1	130.00	$16.00	$2,080.00
			M2	9	1	140.00	$30.00	$4,200.00
			M2	11	2	927.00	$7.09	$6,575.00
		Unit Sub Total	**M2**		**12**	**1,763.00**	**$11.14**	**$19,646.00**
150713	REMOVE PAVEMENT MARKING		SQFT	2	3	2,240.00	$3.42	$7,650.00
			SQFT	3	4	8,320.00	$1.59	$13,200.00
			SQFT	5	1	220.00	$2.00	$440.00
			SQFT	6	2	9,390.00	$1.23	$11,550.00
			SQFT	7	4	2,120.00	$3.18	$6,745.00
			SQFT	8	3	6,812.00	$0.49	$3,363.50
			SQFT	9	2	4,480.00	$2.68	$12,002.00
			SQFT	11	1	1,530.00	$2.70	$4,131.00
			SQFT	12	1	780.00	$1.10	$858.00
		Unit Sub Total	**SQFT**		**21**	**35,892.00**	**$1.67**	**$59,939.50**
	Item Code 150713	**Total No. of Proj.**			**33**		**Total Amount**	**$79,585.50**
150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE		LF	1	5	38,700.00	$0.70	$27,222.00
			LF	2	5	23,890.00	$0.88	$21,134.00
			LF	3	7	55,990.00	$0.70	$39,224.30
			LF	4	30	624,497.00	$0.47	$290,623.90
			LF	5	12	98,180.00	$0.83	$81,034.00
			LF	6	16	290,240.00	$0.42	$121,400.40
			LF	7	32	626,900.00	$0.49	$304,844.00
			LF	8	16	540,160.00	$0.27	$147,775.00
			LF	10	17	243,520.00	$0.52	$126,566.50
			LF	12	21	791,430.00	$0.32	$257,061.00
		Unit Sub Total	**LF**		**161**	**3,333,507.00**	**$0.43**	**$1,416,885.10**
150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE		LS	3	1	1.00	$15,384.00	$15,384.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LS**		**1**	**1.00**	**$15,384.00**	**$15,384.00**
150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	M	3	1	6,100.00	$1.40	$8,540.00
		M	4	11	93,060.00	$1.57	$146,435.00
		M	5	2	8,460.00	$0.50	$4,271.00
		M	6	1	500.00	$1.00	$500.00
		M	7	4	64,600.00	$1.20	$77,383.00
		M	8	2	24,340.00	$0.94	$22,942.00
		M	10	7	6,478.00	$1.93	$12,486.00
	Unit Sub Total	**M**		**28**	**203,538.00**	**$1.34**	**$272,557.00**
150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	SQFT	3	2	6,980.00	$1.40	$9,764.00
		SQFT	10	1	1,250.00	$0.50	$625.00
	Unit Sub Total	**SQFT**		**3**	**8,230.00**	**$1.26**	**$10,389.00**
	Item Code 150714 Total No. of Proj.			**193**		**Total Amount**	**$1,715,215.10**
150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	M2	3	1	30.00	$20.00	$600.00
		M2	4	5	264.00	$27.37	$7,226.00
		M2	5	1	33.00	$1.00	$33.00
		M2	6	1	12.00	$110.00	$1,320.00
		M2	7	3	272.00	$22.83	$6,209.20
		M2	8	2	144.00	$16.04	$2,310.00
		M2	10	4	94.00	$40.29	$3,787.00
	Unit Sub Total	**M2**		**17**	**849.00**	**$25.31**	**$21,485.20**
150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	SQFT	1	3	4,280.00	$5.28	$22,600.00
		SQFT	2	8	12,360.00	$4.90	$60,565.60
		SQFT	3	5	1,576.00	$4.01	$6,319.00
		SQFT	4	24	45,342.00	$0.95	$43,222.80
		SQFT	5	12	13,780.00	$2.06	$28,451.10
		SQFT	6	21	24,178.00	$2.13	$51,382.00
		SQFT	7	21	43,352.00	$1.65	$71,600.40
		SQFT	8	14	7,617.00	$2.87	$21,840.20
		SQFT	9	2	510.00	$5.91	$3,012.00
		SQFT	10	14	12,623.00	$2.30	$28,996.60
		SQFT	12	18	58,750.00	$1.36	$80,086.20
	Unit Sub Total	**SQFT**		**142**	**224,368.00**	**$1.86**	**$418,075.90**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150715 Total No. of Proj.			**159**		**Total Amount**	**$439,561.10**
150717	REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING	SQFT	11	16	489,620.00	$0.49	$238,493.00
	Unit Sub Total	**SQFT**		**16**	**489,620.00**	**$0.49**	**$238,493.00**
	Item Code 150717 Total No. of Proj.			**16**		**Total Amount**	**$238,493.00**
150718	REMOVE THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING	SQFT	3	1	3,390.00	$1.70	$5,763.00
		SQFT	4	1	422.00	$2.75	$1,160.50
		SQFT	7	1	26,100.00	$0.60	$15,660.00
	Unit Sub Total	**SQFT**		**3**	**29,912.00**	**$0.75**	**$22,583.50**
	Item Code 150718 Total No. of Proj.			**3**		**Total Amount**	**$22,583.50**
150720	REMOVE CONTRAST TREATMENT	M2	11	1	600.00	$26.00	$15,600.00
	Unit Sub Total	**M2**		**1**	**600.00**	**$26.00**	**$15,600.00**
150720	REMOVE CONTRAST TREATMENT	SQFT	3	2	175,120.00	$0.43	$75,097.60
		SQFT	4	1	2,353.00	$0.50	$1,176.50
		SQFT	7	1	9,797.00	$0.45	$4,408.65
		SQFT	10	1	65,146.00	$0.12	$7,817.52
		SQFT	11	4	283,385.00	$0.22	$63,488.40
	Unit Sub Total	**SQFT**		**9**	**535,801.00**	**$0.28**	**$151,988.67**
	Item Code 150720 Total No. of Proj.			**10**		**Total Amount**	**$167,588.67**
150722	REMOVE PAVEMENT MARKER	EA	1	1	130.00	$5.00	$650.00
		EA	2	4	2,070.00	$1.73	$3,590.00
		EA	3	1	19.00	$3.00	$57.00
		EA	4	49	221,877.00	$0.72	$158,795.80
		EA	5	8	3,539.00	$1.35	$4,789.94
		EA	6	9	10,624.00	$0.84	$8,931.60
		EA	7	41	184,680.00	$0.75	$137,675.96
		EA	8	28	130,519.00	$0.64	$84,077.90
		EA	10	16	15,353.00	$0.71	$10,973.00
		EA	11	1	153.00	$2.00	$306.00
		EA	12	17	41,520.00	$0.94	$38,969.40
	Unit Sub Total	**EA**		**175**	**610,484.00**	**$0.74**	**$448,816.60**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150722 Total No. of Proj.			**175**		**Total Amount**	**$448,816.60**
150730	REMOVE CHANNELIZERS	EA	1	1	440.00	$25.00	$11,000.00
		EA	4	1	200.00	$12.00	$2,400.00
		EA	7	1	55.00	$10.00	$550.00
		EA	8	2	40.00	$36.88	$1,475.00
		EA	11	1	18.00	$20.00	$360.00
		EA	12	3	742.00	$4.02	$2,984.60
	Unit Sub Total	**EA**		**9**	**1,495.00**	**$12.55**	**$18,769.60**
	Item Code 150730 Total No. of Proj.			**9**		**Total Amount**	**$18,769.60**
150741	REMOVE ROADSIDE SIGN MOUNTED ON MAST ARM	EA	11	1	1.00	$120.00	$120.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$120.00**	**$120.00**
	Item Code 150741 Total No. of Proj.			**1**		**Total Amount**	**$120.00**
150742	REMOVE ROADSIDE SIGN	EA	1	4	12.00	$104.17	$1,250.00
		EA	2	10	135.00	$135.24	$18,258.00
		EA	3	15	371.00	$53.65	$19,906.00
		EA	4	12	301.00	$65.20	$19,625.00
		EA	5	6	67.00	$69.45	$4,653.00
		EA	6	10	90.00	$76.56	$6,890.00
		EA	7	7	138.00	$205.07	$28,300.00
		EA	8	8	154.00	$108.29	$16,676.00
		EA	9	4	76.00	$97.17	$7,385.00
		EA	10	13	99.00	$43.97	$4,353.00
		EA	11	8	291.00	$112.37	$32,700.00
		EA	12	8	78.00	$60.56	$4,724.00
	Unit Sub Total	**EA**		**105**	**1,812.00**	**$90.91**	**$164,720.00**
	Item Code 150742 Total No. of Proj.			**105**		**Total Amount**	**$164,720.00**
150744	REMOVE ROADSIDE SIGN (WOOD POST)	EA	1	1	1.00	$68.00	$68.00
		EA	4	4	56.00	$98.57	$5,520.00
		EA	5	1	1.00	$100.00	$100.00
		EA	7	3	23.00	$103.26	$2,375.00
		EA	8	5	116.00	$108.10	$12,540.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150744	REMOVE ROADSIDE SIGN (WOOD POST)	EA	10	1	2.00	$120.00	$240.00
		EA	12	2	27.00	$170.00	$4,590.00
	Unit Sub Total	**EA**		**17**	**226.00**	**$112.54**	**$25,433.00**
	Item Code 150744 Total No. of Proj.			**17**		**Total Amount**	**$25,433.00**
150745	REMOVE ROADSIDE SIGN (METAL POST)	EA	4	3	17.00	$87.06	$1,480.00
		EA	7	1	5.00	$1.15	$5.75
		EA	10	1	1.00	$120.00	$120.00
		EA	12	1	1.00	$100.00	$100.00
	Unit Sub Total	**EA**		**6**	**24.00**	**$71.07**	**$1,705.75**
	Item Code 150745 Total No. of Proj.			**6**		**Total Amount**	**$1,705.75**
150747	REMOVE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	2	2	3.00	$86.67	$260.00
		EA	3	2	12.00	$50.00	$600.00
		EA	4	6	30.00	$61.17	$1,835.00
		EA	7	3	55.00	$83.62	$4,599.00
		EA	12	3	11.00	$53.64	$590.00
	Unit Sub Total	**EA**		**16**	**111.00**	**$71.03**	**$7,884.00**
	Item Code 150747 Total No. of Proj.			**16**		**Total Amount**	**$7,884.00**
150748	REMOVE ROADSIDE SIGN PANEL	EA	2	2	3.00	$383.33	$1,150.00
		EA	3	2	2.00	$100.00	$200.00
		EA	4	2	7.00	$97.14	$680.00
		EA	7	2	8.00	$21.88	$175.00
		EA	12	2	8.00	$50.00	$400.00
	Unit Sub Total	**EA**		**10**	**28.00**	**$93.04**	**$2,605.00**
	Item Code 150748 Total No. of Proj.			**10**		**Total Amount**	**$2,605.00**
150749	REMOVE METAL POST	EA	5	1	2.00	$25.00	$50.00
		EA	8	1	1.00	$45.00	$45.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$31.67**	**$95.00**
	Item Code 150749 Total No. of Proj.			**2**		**Total Amount**	**$95.00**
150760	REMOVE SIGN STRUCTURE	EA	2	1	2.00	$3,500.00	$7,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150760	REMOVE SIGN STRUCTURE	EA	3	3	28.00	$3,326.79	$93,150.00
		EA	4	10	33.00	$6,212.12	$205,000.00
		EA	6	2	2.00	$14,500.00	$29,000.00
		EA	7	6	42.00	$3,400.00	$142,800.00
		EA	8	4	18.00	$6,972.22	$125,500.00
		EA	11	2	4.00	$2,625.00	$10,500.00
		EA	12	3	12.00	$3,683.33	$44,200.00
	Unit Sub Total	**EA**		**31**	**141.00**	**$4,660.64**	**$657,150.00**
	Item Code 150760 Total No. of Proj.			**31**		**Total Amount**	**$657,150.00**
150763	REMOVE SIGN PANEL	EA	3	1	3.00	$90.00	$270.00
		EA	5	1	4.00	$50.00	$200.00
		EA	7	5	68.00	$180.88	$12,300.00
		EA	8	2	7.00	$185.71	$1,300.00
		EA	10	1	3.00	$42.00	$126.00
	Unit Sub Total	**EA**		**10**	**85.00**	**$167.01**	**$14,196.00**
	Item Code 150763 Total No. of Proj.			**10**		**Total Amount**	**$14,196.00**
150764	REMOVE SIGN OVERLAY	EA	11	1	20.00	$150.00	$3,000.00
	Unit Sub Total	**EA**		**1**	**20.00**	**$150.00**	**$3,000.00**
	Item Code 150764 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
150767	REMOVE BRIDGE MOUNTED SIGN	EA	3	3	16.00	$1,962.50	$31,400.00
		EA	7	4	9.00	$1,977.78	$17,800.00
	Unit Sub Total	**EA**		**7**	**25.00**	**$1,968.00**	**$49,200.00**
	Item Code 150767 Total No. of Proj.			**7**		**Total Amount**	**$49,200.00**
150769	REMOVE ASPHALT CONCRETE	CY	9	3	112.00	$94.38	$10,570.00
	Unit Sub Total	**CY**		**3**	**112.00**	**$94.38**	**$10,570.00**
150769	REMOVE ASPHALT CONCRETE	SQYD	2	1	530.00	$3.60	$1,908.00
	Unit Sub Total	**SQYD**		**1**	**530.00**	**$3.60**	**$1,908.00**
	Item Code 150769 Total No. of Proj.			**4**		**Total Amount**	**$12,478.00**
150771	REMOVE ASPHALT CONCRETE DIKE	LF	1	7	3,240.00	$4.12	$13,358.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150771	REMOVE ASPHALT CONCRETE DIKE	LF	2	6	9,516.00	$2.52	$23,979.40
		LF	3	11	57,440.00	$1.71	$98,222.70
		LF	4	8	110,490.00	$0.76	$83,540.00
		LF	5	8	11,751.00	$4.35	$51,073.00
		LF	6	1	1,850.00	$1.00	$1,850.00
		LF	7	9	5,933.50	$4.22	$25,056.00
		LF	8	11	21,470.00	$3.91	$83,875.60
		LF	9	1	6,300.00	$1.50	$9,450.00
		LF	10	1	590.00	$1.00	$590.00
		LF	11	6	13,585.00	$1.60	$21,743.80
		LF	12	6	8,168.00	$5.29	$43,220.00
	Unit Sub Total	**LF**		**75**	**250,333.50**	**$1.82**	**$455,958.50**
150771	REMOVE ASPHALT CONCRETE DIKE	M	3	1	49.00	$1.00	$49.00
		M	4	7	1,616.00	$15.85	$25,620.00
		M	5	2	2,130.00	$4.52	$9,628.40
		M	6	2	239.00	$18.35	$4,385.00
		M	7	3	2,970.00	$5.41	$16,060.00
		M	8	2	12,156.00	$3.64	$44,288.00
		M	9	1	7,370.00	$1.00	$7,370.00
		M	10	2	1,220.00	$2.24	$2,730.00
		M	11	2	1,590.00	$10.23	$16,270.00
	Unit Sub Total	**M**		**22**	**29,340.00**	**$4.31**	**$126,400.40**
	Item Code 150771 Total No. of Proj.			**97**		**Total Amount**	**$582,358.90**
150772	REMOVE CURB	LF	4	1	2,950.00	$7.00	$20,650.00
	Unit Sub Total	**LF**		**1**	**2,950.00**	**$7.00**	**$20,650.00**
	Item Code 150772 Total No. of Proj.			**1**		**Total Amount**	**$20,650.00**
150780	REMOVE GUTTER DRAIN	CY	12	1	32.00	$232.00	$7,424.00
	Unit Sub Total	**CY**		**1**	**32.00**	**$232.00**	**$7,424.00**
	Item Code 150780 Total No. of Proj.			**1**		**Total Amount**	**$7,424.00**
150801	REMOVE OVERSIDE DRAIN	EA	1	3	4.00	$825.00	$3,300.00
		EA	2	4	7.00	$1,160.71	$8,125.00
		EA	3	2	4.00	$625.00	$2,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150801	REMOVE OVERSIDE DRAIN		EA	4	2	21.00	$733.33	$15,400.00
			EA	5	1	2.00	$400.00	$800.00
			EA	12	1	1.00	$600.00	$600.00
		Unit Sub Total	**EA**		**13**	**39.00**	**$787.82**	**$30,725.00**
150801	REMOVE OVERSIDE DRAIN		LF	5	1	160.00	$15.00	$2,400.00
		Unit Sub Total	**LF**		**1**	**160.00**	**$15.00**	**$2,400.00**
150801	REMOVE OVERSIDE DRAIN		M	4	1	16.00	$25.00	$400.00
		Unit Sub Total	**M**		**1**	**16.00**	**$25.00**	**$400.00**
	Item Code 150801	**Total No. of Proj.**			**15**		**Total Amount**	**$33,525.00**
150804	REMOVE DRAINAGE FACILITY		EA	8	1	27.00	$500.00	$13,500.00
		Unit Sub Total	**EA**		**1**	**27.00**	**$500.00**	**$13,500.00**
150804	REMOVE DRAINAGE FACILITY		LS	7	4	4.00	$8,277.50	$33,110.00
		Unit Sub Total	**LS**		**4**	**4.00**	**$8,277.50**	**$33,110.00**
	Item Code 150804	**Total No. of Proj.**			**5**		**Total Amount**	**$46,610.00**
150805	REMOVE CULVERT		EA	1	9	56.00	$1,503.84	$84,215.00
			EA	2	5	27.00	$2,743.70	$74,080.00
			EA	3	3	48.00	$1,167.71	$56,050.00
			EA	4	1	1.00	$1,500.00	$1,500.00
			EA	6	1	20.00	$700.00	$14,000.00
		Unit Sub Total	**EA**		**19**	**152.00**	**$1,512.14**	**$229,845.00**
150805	REMOVE CULVERT		LF	1	3	970.00	$6.07	$5,892.00
			LF	2	8	1,123.00	$22.11	$24,825.00
			LF	3	5	3,253.00	$7.58	$24,659.00
			LF	4	6	2,032.00	$12.70	$25,809.80
			LF	5	2	119.00	$9.32	$1,109.00
			LF	7	1	84.00	$25.00	$2,100.00
			LF	8	1	2.00	$200.00	$400.00
			LF	11	1	120.00	$20.00	$2,400.00
			LF	12	4	1,072.00	$35.26	$37,795.00
		Unit Sub Total	**LF**		**31**	**8,775.00**	**$14.24**	**$124,989.80**
150805	REMOVE CULVERT		M	3	5	1,126.00	$50.93	$57,350.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150805	REMOVE CULVERT		M	4	11	4,769.00	$58.75	$280,196.00
			M	5	3	147.20	$73.82	$10,866.82
			M	6	3	1,958.00	$29.71	$58,180.00
			M	10	5	331.00	$61.38	$20,316.00
			M	11	1	730.00	$107.00	$78,110.00
		Unit Sub Total	**M**		**28**	**9,061.20**	**$55.73**	**$505,018.82**
	Item Code 150805	**Total No. of Proj.**			**78**		**Total Amount**	**$859,853.62**
150806	REMOVE PIPE		EA	10	2	7.00	$1,090.00	$7,630.00
		Unit Sub Total	**EA**		**2**	**7.00**	**$1,090.00**	**$7,630.00**
150806	REMOVE PIPE		LF	4	2	1,012.00	$3.01	$3,044.00
			LF	5	5	2,155.00	$13.71	$29,550.00
			LF	6	2	80.00	$39.60	$3,168.00
			LF	7	6	3,645.00	$30.00	$109,358.00
			LF	8	2	466.00	$60.07	$27,994.00
			LF	10	1	890.00	$23.00	$20,470.00
			LF	11	1	20.00	$185.00	$3,700.00
			LF	12	1	810.00	$25.00	$20,250.00
		Unit Sub Total	**LF**		**20**	**9,078.00**	**$23.96**	**$217,534.00**
150806	REMOVE PIPE		M	4	1	130.00	$58.00	$7,540.00
			M	7	4	1,294.00	$56.03	$72,500.00
			M	8	1	560.00	$105.00	$58,800.00
			M	10	1	550.00	$40.00	$22,000.00
		Unit Sub Total	**M**		**7**	**2,534.00**	**$63.47**	**$160,840.00**
	Item Code 150806	**Total No. of Proj.**			**29**		**Total Amount**	**$386,004.00**
150820	REMOVE INLET		EA	1	9	26.00	$721.15	$18,750.00
			EA	2	12	58.00	$927.07	$53,770.00
			EA	3	8	80.00	$692.25	$55,380.00
			EA	4	16	304.00	$620.27	$188,561.08
			EA	5	10	43.00	$355.01	$15,265.44
			EA	6	5	17.00	$929.41	$15,800.00
			EA	7	7	210.00	$732.67	$153,860.00
			EA	8	4	25.00	$1,528.00	$38,200.00
			EA	9	1	1.00	$850.00	$850.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150820	REMOVE INLET		EA	10	4	59.00	$363.56	$21,450.00
			EA	11	3	22.00	$740.91	$16,300.00
			EA	12	3	19.00	$568.42	$10,800.00
		Unit Sub Total	**EA**		**82**	**864.00**	**$681.70**	**$588,986.52**
	Item Code 150820	**Total No. of Proj.**			**82**		**Total Amount**	**$588,986.52**
150821	REMOVE HEADWALL		EA	1	5	14.00	$1,210.71	$16,950.00
			EA	2	11	40.00	$563.05	$22,521.82
			EA	3	8	102.00	$522.45	$53,290.00
			EA	4	8	38.00	$963.95	$36,630.00
			EA	5	3	4.00	$1,585.00	$6,340.00
			EA	6	1	16.00	$400.00	$6,400.00
			EA	7	4	10.00	$723.00	$7,230.00
			EA	8	3	9.00	$1,750.00	$15,750.00
			EA	9	2	8.00	$771.88	$6,175.00
			EA	10	3	6.00	$913.33	$5,480.00
			EA	11	1	40.00	$552.00	$22,080.00
			EA	12	1	8.00	$1,000.00	$8,000.00
		Unit Sub Total	**EA**		**50**	**295.00**	**$701.18**	**$206,846.82**
150821	REMOVE HEADWALL		LF	4	1	16.00	$50.00	$800.00
		Unit Sub Total	**LF**		**1**	**16.00**	**$50.00**	**$800.00**
	Item Code 150821	**Total No. of Proj.**			**51**		**Total Amount**	**$207,646.82**
150823	REMOVE DOWNDRAIN		EA	1	7	11.00	$581.82	$6,400.00
			EA	3	3	24.00	$778.75	$18,690.00
			EA	10	1	2.00	$500.00	$1,000.00
		Unit Sub Total	**EA**		**11**	**37.00**	**$705.14**	**$26,090.00**
150823	REMOVE DOWNDRAIN		LF	1	1	21.00	$23.00	$483.00
			LF	2	1	130.00	$11.50	$1,495.00
			LF	3	1	140.00	$25.00	$3,500.00
			LF	4	2	80.00	$38.13	$3,050.00
			LF	5	1	83.00	$25.00	$2,075.00
			LF	8	1	40.00	$45.00	$1,800.00
		Unit Sub Total	**LF**		**7**	**494.00**	**$25.11**	**$12,403.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150823	REMOVE DOWNDRAIN	M	3	1	74.00	$100.00	$7,400.00
		M	5	2	31.00	$74.84	$2,320.00
		M	7	1	72.00	$56.00	$4,032.00
		M	9	1	85.00	$100.00	$8,500.00
		M	10	2	159.00	$29.79	$4,737.00
	Unit Sub Total	**M**		**7**	**421.00**	**$64.11**	**$26,989.00**
	Item Code 150823 Total No. of Proj.			**25**		**Total Amount**	**$65,482.00**
150824	REMOVE SEWER MANHOLE	EA	7	1	15.00	$1,600.00	$24,000.00
		EA	11	1	1.00	$2,900.00	$2,900.00
	Unit Sub Total	**EA**		**2**	**16.00**	**$1,681.25**	**$26,900.00**
	Item Code 150824 Total No. of Proj.			**2**		**Total Amount**	**$26,900.00**
150825	REMOVE REINFORCED CONCRETE BOX CULVERT	M3	3	1	58.00	$100.00	$5,800.00
	Unit Sub Total	**M3**		**1**	**58.00**	**$100.00**	**$5,800.00**
	Item Code 150825 Total No. of Proj.			**1**		**Total Amount**	**$5,800.00**
150826	REMOVE MANHOLE	EA	1	1	1.00	$2,000.00	$2,000.00
		EA	3	1	2.00	$450.00	$900.00
		EA	4	6	15.00	$1,472.00	$22,080.00
		EA	5	1	1.00	$1,200.00	$1,200.00
		EA	7	1	2.00	$1,700.00	$3,400.00
		EA	10	1	6.00	$500.00	$3,000.00
		EA	12	2	2.00	$1,825.00	$3,650.00
	Unit Sub Total	**EA**		**13**	**29.00**	**$1,249.31**	**$36,230.00**
	Item Code 150826 Total No. of Proj.			**13**		**Total Amount**	**$36,230.00**
150827	REMOVE CATCH BASIN	EA	7	1	3.00	$1,700.00	$5,100.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$1,700.00**	**$5,100.00**
	Item Code 150827 Total No. of Proj.			**1**		**Total Amount**	**$5,100.00**
150828	REMOVE JUNCTION BOX	EA	2	1	1.00	$900.00	$900.00
		EA	3	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$950.00**	**$1,900.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150828	**Total No. of Proj.**			**2**		**Total Amount**	**$1,900.00**
150829	REMOVE RETAINING WALL		LF	2	1	88.00	$30.00	$2,640.00
			LF	4	1	250.00	$10.00	$2,500.00
			LF	5	1	12.00	$225.00	$2,700.00
			LF	7	1	170.00	$45.00	$7,650.00
		Unit Sub Total	**LF**		**4**	**520.00**	**$29.79**	**$15,490.00**
150829	REMOVE RETAINING WALL		LS	4	2	2.00	$31,500.00	$63,000.00
		Unit Sub Total	**LS**		**2**	**2.00**	**$31,500.00**	**$63,000.00**
150829	REMOVE RETAINING WALL		M	3	1	240.00	$50.00	$12,000.00
			M	4	2	105.00	$115.57	$12,135.00
			M	7	1	190.00	$500.00	$95,000.00
			M	8	1	310.00	$100.00	$31,000.00
		Unit Sub Total	**M**		**5**	**845.00**	**$177.67**	**$150,135.00**
150829	REMOVE RETAINING WALL		M3	7	1	190.00	$86.00	$16,340.00
		Unit Sub Total	**M3**		**1**	**190.00**	**$86.00**	**$16,340.00**
	Item Code 150829	**Total No. of Proj.**			**12**		**Total Amount**	**$244,965.00**
150830	REMOVE RETAINING WALL (PORTION)		CY	8	1	17.00	$1,100.00	$18,700.00
		Unit Sub Total	**CY**		**1**	**17.00**	**$1,100.00**	**$18,700.00**
150830	REMOVE RETAINING WALL (PORTION)		LS	2	1	1.00	$10,000.00	$10,000.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$10,000.00**	**$10,000.00**
150830	REMOVE RETAINING WALL (PORTION)		M	7	1	30.00	$200.00	$6,000.00
			M	10	1	8.00	$213.00	$1,704.00
		Unit Sub Total	**M**		**2**	**38.00**	**$202.74**	**$7,704.00**
	Item Code 150830	**Total No. of Proj.**			**4**		**Total Amount**	**$36,404.00**
150841	REMOVE SEWER PIPE		LF	4	1	45.00	$5.00	$225.00
		Unit Sub Total	**LF**		**1**	**45.00**	**$5.00**	**$225.00**
150841	REMOVE SEWER PIPE		M	4	1	40.00	$7.00	$280.00
			M	7	1	980.00	$42.00	$41,160.00
			M	11	1	120.00	$28.00	$3,360.00
		Unit Sub Total	**M**		**3**	**1,140.00**	**$39.30**	**$44,800.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150841 Total No. of Proj.			**4**		**Total Amount**	**$45,025.00**
150846	REMOVE CONCRETE PAVEMENT	CY	2	1	1,880.00	$40.00	$75,200.00
	Unit Sub Total	**CY**		**1**	**1,880.00**	**$40.00**	**$75,200.00**
150846	REMOVE CONCRETE PAVEMENT	M2	4	1	11,210.00	$20.00	$224,200.00
		M2	7	1	420.00	$18.00	$7,560.00
		M2	8	1	29,100.00	$4.00	$116,400.00
	Unit Sub Total	**M2**		**3**	**40,730.00**	**$8.55**	**$348,160.00**
150846	REMOVE CONCRETE PAVEMENT	M3	4	1	1,220.00	$33.00	$40,260.00
		M3	7	1	190.00	$225.00	$42,750.00
	Unit Sub Total	**M3**		**2**	**1,410.00**	**$58.87**	**$83,010.00**
150846	REMOVE CONCRETE PAVEMENT	SQYD	7	2	78,600.00	$5.23	$411,450.00
		SQYD	12	1	520.00	$18.00	$9,360.00
	Unit Sub Total	**SQYD**		**3**	**79,120.00**	**$5.32**	**$420,810.00**
	Item Code 150846 Total No. of Proj.			**9**		**Total Amount**	**$927,180.00**
150847	REMOVE CONCRETE PAVEMENT AND BASE	CY	4	1	150.00	$69.90	$10,485.00
	Unit Sub Total	**CY**		**1**	**150.00**	**$69.90**	**$10,485.00**
	Item Code 150847 Total No. of Proj.			**1**		**Total Amount**	**$10,485.00**
150855	REMOVE PAVEMENT	CY	6	1	350.00	$90.00	$31,500.00
	Unit Sub Total	**CY**		**1**	**350.00**	**$90.00**	**$31,500.00**
	Item Code 150855 Total No. of Proj.			**1**		**Total Amount**	**$31,500.00**
150857	REMOVE ASPHALT CONCRETE SURFACING	CY	8	1	310.00	$20.00	$6,200.00
		CY	12	1	11.00	$130.00	$1,430.00
	Unit Sub Total	**CY**		**2**	**321.00**	**$23.77**	**$7,630.00**
150857	REMOVE ASPHALT CONCRETE SURFACING	M2	3	1	305.00	$12.40	$3,782.00
	Unit Sub Total	**M2**		**1**	**305.00**	**$12.40**	**$3,782.00**
150857	REMOVE ASPHALT CONCRETE SURFACING	SQFT	1	4	39,305.00	$2.43	$95,508.75
		SQFT	2	2	70,912.00	$1.94	$137,575.28
		SQFT	3	4	221,189.00	$0.54	$118,996.15
		SQFT	4	6	192,588.00	$1.21	$232,540.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150857	REMOVE ASPHALT CONCRETE SURFACING	SQFT	5	2	11,080.00	$0.41	$4,541.60
		SQFT	7	3	260,640.00	$0.61	$157,848.00
		SQFT	8	5	47,272.00	$1.24	$58,779.75
	Unit Sub Total	**SQFT**		**26**	**842,986.00**	**$0.96**	**$805,789.53**
150857	REMOVE ASPHALT CONCRETE SURFACING	SQYD	3	1	50.00	$10.00	$500.00
	Unit Sub Total	**SQYD**		**1**	**50.00**	**$10.00**	**$500.00**
	Item Code 150857 Total No. of Proj.			**30**		**Total Amount**	**$817,701.53**
150859	REMOVE ASPHALT CONCRETE OVERSIDE DRAIN	EA	1	1	3.00	$400.00	$1,200.00
		EA	3	1	21.00	$160.00	$3,360.00
		EA	8	1	3.00	$750.00	$2,250.00
		EA	9	1	47.00	$450.00	$21,150.00
	Unit Sub Total	**EA**		**4**	**74.00**	**$377.84**	**$27,960.00**
	Item Code 150859 Total No. of Proj.			**4**		**Total Amount**	**$27,960.00**
150860	REMOVE BASE AND SURFACING	CY	3	1	85.00	$134.00	$11,390.00
		CY	4	1	1,300.00	$20.00	$26,000.00
		CY	8	1	1,070.00	$16.00	$17,120.00
		CY	11	1	220.00	$15.00	$3,300.00
	Unit Sub Total	**CY**		**4**	**2,675.00**	**$21.61**	**$57,810.00**
150860	REMOVE BASE AND SURFACING	M3	3	2	10,870.00	$8.63	$93,760.00
		M3	4	6	10,672.00	$15.35	$163,860.00
		M3	6	2	4,835.00	$7.29	$35,245.00
		M3	8	2	5,930.00	$19.65	$116,520.00
		M3	9	1	2,840.00	$5.00	$14,200.00
		M3	10	2	1,830.00	$4.36	$7,986.00
		M3	11	1	2,920.00	$10.00	$29,200.00
	Unit Sub Total	**M3**		**16**	**39,897.00**	**$11.55**	**$460,771.00**
150860	REMOVE BASE AND SURFACING	SQFT	8	1	5,130.00	$1.50	$7,695.00
	Unit Sub Total	**SQFT**		**1**	**5,130.00**	**$1.50**	**$7,695.00**
	Item Code 150860 Total No. of Proj.			**21**		**Total Amount**	**$526,276.00**
150870	REMOVE CONCRETE DECK SURFACE	M2	6	1	230.00	$48.00	$11,040.00
	Unit Sub Total	**M2**		**1**	**230.00**	**$48.00**	**$11,040.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150870	REMOVE CONCRETE DECK SURFACE	SQFT	1	1	8,371.00	$2.75	$23,020.25
		SQFT	2	1	17,989.00	$1.87	$33,639.43
		SQFT	3	2	6,217.00	$2.77	$17,200.00
		SQFT	4	2	16,685.00	$1.40	$23,308.00
		SQFT	7	2	50,980.00	$1.20	$61,176.00
		SQFT	8	1	4,120.00	$5.00	$20,600.00
	Unit Sub Total	**SQFT**		**9**	**104,362.00**	**$1.71**	**$178,943.68**
	Item Code 150870 Total No. of Proj.			**10**		**Total Amount**	**$189,983.68**
151224	REMOVE DELINEATOR	EA	1	1	25.00	$20.00	$500.00
		EA	2	6	125.00	$24.83	$3,104.00
		EA	3	1	6.00	$30.45	$182.70
		EA	8	1	160.00	$7.00	$1,120.00
		EA	9	1	10.00	$65.00	$650.00
		EA	10	3	27.00	$9.44	$255.00
		EA	11	1	35.00	$10.00	$350.00
		EA	12	3	64.00	$14.38	$920.00
	Unit Sub Total	**EA**		**17**	**452.00**	**$15.67**	**$7,081.70**
	Item Code 151224 Total No. of Proj.			**17**		**Total Amount**	**$7,081.70**
151265	SALVAGE SINGLE THRIE BEAM BARRIER	LF	6	1	480.00	$15.00	$7,200.00
	Unit Sub Total	**LF**		**1**	**480.00**	**$15.00**	**$7,200.00**
151265	SALVAGE SINGLE THRIE BEAM BARRIER	M	10	1	1,660.00	$14.00	$23,240.00
	Unit Sub Total	**M**		**1**	**1,660.00**	**$14.00**	**$23,240.00**
	Item Code 151265 Total No. of Proj.			**2**		**Total Amount**	**$30,440.00**
151266	SALVAGE DOUBLE THRIE BEAM BARRIER	M	8	1	1,280.00	$22.00	$28,160.00
	Unit Sub Total	**M**		**1**	**1,280.00**	**$22.00**	**$28,160.00**
	Item Code 151266 Total No. of Proj.			**1**		**Total Amount**	**$28,160.00**
151270	SALVAGE METAL BRIDGE RAILING	LF	2	1	460.00	$5.00	$2,300.00
		LF	4	1	2,940.00	$7.00	$20,580.00
		LF	5	1	50.00	$10.00	$500.00
		LF	6	1	2,820.00	$6.00	$16,920.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**4**	**6,270.00**	**$6.43**	**$40,300.00**
151270	SALVAGE METAL BRIDGE RAILING	LS	8	1	1.00	$5,000.00	$5,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$5,000.00**	**$5,000.00**
151270	SALVAGE METAL BRIDGE RAILING	M	5	1	146.00	$20.00	$2,920.00
		M	7	3	994.00	$23.60	$23,460.00
		M	8	1	2,040.00	$6.00	$12,240.00
	Unit Sub Total	**M**		**5**	**3,180.00**	**$12.14**	**$38,620.00**
	Item Code 151270 Total No. of Proj.			**10**		**Total Amount**	**$83,920.00**
151272	SALVAGE METAL BEAM GUARD RAILING	LF	3	1	4,050.00	$4.00	$16,200.00
		LF	4	1	190.00	$15.00	$2,850.00
		LF	6	1	95.00	$15.00	$1,425.00
		LF	8	1	480.00	$11.00	$5,280.00
	Unit Sub Total	**LF**		**4**	**4,815.00**	**$5.35**	**$25,755.00**
151272	SALVAGE METAL BEAM GUARD RAILING	M	8	1	170.00	$35.00	$5,950.00
		M	9	1	60.00	$17.50	$1,050.00
	Unit Sub Total	**M**		**2**	**230.00**	**$30.43**	**$7,000.00**
	Item Code 151272 Total No. of Proj.			**6**		**Total Amount**	**$32,755.00**
151274	SALVAGE CONCRETE BARRIER (TYPE K)	LF	1	1	370.00	$6.30	$2,331.00
		LF	4	1	700.00	$15.00	$10,500.00
		LF	7	2	11,250.00	$3.34	$37,540.00
		LF	8	1	420.00	$23.00	$9,660.00
	Unit Sub Total	**LF**		**5**	**12,740.00**	**$4.71**	**$60,031.00**
151274	SALVAGE CONCRETE BARRIER (TYPE K)	M	7	3	2,070.00	$9.33	$19,317.50
		M	8	1	6,110.00	$9.50	$58,045.00
	Unit Sub Total	**M**		**4**	**8,180.00**	**$9.46**	**$77,362.50**
	Item Code 151274 Total No. of Proj.			**9**		**Total Amount**	**$137,393.50**
151512	RECONSTRUCT INLET	EA	2	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$2,000.00**	**$2,000.00**
	Item Code 151512 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
151534	RECONSTRUCT WOOD FENCE	LF	2	1	46.00	$46.00	$2,116.00
	Unit Sub Total	**LF**		**1**	**46.00**	**$46.00**	**$2,116.00**
	Item Code 151534 Total No. of Proj.			**1**		**Total Amount**	**$2,116.00**
151536	RECONSTRUCT FENCE (TYPE BW)	LF	5	1	63.00	$45.00	$2,835.00
	Unit Sub Total	**LF**		**1**	**63.00**	**$45.00**	**$2,835.00**
151536	RECONSTRUCT FENCE (TYPE BW)	M	6	1	110.00	$45.00	$4,950.00
	Unit Sub Total	**M**		**1**	**110.00**	**$45.00**	**$4,950.00**
	Item Code 151536 Total No. of Proj.			**2**		**Total Amount**	**$7,785.00**
151537	RECONSTRUCT FENCE (TYPE WM)	M	3	1	91.00	$18.00	$1,638.00
	Unit Sub Total	**M**		**1**	**91.00**	**$18.00**	**$1,638.00**
	Item Code 151537 Total No. of Proj.			**1**		**Total Amount**	**$1,638.00**
151538	RECONSTRUCT CHAIN LINK RAILING	LF	2	1	535.00	$45.60	$24,396.00
	Unit Sub Total	**LF**		**1**	**535.00**	**$45.60**	**$24,396.00**
	Item Code 151538 Total No. of Proj.			**1**		**Total Amount**	**$24,396.00**
151540	RECONSTRUCT CHAIN LINK FENCE	LF	4	1	1,400.00	$15.00	$21,000.00
		LF	5	2	3,160.00	$18.34	$57,966.40
		LF	7	2	123.00	$44.54	$5,479.00
		LF	8	2	680.00	$19.35	$13,160.00
	Unit Sub Total	**LF**		**7**	**5,363.00**	**$18.20**	**$97,605.40**
151540	RECONSTRUCT CHAIN LINK FENCE	M	4	1	120.00	$87.00	$10,440.00
		M	6	2	346.00	$56.53	$19,560.00
		M	7	1	31.00	$150.00	$4,650.00
	Unit Sub Total	**M**		**4**	**497.00**	**$69.72**	**$34,650.00**
	Item Code 151540 Total No. of Proj.			**11**		**Total Amount**	**$132,255.40**
151570	RECONSTRUCT DOUBLE THRIE BEAM BARRIER	LF	4	1	560.00	$21.50	$12,040.00
	Unit Sub Total	**LF**		**1**	**560.00**	**$21.50**	**$12,040.00**
	Item Code 151570 Total No. of Proj.			**1**		**Total Amount**	**$12,040.00**
151572	RECONSTRUCT METAL BEAM GUARD RAILING	LF	1	4	1,305.00	$28.23	$36,845.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
151572	RECONSTRUCT METAL BEAM GUARD RAILING	LF	2	8	15,835.00	$17.65	$279,468.00
		LF	3	2	9,670.00	$24.57	$237,551.80
		LF	4	4	9,810.00	$15.76	$154,639.80
		LF	5	1	130.00	$65.00	$8,450.00
		LF	8	2	3,224.00	$18.27	$58,906.00
	Unit Sub Total	**LF**		**21**	**39,974.00**	**$19.41**	**$775,860.60**
151572	RECONSTRUCT METAL BEAM GUARD RAILING	M	1	1	1,670.00	$40.50	$67,635.00
		M	4	2	43.00	$203.49	$8,750.00
		M	7	1	840.00	$83.50	$70,140.00
		M	9	1	300.00	$86.00	$25,800.00
	Unit Sub Total	**M**		**5**	**2,853.00**	**$60.40**	**$172,325.00**
	Item Code 151572 Total No. of Proj.			**26**		**Total Amount**	**$948,185.60**
151623	RECONSTRUCT METAL BEAM GUARD RAILING (7' POST)	LF	1	1	1,300.00	$20.00	$26,000.00
	Unit Sub Total	**LF**		**1**	**1,300.00**	**$20.00**	**$26,000.00**
	Item Code 151623 Total No. of Proj.			**1**		**Total Amount**	**$26,000.00**
151624	RECONSTRUCT METAL BEAM GUARD RAILING (2.1 M POST)	M	1	1	8.00	$200.00	$1,600.00
	Unit Sub Total	**M**		**1**	**8.00**	**$200.00**	**$1,600.00**
	Item Code 151624 Total No. of Proj.			**1**		**Total Amount**	**$1,600.00**
151625	RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST)	LF	1	1	820.00	$18.00	$14,760.00
		LF	3	3	1,583.00	$22.64	$35,841.00
		LF	4	1	3,070.00	$20.00	$61,400.00
	Unit Sub Total	**LF**		**5**	**5,473.00**	**$20.46**	**$112,001.00**
151625	RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST)	M	10	1	160.00	$38.00	$6,080.00
	Unit Sub Total	**M**		**1**	**160.00**	**$38.00**	**$6,080.00**
	Item Code 151625 Total No. of Proj.			**6**		**Total Amount**	**$118,081.00**
152039	RELAY ENTRANCE TAPER	EA	3	1	2.00	$1,800.00	$3,600.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,800.00**	**$3,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 152039 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
152045	RELAY CONCRETE FLARED END SECTION	EA	2	1	8.00	$750.00	$6,000.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$750.00**	**$6,000.00**
	Item Code 152045 Total No. of Proj.			**1**		**Total Amount**	**$6,000.00**
152255	RESET MAILBOX	EA	1	1	2.00	$275.00	$550.00
		EA	3	1	1.00	$132.00	$132.00
		EA	5	1	1.00	$114.00	$114.00
		EA	6	2	44.00	$288.18	$12,680.00
		EA	10	2	17.00	$170.88	$2,905.00
		EA	11	1	1.00	$500.00	$500.00
	Unit Sub Total	**EA**		**8**	**66.00**	**$255.77**	**$16,881.00**
	Item Code 152255 Total No. of Proj.			**8**		**Total Amount**	**$16,881.00**
152291	RESET GATE	EA	8	1	1.00	$300.00	$300.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$300.00**	**$300.00**
	Item Code 152291 Total No. of Proj.			**1**		**Total Amount**	**$300.00**
152299	RESET MILEPOST MARKER	EA	1	1	1.00	$250.00	$250.00
		EA	7	4	38.00	$23.18	$881.00
		EA	8	2	18.00	$42.22	$760.00
		EA	10	2	3.00	$23.00	$69.00
	Unit Sub Total	**EA**		**9**	**60.00**	**$32.67**	**$1,960.00**
	Item Code 152299 Total No. of Proj.			**9**		**Total Amount**	**$1,960.00**
152301	RESET MARKER	EA	1	1	3.00	$50.00	$150.00
		EA	4	1	6.00	$86.36	$518.16
		EA	10	1	2.00	$50.00	$100.00
	Unit Sub Total	**EA**		**3**	**11.00**	**$69.83**	**$768.16**
	Item Code 152301 Total No. of Proj.			**3**		**Total Amount**	**$768.16**
152303	RESET MARKERS AND DELINEATORS	EA	8	1	3.00	$50.00	$150.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$50.00**	**$150.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 152303	**Total No. of Proj.**			**1**		**Total Amount**	**$150.00**
152316	RESET ROADSIDE SIGN (ONE POST)		EA	1	2	2.00	$175.00	$350.00
			EA	2	1	3.00	$180.00	$540.00
			EA	3	1	1.00	$358.74	$358.74
			EA	5	2	9.00	$185.41	$1,668.67
			EA	6	1	11.00	$185.00	$2,035.00
			EA	7	1	1.00	$200.00	$200.00
			EA	8	2	18.00	$186.11	$3,350.00
		Unit Sub Total	**EA**		**10**	**45.00**	**$188.94**	**$8,502.41**
	Item Code 152316	**Total No. of Proj.**			**10**		**Total Amount**	**$8,502.41**
152317	RESET ROADSIDE SIGN (TWO POST)		EA	2	1	1.00	$500.00	$500.00
			EA	7	1	1.00	$300.00	$300.00
			EA	8	3	6.00	$275.67	$1,654.00
		Unit Sub Total	**EA**		**5**	**8.00**	**$306.75**	**$2,454.00**
	Item Code 152317	**Total No. of Proj.**			**5**		**Total Amount**	**$2,454.00**
152320	RESET ROADSIDE SIGN		EA	1	1	6.00	$100.00	$600.00
			EA	2	3	4.00	$247.50	$990.00
			EA	3	10	92.00	$196.45	$18,073.00
			EA	4	4	128.00	$168.36	$21,550.00
			EA	5	5	32.00	$157.13	$5,028.16
			EA	6	5	47.00	$169.68	$7,975.00
			EA	8	8	46.00	$221.70	$10,198.05
			EA	9	1	5.00	$200.00	$1,000.00
			EA	10	8	38.00	$200.66	$7,625.00
			EA	11	6	58.00	$228.89	$13,275.88
		Unit Sub Total	**EA**		**51**	**456.00**	**$189.29**	**$86,315.09**
152320	RESET ROADSIDE SIGN		LS	4	1	1.00	$500.00	$500.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$500.00**	**$500.00**
	Item Code 152320	**Total No. of Proj.**			**52**		**Total Amount**	**$86,815.09**
152322	RESET ROADSIDE SIGN (WOOD POST)		EA	1	1	1.00	$250.00	$250.00
			EA	3	1	2.00	$285.00	$570.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
152322	RESET ROADSIDE SIGN (WOOD POST)	EA	10	1	1.00	$100.00	$100.00
		EA	11	1	4.00	$570.00	$2,280.00
	Unit Sub Total	**EA**		**4**	**8.00**	**$400.00**	**$3,200.00**
	Item Code 152322 Total No. of Proj.			**4**		**Total Amount**	**$3,200.00**
152351	RELOCATE HYDRANT	EA	4	2	2.00	$4,100.00	$8,200.00
		EA	6	1	1.00	$3,500.00	$3,500.00
	Unit Sub Total	**EA**		**3**	**3.00**	**$3,900.00**	**$11,700.00**
	Item Code 152351 Total No. of Proj.			**3**		**Total Amount**	**$11,700.00**
152370	RELOCATE MAILBOX	EA	4	2	2.00	$275.00	$550.00
		EA	5	2	2.00	$227.50	$455.00
		EA	6	1	39.00	$250.00	$9,750.00
		EA	10	1	10.00	$260.00	$2,600.00
	Unit Sub Total	**EA**		**6**	**53.00**	**$251.98**	**$13,355.00**
	Item Code 152370 Total No. of Proj.			**6**		**Total Amount**	**$13,355.00**
152372	RELOCATE CONCRETE BARRIER (TYPE K)	LF	7	1	17,300.00	$1.00	$17,300.00
		LF	12	1	120.00	$70.00	$8,400.00
	Unit Sub Total	**LF**		**2**	**17,420.00**	**$1.48**	**$25,700.00**
152372	RELOCATE CONCRETE BARRIER (TYPE K)	M	7	1	250.00	$9.00	$2,250.00
	Unit Sub Total	**M**		**1**	**250.00**	**$9.00**	**$2,250.00**
	Item Code 152372 Total No. of Proj.			**3**		**Total Amount**	**$27,950.00**
152379	RELOCATE FENCE	M	4	1	27.00	$100.00	$2,700.00
	Unit Sub Total	**M**		**1**	**27.00**	**$100.00**	**$2,700.00**
	Item Code 152379 Total No. of Proj.			**1**		**Total Amount**	**$2,700.00**
152381	RELOCATE GATE	EA	4	1	2.00	$1,500.00	$3,000.00
		EA	6	1	1.00	$900.25	$900.25
		EA	10	2	2.00	$625.00	$1,250.00
	Unit Sub Total	**EA**		**4**	**5.00**	**$1,030.05**	**$5,150.25**
	Item Code 152381 Total No. of Proj.			**4**		**Total Amount**	**$5,150.25**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
152386	RELOCATE ROADSIDE SIGN-ONE POST	EA	1	3	9.00	$222.22	$2,000.00
		EA	4	2	27.00	$161.11	$4,350.00
		EA	5	2	30.00	$160.00	$4,800.00
		EA	6	2	68.00	$151.62	$10,310.00
		EA	7	2	19.00	$25.74	$489.00
		EA	8	2	2.00	$190.00	$380.00
		EA	10	4	38.00	$140.71	$5,347.00
		EA	11	1	190.00	$855.00	$162,450.00
		EA	12	1	7.00	$130.00	$910.00
	Unit Sub Total	**EA**		**19**	**390.00**	**$489.84**	**$191,036.00**
	Item Code 152386 Total No. of Proj.			**19**		**Total Amount**	**$191,036.00**
152387	RELOCATE ROADSIDE SIGN-TWO POST	EA	1	3	3.00	$333.33	$1,000.00
		EA	4	1	13.00	$250.00	$3,250.00
		EA	6	2	19.00	$304.74	$5,790.00
		EA	7	2	4.00	$376.25	$1,505.00
		EA	8	1	2.00	$450.00	$900.00
		EA	10	4	6.00	$254.67	$1,528.00
	Unit Sub Total	**EA**		**13**	**47.00**	**$297.30**	**$13,973.00**
	Item Code 152387 Total No. of Proj.			**13**		**Total Amount**	**$13,973.00**
152388	RELOCATE CRASH CUSHION	EA	3	1	1.00	$2,500.00	$2,500.00
		EA	4	1	1.00	$3,500.00	$3,500.00
		EA	7	1	3.00	$400.00	$1,200.00
	Unit Sub Total	**EA**		**3**	**5.00**	**$1,440.00**	**$7,200.00**
	Item Code 152388 Total No. of Proj.			**3**		**Total Amount**	**$7,200.00**
152390	RELOCATE ROADSIDE SIGN	EA	1	2	2.00	$175.00	$350.00
		EA	2	2	3.00	$216.67	$650.00
		EA	3	8	56.00	$206.96	$11,590.00
		EA	4	8	90.00	$190.44	$17,140.00
		EA	5	3	34.00	$202.65	$6,890.00
		EA	6	3	20.00	$185.00	$3,700.00
		EA	7	3	7.00	$307.14	$2,150.00
		EA	8	3	17.00	$322.24	$5,478.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
152390	RELOCATE ROADSIDE SIGN	EA	9	1	12.00	$200.00	$2,400.00
		EA	10	4	19.00	$171.63	$3,261.00
		EA	11	8	38.00	$337.21	$12,813.98
		EA	12	1	1.00	$500.00	$500.00
	Unit Sub Total	**EA**		**46**	**299.00**	**$223.82**	**$66,922.98**
	Item Code 152390 Total No. of Proj.			**46**		**Total Amount**	**$66,922.98**
152391	RELOCATE ROADSIDE SIGN (METAL POST)	EA	4	1	1.00	$250.00	$250.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$250.00**	**$250.00**
	Item Code 152391 Total No. of Proj.			**1**		**Total Amount**	**$250.00**
152392	RELOCATE ROADSIDE SIGN (WOOD POST)	EA	4	2	22.00	$211.36	$4,650.00
		EA	7	1	2.00	$250.00	$500.00
		EA	8	1	7.00	$215.00	$1,505.00
		EA	10	1	2.00	$100.00	$200.00
	Unit Sub Total	**EA**		**5**	**33.00**	**$207.73**	**$6,855.00**
	Item Code 152392 Total No. of Proj.			**5**		**Total Amount**	**$6,855.00**
152393	RELOCATE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	4	2	10.00	$72.00	$720.00
		EA	6	1	2.00	$100.00	$200.00
		EA	7	1	9.00	$75.00	$675.00
	Unit Sub Total	**EA**		**4**	**21.00**	**$75.95**	**$1,595.00**
	Item Code 152393 Total No. of Proj.			**4**		**Total Amount**	**$1,595.00**
152394	RELOCATE SIGN STRUCTURE	EA	3	2	2.00	$5,000.00	$10,000.00
		EA	4	1	1.00	$9,900.00	$9,900.00
		EA	7	1	2.00	$20,300.00	$40,600.00
	Unit Sub Total	**EA**		**4**	**5.00**	**$12,100.00**	**$60,500.00**
	Item Code 152394 Total No. of Proj.			**4**		**Total Amount**	**$60,500.00**
152396	RELOCATE SIGN PANEL	EA	4	1	11.00	$150.00	$1,650.00
	Unit Sub Total	**EA**		**1**	**11.00**	**$150.00**	**$1,650.00**
	Item Code 152396 Total No. of Proj.			**1**		**Total Amount**	**$1,650.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
152400	ADJUST SEWER CLEANOUT TO GRADE	EA	3	1	8.00	$200.00	$1,600.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$200.00**	**$1,600.00**
	Item Code 152400 Total No. of Proj.			**1**		**Total Amount**	**$1,600.00**
152401	ADJUST WATER METER TO GRADE	EA	3	1	7.00	$250.00	$1,750.00
	Unit Sub Total	**EA**		**1**	**7.00**	**$250.00**	**$1,750.00**
	Item Code 152401 Total No. of Proj.			**1**		**Total Amount**	**$1,750.00**
152402	ADJUST WATER VALVE COVER TO GRADE	EA	2	1	2.00	$200.00	$400.00
		EA	3	1	13.00	$550.00	$7,150.00
		EA	4	2	7.00	$251.43	$1,760.00
		EA	6	2	6.00	$625.00	$3,750.00
		EA	7	2	14.00	$219.64	$3,075.00
		EA	8	1	12.00	$600.00	$7,200.00
		EA	11	1	2.00	$500.00	$1,000.00
		EA	12	2	300.00	$308.27	$92,480.00
	Unit Sub Total	**EA**		**12**	**356.00**	**$328.13**	**$116,815.00**
	Item Code 152402 Total No. of Proj.			**12**		**Total Amount**	**$116,815.00**
152403	ADJUST WATER METER BOX TO GRADE	EA	8	1	4.00	$109.00	$436.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$109.00**	**$436.00**
	Item Code 152403 Total No. of Proj.			**1**		**Total Amount**	**$436.00**
152422	ADJUST MONUMENT COVER	EA	4	1	3.00	$500.00	$1,500.00
		EA	6	2	9.00	$811.02	$7,299.22
		EA	12	1	12.00	$250.00	$3,000.00
	Unit Sub Total	**EA**		**4**	**24.00**	**$491.63**	**$11,799.22**
	Item Code 152422 Total No. of Proj.			**4**		**Total Amount**	**$11,799.22**
152423	ADJUST MONUMENT TO GRADE	EA	5	1	16.00	$500.00	$8,000.00
		EA	8	2	5.00	$1,011.60	$5,058.00
		EA	10	1	3.00	$550.00	$1,650.00
		EA	12	1	1.00	$1,525.00	$1,525.00
	Unit Sub Total	**EA**		**5**	**25.00**	**$649.32**	**$16,233.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 152423 Total No. of Proj.			**5**		**Total Amount**	**$16,233.00**
152430	ADJUST INLET	EA	1	1	5.00	$1,000.00	$5,000.00
		EA	2	3	7.00	$1,914.29	$13,400.00
		EA	3	5	20.00	$1,010.50	$20,210.00
		EA	4	7	55.00	$1,395.00	$76,725.00
		EA	5	3	19.00	$838.95	$15,940.00
		EA	6	1	2.00	$4,000.00	$8,000.00
		EA	7	3	28.00	$1,832.14	$51,300.00
		EA	10	2	2.00	$1,375.00	$2,750.00
		EA	12	2	9.00	$1,900.00	$17,100.00
	Unit Sub Total	**EA**		**27**	**147.00**	**$1,431.46**	**$210,425.00**
	Item Code 152430 Total No. of Proj.			**27**		**Total Amount**	**$210,425.00**
152432	ADJUST MANHOLE	EA	4	1	1.00	$450.00	$450.00
		EA	12	1	1.00	$500.00	$500.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$475.00**	**$950.00**
	Item Code 152432 Total No. of Proj.			**2**		**Total Amount**	**$950.00**
152438	ADJUST FRAME AND COVER TO GRADE	EA	1	1	1.00	$3,600.00	$3,600.00
		EA	2	1	22.00	$400.00	$8,800.00
		EA	3	1	16.00	$800.00	$12,800.00
		EA	4	1	8.00	$500.00	$4,000.00
		EA	6	2	18.00	$1,300.00	$23,400.00
		EA	7	2	308.00	$320.29	$98,650.00
		EA	8	2	11.00	$440.27	$4,843.00
		EA	9	1	8.00	$800.00	$6,400.00
		EA	10	3	38.00	$484.21	$18,400.00
		EA	11	2	17.00	$2,500.00	$42,500.00
	Unit Sub Total	**EA**		**16**	**447.00**	**$499.76**	**$223,393.00**
	Item Code 152438 Total No. of Proj.			**16**		**Total Amount**	**$223,393.00**
152439	ADJUST FRAME AND GRATE TO GRADE	EA	2	1	1.00	$500.00	$500.00
		EA	9	1	18.00	$800.00	$14,400.00
		EA	10	2	4.00	$1,168.75	$4,675.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**4**	**23.00**	**$851.09**	**$19,575.00**
	Item Code 152439 Total No. of Proj.			**4**		**Total Amount**	**$19,575.00**
152440	ADJUST MANHOLE TO GRADE	EA	3	1	4.00	$570.00	$2,280.00
		EA	4	6	16.00	$687.50	$11,000.00
		EA	6	1	9.00	$650.00	$5,850.00
		EA	7	2	57.00	$438.16	$24,975.00
		EA	8	3	13.00	$1,280.38	$16,645.00
		EA	10	3	166.00	$593.37	$98,500.00
		EA	12	5	130.00	$452.65	$58,845.00
	Unit Sub Total	**EA**		**21**	**395.00**	**$552.14**	**$218,095.00**
	Item Code 152440 Total No. of Proj.			**21**		**Total Amount**	**$218,095.00**
152441	ADJUST VALVE BOX FRAME AND COVER TO GRADE	EA	3	1	4.00	$570.00	$2,280.00
		EA	8	2	17.00	$777.65	$13,220.00
	Unit Sub Total	**EA**		**3**	**21.00**	**$738.10**	**$15,500.00**
	Item Code 152441 Total No. of Proj.			**3**		**Total Amount**	**$15,500.00**
152443	ADJUST PIPE INLET TO GRADE	EA	5	1	2.00	$750.00	$1,500.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$750.00**	**$1,500.00**
	Item Code 152443 Total No. of Proj.			**1**		**Total Amount**	**$1,500.00**
152450	ADJUST WATER METER	EA	2	1	1.00	$175.00	$175.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$175.00**	**$175.00**
	Item Code 152450 Total No. of Proj.			**1**		**Total Amount**	**$175.00**
152451	ADJUST WATER VALVE	EA	11	1	11.00	$325.00	$3,575.00
	Unit Sub Total	**EA**		**1**	**11.00**	**$325.00**	**$3,575.00**
	Item Code 152451 Total No. of Proj.			**1**		**Total Amount**	**$3,575.00**
152453	ADJUST VALVE BOX	EA	3	1	3.00	$250.00	$750.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$250.00**	**$750.00**
	Item Code 152453 Total No. of Proj.			**1**		**Total Amount**	**$750.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
152469	ADJUST UTILITY COVER TO GRADE	EA	3	1	7.00	$800.00	$5,600.00
		EA	4	4	174.00	$417.70	$72,680.00
	Unit Sub Total	**EA**		**5**	**181.00**	**$432.49**	**$78,280.00**
	Item Code 152469 Total No. of Proj.			**5**		**Total Amount**	**$78,280.00**
152475	ADJUST SEWER MANHOLE	EA	11	1	2.00	$1,800.00	$3,600.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,800.00**	**$3,600.00**
	Item Code 152475 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
152500	ADJUST METAL BEAM GUARD RAILING	LF	2	2	2,530.00	$6.45	$16,320.00
		LF	4	1	80.00	$10.00	$800.00
		LF	12	1	110.00	$35.00	$3,850.00
	Unit Sub Total	**LF**		**4**	**2,720.00**	**$7.71**	**$20,970.00**
	Item Code 152500 Total No. of Proj.			**4**		**Total Amount**	**$20,970.00**
152594	MODIFY ELECTRICAL EQUIPMENT	LS	11	1	1.00	$21,975.00	$21,975.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$21,975.00**	**$21,975.00**
	Item Code 152594 Total No. of Proj.			**1**		**Total Amount**	**$21,975.00**
152600	MODIFY DRAINAGE FACILITY	EA	11	1	1.00	$3,000.00	$3,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$3,000.00**	**$3,000.00**
	Item Code 152600 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
152604	MODIFY INLET	EA	2	2	2.00	$3,750.00	$7,500.00
		EA	3	1	1.00	$1,000.00	$1,000.00
		EA	4	6	30.00	$1,091.67	$32,750.00
		EA	6	1	2.00	$3,300.00	$6,600.00
		EA	7	1	47.00	$3,553.88	$167,032.36
		EA	11	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**EA**		**12**	**83.00**	**$2,613.04**	**$216,882.36**
	Item Code 152604 Total No. of Proj.			**12**		**Total Amount**	**$216,882.36**
152609	MODIFY INLET TO MANHOLE	EA	4	4	9.00	$2,344.44	$21,100.00
	Unit Sub Total	**EA**		**4**	**9.00**	**$2,344.44**	**$21,100.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 152609 Total No. of Proj.			**4**		**Total Amount**	**$21,100.00**
152610	MODIFY MANHOLE	EA	11	1	2.00	$6,300.00	$12,600.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$6,300.00**	**$12,600.00**
	Item Code 152610 Total No. of Proj.			**1**		**Total Amount**	**$12,600.00**
152632	MODIFY METAL BEAM GUARD RAILING	LF	3	1	5,550.00	$7.20	$39,960.00
	Unit Sub Total	**LF**		**1**	**5,550.00**	**$7.20**	**$39,960.00**
	Item Code 152632 Total No. of Proj.			**1**		**Total Amount**	**$39,960.00**
152659	PLASTIC PIPE LINER	LF	4	1	41.00	$160.62	$6,585.42
		LF	7	1	230.00	$110.00	$25,300.00
	Unit Sub Total	**LF**		**2**	**271.00**	**$117.66**	**$31,885.42**
	Item Code 152659 Total No. of Proj.			**2**		**Total Amount**	**$31,885.42**
152664	PLASTIC PIPE LINER (21.50" O.D.)	LF	3	1	100.00	$370.00	$37,000.00
	Unit Sub Total	**LF**		**1**	**100.00**	**$370.00**	**$37,000.00**
	Item Code 152664 Total No. of Proj.			**1**		**Total Amount**	**$37,000.00**
152666	400 MM PLASTIC PIPE-LINER	M	3	1	390.00	$434.00	$169,260.00
	Unit Sub Total	**M**		**1**	**390.00**	**$434.00**	**$169,260.00**
	Item Code 152666 Total No. of Proj.			**1**		**Total Amount**	**$169,260.00**
152668	525 MM PLASTIC PIPE-LINER	M	3	1	780.00	$491.00	$382,980.00
	Unit Sub Total	**M**		**1**	**780.00**	**$491.00**	**$382,980.00**
	Item Code 152668 Total No. of Proj.			**1**		**Total Amount**	**$382,980.00**
152669	675 MM PLASTIC PIPE-LINER	M	3	1	32.00	$654.00	$20,928.00
	Unit Sub Total	**M**		**1**	**32.00**	**$654.00**	**$20,928.00**
	Item Code 152669 Total No. of Proj.			**1**		**Total Amount**	**$20,928.00**
152703	REMODEL INLET	EA	4	2	7.00	$1,142.86	$8,000.00
	Unit Sub Total	**EA**		**2**	**7.00**	**$1,142.86**	**$8,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 152703 Total No. of Proj.			**2**		**Total Amount**	**$8,000.00**
153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	M2	1	2	1,710.00	$9.44	$16,150.00
		M2	2	1	9,430.00	$7.00	$66,010.00
		M2	3	5	190,890.00	$1.38	$264,118.00
		M2	4	10	265,540.00	$2.44	$648,575.00
		M2	5	2	2,690.00	$7.77	$20,890.00
		M2	6	5	8,290.00	$5.12	$42,456.00
		M2	7	1	2,220.00	$12.00	$26,640.00
		M2	8	3	118,420.00	$3.43	$405,950.00
		M2	9	2	73,670.00	$1.71	$125,767.50
		M2	10	7	115,880.00	$1.51	$174,903.00
		M2	11	2	43,800.00	$3.67	$160,950.00
	Unit Sub Total	**M2**		**40**	**832,540.00**	**$2.35**	**$1,952,409.50**
153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQFT	4	2	10,300.00	$2.14	$22,050.00
		SQFT	8	1	1,250.00	$1.00	$1,250.00
		SQFT	10	1	4,030.00	$0.50	$2,015.00
	Unit Sub Total	**SQFT**		**4**	**15,580.00**	**$1.62**	**$25,315.00**
153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	1	23	36,600.00	$6.11	$223,509.00
		SQYD	2	21	165,070.00	$2.18	$359,762.54
		SQYD	3	17	421,860.00	$1.06	$447,223.50
		SQYD	4	26	2,305,830.00	$1.36	$3,129,732.00
		SQYD	5	14	528,920.00	$1.23	$649,050.00
		SQYD	6	19	129,850.00	$2.91	$377,776.00
		SQYD	7	19	968,310.00	$1.13	$1,096,881.00
		SQYD	8	25	3,253,960.00	$0.66	$2,157,539.80
		SQYD	9	3	26,030.00	$4.61	$120,080.00
		SQYD	10	10	62,720.00	$5.31	$333,344.00
		SQYD	11	7	62,710.00	$4.67	$292,772.80
		SQYD	12	10	579,120.00	$1.23	$713,942.00
	Unit Sub Total	**SQYD**		**194**	**8,540,980.00**	**$1.16**	**$9,901,612.64**
	Item Code 153103 Total No. of Proj.			**238**		**Total Amount**	**$11,879,337.14**
153109	COLD PLANE ASPHALT CONCRETE PAVEMENT (.08' MAXIMUM)	SQYD	3	2	264,700.00	$1.34	$355,675.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**SQYD**		**2**	**264,700.00**	**$1.34**	**$355,675.00**
	Item Code 153109	**Total No. of Proj.**			**2**		**Total Amount**	**$355,675.00**
153210	REMOVE CONCRETE		CY	2	5	156.00	$105.16	$16,405.20
			CY	3	3	576.00	$83.96	$48,360.00
			CY	4	4	214.00	$86.43	$18,495.00
			CY	5	4	131.70	$392.17	$51,649.00
			CY	6	1	2.00	$1,000.00	$2,000.00
			CY	7	6	126.00	$169.94	$21,413.00
			CY	8	1	70.00	$135.00	$9,450.00
			CY	9	1	200.00	$95.00	$19,000.00
			CY	11	4	254.50	$108.50	$27,612.50
			CY	12	5	512.00	$165.20	$84,580.00
		Unit Sub Total	**CY**		**34**	**2,242.20**	**$133.34**	**$298,964.70**
153210	REMOVE CONCRETE		LF	8	1	110.00	$20.00	$2,200.00
		Unit Sub Total	**LF**		**1**	**110.00**	**$20.00**	**$2,200.00**
153210	REMOVE CONCRETE		LS	3	1	1.00	$3,000.00	$3,000.00
			LS	7	1	1.00	$3,500.00	$3,500.00
		Unit Sub Total	**LS**		**2**	**2.00**	**$3,250.00**	**$6,500.00**
153210	REMOVE CONCRETE		M	5	1	890.00	$21.00	$18,690.00
			M	11	1	2,970.00	$23.00	$68,310.00
		Unit Sub Total	**M**		**2**	**3,860.00**	**$22.54**	**$87,000.00**
153210	REMOVE CONCRETE		M3	1	1	30.00	$415.00	$12,450.00
			M3	3	1	21.00	$425.00	$8,925.00
			M3	4	4	1,069.00	$91.02	$97,302.00
			M3	7	2	100.80	$63.49	$6,400.00
			M3	8	1	31.00	$90.00	$2,790.00
			M3	10	3	457.40	$96.35	$44,071.00
			M3	11	2	3,444.00	$11.15	$38,400.00
		Unit Sub Total	**M3**		**14**	**5,153.20**	**$40.82**	**$210,338.00**
153210	REMOVE CONCRETE		SQFT	9	1	15,200.00	$1.40	$21,280.00
		Unit Sub Total	**SQFT**		**1**	**15,200.00**	**$1.40**	**$21,280.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 153210 Total No. of Proj.			**54**		**Total Amount**	**$626,282.70**
153211	REMOVE CONCRETE SIDEWALK AND DRIVEWAY	M2	4	2	850.00	$18.00	$15,300.00
	Unit Sub Total	**M2**		**2**	**850.00**	**$18.00**	**$15,300.00**
	Item Code 153211 Total No. of Proj.			**2**		**Total Amount**	**$15,300.00**
153213	REMOVE CONCRETE (STRUCTURE)	CY	3	1	8.00	$465.00	$3,720.00
	Unit Sub Total	**CY**		**1**	**8.00**	**$465.00**	**$3,720.00**
153213	REMOVE CONCRETE (STRUCTURE)	M2	8	1	1,330.00	$22.00	$29,260.00
	Unit Sub Total	**M2**		**1**	**1,330.00**	**$22.00**	**$29,260.00**
153213	REMOVE CONCRETE (STRUCTURE)	M3	7	1	250.00	$150.00	$37,500.00
		M3	8	1	7.00	$200.00	$1,400.00
	Unit Sub Total	**M3**		**2**	**257.00**	**$151.36**	**$38,900.00**
	Item Code 153213 Total No. of Proj.			**4**		**Total Amount**	**$71,880.00**
153214	REMOVE CONCRETE CURB	CY	3	1	1.00	$4,000.00	$4,000.00
		CY	4	2	99.00	$116.60	$11,543.50
	Unit Sub Total	**CY**		**3**	**100.00**	**$155.44**	**$15,543.50**
153214	REMOVE CONCRETE CURB	LF	3	1	1,140.00	$2.20	$2,508.00
		LF	4	1	710.00	$8.00	$5,680.00
		LF	6	1	260.00	$4.00	$1,040.00
		LF	7	3	29,140.00	$1.14	$33,260.00
		LF	8	3	335.00	$12.69	$4,250.00
		LF	9	2	760.00	$4.11	$3,120.00
		LF	12	4	12,510.00	$7.93	$99,200.00
	Unit Sub Total	**LF**		**15**	**44,855.00**	**$3.32**	**$149,058.00**
153214	REMOVE CONCRETE CURB	M	4	4	5,420.00	$31.48	$170,610.00
		M	5	1	55.00	$52.06	$2,863.30
		M	7	1	4,000.00	$6.00	$24,000.00
	Unit Sub Total	**M**		**6**	**9,475.00**	**$20.84**	**$197,473.30**
	Item Code 153214 Total No. of Proj.			**24**		**Total Amount**	**$362,074.80**
153215	REMOVE CONCRETE (CURB AND GUTTER)	CY	7	1	1.70	$650.00	$1,105.00
		CY	8	1	16.00	$500.00	$8,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**CY**		**2**	**17.70**	**$514.41**	**$9,105.00**
153215	REMOVE CONCRETE (CURB AND GUTTER)	LF	2	1	110.00	$6.24	$686.40
		LF	3	1	3,190.00	$2.30	$7,337.00
		LF	4	1	2,840.00	$6.00	$17,040.00
		LF	5	1	260.00	$10.00	$2,600.00
		LF	6	1	3,460.00	$8.00	$27,680.00
		LF	7	2	64,150.00	$3.77	$241,875.00
		LF	11	1	85.00	$12.07	$1,025.95
	Unit Sub Total	**LF**		**8**	**74,095.00**	**$4.03**	**$298,244.35**
153215	REMOVE CONCRETE (CURB AND GUTTER)	M	4	2	4,450.00	$21.44	$95,400.00
		M	7	2	11,480.00	$9.10	$104,500.00
		M	8	1	1,640.00	$5.00	$8,200.00
	Unit Sub Total	**M**		**5**	**17,570.00**	**$11.84**	**$208,100.00**
	Item Code 153215 Total No. of Proj.			**15**		**Total Amount**	**$515,449.35**
153216	REMOVE CONCRETE CURB AND SIDEWALK	CY	7	1	2.30	$250.00	$575.00
	Unit Sub Total	**CY**		**1**	**2.30**	**$250.00**	**$575.00**
153216	REMOVE CONCRETE CURB AND SIDEWALK	LF	11	1	270.00	$25.00	$6,750.00
	Unit Sub Total	**LF**		**1**	**270.00**	**$25.00**	**$6,750.00**
	Item Code 153216 Total No. of Proj.			**2**		**Total Amount**	**$7,325.00**
153218	REMOVE CONCRETE SIDEWALK	CY	4	1	220.00	$160.00	$35,200.00
		CY	10	1	2.80	$200.00	$560.00
	Unit Sub Total	**CY**		**2**	**222.80**	**$160.50**	**$35,760.00**
153218	REMOVE CONCRETE SIDEWALK	LF	5	1	230.00	$10.00	$2,300.00
	Unit Sub Total	**LF**		**1**	**230.00**	**$10.00**	**$2,300.00**
153218	REMOVE CONCRETE SIDEWALK	M	8	1	1,360.00	$6.00	$8,160.00
	Unit Sub Total	**M**		**1**	**1,360.00**	**$6.00**	**$8,160.00**
153218	REMOVE CONCRETE SIDEWALK	M2	2	1	1,550.00	$6.23	$9,656.50
		M2	6	1	24.00	$80.00	$1,920.00
		M2	7	1	6,140.00	$6.00	$36,840.00
	Unit Sub Total	**M2**		**3**	**7,714.00**	**$6.28**	**$48,416.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 153218 Total No. of Proj.			**7**		**Total Amount**	**$94,636.50**
153219	REMOVE CONCRETE FLARED END SECTION	EA	3	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,000.00**	**$1,000.00**
	Item Code 153219 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
153220	REMOVE CONCRETE (CHANNEL)	CY	7	1	6.00	$300.00	$1,800.00
		CY	8	1	13.00	$900.00	$11,700.00
	Unit Sub Total	**CY**		**2**	**19.00**	**$710.53**	**$13,500.00**
153220	REMOVE CONCRETE (CHANNEL)	LF	12	1	42.00	$11.00	$462.00
	Unit Sub Total	**LF**		**1**	**42.00**	**$11.00**	**$462.00**
153220	REMOVE CONCRETE (CHANNEL)	M3	4	1	17.00	$340.00	$5,780.00
		M3	5	1	650.00	$16.00	$10,400.00
		M3	6	1	14.00	$140.00	$1,960.00
		M3	8	1	32.00	$100.00	$3,200.00
	Unit Sub Total	**M3**		**4**	**713.00**	**$29.93**	**$21,340.00**
	Item Code 153220 Total No. of Proj.			**7**		**Total Amount**	**$35,302.00**
153221	REMOVE CONCRETE BARRIER	LF	2	2	840.00	$44.00	$36,960.00
		LF	3	1	2,890.00	$15.00	$43,350.00
		LF	4	3	3,350.00	$15.29	$51,230.00
		LF	5	2	1,280.00	$17.50	$22,400.00
		LF	7	2	11,360.00	$10.39	$118,080.00
		LF	12	3	1,461.00	$18.50	$27,022.00
	Unit Sub Total	**LF**		**13**	**21,181.00**	**$14.12**	**$299,042.00**
153221	REMOVE CONCRETE BARRIER	M	1	1	2,540.00	$39.00	$99,060.00
		M	2	1	1,840.00	$62.00	$114,080.00
		M	3	1	3,590.00	$27.00	$96,930.00
		M	4	3	1,710.00	$63.08	$107,860.00
		M	5	1	100.00	$80.00	$8,000.00
		M	6	1	62.00	$100.00	$6,200.00
		M	7	4	4,204.00	$43.81	$184,172.00
	Unit Sub Total	**M**		**12**	**14,046.00**	**$43.88**	**$616,302.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 153221 Total No. of Proj.			**25**		**Total Amount**	**$915,344.00**
153222	REMOVE CONCRETE ISLAND (PORTIONS)	CY	4	1	41.00	$215.00	$8,815.00
		CY	12	1	4.00	$350.00	$1,400.00
	Unit Sub Total	**CY**		**2**	**45.00**	**$227.00**	**$10,215.00**
153222	REMOVE CONCRETE ISLAND (PORTIONS)	M2	6	1	320.00	$30.00	$9,600.00
	Unit Sub Total	**M2**		**1**	**320.00**	**$30.00**	**$9,600.00**
153222	REMOVE CONCRETE ISLAND (PORTIONS)	M3	4	1	690.00	$89.00	$61,410.00
	Unit Sub Total	**M3**		**1**	**690.00**	**$89.00**	**$61,410.00**
	Item Code 153222 Total No. of Proj.			**4**		**Total Amount**	**$81,225.00**
153223	REMOVE UNSOUND CONCRETE	CF	1	5	678.00	$46.03	$31,208.00
		CF	2	3	1,301.00	$61.55	$80,080.00
		CF	3	6	4,006.00	$20.45	$81,924.00
		CF	4	16	13,844.00	$22.86	$316,529.00
		CF	6	1	753.00	$33.00	$24,849.00
		CF	7	17	7,226.00	$27.65	$199,768.00
		CF	8	10	2,986.00	$35.93	$107,290.00
		CF	10	4	2,355.00	$27.83	$65,532.00
		CF	11	6	7,294.00	$16.42	$119,788.00
		CF	12	1	645.00	$31.00	$19,995.00
	Unit Sub Total	**CF**		**69**	**41,088.00**	**$25.48**	**$1,046,963.00**
	Item Code 153223 Total No. of Proj.			**69**		**Total Amount**	**$1,046,963.00**
153225	PREPARE CONCRETE BRIDGE DECK SURFACE	M2	2	1	18,400.00	$5.00	$92,000.00
		M2	6	1	230.00	$7.20	$1,656.00
		M2	7	2	1,076.00	$13.47	$14,490.00
	Unit Sub Total	**M2**		**4**	**19,706.00**	**$5.49**	**$108,146.00**
153225	PREPARE CONCRETE BRIDGE DECK SURFACE	SQFT	1	2	25,246.00	$0.19	$4,820.76
		SQFT	2	4	304,352.00	$0.24	$73,635.96
		SQFT	3	6	398,681.00	$0.39	$157,289.32
		SQFT	4	4	208,267.00	$0.43	$89,321.25
		SQFT	5	1	54.00	$30.00	$1,620.00
		SQFT	7	2	50,980.00	$0.18	$8,921.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
153225	PREPARE CONCRETE BRIDGE DECK SURFACE	SQFT	8	7	132,726.00	$0.90	$119,335.10
	Unit Sub Total	**SQFT**		**26**	**1,120,306.00**	**$0.41**	**$454,943.89**
	Item Code 153225 Total No. of Proj.			**30**		**Total Amount**	**$563,089.89**
153229	REMOVE CONCRETE BARRIER (TYPE K)	LF	11	2	2,630.00	$5.94	$15,620.00
	Unit Sub Total	**LF**		**2**	**2,630.00**	**$5.94**	**$15,620.00**
153229	REMOVE CONCRETE BARRIER (TYPE K)	M	4	4	2,190.00	$14.77	$32,340.00
		M	5	1	220.00	$28.00	$6,160.00
		M	7	1	1,060.00	$10.00	$10,600.00
		M	8	1	1,630.00	$5.00	$8,150.00
		M	11	3	2,330.00	$9.70	$22,590.00
	Unit Sub Total	**M**		**10**	**7,430.00**	**$10.75**	**$79,840.00**
	Item Code 153229 Total No. of Proj.			**12**		**Total Amount**	**$95,460.00**
153230	REMOVE CONCRETE BARRIER (TYPE 50)	LF	4	1	20.00	$500.00	$10,000.00
		LF	5	1	580.00	$55.00	$31,900.00
	Unit Sub Total	**LF**		**2**	**600.00**	**$69.83**	**$41,900.00**
	Item Code 153230 Total No. of Proj.			**2**		**Total Amount**	**$41,900.00**
153235	CLEAN BRIDGE DECK	M2	6	1	643.00	$3.40	$2,186.20
		M2	8	1	39,200.00	$2.12	$83,104.00
	Unit Sub Total	**M2**		**2**	**39,843.00**	**$2.14**	**$85,290.20**
153235	CLEAN BRIDGE DECK	SQFT	1	5	102,750.00	$0.16	$16,837.30
		SQFT	2	2	10,792.00	$0.30	$3,252.80
		SQFT	3	7	1,259,069.00	$0.13	$164,507.82
		SQFT	4	16	6,118,964.00	$0.13	$777,754.60
		SQFT	6	1	223,000.00	$0.20	$44,600.00
		SQFT	7	17	2,186,434.00	$0.16	$340,860.44
		SQFT	8	7	873,192.00	$0.16	$143,129.81
		SQFT	10	4	702,063.00	$0.12	$81,783.86
		SQFT	11	6	2,144,311.00	$0.14	$310,723.98
		SQFT	12	1	254,135.00	$0.13	$33,037.55
	Unit Sub Total	**SQFT**		**66**	**13,874,710.00**	**$0.14**	**$1,916,488.16**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 153235 Total No. of Proj.			**68**		**Total Amount**	**$2,001,778.36**
153239	REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK)	CY	2	1	50.00	$75.00	$3,750.00
		CY	3	3	191.00	$354.35	$67,680.00
		CY	4	2	43.00	$178.37	$7,670.00
		CY	7	1	16.00	$120.00	$1,920.00
		CY	8	2	100.00	$250.66	$25,065.50
		CY	9	1	47.00	$150.00	$7,050.00
	Unit Sub Total	**CY**		**10**	**447.00**	**$253.10**	**$113,135.50**
153239	REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK)	M	3	1	88.00	$25.00	$2,200.00
	Unit Sub Total	**M**		**1**	**88.00**	**$25.00**	**$2,200.00**
153239	REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK)	M3	8	1	450.00	$28.00	$12,600.00
	Unit Sub Total	**M3**		**1**	**450.00**	**$28.00**	**$12,600.00**
	Item Code 153239 Total No. of Proj.			**12**		**Total Amount**	**$127,935.50**
153246	REMOVE CONCRETE (MISCELLANEOUS)	CY	1	1	35.00	$410.00	$14,350.00
		CY	4	1	290.00	$52.00	$15,080.00
		CY	12	1	27.00	$332.00	$8,964.00
	Unit Sub Total	**CY**		**3**	**352.00**	**$109.07**	**$38,394.00**
153246	REMOVE CONCRETE (MISCELLANEOUS)	LF	4	1	340.00	$17.00	$5,780.00
	Unit Sub Total	**LF**		**1**	**340.00**	**$17.00**	**$5,780.00**
153246	REMOVE CONCRETE (MISCELLANEOUS)	M2	8	1	340.00	$5.00	$1,700.00
	Unit Sub Total	**M2**		**1**	**340.00**	**$5.00**	**$1,700.00**
153246	REMOVE CONCRETE (MISCELLANEOUS)	M3	3	1	30.00	$100.00	$3,000.00
		M3	7	2	36.00	$774.58	$27,885.00
		M3	10	1	10.00	$125.00	$1,250.00
		M3	11	1	1,080.00	$43.00	$46,440.00
	Unit Sub Total	**M3**		**5**	**1,156.00**	**$67.97**	**$78,575.00**
153246	REMOVE CONCRETE (MISCELLANEOUS)	SQFT	7	1	30.00	$1.00	$30.00
	Unit Sub Total	**SQFT**		**1**	**30.00**	**$1.00**	**$30.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 153246	**Total No. of Proj.**			**11**		**Total Amount**	**$124,479.00**
153250	REMOVE SOUND WALL		LF	3	1	480.00	$25.00	$12,000.00
		Unit Sub Total	**LF**		**1**	**480.00**	**$25.00**	**$12,000.00**
153250	REMOVE SOUND WALL		M2	7	1	440.00	$70.00	$30,800.00
		Unit Sub Total	**M2**		**1**	**440.00**	**$70.00**	**$30,800.00**
	Item Code 153250	**Total No. of Proj.**			**2**		**Total Amount**	**$42,800.00**
153531	ACCESS OPENING, SOFFIT		EA	7	2	44.00	$786.36	$34,600.00
		Unit Sub Total	**EA**		**2**	**44.00**	**$786.36**	**$34,600.00**
	Item Code 153531	**Total No. of Proj.**			**2**		**Total Amount**	**$34,600.00**
155002	PLUG PIPE		EA	7	1	2.00	$630.00	$1,260.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$630.00**	**$1,260.00**
	Item Code 155002	**Total No. of Proj.**			**1**		**Total Amount**	**$1,260.00**
155003	CAP INLET		EA	2	1	7.00	$1,400.00	$9,800.00
			EA	3	3	6.00	$1,103.33	$6,620.00
			EA	4	9	69.00	$1,083.62	$74,770.00
			EA	5	2	11.00	$2,172.73	$23,900.00
			EA	7	4	43.00	$585.58	$25,180.00
			EA	8	2	32.00	$1,309.38	$41,900.00
			EA	10	2	3.00	$1,433.33	$4,300.00
			EA	11	2	2.00	$1,625.00	$3,250.00
			EA	12	1	2.00	$1,400.00	$2,800.00
		Unit Sub Total	**EA**		**26**	**175.00**	**$1,100.11**	**$192,520.00**
	Item Code 155003	**Total No. of Proj.**			**26**		**Total Amount**	**$192,520.00**
155006	CAP RISER		EA	11	1	2.00	$975.00	$1,950.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$975.00**	**$1,950.00**
	Item Code 155006	**Total No. of Proj.**			**1**		**Total Amount**	**$1,950.00**
155007	CAP MANHOLE		EA	4	3	3.00	$2,050.00	$6,150.00
		Unit Sub Total	**EA**		**3**	**3.00**	**$2,050.00**	**$6,150.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 155007	**Total No. of Proj.**			**3**		**Total Amount**	**$6,150.00**
156535	REMOVE BOX CULVERT		CY	6	1	540.00	$50.00	$27,000.00
		Unit Sub Total	**CY**		**1**	**540.00**	**$50.00**	**$27,000.00**
156535	REMOVE BOX CULVERT		LF	2	1	170.00	$77.00	$13,090.00
			LF	12	1	46.00	$250.00	$11,500.00
		Unit Sub Total	**LF**		**2**	**216.00**	**$113.84**	**$24,590.00**
156535	REMOVE BOX CULVERT		M	8	1	15.00	$100.00	$1,500.00
		Unit Sub Total	**M**		**1**	**15.00**	**$100.00**	**$1,500.00**
	Item Code 156535	**Total No. of Proj.**			**4**		**Total Amount**	**$53,090.00**
156572	REMOVE RAILING		LS	7	1	1.00	$100.00	$100.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$100.00**	**$100.00**
	Item Code 156572	**Total No. of Proj.**			**1**		**Total Amount**	**$100.00**
156576	REMOVE METAL RAILING		LF	4	2	1,930.00	$24.02	$46,350.00
			LF	12	1	29.00	$20.00	$580.00
		Unit Sub Total	**LF**		**3**	**1,959.00**	**$23.96**	**$46,930.00**
156576	REMOVE METAL RAILING		M	8	1	530.00	$18.00	$9,540.00
		Unit Sub Total	**M**		**1**	**530.00**	**$18.00**	**$9,540.00**
	Item Code 156576	**Total No. of Proj.**			**4**		**Total Amount**	**$56,470.00**
156577	REMOVE BARRIER RAILING		EA	5	1	5.00	$250.00	$1,250.00
		Unit Sub Total	**EA**		**1**	**5.00**	**$250.00**	**$1,250.00**
156577	REMOVE BARRIER RAILING		LF	4	1	55.00	$15.00	$825.00
		Unit Sub Total	**LF**		**1**	**55.00**	**$15.00**	**$825.00**
156577	REMOVE BARRIER RAILING		M	11	1	200.00	$24.00	$4,800.00
		Unit Sub Total	**M**		**1**	**200.00**	**$24.00**	**$4,800.00**
	Item Code 156577	**Total No. of Proj.**			**3**		**Total Amount**	**$6,875.00**
156579	REMOVE BRIDGE RAILING		LF	12	1	140.00	$30.00	$4,200.00
		Unit Sub Total	**LF**		**1**	**140.00**	**$30.00**	**$4,200.00**
156579	REMOVE BRIDGE RAILING		M	8	1	23.00	$25.00	$575.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**1**	**23.00**	**$25.00**	**$575.00**
	Item Code 156579	**Total No. of Proj.**			**2**		**Total Amount**	**$4,775.00**
156585	REMOVE CRASH CUSHION		EA	2	1	1.00	$450.00	$450.00
			EA	4	5	29.00	$527.59	$15,300.00
			EA	5	2	10.00	$1,254.00	$12,540.00
			EA	7	2	5.00	$545.00	$2,725.00
			EA	8	1	5.00	$500.00	$2,500.00
			EA	11	1	13.00	$2,500.00	$32,500.00
		Unit Sub Total	**EA**		**12**	**63.00**	**$1,047.86**	**$66,015.00**
	Item Code 156585	**Total No. of Proj.**			**12**		**Total Amount**	**$66,015.00**
156590	REMOVE CRASH CUSHION (SAND FILLED)		EA	4	7	321.00	$124.80	$40,060.00
			EA	5	2	4.00	$1,325.00	$5,300.00
			EA	6	1	1.00	$1,800.00	$1,800.00
			EA	7	2	10.00	$200.00	$2,000.00
			EA	8	1	1.00	$650.00	$650.00
		Unit Sub Total	**EA**		**13**	**337.00**	**$147.80**	**$49,810.00**
156590	REMOVE CRASH CUSHION (SAND FILLED)		LS	2	1	1.00	$5,000.00	$5,000.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$5,000.00**	**$5,000.00**
	Item Code 156590	**Total No. of Proj.**			**14**		**Total Amount**	**$54,810.00**
157550	BRIDGE REMOVAL		LS	1	1	1.00	$115,000.00	$115,000.00
			LS	4	3	3.00	$201,000.00	$603,000.00
			LS	6	3	3.00	$71,666.67	$215,000.00
			LS	7	2	2.00	$57,500.00	$115,000.00
			LS	8	2	2.00	$39,000.00	$78,000.00
			LS	10	1	1.00	$275,000.00	$275,000.00
			LS	11	1	1.00	$70,500.00	$70,500.00
		Unit Sub Total	**LS**		**13**	**13.00**	**$113,192.31**	**$1,471,500.00**
	Item Code 157550	**Total No. of Proj.**			**13**		**Total Amount**	**$1,471,500.00**
157551	BRIDGE REMOVAL, LOCATION A		LS	1	1	1.00	$140,000.00	$140,000.00
			LS	3	1	1.00	$80,000.00	$80,000.00
			LS	4	6	6.00	$385,450.00	$2,312,700.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
157551	BRIDGE REMOVAL, LOCATION A	LS	5	1	1.00	$90,000.00	$90,000.00
		LS	8	1	1.00	$100,000.00	$100,000.00
		LS	11	1	1.00	$35,000.00	$35,000.00
	Unit Sub Total	**LS**		**11**	**11.00**	**$250,700.00**	**$2,757,700.00**
	Item Code 157551 Total No. of Proj.			**11**		**Total Amount**	**$2,757,700.00**
157552	BRIDGE REMOVAL, LOCATION B	LS	1	1	1.00	$115,000.00	$115,000.00
		LS	3	1	1.00	$55,000.00	$55,000.00
		LS	4	5	5.00	$179,400.00	$897,000.00
		LS	8	1	1.00	$300,000.00	$300,000.00
		LS	11	1	1.00	$29,000.00	$29,000.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$155,111.11**	**$1,396,000.00**
	Item Code 157552 Total No. of Proj.			**9**		**Total Amount**	**$1,396,000.00**
157553	BRIDGE REMOVAL, LOCATION C	LS	1	1	1.00	$80,000.00	$80,000.00
		LS	4	2	2.00	$212,500.00	$425,000.00
		LS	8	1	1.00	$120,000.00	$120,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$156,250.00**	**$625,000.00**
	Item Code 157553 Total No. of Proj.			**4**		**Total Amount**	**$625,000.00**
157554	BRIDGE REMOVAL, LOCATION D	LS	1	1	1.00	$50,000.00	$50,000.00
		LS	4	2	2.00	$45,000.00	$90,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$46,666.67**	**$140,000.00**
	Item Code 157554 Total No. of Proj.			**3**		**Total Amount**	**$140,000.00**
157555	BRIDGE REMOVAL, LOCATION E	LS	4	1	1.00	$100,000.00	$100,000.00
		LS	7	1	1.00	$345,000.00	$345,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$222,500.00**	**$445,000.00**
	Item Code 157555 Total No. of Proj.			**2**		**Total Amount**	**$445,000.00**
157556	BRIDGE REMOVAL, LOCATION F	LS	7	1	1.00	$110,000.00	$110,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$110,000.00**	**$110,000.00**
	Item Code 157556 Total No. of Proj.			**1**		**Total Amount**	**$110,000.00**
157557	BRIDGE REMOVAL, LOCATION G	LS	7	1	1.00	$250,000.00	$250,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LS**		**1**	**1.00**	**$250,000.00**	**$250,000.00**
	Item Code 157557	**Total No. of Proj.**			**1**		**Total Amount**	**$250,000.00**
157558	BRIDGE REMOVAL, LOCATION H		LS	7	1	1.00	$150,000.00	$150,000.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$150,000.00**	**$150,000.00**
	Item Code 157558	**Total No. of Proj.**			**1**		**Total Amount**	**$150,000.00**
157560	BRIDGE REMOVAL (PORTION)		LS	1	1	1.00	$4,000.00	$4,000.00
			LS	2	4	4.00	$90,575.00	$362,300.00
			LS	3	6	6.00	$42,091.67	$252,550.00
			LS	4	9	9.00	$73,500.00	$661,500.00
			LS	5	1	1.00	$15,000.00	$15,000.00
			LS	6	4	4.00	$34,750.00	$139,000.00
			LS	7	8	8.00	$11,831.25	$94,650.00
			LS	8	2	2.00	$115,000.00	$230,000.00
			LS	10	5	5.00	$22,500.00	$112,500.00
			LS	11	5	5.00	$29,200.00	$146,000.00
			LS	12	1	1.00	$15,500.00	$15,500.00
		Unit Sub Total	**LS**		**46**	**46.00**	**$44,195.65**	**$2,033,000.00**
	Item Code 157560	**Total No. of Proj.**			**46**		**Total Amount**	**$2,033,000.00**
157561	BRIDGE REMOVAL (PORTION), LOCATION A		LS	1	1	1.00	$19,488.00	$19,488.00
			LS	3	3	3.00	$73,333.33	$220,000.00
			LS	4	5	5.00	$41,240.00	$206,200.00
			LS	5	3	3.00	$6,872.50	$20,617.50
			LS	6	1	1.00	$11,500.00	$11,500.00
			LS	7	3	3.00	$59,666.67	$179,000.00
			LS	8	2	2.00	$76,750.00	$153,500.00
			LS	10	1	1.00	$25,000.00	$25,000.00
			LS	11	2	2.00	$21,500.00	$43,000.00
			LS	12	1	1.00	$60,000.00	$60,000.00
		Unit Sub Total	**LS**		**22**	**22.00**	**$42,650.25**	**$938,305.50**
	Item Code 157561	**Total No. of Proj.**			**22**		**Total Amount**	**$938,305.50**
157562	BRIDGE REMOVAL (PORTION), LOCATION B		LS	1	1	1.00	$28,420.00	$28,420.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
157562	BRIDGE REMOVAL (PORTION), LOCATION B	LS	3	3	3.00	$41,666.67	$125,000.00
		LS	4	4	4.00	$37,000.00	$148,000.00
		LS	5	4	4.00	$43,954.38	$175,817.50
		LS	6	1	1.00	$11,500.00	$11,500.00
		LS	7	3	3.00	$43,500.00	$130,500.00
		LS	8	2	2.00	$58,470.00	$116,940.00
		LS	10	1	1.00	$25,000.00	$25,000.00
		LS	11	2	2.00	$19,500.00	$39,000.00
		LS	12	1	1.00	$40,000.00	$40,000.00
	Unit Sub Total	**LS**		**22**	**22.00**	**$38,189.89**	**$840,177.50**
	Item Code 157562 Total No. of Proj.			**22**		**Total Amount**	**$840,177.50**
157563	BRIDGE REMOVAL (PORTION), LOCATION C	LS	3	2	2.00	$57,500.00	$115,000.00
		LS	4	1	1.00	$113,000.00	$113,000.00
		LS	5	2	2.00	$6,758.75	$13,517.50
		LS	6	1	1.00	$11,500.00	$11,500.00
		LS	7	3	3.00	$55,333.33	$166,000.00
		LS	8	2	2.00	$67,430.00	$134,860.00
		LS	11	1	1.00	$12,000.00	$12,000.00
		LS	12	1	1.00	$60,000.00	$60,000.00
	Unit Sub Total	**LS**		**13**	**13.00**	**$48,144.42**	**$625,877.50**
	Item Code 157563 Total No. of Proj.			**13**		**Total Amount**	**$625,877.50**
157564	BRIDGE REMOVAL (PORTION), LOCATION D	LS	3	1	1.00	$15,000.00	$15,000.00
		LS	6	1	1.00	$11,500.00	$11,500.00
		LS	7	3	3.00	$35,333.33	$106,000.00
		LS	8	2	2.00	$182,850.00	$365,700.00
		LS	11	1	1.00	$21,500.00	$21,500.00
		LS	12	1	1.00	$25,000.00	$25,000.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$60,522.22**	**$544,700.00**
	Item Code 157564 Total No. of Proj.			**9**		**Total Amount**	**$544,700.00**
157565	BRIDGE REMOVAL (PORTION), LOCATION E	LS	3	1	1.00	$15,000.00	$15,000.00
		LS	7	2	2.00	$28,500.00	$57,000.00
		LS	8	1	1.00	$37,100.00	$37,100.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
157565	BRIDGE REMOVAL (PORTION), LOCATION E	LS	11	1	1.00	$4,500.00	$4,500.00
		LS	12	1	1.00	$20,000.00	$20,000.00
	Unit Sub Total	**LS**		**6**	**6.00**	**$22,266.67**	**$133,600.00**
	Item Code 157565 Total No. of Proj.			**6**		**Total Amount**	**$133,600.00**
157566	BRIDGE REMOVAL (PORTION), LOCATION F	LS	3	1	1.00	$15,000.00	$15,000.00
		LS	7	1	1.00	$12,000.00	$12,000.00
		LS	8	1	1.00	$30,700.00	$30,700.00
		LS	11	1	1.00	$7,700.00	$7,700.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$16,350.00**	**$65,400.00**
	Item Code 157566 Total No. of Proj.			**4**		**Total Amount**	**$65,400.00**
157567	BRIDGE REMOVAL (PORTION), LOCATION G	LS	11	1	1.00	$12,000.00	$12,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$12,000.00**	**$12,000.00**
	Item Code 157567 Total No. of Proj.			**1**		**Total Amount**	**$12,000.00**
158101	SALVAGE CRASH CUSHION MODULES	EA	8	1	1.00	$2,500.00	$2,500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$2,500.00**	**$2,500.00**
	Item Code 158101 Total No. of Proj.			**1**		**Total Amount**	**$2,500.00**
158210	RESET TEMPORARY RAILING (TYPE K)	LF	1	1	1,180.00	$4.50	$5,310.00
		LF	8	1	5,360.00	$21.00	$112,560.00
	Unit Sub Total	**LF**		**2**	**6,540.00**	**$18.02**	**$117,870.00**
	Item Code 158210 Total No. of Proj.			**2**		**Total Amount**	**$117,870.00**
159010	RECONSTRUCT METAL RAILING (BRIDGE)	LS	3	1	1.00	$6,565.00	$6,565.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$6,565.00**	**$6,565.00**
	Item Code 159010 Total No. of Proj.			**1**		**Total Amount**	**$6,565.00**
159110	MODIFY CONCRETE BARRIER	LF	11	1	12.00	$200.00	$2,400.00
	Unit Sub Total	**LF**		**1**	**12.00**	**$200.00**	**$2,400.00**
	Item Code 159110 Total No. of Proj.			**1**		**Total Amount**	**$2,400.00**
160101	CLEARING AND GRUBBING	HA	11	1	64.00	$4,500.00	$288,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**HA**		**1**	**64.00**	**$4,500.00**	**$288,000.00**
160101	CLEARING AND GRUBBING		LS	1	20	20.00	$9,822.50	$196,450.00
			LS	2	21	21.00	$22,459.95	$471,659.00
			LS	3	20	20.00	$61,127.02	$1,222,540.42
			LS	4	29	29.00	$47,232.41	$1,369,740.00
			LS	5	18	18.00	$23,914.17	$430,455.00
			LS	6	17	17.00	$29,042.67	$493,725.40
			LS	7	24	24.00	$25,651.42	$615,634.00
			LS	8	21	21.00	$14,734.24	$309,419.00
			LS	9	4	4.00	$22,750.00	$91,000.00
			LS	10	15	15.00	$19,227.67	$288,415.00
			LS	11	7	7.00	$88,873.71	$622,116.00
			LS	12	15	15.00	$31,613.33	$474,200.00
		Unit Sub Total	**LS**		**211**	**211.00**	**$31,210.21**	**$6,585,353.82**
	Item Code 160101	**Total No. of Proj.**			**212**		**Total Amount**	**$6,873,353.82**
160120	REMOVE TREE		EA	3	3	352.00	$562.41	$197,970.00
			EA	4	2	51.00	$361.76	$18,450.00
			EA	6	1	4.00	$500.00	$2,000.00
			EA	8	1	5.00	$1,000.00	$5,000.00
			EA	9	1	3.00	$600.00	$1,800.00
		Unit Sub Total	**EA**		**8**	**415.00**	**$542.70**	**$225,220.00**
160120	REMOVE TREE		LS	4	1	1.00	$50,000.00	$50,000.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$50,000.00**	**$50,000.00**
	Item Code 160120	**Total No. of Proj.**			**9**		**Total Amount**	**$275,220.00**
160121	REMOVE TREE STUMP		EA	9	1	2.00	$300.00	$600.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$300.00**	**$600.00**
	Item Code 160121	**Total No. of Proj.**			**1**		**Total Amount**	**$600.00**
170101	DEVELOP WATER SUPPLY		LS	2	13	13.00	$6,319.23	$82,150.00
			LS	3	2	2.00	$10,800.00	$21,600.00
			LS	4	10	10.00	$27,415.00	$274,150.00
			LS	5	4	4.00	$35,000.00	$140,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
170101	DEVELOP WATER SUPPLY	LS	6	3	3.00	$35,000.00	$105,000.00
		LS	8	7	7.00	$24,253.57	$169,775.00
		LS	9	1	1.00	$10,000.00	$10,000.00
		LS	11	4	4.00	$53,750.00	$215,000.00
	Unit Sub Total	**LS**		**44**	**44.00**	**$23,128.98**	**$1,017,675.00**
	Item Code 170101 Total No. of Proj.			**44**		**Total Amount**	**$1,017,675.00**
190101	ROADWAY EXCAVATION	CY	1	23	49,895.00	$21.34	$1,064,762.50
		CY	2	16	343,522.00	$10.64	$3,653,935.00
		CY	3	14	240,268.00	$5.91	$1,420,067.20
		CY	4	10	15,649.00	$32.24	$504,585.00
		CY	5	13	80,133.00	$16.33	$1,308,217.50
		CY	6	12	95,788.00	$9.04	$866,071.70
		CY	7	20	143,216.10	$13.51	$1,934,367.00
		CY	8	19	46,572.00	$20.04	$933,234.60
		CY	9	3	478.00	$55.90	$26,720.00
		CY	10	7	8,450.00	$28.68	$242,355.00
		CY	11	13	23,121.00	$26.98	$623,857.10
		CY	12	13	58,449.00	$21.82	$1,275,435.00
	Unit Sub Total	**CY**		**163**	**1,105,541.10**	**$12.53**	**$13,853,607.60**
190101	ROADWAY EXCAVATION	M3	1	5	16,937.00	$18.83	$318,960.00
		M3	2	3	238,184.00	$48.01	$11,434,384.96
		M3	3	5	291,900.00	$11.74	$3,426,150.00
		M3	4	12	414,810.00	$15.33	$6,357,439.00
		M3	5	3	324,420.00	$11.06	$3,586,991.20
		M3	6	6	306,060.00	$10.47	$3,205,280.00
		M3	7	5	117,560.00	$29.52	$3,470,175.00
		M3	8	3	371,300.00	$11.34	$4,211,400.00
		M3	9	3	71,910.00	$16.07	$1,155,310.00
		M3	10	10	60,430.00	$27.99	$1,691,285.00
		M3	11	3	2,137,500.00	$5.41	$11,562,000.00
	Unit Sub Total	**M3**		**58**	**4,351,011.00**	**$11.59**	**$50,419,375.16**
	Item Code 190101 Total No. of Proj.			**221**		**Total Amount**	**$64,272,982.76**
190105	ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	CY	1	1	7.00	$450.00	$3,150.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
190105	ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	CY	3	1	550.00	$160.00	$88,000.00
		CY	4	5	12,910.00	$135.26	$1,746,180.00
		CY	5	3	1,237.00	$186.91	$231,208.20
		CY	7	5	7,050.00	$41.95	$295,720.00
		CY	11	2	1,160.00	$98.07	$113,760.00
		CY	12	2	14,675.00	$84.59	$1,241,400.00
	Unit Sub Total	**CY**		**19**	**37,589.00**	**$98.95**	**$3,719,418.20**
190105	ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	M3	3	1	2,000.00	$160.00	$320,000.00
		M3	4	3	31,900.00	$81.55	$2,601,360.00
		M3	7	1	13,000.00	$120.00	$1,560,000.00
	Unit Sub Total	**M3**		**5**	**46,900.00**	**$95.55**	**$4,481,360.00**
	Item Code 190105 Total No. of Proj.			**24**		**Total Amount**	**$8,200,778.20**
190106	ROADWAY EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD)	CY	7	3	860.00	$134.71	$115,850.00
	Unit Sub Total	**CY**		**3**	**860.00**	**$134.71**	**$115,850.00**
190106	ROADWAY EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD)	M3	7	2	6,050.00	$242.94	$1,469,800.00
	Unit Sub Total	**M3**		**2**	**6,050.00**	**$242.94**	**$1,469,800.00**
	Item Code 190106 Total No. of Proj.			**5**		**Total Amount**	**$1,585,650.00**
190107	ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	CY	7	2	230.00	$45.04	$10,360.00
		CY	12	3	25,895.00	$7.27	$188,175.00
	Unit Sub Total	**CY**		**5**	**26,125.00**	**$7.60**	**$198,535.00**
190107	ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	M3	4	2	10,880.00	$16.48	$179,320.00
		M3	7	2	7,380.00	$27.83	$205,380.00
		M3	8	1	20,600.00	$10.00	$206,000.00
		M3	11	1	6,050.00	$15.00	$90,750.00
	Unit Sub Total	**M3**		**6**	**44,910.00**	**$15.17**	**$681,450.00**
	Item Code 190107 Total No. of Proj.			**11**		**Total Amount**	**$879,985.00**
190108	ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	CY	11	1	2,570.00	$47.11	$121,072.70

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
190108	ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	CY	12	1	13,900.00	$8.00	$111,200.00
	Unit Sub Total	**CY**		**2**	**16,470.00**	**$14.10**	**$232,272.70**
190108	ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	M3	4	3	61,350.00	$5.92	$362,910.00
		M3	7	2	26,900.00	$11.74	$315,800.00
		M3	8	1	12,100.00	$10.00	$121,000.00
	Unit Sub Total	**M3**		**6**	**100,350.00**	**$7.97**	**$799,710.00**
	Item Code 190108 Total No. of Proj.			**8**		**Total Amount**	**$1,031,982.70**
190109	ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS)	CY	1	2	4,201.60	$39.37	$165,400.00
		CY	2	2	62,410.00	$7.08	$441,800.00
		CY	4	3	9,450.00	$57.83	$546,500.00
	Unit Sub Total	**CY**		**7**	**76,061.60**	**$15.17**	**$1,153,700.00**
	Item Code 190109 Total No. of Proj.			**7**		**Total Amount**	**$1,153,700.00**
190110	LEAD COMPLIANCE PLAN	LS	1	36	36.00	$2,240.28	$80,650.00
		LS	2	33	33.00	$1,972.58	$65,095.00
		LS	3	36	36.00	$2,293.19	$82,555.00
		LS	4	37	37.00	$2,767.43	$102,395.00
		LS	5	22	22.00	$2,658.53	$58,487.69
		LS	6	41	41.00	$2,423.83	$99,377.19
		LS	7	47	47.00	$2,252.45	$105,865.00
		LS	8	47	47.00	$2,407.10	$113,133.71
		LS	9	8	8.00	$1,875.00	$15,000.00
		LS	10	35	35.00	$2,379.00	$83,265.00
		LS	11	14	14.00	$8,841.97	$123,787.52
		LS	12	23	23.00	$3,227.26	$74,227.00
	Unit Sub Total	**LS**		**379**	**379.00**	**$2,648.65**	**$1,003,838.11**
	Item Code 190110 Total No. of Proj.			**379**		**Total Amount**	**$1,003,838.11**
190113	ASBESTOS COMPLIANCE PLAN	LS	1	1	1.00	$8,500.00	$8,500.00
		LS	2	2	2.00	$1,327.50	$2,655.00
		LS	3	1	1.00	$5,000.00	$5,000.00
		LS	4	3	3.00	$3,333.33	$10,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
190113	ASBESTOS COMPLIANCE PLAN	LS	5	1	1.00	$3,500.00	$3,500.00
		LS	7	1	1.00	$2,000.00	$2,000.00
		LS	8	1	1.00	$1,000.00	$1,000.00
		LS	10	1	1.00	$2,500.00	$2,500.00
		LS	12	1	1.00	$3,500.00	$3,500.00
	Unit Sub Total	**LS**		**12**	**12.00**	**$3,221.25**	**$38,655.00**
	Item Code 190113 Total No. of Proj.			**12**		**Total Amount**	**$38,655.00**
190115	ASBESTOS COMPLIANCE PLAN (NATURALLY OCCURING ASBESTOS)	LS	1	9	9.00	$2,397.78	$21,580.00
		LS	2	1	1.00	$1,500.00	$1,500.00
		LS	3	1	1.00	$8,000.00	$8,000.00
		LS	4	3	3.00	$2,000.00	$6,000.00
	Unit Sub Total	**LS**		**14**	**14.00**	**$2,648.57**	**$37,080.00**
	Item Code 190115 Total No. of Proj.			**14**		**Total Amount**	**$37,080.00**
190116	DUST CONTROL PLAN (NATURALLY OCCURRING ASBESTOS)	LS	1	8	8.00	$1,769.38	$14,155.00
		LS	2	2	2.00	$950.00	$1,900.00
		LS	3	1	1.00	$8,000.00	$8,000.00
		LS	4	3	3.00	$4,333.33	$13,000.00
	Unit Sub Total	**LS**		**14**	**14.00**	**$2,646.79**	**$37,055.00**
	Item Code 190116 Total No. of Proj.			**14**		**Total Amount**	**$37,055.00**
190117	SAMPLING AND ANALYSIS PLAN (NATURALLY OCCURRING ASBESTOS)	LS	1	1	1.00	$4,800.00	$4,800.00
		LS	2	1	1.00	$2,000.00	$2,000.00
		LS	4	1	1.00	$500.00	$500.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$2,433.33**	**$7,300.00**
	Item Code 190117 Total No. of Proj.			**3**		**Total Amount**	**$7,300.00**
190130	ROADWAY EXCAVATION (SLIDE REMOVAL)	CY	5	1	1,750.00	$15.00	$26,250.00
	Unit Sub Total	**CY**		**1**	**1,750.00**	**$15.00**	**$26,250.00**
	Item Code 190130 Total No. of Proj.			**1**		**Total Amount**	**$26,250.00**
190138	ROADWAY EXCAVATION (DETOUR REMOVAL)	CY	8	1	1,440.00	$9.00	$12,960.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**CY**		**1**	**1,440.00**	**$9.00**	**$12,960.00**
	Item Code 190138 Total No. of Proj.			**1**		**Total Amount**	**$12,960.00**
190139	ROADWAY EXCAVATION (UNSUITABLE MATERIAL)	M3	4	1	4,140.00	$20.00	$82,800.00
	Unit Sub Total	**M3**		**1**	**4,140.00**	**$20.00**	**$82,800.00**
	Item Code 190139 Total No. of Proj.			**1**		**Total Amount**	**$82,800.00**
190151	CHANNEL EXCAVATION	M3	4	1	250.00	$21.00	$5,250.00
	Unit Sub Total	**M3**		**1**	**250.00**	**$21.00**	**$5,250.00**
	Item Code 190151 Total No. of Proj.			**1**		**Total Amount**	**$5,250.00**
190167	REMOVE UNSUITABLE MATERIAL	CY	7	1	38.00	$80.00	$3,040.00
	Unit Sub Total	**CY**		**1**	**38.00**	**$80.00**	**$3,040.00**
	Item Code 190167 Total No. of Proj.			**1**		**Total Amount**	**$3,040.00**
190185	SHOULDER BACKING	TON	2	1	1,540.00	$25.00	$38,500.00
	Unit Sub Total	**TON**		**1**	**1,540.00**	**$25.00**	**$38,500.00**
	Item Code 190185 Total No. of Proj.			**1**		**Total Amount**	**$38,500.00**
192001	STRUCTURE EXCAVATION	CY	4	3	213.00	$60.44	$12,873.56
		CY	7	1	11,355.00	$37.00	$420,135.00
		CY	10	1	23.00	$150.00	$3,450.00
	Unit Sub Total	**CY**		**5**	**11,591.00**	**$37.65**	**$436,458.56**
192001	STRUCTURE EXCAVATION	M3	7	1	51.00	$140.00	$7,140.00
	Unit Sub Total	**M3**		**1**	**51.00**	**$140.00**	**$7,140.00**
	Item Code 192001 Total No. of Proj.			**6**		**Total Amount**	**$443,598.56**
192003	STRUCTURE EXCAVATION (BRIDGE)	CY	3	1	2,596.00	$22.00	$57,112.00
		CY	4	1	560.00	$80.00	$44,800.00
		CY	5	2	54.00	$130.09	$7,025.00
		CY	6	2	1,165.00	$42.31	$49,290.00
		CY	8	2	1,231.00	$56.22	$69,212.00
		CY	11	1	395.00	$165.00	$65,175.00
		CY	12	2	533.00	$242.33	$129,160.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**CY**		**11**	**6,534.00**	**$64.55**	**$421,774.00**
192003	STRUCTURE EXCAVATION (BRIDGE)		M3	1	1	853.00	$200.00	$170,600.00
			M3	2	1	2,060.00	$30.00	$61,800.00
			M3	3	2	475.00	$213.52	$101,420.00
			M3	4	8	16,208.00	$68.22	$1,105,780.00
			M3	5	2	2,115.00	$87.51	$185,085.00
			M3	6	2	1,495.00	$70.89	$105,975.00
			M3	7	4	4,286.00	$51.30	$219,870.00
			M3	8	3	11,050.00	$54.25	$599,470.00
			M3	10	1	3,670.00	$88.00	$322,960.00
			M3	11	3	10,086.00	$35.48	$357,890.00
		Unit Sub Total	**M3**		**27**	**52,298.00**	**$61.78**	**$3,230,850.00**
	Item Code 192003	**Total No. of Proj.**			**38**		**Total Amount**	**$3,652,624.00**
192008	STRUCTURE EXCAVATION (TYPE A)		M3	4	1	1,625.00	$210.00	$341,250.00
		Unit Sub Total	**M3**		**1**	**1,625.00**	**$210.00**	**$341,250.00**
	Item Code 192008	**Total No. of Proj.**			**1**		**Total Amount**	**$341,250.00**
192009	STRUCTURE EXCAVATION (NATURALLY OCCURRING ASBESTOS)		CY	1	1	4.50	$1,000.00	$4,500.00
			CY	4	1	435.00	$20.00	$8,700.00
		Unit Sub Total	**CY**		**2**	**439.50**	**$30.03**	**$13,200.00**
	Item Code 192009	**Total No. of Proj.**			**2**		**Total Amount**	**$13,200.00**
192020	STRUCTURE EXCAVATION (TYPE D)		CY	3	2	372.00	$105.73	$39,330.00
			CY	12	1	215.00	$175.00	$37,625.00
		Unit Sub Total	**CY**		**3**	**587.00**	**$131.10**	**$76,955.00**
192020	STRUCTURE EXCAVATION (TYPE D)		M3	1	1	470.00	$95.00	$44,650.00
			M3	2	1	100.00	$100.00	$10,000.00
			M3	3	1	179.00	$90.00	$16,110.00
			M3	4	1	244.00	$72.00	$17,568.00
			M3	5	1	130.00	$75.00	$9,750.00
		Unit Sub Total	**M3**		**5**	**1,123.00**	**$87.34**	**$98,078.00**
	Item Code 192020	**Total No. of Proj.**			**8**		**Total Amount**	**$175,033.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
192026	STRUCTURE EXCAVATION (PUMPING PLANT)	M3	4	1	940.00	$150.00	$141,000.00
	Unit Sub Total	**M3**		**1**	**940.00**	**$150.00**	**$141,000.00**
	Item Code 192026 Total No. of Proj.			**1**		**Total Amount**	**$141,000.00**
192027	STRUCTURE BACKFILL (PUMPING PLANT)	M3	4	1	390.00	$100.00	$39,000.00
	Unit Sub Total	**M3**		**1**	**390.00**	**$100.00**	**$39,000.00**
	Item Code 192027 Total No. of Proj.			**1**		**Total Amount**	**$39,000.00**
192032	STRUCTURE EXCAVATION (ROCK SLOPE PROTECTION)	CY	7	1	200.00	$13.00	$2,600.00
	Unit Sub Total	**CY**		**1**	**200.00**	**$13.00**	**$2,600.00**
	Item Code 192032 Total No. of Proj.			**1**		**Total Amount**	**$2,600.00**
192035	STRUCTURE EXCAVATION (ROCK)	CY	2	1	374.00	$100.00	$37,400.00
	Unit Sub Total	**CY**		**1**	**374.00**	**$100.00**	**$37,400.00**
	Item Code 192035 Total No. of Proj.			**1**		**Total Amount**	**$37,400.00**
192036	STRUCTURE EXCAVATION (CRIB WALL)	M3	11	1	3,780.00	$5.50	$20,790.00
	Unit Sub Total	**M3**		**1**	**3,780.00**	**$5.50**	**$20,790.00**
	Item Code 192036 Total No. of Proj.			**1**		**Total Amount**	**$20,790.00**
192037	STRUCTURE EXCAVATION (RETAINING WALL)	CY	2	1	254.00	$55.00	$13,970.00
		CY	3	1	7,002.00	$75.00	$525,150.00
		CY	4	4	2,705.00	$37.62	$101,762.06
		CY	5	3	213.00	$131.69	$28,050.00
		CY	6	2	1,504.00	$62.43	$93,895.00
		CY	7	2	4,098.00	$77.76	$318,671.00
		CY	8	1	300.00	$8.00	$2,400.00
		CY	11	3	2,673.00	$33.17	$88,657.00
		CY	12	2	3,069.00	$90.17	$276,720.00
	Unit Sub Total	**CY**		**19**	**21,818.00**	**$66.43**	**$1,449,275.06**
192037	STRUCTURE EXCAVATION (RETAINING WALL)	M3	2	1	411.00	$50.00	$20,550.00
		M3	3	2	7,531.00	$15.78	$118,840.00
		M3	4	8	16,375.00	$30.99	$507,408.50
		M3	7	3	24,548.00	$31.28	$767,880.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
192037	STRUCTURE EXCAVATION (RETAINING WALL)	M3	8	2	10,965.00	$25.30	$277,425.00
		M3	10	1	9,840.00	$8.00	$78,720.00
		M3	11	3	5,240.00	$37.60	$197,020.00
	Unit Sub Total	**M3**		**20**	**74,910.00**	**$26.27**	**$1,967,843.50**
	Item Code 192037 Total No. of Proj.			**39**		**Total Amount**	**$3,417,118.56**
192038	STRUCTURE EXCAVATION (SOUND WALL)	M3	7	1	105.00	$45.00	$4,725.00
	Unit Sub Total	**M3**		**1**	**105.00**	**$45.00**	**$4,725.00**
	Item Code 192038 Total No. of Proj.			**1**		**Total Amount**	**$4,725.00**
192049	STRUCTURE EXCAVATION (SOLDIER PILE WALL)	CY	1	7	3,705.00	$39.01	$144,550.00
		CY	2	1	537.00	$47.00	$25,239.00
		CY	5	2	1,285.00	$104.11	$133,775.00
		CY	7	2	1,573.00	$31.41	$49,407.00
		CY	10	1	26.00	$100.00	$2,600.00
	Unit Sub Total	**CY**		**13**	**7,126.00**	**$49.90**	**$355,571.00**
192049	STRUCTURE EXCAVATION (SOLDIER PILE WALL)	M3	4	2	1,081.00	$23.84	$25,770.00
	Unit Sub Total	**M3**		**2**	**1,081.00**	**$23.84**	**$25,770.00**
	Item Code 192049 Total No. of Proj.			**15**		**Total Amount**	**$381,341.00**
192050	STRUCTURE EXCAVATION (TIEBACK WALL)	CY	3	1	1,100.00	$91.00	$100,100.00
		CY	4	1	125.00	$130.00	$16,250.00
	Unit Sub Total	**CY**		**2**	**1,225.00**	**$94.98**	**$116,350.00**
192050	STRUCTURE EXCAVATION (TIEBACK WALL)	M3	3	1	752.00	$45.00	$33,840.00
		M3	4	1	290.00	$125.00	$36,250.00
		M3	7	1	149.00	$600.00	$89,400.00
	Unit Sub Total	**M3**		**3**	**1,191.00**	**$133.91**	**$159,490.00**
	Item Code 192050 Total No. of Proj.			**5**		**Total Amount**	**$275,840.00**
192053	STRUCTURE EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	CY	2	1	15.00	$750.00	$11,250.00
		CY	4	4	3,899.00	$108.94	$424,740.00
		CY	5	1	151.00	$200.00	$30,200.00
		CY	7	1	82.00	$130.00	$10,660.00
		CY	12	1	5,995.00	$20.00	$119,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**CY**		**8**	**10,142.00**	**$58.84**	**$596,750.00**
192053	STRUCTURE EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	M3	3	1	12.00	$300.00	$3,600.00
		M3	4	1	528.00	$180.00	$95,040.00
		M3	7	1	20,373.00	$185.00	$3,769,005.00
	Unit Sub Total	**M3**		**3**	**20,913.00**	**$184.94**	**$3,867,645.00**
	Item Code 192053 Total No. of Proj.			**11**		**Total Amount**	**$4,464,395.00**
192054	STRUCTURE EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD)	CY	7	1	10.00	$130.00	$1,300.00
	Unit Sub Total	**CY**		**1**	**10.00**	**$130.00**	**$1,300.00**
192054	STRUCTURE EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD)	M3	7	1	1,287.00	$570.00	$733,590.00
	Unit Sub Total	**M3**		**1**	**1,287.00**	**$570.00**	**$733,590.00**
	Item Code 192054 Total No. of Proj.			**2**		**Total Amount**	**$734,890.00**
192055	STRUCTURE EXCAVATION (SOIL NAIL WALL)	CY	2	1	156.00	$26.50	$4,134.00
		CY	12	1	8,145.00	$17.00	$138,465.00
	Unit Sub Total	**CY**		**2**	**8,301.00**	**$17.18**	**$142,599.00**
192055	STRUCTURE EXCAVATION (SOIL NAIL WALL)	M3	4	4	8,990.00	$28.93	$260,090.00
	Unit Sub Total	**M3**		**4**	**8,990.00**	**$28.93**	**$260,090.00**
	Item Code 192055 Total No. of Proj.			**6**		**Total Amount**	**$402,689.00**
192057	STRUCTURE EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	CY	12	1	1,189.00	$25.00	$29,725.00
	Unit Sub Total	**CY**		**1**	**1,189.00**	**$25.00**	**$29,725.00**
192057	STRUCTURE EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	M3	7	1	1,768.00	$7.00	$12,376.00
	Unit Sub Total	**M3**		**1**	**1,768.00**	**$7.00**	**$12,376.00**
	Item Code 192057 Total No. of Proj.			**2**		**Total Amount**	**$42,101.00**
192058	STRUCTURE EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	CY	12	1	3,761.00	$19.00	$71,459.00
	Unit Sub Total	**CY**		**1**	**3,761.00**	**$19.00**	**$71,459.00**
192058	STRUCTURE EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	M3	7	2	4,611.00	$57.25	$263,993.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**2**	**4,611.00**	**$57.25**	**$263,993.00**
	Item Code 192058	**Total No. of Proj.**			**3**		**Total Amount**	**$335,452.00**
192502	SAND BEDDING		CY	4	1	360.00	$45.00	$16,200.00
		Unit Sub Total	**CY**		**1**	**360.00**	**$45.00**	**$16,200.00**
	Item Code 192502	**Total No. of Proj.**			**1**		**Total Amount**	**$16,200.00**
193001	STRUCTURE BACKFILL		CY	3	1	44.00	$430.00	$18,920.00
			CY	4	3	122.00	$103.69	$12,649.97
			CY	7	2	1,014.00	$22.69	$23,010.00
			CY	10	1	11.00	$250.00	$2,750.00
		Unit Sub Total	**CY**		**7**	**1,191.00**	**$48.14**	**$57,329.97**
193001	STRUCTURE BACKFILL		M3	7	1	33.00	$80.00	$2,640.00
		Unit Sub Total	**M3**		**1**	**33.00**	**$80.00**	**$2,640.00**
	Item Code 193001	**Total No. of Proj.**			**8**		**Total Amount**	**$59,969.97**
193003	STRUCTURE BACKFILL (BRIDGE)		CY	2	1	12.00	$500.00	$6,000.00
			CY	3	1	1,459.00	$40.00	$58,360.00
			CY	4	4	4,260.00	$76.90	$327,600.00
			CY	5	2	1,177.00	$119.64	$140,820.00
			CY	6	2	1,310.00	$77.50	$101,525.00
			CY	8	2	767.00	$83.46	$64,016.00
			CY	11	1	255.00	$115.00	$29,325.00
			CY	12	1	1,770.00	$38.00	$67,260.00
		Unit Sub Total	**CY**		**14**	**11,010.00**	**$72.20**	**$794,906.00**
193003	STRUCTURE BACKFILL (BRIDGE)		M3	1	2	403.00	$194.54	$78,400.00
			M3	2	1	1,020.00	$78.00	$79,560.00
			M3	3	2	285.00	$114.88	$32,740.00
			M3	4	8	8,560.00	$94.49	$808,825.00
			M3	5	2	998.00	$99.90	$99,700.00
			M3	6	2	813.00	$94.01	$76,430.00
			M3	7	4	13,151.00	$53.89	$708,677.00
			M3	8	3	7,203.00	$37.34	$268,939.00
			M3	10	1	1,900.00	$62.00	$117,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
193003	STRUCTURE BACKFILL (BRIDGE)	M3	11	3	9,063.00	$18.46	$167,310.00
	Unit Sub Total	**M3**		**28**	**43,396.00**	**$56.19**	**$2,438,381.00**
	Item Code 193003 Total No. of Proj.			**42**		**Total Amount**	**$3,233,287.00**
193004	STRUCTURE BACKFILL (CULVERT)	CY	5	1	1,020.00	$100.00	$102,000.00
	Unit Sub Total	**CY**		**1**	**1,020.00**	**$100.00**	**$102,000.00**
193004	STRUCTURE BACKFILL (CULVERT)	M3	4	1	1,490.00	$37.00	$55,130.00
	Unit Sub Total	**M3**		**1**	**1,490.00**	**$37.00**	**$55,130.00**
	Item Code 193004 Total No. of Proj.			**2**		**Total Amount**	**$157,130.00**
193006	STRUCTURE BACKFILL (SLURRY CEMENT)	CY	3	2	509.00	$78.37	$39,890.56
		CY	4	1	220.00	$130.00	$28,600.00
		CY	6	1	2.00	$2,000.00	$4,000.00
		CY	10	1	1.20	$100.00	$120.00
	Unit Sub Total	**CY**		**5**	**732.20**	**$99.17**	**$72,610.56**
193006	STRUCTURE BACKFILL (SLURRY CEMENT)	M3	4	3	497.00	$135.61	$67,398.00
	Unit Sub Total	**M3**		**3**	**497.00**	**$135.61**	**$67,398.00**
	Item Code 193006 Total No. of Proj.			**8**		**Total Amount**	**$140,008.56**
193012	STRUCTURE BACKFILL (CRIB WALL)	M3	11	1	9,810.00	$48.00	$470,880.00
	Unit Sub Total	**M3**		**1**	**9,810.00**	**$48.00**	**$470,880.00**
	Item Code 193012 Total No. of Proj.			**1**		**Total Amount**	**$470,880.00**
193013	STRUCTURE BACKFILL (RETAINING WALL)	CY	2	1	39.00	$35.00	$1,365.00
		CY	3	1	6,616.00	$50.00	$330,800.00
		CY	4	7	8,420.00	$55.17	$464,548.44
		CY	5	3	94.00	$175.02	$16,452.00
		CY	6	2	2,344.00	$46.64	$109,322.00
		CY	7	2	2,817.00	$70.84	$199,555.00
		CY	8	1	100.00	$20.00	$2,000.00
		CY	11	3	1,960.00	$59.88	$117,372.00
		CY	12	2	12,665.00	$33.67	$426,445.00
	Unit Sub Total	**CY**		**22**	**35,055.00**	**$47.58**	**$1,667,859.44**
193013	STRUCTURE BACKFILL (RETAINING WALL)	M3	2	1	356.00	$67.00	$23,852.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
193013	STRUCTURE BACKFILL (RETAINING WALL)	M3	3	2	4,971.00	$22.22	$110,466.00
		M3	4	8	16,206.00	$58.38	$946,160.00
		M3	7	3	37,842.00	$33.60	$1,271,475.00
		M3	8	2	17,050.00	$20.16	$343,700.00
		M3	10	1	18,267.00	$16.00	$292,272.00
		M3	11	3	5,639.00	$18.87	$106,400.00
	Unit Sub Total	**M3**		**20**	**100,331.00**	**$30.84**	**$3,094,325.00**
	Item Code 193013 Total No. of Proj.			**42**		**Total Amount**	**$4,762,184.44**
193014	STRUCTURE BACKFILL (SOUND WALL)	M3	7	1	388.00	$35.00	$13,580.00
	Unit Sub Total	**M3**		**1**	**388.00**	**$35.00**	**$13,580.00**
	Item Code 193014 Total No. of Proj.			**1**		**Total Amount**	**$13,580.00**
193026	STRUCTURE BACKFILL (TIEBACK WALL)	CY	3	1	83.00	$170.00	$14,110.00
		CY	4	1	33.00	$80.00	$2,640.00
	Unit Sub Total	**CY**		**2**	**116.00**	**$144.40**	**$16,750.00**
193026	STRUCTURE BACKFILL (TIEBACK WALL)	M3	3	1	63.00	$60.00	$3,780.00
		M3	4	1	32.00	$200.00	$6,400.00
		M3	7	1	26.00	$400.00	$10,400.00
	Unit Sub Total	**M3**		**3**	**121.00**	**$170.08**	**$20,580.00**
	Item Code 193026 Total No. of Proj.			**5**		**Total Amount**	**$37,330.00**
193028	STRUCTURE BACKFILL (SOIL NAIL WALL)	CY	2	1	16.00	$65.00	$1,040.00
		CY	12	1	400.00	$100.00	$40,000.00
	Unit Sub Total	**CY**		**2**	**416.00**	**$98.65**	**$41,040.00**
193028	STRUCTURE BACKFILL (SOIL NAIL WALL)	M3	4	4	301.00	$84.29	$25,371.00
	Unit Sub Total	**M3**		**4**	**301.00**	**$84.29**	**$25,371.00**
	Item Code 193028 Total No. of Proj.			**6**		**Total Amount**	**$66,411.00**
193029	STRUCTURE BACKFILL (SOLDIER PILE WALL)	CY	1	6	1,919.00	$34.06	$65,359.00
		CY	2	1	502.00	$40.00	$20,080.00
		CY	5	3	526.00	$146.54	$77,080.00
		CY	7	2	1,765.00	$57.84	$102,080.00
		CY	10	1	25.00	$100.00	$2,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**CY**		**13**	**4,737.00**	**$56.39**	**$267,099.00**
193029	STRUCTURE BACKFILL (SOLDIER PILE WALL)	M3	4	2	152.00	$102.30	$15,550.00
	Unit Sub Total	**M3**		**2**	**152.00**	**$102.30**	**$15,550.00**
	Item Code 193029 Total No. of Proj.			**15**		**Total Amount**	**$282,649.00**
193030	PERVIOUS BACKFILL MATERIAL	M3	1	2	73.00	$261.07	$19,058.00
		M3	3	1	21.00	$75.00	$1,575.00
		M3	4	1	6.00	$150.00	$900.00
		M3	7	3	765.00	$76.65	$58,640.00
	Unit Sub Total	**M3**		**7**	**865.00**	**$92.69**	**$80,173.00**
	Item Code 193030 Total No. of Proj.			**7**		**Total Amount**	**$80,173.00**
193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	CY	1	1	75.00	$90.00	$6,750.00
		CY	7	1	374.00	$42.00	$15,708.00
		CY	11	3	396.00	$90.43	$35,812.00
	Unit Sub Total	**CY**		**5**	**845.00**	**$68.96**	**$58,270.00**
193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	M3	3	1	479.00	$100.00	$47,900.00
		M3	4	6	1,251.00	$145.16	$181,601.00
		M3	7	2	2,171.00	$91.13	$197,835.00
		M3	8	2	1,776.00	$40.08	$71,190.00
		M3	11	3	428.00	$63.20	$27,050.00
	Unit Sub Total	**M3**		**14**	**6,105.00**	**$86.09**	**$525,576.00**
	Item Code 193031 Total No. of Proj.			**19**		**Total Amount**	**$583,846.00**
193114	SAND BACKFILL	CY	1	4	32.00	$235.00	$7,520.00
		CY	2	2	34.00	$157.65	$5,360.00
		CY	3	1	250.00	$60.00	$15,000.00
		CY	4	2	360.00	$103.75	$37,350.00
		CY	5	1	31.00	$190.00	$5,890.00
		CY	7	2	840.00	$80.00	$67,200.00
		CY	11	1	21.00	$200.00	$4,200.00
	Unit Sub Total	**CY**		**13**	**1,568.00**	**$90.89**	**$142,520.00**
193114	SAND BACKFILL	M3	2	2	40.00	$101.96	$4,078.20

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
193114	SAND BACKFILL	M3	3	1	50.00	$275.00	$13,750.00
		M3	4	8	1,565.10	$167.08	$261,493.20
		M3	5	1	30.00	$70.00	$2,100.00
		M3	6	1	7.00	$150.00	$1,050.00
		M3	7	4	179.00	$126.42	$22,630.00
		M3	8	2	299.00	$75.10	$22,455.00
		M3	9	1	23.00	$250.00	$5,750.00
		M3	10	1	7.00	$200.00	$1,400.00
		M3	11	2	830.00	$37.41	$31,050.00
	Unit Sub Total	**M3**		**23**	**3,030.10**	**$120.71**	**$365,756.40**
	Item Code 193114 Total No. of Proj.			**36**		**Total Amount**	**$508,276.40**
193116	CONCRETE BACKFILL (SOLDIER PILE WALL)	CY	7	2	257.00	$268.74	$69,065.00
	Unit Sub Total	**CY**		**2**	**257.00**	**$268.74**	**$69,065.00**
	Item Code 193116 Total No. of Proj.			**2**		**Total Amount**	**$69,065.00**
193117	CONCRETE BACKFILL FAST SETTING	M3	4	1	68.00	$230.00	$15,640.00
	Unit Sub Total	**M3**		**1**	**68.00**	**$230.00**	**$15,640.00**
	Item Code 193117 Total No. of Proj.			**1**		**Total Amount**	**$15,640.00**
193118	CONCRETE BACKFILL	CY	2	2	21.00	$150.00	$3,150.00
		CY	3	1	120.00	$160.00	$19,200.00
		CY	5	2	74.00	$172.70	$12,780.00
		CY	10	1	66.00	$250.00	$16,500.00
	Unit Sub Total	**CY**		**6**	**281.00**	**$183.74**	**$51,630.00**
193118	CONCRETE BACKFILL	M3	4	1	0.40	$1,000.00	$400.00
		M3	6	2	128.00	$230.31	$29,480.00
		M3	10	2	27.60	$164.67	$4,545.00
	Unit Sub Total	**M3**		**5**	**156.00**	**$220.67**	**$34,425.00**
	Item Code 193118 Total No. of Proj.			**11**		**Total Amount**	**$86,055.00**
193119	LEAN CONCRETE BACKFILL	CY	1	7	585.00	$200.65	$117,382.00
		CY	2	1	50.00	$199.00	$9,950.00
		CY	5	3	453.00	$201.95	$91,485.00
		CY	7	2	15.00	$200.00	$3,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
193119	LEAN CONCRETE BACKFILL		CY	10	1	5.00	$700.00	$3,500.00
		Unit Sub Total	**CY**		**14**	**1,108.00**	**$203.35**	**$225,317.00**
193119	LEAN CONCRETE BACKFILL		M3	4	1	233.00	$140.00	$32,620.00
			M3	7	1	243.00	$180.00	$43,740.00
			M3	11	1	215.00	$250.00	$53,750.00
		Unit Sub Total	**M3**		**3**	**691.00**	**$188.29**	**$130,110.00**
	Item Code 193119	**Total No. of Proj.**			**17**		**Total Amount**	**$355,427.00**
194001	DITCH EXCAVATION		CY	1	8	233.30	$55.77	$13,010.00
			CY	2	5	378.00	$91.59	$34,621.00
			CY	3	3	1,980.00	$20.59	$40,776.00
			CY	4	4	467.00	$29.31	$13,690.00
			CY	5	1	2.00	$350.00	$700.00
			CY	7	6	2,136.00	$23.37	$49,920.00
			CY	8	3	770.00	$17.97	$13,835.70
			CY	9	1	1.00	$90.00	$90.00
			CY	11	1	5.00	$25.00	$125.00
			CY	12	1	126.00	$9.00	$1,134.00
		Unit Sub Total	**CY**		**33**	**6,098.30**	**$27.53**	**$167,901.70**
194001	DITCH EXCAVATION		M3	2	2	80.00	$58.92	$4,713.20
			M3	3	1	35.00	$35.00	$1,225.00
			M3	4	4	5,750.00	$24.56	$141,210.00
			M3	6	1	190.00	$41.00	$7,790.00
			M3	7	2	922.00	$16.56	$15,270.00
			M3	8	1	1,190.00	$30.00	$35,700.00
			M3	9	2	900.00	$36.00	$32,400.00
			M3	10	2	3,845.00	$12.43	$47,795.00
			M3	11	2	1,388.00	$47.41	$65,812.00
		Unit Sub Total	**M3**		**17**	**14,300.00**	**$24.61**	**$351,915.20**
	Item Code 194001	**Total No. of Proj.**			**50**		**Total Amount**	**$519,816.90**
197003	CONTOUR GRADING		SQYD	3	1	2,770.00	$10.00	$27,700.00
		Unit Sub Total	**SQYD**		**1**	**2,770.00**	**$10.00**	**$27,700.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 197003	**Total No. of Proj.**			**1**		**Total Amount**	**$27,700.00**
197020	EARTH RETAINING STRUCTURE		M2	4	1	2,820.00	$385.00	$1,085,700.00
		Unit Sub Total	**M2**		**1**	**2,820.00**	**$385.00**	**$1,085,700.00**
197020	EARTH RETAINING STRUCTURE		SQFT	2	1	3,011.00	$32.50	$97,857.50
		Unit Sub Total	**SQFT**		**1**	**3,011.00**	**$32.50**	**$97,857.50**
	Item Code 197020	**Total No. of Proj.**			**2**		**Total Amount**	**$1,183,557.50**
197060	SOIL NAIL ASSEMBLY		LF	2	1	1,147.00	$79.25	$90,899.75
			LF	5	1	1,840.00	$35.00	$64,400.00
			LF	6	1	4,500.00	$63.20	$284,400.00
			LF	12	1	141,380.00	$18.00	$2,544,840.00
		Unit Sub Total	**LF**		**4**	**148,867.00**	**$20.05**	**$2,984,539.75**
197060	SOIL NAIL ASSEMBLY		M	4	3	29,045.00	$62.29	$1,809,138.00
		Unit Sub Total	**M**		**3**	**29,045.00**	**$62.29**	**$1,809,138.00**
	Item Code 197060	**Total No. of Proj.**			**7**		**Total Amount**	**$4,793,677.75**
198001	IMPORTED BORROW		CY	1	5	675.00	$68.24	$46,065.00
			CY	2	4	18,585.00	$13.38	$248,730.00
			CY	3	5	22,003.00	$23.24	$511,358.00
			CY	4	7	31,289.00	$18.66	$583,700.00
			CY	5	5	2,539.00	$12.95	$32,890.00
			CY	6	5	1,196,880.00	$5.03	$6,015,990.00
			CY	7	13	34,194.00	$21.42	$732,485.00
			CY	8	9	10,390.00	$20.48	$212,749.00
			CY	10	2	787.00	$30.69	$24,154.50
			CY	11	3	7,640.00	$8.58	$65,567.00
			CY	12	1	400.00	$20.00	$8,000.00
		Unit Sub Total	**CY**		**59**	**1,325,382.00**	**$6.40**	**$8,481,688.50**
198001	IMPORTED BORROW		M3	1	2	847.20	$55.68	$47,172.00
			M3	2	1	140.00	$133.00	$18,620.00
			M3	3	2	93,100.00	$11.22	$1,044,500.00
			M3	4	7	397,070.00	$5.97	$2,369,803.00
			M3	5	2	3,618.00	$21.29	$77,040.08

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
198001	IMPORTED BORROW	M3	6	2	366,000.00	$8.93	$3,267,000.00
		M3	7	1	3,310.00	$0.01	$33.10
		M3	8	2	697,000.00	$8.16	$5,687,200.00
		M3	9	1	1,750.00	$15.00	$26,250.00
		M3	10	5	274,360.00	$8.36	$2,292,687.00
		M3	11	1	32,200.00	$5.00	$161,000.00
	Unit Sub Total	**M3**		**26**	**1,869,395.20**	**$8.02**	**$14,991,305.18**
198001	IMPORTED BORROW	TON	1	1	250.00	$45.00	$11,250.00
		TON	3	1	90.00	$100.00	$9,000.00
		TON	11	4	3,425.00	$30.49	$104,429.60
	Unit Sub Total	**TON**		**6**	**3,765.00**	**$33.12**	**$124,679.60**
198001	IMPORTED BORROW	TONN	2	2	640.00	$57.65	$36,892.80
	Unit Sub Total	**TONN**		**2**	**640.00**	**$57.65**	**$36,892.80**
	Item Code 198001 Total No. of Proj.			**93**		**Total Amount**	**$23,634,566.08**
198007	IMPORTED MATERIAL (SHOULDER BACKING)	CY	3	2	210.00	$74.29	$15,600.00
		CY	8	1	200.00	$40.00	$8,000.00
		CY	10	1	560.00	$42.00	$23,520.00
	Unit Sub Total	**CY**		**4**	**970.00**	**$48.58**	**$47,120.00**
198007	IMPORTED MATERIAL (SHOULDER BACKING)	TON	1	14	3,098.90	$45.72	$141,672.00
		TON	2	19	46,146.00	$26.17	$1,207,720.00
		TON	3	9	22,159.00	$18.41	$407,999.12
		TON	4	13	8,092.00	$35.99	$291,226.00
		TON	5	12	8,086.00	$45.21	$365,542.50
		TON	6	10	12,340.00	$36.45	$449,792.10
		TON	7	2	1,450.00	$35.99	$52,180.00
		TON	8	2	149.00	$117.72	$17,540.00
		TON	9	3	4,793.00	$17.90	$85,783.80
		TON	10	8	13,376.00	$31.48	$421,120.00
		TON	11	4	7,650.00	$28.32	$216,650.00
	Unit Sub Total	**TON**		**96**	**127,339.90**	**$28.72**	**$3,657,225.52**
198007	IMPORTED MATERIAL (SHOULDER BACKING)	TONN	3	2	1,542.00	$10.31	$15,900.00
		TONN	4	3	710.00	$55.94	$39,720.00
		TONN	5	1	8.00	$302.51	$2,420.08

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
198007	IMPORTED MATERIAL (SHOULDER BACKING)	TONN	6	5	3,506.00	$28.69	$100,585.00
		TONN	8	2	281.00	$26.32	$7,395.00
		TONN	9	1	70.00	$175.00	$12,250.00
		TONN	10	3	13,466.00	$13.27	$178,660.00
	Unit Sub Total	**TONN**		**17**	**19,583.00**	**$18.23**	**$356,930.08**
	Item Code 198007 Total No. of Proj.			**117**		**Total Amount**	**$4,061,275.60**
198021	IMPORTED ROCKY MATERIAL	M3	1	1	16.00	$120.00	$1,920.00
	Unit Sub Total	**M3**		**1**	**16.00**	**$120.00**	**$1,920.00**
	Item Code 198021 Total No. of Proj.			**1**		**Total Amount**	**$1,920.00**
198200	SUBGRADE ENHANCEMENT FABRIC	M2	10	1	55,000.00	$1.00	$55,000.00
	Unit Sub Total	**M2**		**1**	**55,000.00**	**$1.00**	**$55,000.00**
	Item Code 198200 Total No. of Proj.			**1**		**Total Amount**	**$55,000.00**
198205	SUBGRADE ENHANCEMENT GEOTEXTILE	SQYD	1	1	1,480.00	$1.00	$1,480.00
		SQYD	7	2	145,400.00	$1.08	$157,700.00
	Unit Sub Total	**SQYD**		**3**	**146,880.00**	**$1.08**	**$159,180.00**
	Item Code 198205 Total No. of Proj.			**3**		**Total Amount**	**$159,180.00**
198250	GEOSYNTHETIC REINFORCEMENT	SQYD	4	1	1,300.00	$5.25	$6,825.00
	Unit Sub Total	**SQYD**		**1**	**1,300.00**	**$5.25**	**$6,825.00**
	Item Code 198250 Total No. of Proj.			**1**		**Total Amount**	**$6,825.00**
200001	HIGHWAY PLANTING	LS	1	1	1.00	$4,700.00	$4,700.00
		LS	2	2	2.00	$9,103.50	$18,207.00
		LS	3	4	4.00	$122,690.00	$490,760.00
		LS	4	9	9.00	$45,191.11	$406,720.00
		LS	5	4	4.00	$27,245.00	$108,980.00
		LS	6	6	6.00	$29,519.63	$177,117.77
		LS	7	10	10.00	$90,040.50	$900,405.00
		LS	8	1	1.00	$9,020.00	$9,020.00
		LS	9	1	1.00	$13,300.00	$13,300.00
		LS	10	2	2.00	$8,750.00	$17,500.00
		LS	11	4	4.00	$277,839.50	$1,111,358.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
200001	HIGHWAY PLANTING		LS	12	1	1.00	$100,000.00	$100,000.00
		Unit Sub Total	**LS**		**45**	**45.00**	**$74,623.73**	**$3,358,067.77**
	Item Code 200001	**Total No. of Proj.**			**45**		**Total Amount**	**$3,358,067.77**
200002	ROADSIDE CLEARING		EA	2	1	1.00	$1,200.00	$1,200.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$1,200.00**	**$1,200.00**
200002	ROADSIDE CLEARING		LS	3	2	2.00	$16,000.00	$32,000.00
			LS	4	5	5.00	$27,002.60	$135,013.00
			LS	5	3	3.00	$47,130.27	$141,390.82
			LS	7	2	2.00	$85,000.00	$170,000.00
			LS	8	2	2.00	$3,500.00	$7,000.00
			LS	10	2	2.00	$7,500.00	$15,000.00
			LS	11	3	3.00	$64,214.96	$192,644.87
			LS	12	1	1.00	$5,850.00	$5,850.00
		Unit Sub Total	**LS**		**20**	**20.00**	**$34,944.93**	**$698,898.69**
	Item Code 200002	**Total No. of Proj.**			**21**		**Total Amount**	**$700,098.69**
200052	PRUNE EXISTING PLANTS		EA	10	1	17.00	$100.00	$1,700.00
		Unit Sub Total	**EA**		**1**	**17.00**	**$100.00**	**$1,700.00**
200052	PRUNE EXISTING PLANTS		LS	2	1	1.00	$13,000.00	$13,000.00
			LS	3	1	1.00	$1,700.00	$1,700.00
			LS	4	2	2.00	$2,150.00	$4,300.00
			LS	5	2	2.00	$708.75	$1,417.50
			LS	7	2	2.00	$9,000.00	$18,000.00
			LS	8	1	1.00	$3,000.00	$3,000.00
			LS	10	1	1.00	$2,500.00	$2,500.00
			LS	11	1	1.00	$1,550.19	$1,550.19
			LS	12	1	1.00	$3,000.00	$3,000.00
		Unit Sub Total	**LS**		**12**	**12.00**	**$4,038.97**	**$48,467.69**
200052	PRUNE EXISTING PLANTS		M	11	1	440.00	$26.00	$11,440.00
		Unit Sub Total	**M**		**1**	**440.00**	**$26.00**	**$11,440.00**
	Item Code 200052	**Total No. of Proj.**			**14**		**Total Amount**	**$61,607.69**
200101	IMPORTED TOPSOIL		CY	1	2	244.00	$108.57	$26,490.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
200101	IMPORTED TOPSOIL		CY	2	1	85.00	$73.72	$6,266.20
			CY	3	1	160.00	$70.00	$11,200.00
			CY	4	4	3,230.00	$48.25	$155,860.00
			CY	11	1	820.00	$31.76	$26,043.20
		Unit Sub Total	**CY**		**9**	**4,539.00**	**$49.76**	**$225,859.40**
200101	IMPORTED TOPSOIL		M3	4	2	514.00	$62.45	$32,100.00
			M3	11	1	830.00	$29.00	$24,070.00
		Unit Sub Total	**M3**		**3**	**1,344.00**	**$41.79**	**$56,170.00**
	Item Code 200101	**Total No. of Proj.**			**12**		**Total Amount**	**$282,029.40**
200108	PREPARE HOLE (SOIL AMENDMENT)		CY	4	1	6.00	$70.00	$420.00
		Unit Sub Total	**CY**		**1**	**6.00**	**$70.00**	**$420.00**
	Item Code 200108	**Total No. of Proj.**			**1**		**Total Amount**	**$420.00**
200110	PREPARE HOLE		EA	2	1	220.00	$130.00	$28,600.00
		Unit Sub Total	**EA**		**1**	**220.00**	**$130.00**	**$28,600.00**
	Item Code 200110	**Total No. of Proj.**			**1**		**Total Amount**	**$28,600.00**
200114	ROCK BLANKET		M2	4	1	620.00	$110.00	$68,200.00
			M2	7	2	2,530.00	$70.49	$178,330.00
			M2	8	1	15,100.00	$75.00	$1,132,500.00
		Unit Sub Total	**M2**		**4**	**18,250.00**	**$75.56**	**$1,379,030.00**
200114	ROCK BLANKET		SQFT	2	1	110.00	$10.77	$1,184.70
		Unit Sub Total	**SQFT**		**1**	**110.00**	**$10.77**	**$1,184.70**
200114	ROCK BLANKET		SQYD	4	1	190.00	$100.00	$19,000.00
			SQYD	7	2	1,230.00	$55.00	$67,650.00
			SQYD	8	2	736.00	$99.18	$73,000.00
			SQYD	12	1	770.00	$72.00	$55,440.00
		Unit Sub Total	**SQYD**		**6**	**2,926.00**	**$73.51**	**$215,090.00**
	Item Code 200114	**Total No. of Proj.**			**11**		**Total Amount**	**$1,595,304.70**
200120	CULTIVATE		SQYD	5	1	1,560.00	$2.25	$3,510.00
		Unit Sub Total	**SQYD**		**1**	**1,560.00**	**$2.25**	**$3,510.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 200120	**Total No. of Proj.**			**1**		**Total Amount**	**$3,510.00**
200121	CULTIVATE (SOIL AMENDMENT)		SQYD	4	1	3,850.00	$2.50	$9,625.00
		Unit Sub Total	**SQYD**		**1**	**3,850.00**	**$2.50**	**$9,625.00**
	Item Code 200121	**Total No. of Proj.**			**1**		**Total Amount**	**$9,625.00**
202003	IRON SULFATE		KG	11	1	460.00	$1.35	$621.00
		Unit Sub Total	**KG**		**1**	**460.00**	**$1.35**	**$621.00**
202003	IRON SULFATE		LB	11	2	370.00	$0.58	$213.00
		Unit Sub Total	**LB**		**2**	**370.00**	**$0.58**	**$213.00**
	Item Code 202003	**Total No. of Proj.**			**3**		**Total Amount**	**$834.00**
202006	SOIL AMENDMENT		CY	4	3	473.00	$32.81	$15,521.00
			CY	10	1	10.00	$50.00	$500.00
		Unit Sub Total	**CY**		**4**	**483.00**	**$33.17**	**$16,021.00**
202006	SOIL AMENDMENT		M3	3	1	790.00	$14.00	$11,060.00
			M3	4	1	260.00	$40.00	$10,400.00
		Unit Sub Total	**M3**		**2**	**1,050.00**	**$20.44**	**$21,460.00**
	Item Code 202006	**Total No. of Proj.**			**6**		**Total Amount**	**$37,481.00**
202007	DUFF		CY	6	1	6,370.00	$6.00	$38,220.00
		Unit Sub Total	**CY**		**1**	**6,370.00**	**$6.00**	**$38,220.00**
202007	DUFF		HA	9	1	12.00	$500.00	$6,000.00
			HA	10	1	0.30	$12,500.00	$3,750.00
		Unit Sub Total	**HA**		**2**	**12.30**	**$792.68**	**$9,750.00**
202007	DUFF		M2	9	1	6,180.00	$1.80	$11,124.00
			M2	10	2	14,700.00	$4.07	$59,760.00
			M2	11	1	479,000.00	$1.90	$910,100.00
		Unit Sub Total	**M2**		**4**	**499,880.00**	**$1.96**	**$980,984.00**
202007	DUFF		SQYD	1	1	80.00	$52.00	$4,160.00
			SQYD	2	1	213,000.00	$0.47	$100,110.00
			SQYD	8	1	420.00	$4.00	$1,680.00
		Unit Sub Total	**SQYD**		**3**	**213,500.00**	**$0.50**	**$105,950.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 202007 Total No. of Proj.			**10**		**Total Amount**	**$1,134,904.00**
202011	MULCH	CY	3	3	213.00	$68.23	$14,532.00
		CY	4	7	4,696.00	$31.91	$149,840.00
		CY	5	2	424.00	$29.41	$12,470.00
		CY	7	4	4,460.00	$26.12	$116,515.00
		CY	8	2	559.00	$38.54	$21,546.20
		CY	10	1	440.00	$20.00	$8,800.00
		CY	11	3	1,190.00	$53.85	$64,085.20
		CY	12	2	185.00	$51.35	$9,500.00
	Unit Sub Total	**CY**		**24**	**12,167.00**	**$32.65**	**$397,288.40**
202011	MULCH	M2	2	1	15,100.00	$5.00	$75,500.00
	Unit Sub Total	**M2**		**1**	**15,100.00**	**$5.00**	**$75,500.00**
202011	MULCH	M3	3	1	2,900.00	$29.00	$84,100.00
		M3	4	2	4,640.00	$15.75	$73,080.00
		M3	5	1	400.00	$30.00	$12,000.00
		M3	11	1	400.00	$53.39	$21,356.00
	Unit Sub Total	**M3**		**5**	**8,340.00**	**$22.85**	**$190,536.00**
	Item Code 202011 Total No. of Proj.			**30**		**Total Amount**	**$663,324.40**
202018	COMMERCIAL FERTILIZER	LB	7	1	22,100.00	$0.50	$11,050.00
	Unit Sub Total	**LB**		**1**	**22,100.00**	**$0.50**	**$11,050.00**
	Item Code 202018 Total No. of Proj.			**1**		**Total Amount**	**$11,050.00**
202031	COMMERCIAL FERTILIZER (SLOW RELEASE)	KG	3	1	1,070.00	$1.00	$1,070.00
		KG	4	1	850.00	$3.50	$2,975.00
		KG	11	1	2,700.00	$1.37	$3,699.00
	Unit Sub Total	**KG**		**3**	**4,620.00**	**$1.68**	**$7,744.00**
202031	COMMERCIAL FERTILIZER (SLOW RELEASE)	LB	4	2	780.00	$0.50	$390.00
		LB	10	1	160.00	$2.00	$320.00
		LB	11	2	1,760.00	$0.64	$1,134.00
	Unit Sub Total	**LB**		**5**	**2,700.00**	**$0.68**	**$1,844.00**
	Item Code 202031 Total No. of Proj.			**8**		**Total Amount**	**$9,588.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
202033	COMMERCIAL FERTILIZER (PACKET)		EA	3	1	1,300.00	$0.30	$390.00
			EA	4	2	1,180.00	$0.37	$440.00
			EA	5	3	14,840.00	$0.27	$3,936.00
			EA	6	1	42.00	$1.00	$42.00
			EA	11	2	22,280.00	$0.12	$2,663.00
		Unit Sub Total	**EA**		**9**	**39,642.00**	**$0.19**	**$7,471.00**
	Item Code 202033	**Total No. of Proj.**			**9**		**Total Amount**	**$7,471.00**
203001	EROSION CONTROL (BLANKET)		M2	3	1	180.00	$5.25	$945.00
			M2	8	1	13,500.00	$1.45	$19,575.00
			M2	9	2	44,680.00	$2.08	$92,723.00
		Unit Sub Total	**M2**		**4**	**58,360.00**	**$1.94**	**$113,243.00**
203001	EROSION CONTROL (BLANKET)		SQFT	9	1	42,900.00	$0.80	$34,320.00
		Unit Sub Total	**SQFT**		**1**	**42,900.00**	**$0.80**	**$34,320.00**
203001	EROSION CONTROL (BLANKET)		SQYD	1	1	450.00	$11.00	$4,950.00
			SQYD	2	2	620.00	$3.23	$2,005.00
			SQYD	3	2	1,580.00	$6.01	$9,490.00
			SQYD	5	1	84.00	$17.00	$1,428.00
			SQYD	8	1	150.00	$1.60	$240.00
		Unit Sub Total	**SQYD**		**7**	**2,884.00**	**$6.28**	**$18,113.00**
	Item Code 203001	**Total No. of Proj.**			**12**		**Total Amount**	**$165,676.00**
203002	EROSION CONTROL (COMPOST BLANKET)		CY	1	9	1,125.00	$101.82	$114,552.00
			CY	3	1	130.00	$52.50	$6,825.00
			CY	4	3	421.00	$44.89	$18,899.99
			CY	5	9	1,924.00	$59.59	$114,657.40
			CY	6	5	1,416.00	$76.81	$108,768.00
			CY	7	1	2,930.00	$40.00	$117,200.00
			CY	10	3	113.00	$86.58	$9,784.09
			CY	12	1	80.00	$70.00	$5,600.00
		Unit Sub Total	**CY**		**32**	**8,139.00**	**$60.98**	**$496,286.48**
203002	EROSION CONTROL (COMPOST BLANKET)		M3	1	2	80.00	$191.13	$15,290.00
			M3	4	1	220.00	$130.00	$28,600.00
			M3	5	1	4,200.00	$25.00	$105,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
203002	EROSION CONTROL (COMPOST BLANKET)	M3	6	4	3,135.00	$62.49	$195,920.00
	Unit Sub Total	**M3**		**8**	**7,635.00**	**$45.16**	**$344,810.00**
	Item Code 203002 Total No. of Proj.			**40**		**Total Amount**	**$841,096.48**
203011	EROSION CONTROL (TYPE C)	ACRE	6	2	38.70	$2,783.72	$107,730.00
		ACRE	9	1	1.70	$9,000.00	$15,300.00
	Unit Sub Total	**ACRE**		**3**	**40.40**	**$3,045.30**	**$123,030.00**
203011	EROSION CONTROL (TYPE C)	HA	9	2	10.00	$4,085.00	$40,850.00
	Unit Sub Total	**HA**		**2**	**10.00**	**$4,085.00**	**$40,850.00**
203011	EROSION CONTROL (TYPE C)	M2	9	1	5,000.00	$1.40	$7,000.00
		M2	10	4	84,840.00	$1.26	$106,985.00
	Unit Sub Total	**M2**		**5**	**89,840.00**	**$1.27**	**$113,985.00**
	Item Code 203011 Total No. of Proj.			**10**		**Total Amount**	**$277,865.00**
203012	EROSION CONTROL (DRILL SEED)	ACRE	5	1	6.00	$3,200.00	$19,200.00
		ACRE	6	2	240.00	$3,022.42	$725,380.00
	Unit Sub Total	**ACRE**		**3**	**246.00**	**$3,026.75**	**$744,580.00**
203012	EROSION CONTROL (DRILL SEED)	HA	6	2	45.00	$6,180.00	$278,100.00
	Unit Sub Total	**HA**		**2**	**45.00**	**$6,180.00**	**$278,100.00**
203012	EROSION CONTROL (DRILL SEED)	M2	3	1	87,700.00	$0.40	$35,080.00
		M2	10	1	1,000.00	$1.50	$1,500.00
	Unit Sub Total	**M2**		**2**	**88,700.00**	**$0.41**	**$36,580.00**
203012	EROSION CONTROL (DRILL SEED)	SQYD	6	1	1,170.00	$4.00	$4,680.00
		SQYD	7	1	58,900.00	$2.50	$147,250.00
	Unit Sub Total	**SQYD**		**2**	**60,070.00**	**$2.53**	**$151,930.00**
	Item Code 203012 Total No. of Proj.			**9**		**Total Amount**	**$1,211,190.00**
203016	EROSION CONTROL (TYPE D)	ACRE	2	9	80.20	$3,553.74	$285,010.00
		ACRE	3	2	20.00	$1,975.00	$39,500.00
		ACRE	4	2	7.60	$8,947.37	$68,000.00
		ACRE	5	1	2.40	$2,700.00	$6,480.00
		ACRE	6	2	2.70	$8,017.78	$21,648.00
		ACRE	8	4	9.30	$3,483.87	$32,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
203016	EROSION CONTROL (TYPE D)		ACRE	10	1	0.10	$1,000.00	$100.00
		Unit Sub Total	**ACRE**		**21**	**122.30**	**$3,705.13**	**$453,138.00**
203016	EROSION CONTROL (TYPE D)		HA	2	2	0.80	$20,873.24	$16,698.59
			HA	3	3	25.60	$8,126.17	$208,030.00
			HA	4	7	39.10	$9,703.07	$379,390.00
			HA	6	2	66.00	$5,393.94	$356,000.00
			HA	8	3	36.20	$10,826.52	$391,920.00
			HA	10	2	2.40	$6,812.50	$16,350.00
			HA	11	1	47.00	$8,600.00	$404,200.00
		Unit Sub Total	**HA**		**20**	**217.10**	**$8,164.85**	**$1,772,588.59**
203016	EROSION CONTROL (TYPE D)		M2	1	4	15,450.00	$1.46	$22,520.00
			M2	2	1	5,000.00	$1.00	$5,000.00
			M2	3	3	86,200.00	$0.29	$24,700.00
			M2	4	5	74,992.70	$0.96	$72,072.00
			M2	5	2	48,400.00	$0.52	$25,400.00
			M2	6	1	7,870.00	$2.70	$21,249.00
			M2	7	2	23,410.00	$1.30	$30,515.00
			M2	10	4	126,410.00	$1.36	$171,315.00
			M2	11	3	308,100.00	$1.59	$490,880.00
		Unit Sub Total	**M2**		**25**	**695,832.70**	**$1.24**	**$863,651.00**
203016	EROSION CONTROL (TYPE D)		SQFT	3	1	2,100.00	$3.66	$7,686.00
		Unit Sub Total	**SQFT**		**1**	**2,100.00**	**$3.66**	**$7,686.00**
203016	EROSION CONTROL (TYPE D)		SQYD	1	12	48,520.00	$1.77	$85,894.00
			SQYD	2	8	70,310.00	$0.82	$57,375.80
			SQYD	3	7	219,020.00	$1.69	$369,306.60
			SQYD	4	8	34,630.00	$1.78	$61,517.70
			SQYD	5	4	9,210.00	$1.77	$16,322.00
			SQYD	6	1	13,400.00	$1.00	$13,400.00
			SQYD	7	7	181,130.00	$1.67	$303,114.00
			SQYD	8	4	16,590.00	$0.71	$11,860.60
			SQYD	10	4	10,560.00	$2.05	$21,690.00
			SQYD	11	1	1,140.00	$1.60	$1,824.00
			SQYD	12	1	79,600.00	$1.45	$115,420.00
		Unit Sub Total	**SQYD**		**57**	**684,110.00**	**$1.55**	**$1,057,724.70**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 203016 Total No. of Proj.			**124**		**Total Amount**	**$4,154,788.29**
203017	EROSION CONTROL (HYDRAULIC MATRIX)	M2	11	1	9,200.00	$1.16	$10,672.00
	Unit Sub Total	**M2**		**1**	**9,200.00**	**$1.16**	**$10,672.00**
203017	EROSION CONTROL (HYDRAULIC MATRIX)	SQYD	10	1	2,510.00	$1.00	$2,510.00
		SQYD	11	2	23,870.00	$1.48	$35,370.00
	Unit Sub Total	**SQYD**		**3**	**26,380.00**	**$1.44**	**$37,880.00**
	Item Code 203017 Total No. of Proj.			**4**		**Total Amount**	**$48,552.00**
203018	EROSION CONTROL (NETTING)	M2	1	1	5.00	$35.00	$175.00
		M2	3	1	1,980.00	$6.00	$11,880.00
		M2	4	11	71,530.00	$5.72	$409,116.00
		M2	5	1	170.00	$10.00	$1,700.00
		M2	7	1	1,030.00	$4.40	$4,532.00
		M2	11	1	27,500.00	$2.90	$79,750.00
	Unit Sub Total	**M2**		**16**	**102,215.00**	**$4.96**	**$507,153.00**
203018	EROSION CONTROL (NETTING)	SQYD	2	1	10,600.00	$7.00	$74,200.00
		SQYD	3	3	27,890.00	$3.94	$109,834.80
		SQYD	4	7	19,827.00	$5.46	$108,213.94
		SQYD	5	1	470.00	$6.00	$2,820.00
		SQYD	12	2	2,430.00	$2.81	$6,820.00
	Unit Sub Total	**SQYD**		**14**	**61,217.00**	**$4.93**	**$301,888.74**
	Item Code 203018 Total No. of Proj.			**30**		**Total Amount**	**$809,041.74**
203019	EROSION CONTROL (BFM)	SQYD	1	2	1,060.00	$3.59	$3,809.60
	Unit Sub Total	**SQYD**		**2**	**1,060.00**	**$3.59**	**$3,809.60**
	Item Code 203019 Total No. of Proj.			**2**		**Total Amount**	**$3,809.60**
203020	EROSION CONTROL HYDRAULIC MULCH (BONDED FIBER MATRIX)	SQFT	1	1	11,200.00	$1.00	$11,200.00
	Unit Sub Total	**SQFT**		**1**	**11,200.00**	**$1.00**	**$11,200.00**
	Item Code 203020 Total No. of Proj.			**1**		**Total Amount**	**$11,200.00**
203021	FIBER ROLLS	LF	1	1	60.00	$35.00	$2,100.00
		LF	4	14	30,984.00	$3.58	$111,048.34

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
203021	FIBER ROLLS	LF	5	3	2,030.00	$11.36	$23,060.00
		LF	6	2	27,100.00	$2.09	$56,615.00
		LF	7	1	28,400.00	$2.50	$71,000.00
		LF	11	4	33,400.00	$1.94	$64,828.00
	Unit Sub Total	**LF**		**25**	**121,974.00**	**$2.69**	**$328,651.34**
203021	FIBER ROLLS	M	1	1	92.00	$28.75	$2,645.00
		M	2	1	6,170.00	$10.00	$61,700.00
		M	4	13	51,487.00	$6.76	$347,998.50
		M	5	2	8,160.00	$10.34	$84,360.00
		M	8	1	15,400.00	$6.25	$96,250.00
		M	11	4	138,910.00	$7.06	$980,110.00
	Unit Sub Total	**M**		**22**	**220,219.00**	**$7.14**	**$1,573,063.50**
	Item Code 203021 Total No. of Proj.			**47**		**Total Amount**	**$1,901,714.84**
203022	EROSION CONTROL HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	M2	11	1	500,000.00	$0.60	$300,000.00
	Unit Sub Total	**M2**		**1**	**500,000.00**	**$0.60**	**$300,000.00**
203022	EROSION CONTROL HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	SQFT	1	1	5,630.00	$0.45	$2,533.50
	Unit Sub Total	**SQFT**		**1**	**5,630.00**	**$0.45**	**$2,533.50**
	Item Code 203022 Total No. of Proj.			**2**		**Total Amount**	**$302,533.50**
203025	COMPOST, INCORPORATE	M2	2	1	107,000.00	$6.70	$716,900.00
		M2	4	7	13,108.00	$6.47	$84,744.50
	Unit Sub Total	**M2**		**8**	**120,108.00**	**$6.67**	**$801,644.50**
203025	COMPOST, INCORPORATE	SQYD	3	3	50,830.00	$7.90	$401,654.00
		SQYD	7	1	58,900.00	$5.00	$294,500.00
	Unit Sub Total	**SQYD**		**4**	**109,730.00**	**$6.34**	**$696,154.00**
	Item Code 203025 Total No. of Proj.			**12**		**Total Amount**	**$1,497,798.50**
203026	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	1	5	20.00	$818.75	$16,375.00
		EA	2	1	6.00	$1,000.00	$6,000.00
		EA	3	9	67.00	$386.27	$25,880.00
		EA	4	14	79.00	$760.00	$60,040.00
		EA	5	4	23.00	$587.05	$13,502.12

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
203026	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	6	5	34.00	$749.71	$25,490.00
		EA	7	1	5.00	$500.00	$2,500.00
		EA	8	6	18.00	$638.22	$11,488.00
		EA	9	2	3.00	$1,000.00	$3,000.00
		EA	10	8	25.00	$1,025.52	$25,637.90
		EA	11	4	26.00	$442.31	$11,500.00
		EA	12	1	6.00	$525.00	$3,150.00
	Unit Sub Total	**EA**		**60**	**312.00**	**$655.65**	**$204,563.02**
	Item Code 203026 Total No. of Proj.			**60**		**Total Amount**	**$204,563.02**
203027	EROSION CONTROL (BONDED FIBER MATRIX) (SQFT)	SQFT	3	1	12,200.00	$0.50	$6,100.00
		SQFT	7	2	11,390.00	$0.50	$5,690.00
	Unit Sub Total	**SQFT**		**3**	**23,590.00**	**$0.50**	**$11,790.00**
	Item Code 203027 Total No. of Proj.			**3**		**Total Amount**	**$11,790.00**
203031	EROSION CONTROL (HYDROSEED) (SQFT)	SQFT	4	1	9,170.00	$0.30	$2,751.00
		SQFT	10	1	750.00	$4.00	$3,000.00
	Unit Sub Total	**SQFT**		**2**	**9,920.00**	**$0.58**	**$5,751.00**
	Item Code 203031 Total No. of Proj.			**2**		**Total Amount**	**$5,751.00**
203032	EROSION CONTROL (HYDROSEED) (ACRE)	ACRE	2	1	4.90	$4,400.00	$21,560.00
	Unit Sub Total	**ACRE**		**1**	**4.90**	**$4,400.00**	**$21,560.00**
	Item Code 203032 Total No. of Proj.			**1**		**Total Amount**	**$21,560.00**
203034	ROLLED EROSION CONTROL PRODUCT (NETTING)	SQFT	4	1	7,210.00	$0.60	$4,326.00
	Unit Sub Total	**SQFT**		**1**	**7,210.00**	**$0.60**	**$4,326.00**
	Item Code 203034 Total No. of Proj.			**1**		**Total Amount**	**$4,326.00**
203561	JUTE MESH	SQYD	6	1	13,200.00	$4.00	$52,800.00
	Unit Sub Total	**SQYD**		**1**	**13,200.00**	**$4.00**	**$52,800.00**
	Item Code 203561 Total No. of Proj.			**1**		**Total Amount**	**$52,800.00**
204001	PLANT (GROUP A)	EA	10	1	600.00	$5.00	$3,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**600.00**	**$5.00**	**$3,000.00**
	Item Code 204001	**Total No. of Proj.**			**1**		**Total Amount**	**$3,000.00**
204002	PLANT (GROUP B)		EA	10	1	13.00	$25.00	$325.00
		Unit Sub Total	**EA**		**1**	**13.00**	**$25.00**	**$325.00**
	Item Code 204002	**Total No. of Proj.**			**1**		**Total Amount**	**$325.00**
204005	PLANT (GROUP E)		EA	8	1	3,770.00	$3.00	$11,310.00
		Unit Sub Total	**EA**		**1**	**3,770.00**	**$3.00**	**$11,310.00**
	Item Code 204005	**Total No. of Proj.**			**1**		**Total Amount**	**$11,310.00**
204006	PLANT (GROUP F)		EA	3	1	76,800.00	$0.30	$23,040.00
			EA	5	1	540.00	$0.50	$270.00
			EA	7	1	65,400.00	$0.25	$16,350.00
			EA	11	3	167,300.00	$0.34	$56,140.00
		Unit Sub Total	**EA**		**6**	**310,040.00**	**$0.31**	**$95,800.00**
	Item Code 204006	**Total No. of Proj.**			**6**		**Total Amount**	**$95,800.00**
204007	PLANT (GROUP G)		EA	11	1	12,100.00	$0.35	$4,235.00
		Unit Sub Total	**EA**		**1**	**12,100.00**	**$0.35**	**$4,235.00**
	Item Code 204007	**Total No. of Proj.**			**1**		**Total Amount**	**$4,235.00**
204008	PLANT (GROUP H)		EA	5	2	14,380.00	$0.36	$5,216.00
			EA	7	1	72,400.00	$0.25	$18,100.00
			EA	11	3	1,075,275.00	$0.21	$221,956.35
			EA	12	1	11,400.00	$0.50	$5,700.00
		Unit Sub Total	**EA**		**7**	**1,173,455.00**	**$0.21**	**$250,972.35**
	Item Code 204008	**Total No. of Proj.**			**7**		**Total Amount**	**$250,972.35**
204009	PLANT (GROUP I)		EA	5	1	430.00	$1.00	$430.00
		Unit Sub Total	**EA**		**1**	**430.00**	**$1.00**	**$430.00**
	Item Code 204009	**Total No. of Proj.**			**1**		**Total Amount**	**$430.00**
204010	PLANT (GROUP O)		EA	5	2	350.00	$6.57	$2,300.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
204010	PLANT (GROUP O)		EA	8	1	45.00	$33.00	$1,485.00
		Unit Sub Total	**EA**		**3**	**395.00**	**$9.58**	**$3,785.00**
	Item Code 204010	**Total No. of Proj.**			**3**		**Total Amount**	**$3,785.00**
204011	PLANT (GROUP K)		EA	4	1	1.00	$230.00	$230.00
			EA	11	2	59.00	$178.37	$10,523.72
		Unit Sub Total	**EA**		**3**	**60.00**	**$179.23**	**$10,753.72**
	Item Code 204011	**Total No. of Proj.**			**3**		**Total Amount**	**$10,753.72**
204013	PLANT (GROUP M)		EA	4	5	3,075.00	$6.48	$19,915.00
			EA	5	1	150.00	$10.00	$1,500.00
			EA	6	1	42.00	$64.00	$2,688.00
			EA	11	1	5,200.00	$1.25	$6,500.00
		Unit Sub Total	**EA**		**8**	**8,467.00**	**$3.61**	**$30,603.00**
	Item Code 204013	**Total No. of Proj.**			**8**		**Total Amount**	**$30,603.00**
204015	PLANT (GROUP S)		EA	5	1	19.00	$40.00	$760.00
			EA	8	1	660.00	$2.50	$1,650.00
		Unit Sub Total	**EA**		**2**	**679.00**	**$3.55**	**$2,410.00**
	Item Code 204015	**Total No. of Proj.**			**2**		**Total Amount**	**$2,410.00**
204017	PLANT (GROUP W)		EA	4	2	105.00	$37.57	$3,945.00
			EA	7	2	3,560.00	$4.98	$17,737.50
			EA	11	1	640.00	$6.00	$3,840.00
		Unit Sub Total	**EA**		**5**	**4,305.00**	**$5.93**	**$25,522.50**
204017	PLANT (GROUP W)		LS	4	1	1.00	$7,500.00	$7,500.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$7,500.00**	**$7,500.00**
	Item Code 204017	**Total No. of Proj.**			**6**		**Total Amount**	**$33,022.50**
204021	PLANT (GROUP U)		EA	4	1	130.00	$87.00	$11,310.00
		Unit Sub Total	**EA**		**1**	**130.00**	**$87.00**	**$11,310.00**
	Item Code 204021	**Total No. of Proj.**			**1**		**Total Amount**	**$11,310.00**
204022	PLANT (GROUP Z)		EA	11	1	22.00	$700.00	$15,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**22.00**	**$700.00**	**$15,400.00**
	Item Code 204022	**Total No. of Proj.**			**1**		**Total Amount**	**$15,400.00**
204031	TRANSPLANT PALM TREE		EA	6	1	19.00	$6,500.00	$123,500.00
			EA	7	2	34.00	$2,431.62	$82,675.00
		Unit Sub Total	**EA**		**3**	**53.00**	**$3,890.09**	**$206,175.00**
	Item Code 204031	**Total No. of Proj.**			**3**		**Total Amount**	**$206,175.00**
204035	PLANT (GROUP A)		EA	3	1	1,030.00	$12.00	$12,360.00
			EA	4	4	9,590.00	$6.11	$58,585.00
			EA	5	2	3,010.00	$9.64	$29,003.50
			EA	8	1	206.00	$10.00	$2,060.00
			EA	11	2	2,920.00	$6.37	$18,604.80
			EA	12	1	2,580.00	$9.00	$23,220.00
		Unit Sub Total	**EA**		**11**	**19,336.00**	**$7.44**	**$143,833.30**
	Item Code 204035	**Total No. of Proj.**			**11**		**Total Amount**	**$143,833.30**
204036	PLANT (GROUP B)		EA	3	1	89.00	$25.00	$2,225.00
			EA	4	4	1,654.00	$17.66	$29,204.00
			EA	5	2	1,225.00	$18.90	$23,155.70
			EA	8	1	35.00	$130.00	$4,550.00
			EA	11	2	2,030.00	$13.30	$26,996.00
			EA	12	1	80.00	$18.00	$1,440.00
		Unit Sub Total	**EA**		**11**	**5,113.00**	**$17.13**	**$87,570.70**
	Item Code 204036	**Total No. of Proj.**			**11**		**Total Amount**	**$87,570.70**
204038	PLANT (GROUP U)		EA	4	2	264.00	$50.76	$13,400.00
			EA	5	3	1,110.00	$85.42	$94,815.00
			EA	8	1	46.00	$115.00	$5,290.00
			EA	11	2	670.00	$58.44	$39,153.80
			EA	12	1	25.00	$160.00	$4,000.00
		Unit Sub Total	**EA**		**9**	**2,115.00**	**$74.07**	**$156,658.80**
	Item Code 204038	**Total No. of Proj.**			**9**		**Total Amount**	**$156,658.80**
204051	SEEDING		HA	11	1	7.00	$4,000.00	$28,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**HA**		**1**	**7.00**	**$4,000.00**	**$28,000.00**
204051	SEEDING		M2	4	1	610.00	$8.00	$4,880.00
		Unit Sub Total	**M2**		**1**	**610.00**	**$8.00**	**$4,880.00**
	Item Code 204051	**Total No. of Proj.**			**2**		**Total Amount**	**$32,880.00**
204053	WILD FLOWER SEEDING		SQYD	4	1	660.00	$3.00	$1,980.00
			SQYD	5	1	200.00	$1.50	$300.00
			SQYD	10	1	5,660.00	$1.00	$5,660.00
		Unit Sub Total	**SQYD**		**3**	**6,520.00**	**$1.22**	**$7,940.00**
	Item Code 204053	**Total No. of Proj.**			**3**		**Total Amount**	**$7,940.00**
204055	WILD FLOWER SEEDING (SQYD)		SQYD	4	1	4,190.00	$3.00	$12,570.00
		Unit Sub Total	**SQYD**		**1**	**4,190.00**	**$3.00**	**$12,570.00**
	Item Code 204055	**Total No. of Proj.**			**1**		**Total Amount**	**$12,570.00**
204096	MAINTAIN EXISTING PLANTED AREAS		LS	2	1	1.00	$9,000.00	$9,000.00
			LS	3	2	2.00	$10,000.00	$20,000.00
			LS	4	2	2.00	$5,250.00	$10,500.00
			LS	5	2	2.00	$3,160.00	$6,320.00
			LS	6	5	5.00	$3,183.00	$15,915.00
			LS	7	3	3.00	$16,833.33	$50,500.00
			LS	8	1	1.00	$2,000.00	$2,000.00
			LS	10	1	1.00	$3,500.00	$3,500.00
			LS	11	2	2.00	$46,000.00	$92,000.00
			LS	12	1	1.00	$5,000.00	$5,000.00
		Unit Sub Total	**LS**		**20**	**20.00**	**$10,736.75**	**$214,735.00**
	Item Code 204096	**Total No. of Proj.**			**20**		**Total Amount**	**$214,735.00**
204098	MAINTAIN EXISTING PLANTS		LS	2	1	1.00	$4,500.00	$4,500.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$4,500.00**	**$4,500.00**
	Item Code 204098	**Total No. of Proj.**			**1**		**Total Amount**	**$4,500.00**
204099	PLANT ESTABLISHMENT WORK		LS	1	1	1.00	$4,000.00	$4,000.00
			LS	2	1	1.00	$6,000.00	$6,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
204099	PLANT ESTABLISHMENT WORK	LS	3	5	5.00	$47,900.00	$239,500.00
		LS	4	15	15.00	$56,653.33	$849,800.00
		LS	5	7	7.00	$38,935.73	$272,550.12
		LS	6	7	7.00	$4,480.00	$31,360.00
		LS	7	12	12.00	$31,008.33	$372,100.00
		LS	8	4	4.00	$20,414.75	$81,659.00
		LS	9	1	1.00	$5,200.00	$5,200.00
		LS	10	3	3.00	$14,583.33	$43,750.00
		LS	11	7	7.00	$43,376.99	$303,638.90
		LS	12	2	2.00	$8,250.00	$16,500.00
	Unit Sub Total	**LS**		**65**	**65.00**	**$34,247.05**	**$2,226,058.02**
	Item Code 204099 Total No. of Proj.			**65**		**Total Amount**	**$2,226,058.02**
204100	ESTABLISH EXISTING PLANTING	LS	7	1	1.00	$45,664.00	$45,664.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$45,664.00**	**$45,664.00**
	Item Code 204100 Total No. of Proj.			**1**		**Total Amount**	**$45,664.00**
205051	FOLIAGE PROTECTOR	EA	4	3	1,788.00	$28.60	$51,140.00
	Unit Sub Total	**EA**		**3**	**1,788.00**	**$28.60**	**$51,140.00**
	Item Code 205051 Total No. of Proj.			**3**		**Total Amount**	**$51,140.00**
205061	ROOT PROTECTOR	EA	5	3	4,380.00	$5.03	$22,039.80
	Unit Sub Total	**EA**		**3**	**4,380.00**	**$5.03**	**$22,039.80**
	Item Code 205061 Total No. of Proj.			**3**		**Total Amount**	**$22,039.80**
206401	MAINTAIN EXISTING IRRIGATION FACILITIES	LS	2	1	1.00	$2,850.00	$2,850.00
		LS	3	3	3.00	$7,333.33	$22,000.00
		LS	4	3	3.00	$3,033.33	$9,100.00
		LS	6	2	2.00	$2,250.00	$4,500.00
		LS	7	3	3.00	$3,966.67	$11,900.00
		LS	10	2	2.00	$3,050.00	$6,100.00
		LS	11	1	1.00	$44,000.00	$44,000.00
		LS	12	2	2.00	$6,500.00	$13,000.00
	Unit Sub Total	**LS**		**17**	**17.00**	**$6,673.53**	**$113,450.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 206401 Total No. of Proj.			**17**		**Total Amount**	**$113,450.00**
206560	CONTROL AND NEUTRAL CONDUCTORS	LS	3	1	1.00	$30,265.00	$30,265.00
		LS	4	3	3.00	$20,266.67	$60,800.00
		LS	5	2	2.00	$89,276.15	$178,552.30
		LS	7	1	1.00	$10,000.00	$10,000.00
		LS	8	1	1.00	$1,900.00	$1,900.00
		LS	10	1	1.00	$3,500.00	$3,500.00
		LS	11	3	3.00	$27,994.70	$83,984.11
		LS	12	1	1.00	$3,000.00	$3,000.00
	Unit Sub Total	**LS**		**13**	**13.00**	**$28,615.49**	**$372,001.41**
	Item Code 206560 Total No. of Proj.			**13**		**Total Amount**	**$372,001.41**
206602	1" ELECTRIC REMOTE CONTROL VALVE	EA	5	3	54.00	$294.23	$15,888.22
		EA	7	1	49.00	$250.00	$12,250.00
		EA	8	1	3.00	$200.00	$600.00
		EA	11	2	84.00	$177.32	$14,895.10
	Unit Sub Total	**EA**		**7**	**190.00**	**$229.65**	**$43,633.32**
	Item Code 206602 Total No. of Proj.			**7**		**Total Amount**	**$43,633.32**
206603	1 1/4" ELECTRIC REMOTE CONTROL VALVE	EA	7	1	8.00	$275.00	$2,200.00
		EA	8	1	1.00	$300.00	$300.00
		EA	12	1	2.00	$280.00	$560.00
	Unit Sub Total	**EA**		**3**	**11.00**	**$278.18**	**$3,060.00**
	Item Code 206603 Total No. of Proj.			**3**		**Total Amount**	**$3,060.00**
206604	1 1/2" ELECTRIC REMOTE CONTROL VALVE	EA	5	2	128.00	$289.75	$37,088.28
		EA	11	1	43.00	$195.00	$8,385.00
		EA	12	1	9.00	$300.00	$2,700.00
	Unit Sub Total	**EA**		**4**	**180.00**	**$267.63**	**$48,173.28**
	Item Code 206604 Total No. of Proj.			**4**		**Total Amount**	**$48,173.28**
206605	2" ELECTRIC REMOTE CONTROL VALVE	EA	4	1	8.00	$310.00	$2,480.00
		EA	5	1	4.00	$396.13	$1,584.52
		EA	10	1	6.00	$250.00	$1,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
206605	2" ELECTRIC REMOTE CONTROL VALVE	EA	11	1	2.00	$230.00	$460.00
		EA	12	1	3.00	$320.00	$960.00
	Unit Sub Total	**EA**		**5**	**23.00**	**$303.67**	**$6,984.52**
	Item Code 206605 Total No. of Proj.			**5**		**Total Amount**	**$6,984.52**
206607	3" ELECTRIC REMOTE CONTROL VALVE	EA	7	1	2.00	$650.00	$1,300.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$650.00**	**$1,300.00**
	Item Code 206607 Total No. of Proj.			**1**		**Total Amount**	**$1,300.00**
206611	25 MM ELECTRIC REMOTE CONTROL VALVE	EA	3	1	31.00	$150.00	$4,650.00
		EA	4	1	5.00	$175.00	$875.00
		EA	11	1	61.00	$215.25	$13,130.25
	Unit Sub Total	**EA**		**3**	**97.00**	**$192.32**	**$18,655.25**
	Item Code 206611 Total No. of Proj.			**3**		**Total Amount**	**$18,655.25**
206612	32 MM ELECTRIC REMOTE CONTROL VALVE	EA	4	1	12.00	$185.00	$2,220.00
	Unit Sub Total	**EA**		**1**	**12.00**	**$185.00**	**$2,220.00**
	Item Code 206612 Total No. of Proj.			**1**		**Total Amount**	**$2,220.00**
206613	40 MM ELECTRIC REMOTE CONTROL VALVE	EA	3	1	19.00	$160.00	$3,040.00
		EA	4	1	9.00	$240.00	$2,160.00
		EA	11	1	130.00	$245.25	$31,882.50
	Unit Sub Total	**EA**		**3**	**158.00**	**$234.70**	**$37,082.50**
	Item Code 206613 Total No. of Proj.			**3**		**Total Amount**	**$37,082.50**
206614	50 MM ELECTRIC REMOTE CONTROL VALVE	EA	3	1	6.00	$185.00	$1,110.00
		EA	4	1	10.00	$250.00	$2,500.00
	Unit Sub Total	**EA**		**2**	**16.00**	**$225.63**	**$3,610.00**
	Item Code 206614 Total No. of Proj.			**2**		**Total Amount**	**$3,610.00**
206615	65 MM ELECTRIC REMOTE CONTROL VALVE	EA	3	1	1.00	$220.00	$220.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$220.00**	**$220.00**
	Item Code 206615 Total No. of Proj.			**1**		**Total Amount**	**$220.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
206751	12 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	4	1	2.00	$800.00	$1,600.00
		EA	10	1	1.00	$250.00	$250.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$616.67**	**$1,850.00**
	Item Code 206751 Total No. of Proj.			**2**		**Total Amount**	**$1,850.00**
206753	24 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	4	1	1.00	$1,000.00	$1,000.00
		EA	12	1	2.00	$1,500.00	$3,000.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$1,333.33**	**$4,000.00**
	Item Code 206753 Total No. of Proj.			**2**		**Total Amount**	**$4,000.00**
206929	IRRIGATION CONTROLLER (BATTERY)	EA	5	1	4.00	$600.00	$2,400.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$600.00**	**$2,400.00**
	Item Code 206929 Total No. of Proj.			**1**		**Total Amount**	**$2,400.00**
208000	IRRIGATION SYSTEM	EA	10	1	2.00	$10,000.00	$20,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$10,000.00**	**$20,000.00**
208000	IRRIGATION SYSTEM	LS	2	3	3.00	$27,461.67	$82,385.00
		LS	3	4	4.00	$132,562.50	$530,250.00
		LS	4	7	7.00	$35,742.86	$250,200.00
		LS	5	4	4.00	$37,785.59	$151,142.35
		LS	6	5	5.00	$43,263.02	$216,315.10
		LS	7	12	12.00	$131,010.42	$1,572,125.00
		LS	9	1	1.00	$19,400.00	$19,400.00
		LS	10	2	2.00	$18,825.00	$37,650.00
		LS	11	6	6.00	$254,471.67	$1,526,830.00
		LS	12	2	2.00	$14,300.00	$28,600.00
	Unit Sub Total	**LS**		**46**	**46.00**	**$95,976.03**	**$4,414,897.45**
	Item Code 208000 Total No. of Proj.			**47**		**Total Amount**	**$4,434,897.45**
208002	3/4" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	4	1	2,040.00	$2.25	$4,590.00
	Unit Sub Total	**LF**		**1**	**2,040.00**	**$2.25**	**$4,590.00**
	Item Code 208002 Total No. of Proj.			**1**		**Total Amount**	**$4,590.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208004	1 1/4" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	5	1	280.00	$40.00	$11,200.00
		LF	8	1	20.00	$20.00	$400.00
	Unit Sub Total	**LF**		**2**	**300.00**	**$38.67**	**$11,600.00**
	Item Code 208004 Total No. of Proj.			**2**		**Total Amount**	**$11,600.00**
208006	2" GALVANIZED STEEL PIPE (SUPPLY LINE)	LB	7	1	9,570.00	$6.00	$57,420.00
	Unit Sub Total	**LB**		**1**	**9,570.00**	**$6.00**	**$57,420.00**
208006	2" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	5	1	825.00	$28.84	$23,793.00
	Unit Sub Total	**LF**		**1**	**825.00**	**$28.84**	**$23,793.00**
	Item Code 208006 Total No. of Proj.			**2**		**Total Amount**	**$81,213.00**
208008	3" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	5	2	360.00	$33.58	$12,088.65
	Unit Sub Total	**LF**		**2**	**360.00**	**$33.58**	**$12,088.65**
	Item Code 208008 Total No. of Proj.			**2**		**Total Amount**	**$12,088.65**
208009	4" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	5	1	65.00	$30.00	$1,950.00
	Unit Sub Total	**LF**		**1**	**65.00**	**$30.00**	**$1,950.00**
	Item Code 208009 Total No. of Proj.			**1**		**Total Amount**	**$1,950.00**
208021	50 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	4	1	20.00	$15.00	$300.00
	Unit Sub Total	**M**		**1**	**20.00**	**$15.00**	**$300.00**
	Item Code 208021 Total No. of Proj.			**1**		**Total Amount**	**$300.00**
208036	NPS 2 SUPPLY LINE (BRIDGE)	M	6	1	86.00	$90.00	$7,740.00
		M	7	1	117.00	$330.00	$38,610.00
		M	10	1	285.00	$88.00	$25,080.00
	Unit Sub Total	**M**		**3**	**488.00**	**$146.37**	**$71,430.00**
	Item Code 208036 Total No. of Proj.			**3**		**Total Amount**	**$71,430.00**
208038	NPS 3 SUPPLY LINE (BRIDGE)	M	4	2	865.00	$171.57	$148,405.00
		M	5	2	203.00	$265.52	$53,900.00
		M	7	2	130.00	$355.15	$46,170.00
		M	8	2	401.00	$195.44	$78,370.00
		M	11	2	535.00	$223.36	$119,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**10**	**2,134.00**	**$209.16**	**$446,345.00**
	Item Code 208038 Total No. of Proj.			**10**		**Total Amount**	**$446,345.00**
208211	1/2" PLASTIC PIPE (IRRIGATION LINE)	LF	4	1	45,395.00	$0.38	$17,250.10
	Unit Sub Total	**LF**		**1**	**45,395.00**	**$0.38**	**$17,250.10**
	Item Code 208211 Total No. of Proj.			**1**		**Total Amount**	**$17,250.10**
208213	3/4" PLASTIC PIPE (IRRIGATION LINE)	LF	5	1	1,380.00	$1.84	$2,539.20
	Unit Sub Total	**LF**		**1**	**1,380.00**	**$1.84**	**$2,539.20**
	Item Code 208213 Total No. of Proj.			**1**		**Total Amount**	**$2,539.20**
208249	20 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	4	1	3,423.00	$3.00	$10,269.00
	Unit Sub Total	**M**		**1**	**3,423.00**	**$3.00**	**$10,269.00**
	Item Code 208249 Total No. of Proj.			**1**		**Total Amount**	**$10,269.00**
208250	25 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	6,205.00	$8.00	$49,640.00
		M	4	1	1,164.00	$3.50	$4,074.00
		M	11	1	16,031.00	$0.84	$13,466.04
	Unit Sub Total	**M**		**3**	**23,400.00**	**$2.87**	**$67,180.04**
	Item Code 208250 Total No. of Proj.			**3**		**Total Amount**	**$67,180.04**
208251	32 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	1,200.00	$7.00	$8,400.00
		M	4	1	902.00	$4.00	$3,608.00
		M	11	1	3,970.00	$1.30	$5,161.00
	Unit Sub Total	**M**		**3**	**6,072.00**	**$2.83**	**$17,169.00**
	Item Code 208251 Total No. of Proj.			**3**		**Total Amount**	**$17,169.00**
208252	40 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	715.00	$8.00	$5,720.00
		M	4	1	281.00	$4.00	$1,124.00
		M	11	1	3,816.00	$1.68	$6,410.88
	Unit Sub Total	**M**		**3**	**4,812.00**	**$2.75**	**$13,254.88**
	Item Code 208252 Total No. of Proj.			**3**		**Total Amount**	**$13,254.88**
208253	50 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	955.00	$9.00	$8,595.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208253	50 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	4	1	1,265.00	$4.00	$5,060.00
		M	6	1	60.00	$77.00	$4,620.00
		M	11	1	3,621.00	$2.63	$9,523.23
	Unit Sub Total	**M**		**4**	**5,901.00**	**$4.71**	**$27,798.23**
	Item Code 208253 Total No. of Proj.			**4**		**Total Amount**	**$27,798.23**
208254	65 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	388.00	$10.00	$3,880.00
		M	4	1	1,455.00	$4.00	$5,820.00
		M	11	1	2,831.00	$3.90	$11,040.90
	Unit Sub Total	**M**		**3**	**4,674.00**	**$4.44**	**$20,740.90**
	Item Code 208254 Total No. of Proj.			**3**		**Total Amount**	**$20,740.90**
208255	75 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	2,430.00	$15.00	$36,450.00
		M	11	1	3,363.00	$5.80	$19,505.40
	Unit Sub Total	**M**		**2**	**5,793.00**	**$9.66**	**$55,955.40**
	Item Code 208255 Total No. of Proj.			**2**		**Total Amount**	**$55,955.40**
208256	100 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	11	1	1,652.00	$9.45	$15,611.40
	Unit Sub Total	**M**		**1**	**1,652.00**	**$9.45**	**$15,611.40**
	Item Code 208256 Total No. of Proj.			**1**		**Total Amount**	**$15,611.40**
208262	3/4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	1	53,550.00	$1.20	$64,260.00
		LF	5	1	3,362.00	$2.00	$6,724.00
		LF	7	1	14,170.00	$1.50	$21,255.00
		LF	8	1	850.00	$1.00	$850.00
		LF	10	1	1,175.00	$3.00	$3,525.00
	Unit Sub Total	**LF**		**5**	**73,107.00**	**$1.32**	**$96,614.00**
	Item Code 208262 Total No. of Proj.			**5**		**Total Amount**	**$96,614.00**
208263	1" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	1	16,000.00	$1.50	$24,000.00
		LF	5	2	54,005.00	$1.67	$89,951.90
		LF	7	1	7,290.00	$1.60	$11,664.00
		LF	8	1	225.00	$2.00	$450.00
		LF	10	1	1,340.00	$3.00	$4,020.00
		LF	11	2	38,220.00	$2.00	$76,630.35

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208263	1" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	12	1	4,225.00	$3.90	$16,477.50
	Unit Sub Total	**LF**		**9**	**121,305.00**	**$1.84**	**$223,193.75**
	Item Code 208263 Total No. of Proj.			**9**		**Total Amount**	**$223,193.75**
208264	1 1/4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	1	8,110.00	$1.80	$14,598.00
		LF	5	1	1,015.00	$3.00	$3,045.00
		LF	7	1	5,950.00	$1.70	$10,115.00
		LF	8	1	332.00	$3.00	$996.00
		LF	10	1	2,065.00	$3.00	$6,195.00
		LF	11	2	6,885.00	$2.10	$14,488.25
		LF	12	1	522.00	$4.00	$2,088.00
	Unit Sub Total	**LF**		**8**	**24,879.00**	**$2.07**	**$51,525.25**
	Item Code 208264 Total No. of Proj.			**8**		**Total Amount**	**$51,525.25**
208265	1 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	1	2,650.00	$2.30	$6,095.00
		LF	5	2	26,545.00	$1.98	$52,459.60
		LF	7	1	3,140.00	$1.80	$5,652.00
		LF	10	1	1,905.00	$3.00	$5,715.00
		LF	11	2	5,430.00	$2.16	$11,735.55
		LF	12	1	1,587.00	$4.10	$6,506.70
	Unit Sub Total	**LF**		**8**	**41,257.00**	**$2.14**	**$88,163.85**
	Item Code 208265 Total No. of Proj.			**8**		**Total Amount**	**$88,163.85**
208266	2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	1	4,550.00	$2.80	$12,740.00
		LF	5	2	13,750.00	$2.37	$32,571.30
		LF	7	1	1,560.00	$2.00	$3,120.00
		LF	10	1	2,151.00	$4.00	$8,604.00
		LF	11	2	3,785.00	$2.34	$8,874.90
		LF	12	1	154.00	$4.50	$693.00
	Unit Sub Total	**LF**		**8**	**25,950.00**	**$2.57**	**$66,603.20**
	Item Code 208266 Total No. of Proj.			**8**		**Total Amount**	**$66,603.20**
208267	2 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	1	7,120.00	$3.70	$26,344.00
		LF	5	1	8,025.00	$2.75	$22,068.75
		LF	7	1	10.00	$3.00	$30.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208267	2 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	10	1	398.00	$4.00	$1,592.00
		LF	11	1	1,660.00	$2.50	$4,150.00
	Unit Sub Total	**LF**		**5**	**17,213.00**	**$3.15**	**$54,184.75**
	Item Code 208267 Total No. of Proj.			**5**		**Total Amount**	**$54,184.75**
208268	3" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	10	1	729.00	$4.50	$3,280.50
		LF	11	2	15,985.00	$3.89	$62,110.10
	Unit Sub Total	**LF**		**3**	**16,714.00**	**$3.91**	**$65,390.60**
	Item Code 208268 Total No. of Proj.			**3**		**Total Amount**	**$65,390.60**
208276	2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	5	2	5,220.00	$3.07	$16,023.15
		LF	12	1	489.00	$4.50	$2,200.50
	Unit Sub Total	**LF**		**3**	**5,709.00**	**$3.19**	**$18,223.65**
	Item Code 208276 Total No. of Proj.			**3**		**Total Amount**	**$18,223.65**
208277	2 1/2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	5	2	2,435.00	$3.25	$7,914.60
	Unit Sub Total	**LF**		**2**	**2,435.00**	**$3.25**	**$7,914.60**
	Item Code 208277 Total No. of Proj.			**2**		**Total Amount**	**$7,914.60**
208278	3" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	4	1	10,340.00	$4.00	$41,360.00
		LF	5	2	9,655.00	$4.09	$39,534.50
		LF	7	1	7,180.00	$4.75	$34,105.00
	Unit Sub Total	**LF**		**4**	**27,175.00**	**$4.23**	**$114,999.50**
	Item Code 208278 Total No. of Proj.			**4**		**Total Amount**	**$114,999.50**
208279	4" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	5	1	1,890.00	$4.00	$7,560.00
	Unit Sub Total	**LF**		**1**	**1,890.00**	**$4.00**	**$7,560.00**
	Item Code 208279 Total No. of Proj.			**1**		**Total Amount**	**$7,560.00**
208280	6" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	7	1	32.00	$55.00	$1,760.00
	Unit Sub Total	**LF**		**1**	**32.00**	**$55.00**	**$1,760.00**
	Item Code 208280 Total No. of Proj.			**1**		**Total Amount**	**$1,760.00**
208295	200 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	5	1	112.00	$25.00	$2,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**1**	**112.00**	**$25.00**	**$2,800.00**
	Item Code 208295	**Total No. of Proj.**			**1**		**Total Amount**	**$2,800.00**
208301	IRRIGATION CONTROLLER ENCLOSURE CABINET		EA	4	2	6.00	$1,666.67	$10,000.00
			EA	5	1	1.00	$1,605.66	$1,605.66
			EA	10	1	1.00	$3,000.00	$3,000.00
		Unit Sub Total	**EA**		**4**	**8.00**	**$1,825.71**	**$14,605.66**
	Item Code 208301	**Total No. of Proj.**			**4**		**Total Amount**	**$14,605.66**
208304	WATER METER		EA	3	2	3.00	$38,333.33	$115,000.00
			EA	4	2	5.00	$15,100.00	$75,500.00
			EA	5	1	1.00	$24,048.00	$24,048.00
			EA	7	2	12.00	$4,633.33	$55,600.00
			EA	11	2	10.00	$70,100.00	$701,000.00
		Unit Sub Total	**EA**		**9**	**31.00**	**$31,327.35**	**$971,148.00**
208304	WATER METER		LS	6	1	1.00	$25,000.00	$25,000.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$25,000.00**	**$25,000.00**
	Item Code 208304	**Total No. of Proj.**			**10**		**Total Amount**	**$996,148.00**
208310	IRRIGATION SLEEVE		LF	3	1	175.00	$20.00	$3,500.00
			LF	4	3	300.00	$8.20	$2,460.50
			LF	5	2	650.00	$17.77	$11,550.00
			LF	6	1	330.00	$21.40	$7,062.00
			LF	7	3	500.00	$18.44	$9,220.00
			LF	8	1	18.00	$11.00	$198.00
			LF	11	1	280.00	$4.20	$1,176.00
		Unit Sub Total	**LF**		**12**	**2,253.00**	**$15.61**	**$35,166.50**
208310	IRRIGATION SLEEVE		M	4	1	12.00	$250.00	$3,000.00
			M	7	1	130.00	$160.00	$20,800.00
			M	11	1	540.00	$25.00	$13,500.00
		Unit Sub Total	**M**		**3**	**682.00**	**$54.69**	**$37,300.00**
	Item Code 208310	**Total No. of Proj.**			**15**		**Total Amount**	**$72,466.50**
208420	BACKFLOW PREVENTER ASSEMBLY		EA	8	1	6.00	$7,262.00	$43,572.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**1**	**6.00**	**$7,262.00**	**$43,572.00**
	Item Code 208420 Total No. of Proj.			**1**		**Total Amount**	**$43,572.00**
208421	BACKFLOW PREVENTER ASSEMBLY ENCLOSURE	EA	4	2	6.00	$1,733.33	$10,400.00
		EA	5	1	4.00	$2,264.74	$9,058.96
		EA	8	2	7.00	$2,164.29	$15,150.00
	Unit Sub Total	**EA**		**5**	**17.00**	**$2,035.82**	**$34,608.96**
	Item Code 208421 Total No. of Proj.			**5**		**Total Amount**	**$34,608.96**
208424	1 1/4" BACKFLOW PREVENTER ASSEMBLY	EA	8	1	1.00	$1,500.00	$1,500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,500.00**	**$1,500.00**
	Item Code 208424 Total No. of Proj.			**1**		**Total Amount**	**$1,500.00**
208425	1 1/2" BACKFLOW PREVENTER ASSEMBLY	EA	4	1	2.00	$1,350.00	$2,700.00
		EA	5	1	1.00	$1,161.01	$1,161.01
	Unit Sub Total	**EA**		**2**	**3.00**	**$1,287.00**	**$3,861.01**
	Item Code 208425 Total No. of Proj.			**2**		**Total Amount**	**$3,861.01**
208426	2" BACKFLOW PREVENTER ASSEMBLY	EA	5	1	3.00	$1,209.46	$3,628.38
	Unit Sub Total	**EA**		**1**	**3.00**	**$1,209.46**	**$3,628.38**
	Item Code 208426 Total No. of Proj.			**1**		**Total Amount**	**$3,628.38**
208428	3" BACKFLOW PREVENTER ASSEMBLY	EA	10	1	1.00	$1,500.00	$1,500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,500.00**	**$1,500.00**
	Item Code 208428 Total No. of Proj.			**1**		**Total Amount**	**$1,500.00**
208435	50 MM BACKFLOW PREVENTER ASSEMBLY	EA	4	1	4.00	$1,000.00	$4,000.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$1,000.00**	**$4,000.00**
	Item Code 208435 Total No. of Proj.			**1**		**Total Amount**	**$4,000.00**
208436	65 MM BACKFLOW PREVENTER ASSEMBLY	EA	3	1	1.00	$3,300.00	$3,300.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$3,300.00**	**$3,300.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208436 Total No. of Proj.			**1**		**Total Amount**	**$3,300.00**
208461	SPRINKLER (TYPE A-1)	EA	5	2	920.00	$39.49	$36,333.40
	Unit Sub Total	**EA**		**2**	**920.00**	**$39.49**	**$36,333.40**
	Item Code 208461 Total No. of Proj.			**2**		**Total Amount**	**$36,333.40**
208465	SPRINKLER (TYPE A-5)	EA	4	1	100.00	$25.00	$2,500.00
		EA	5	1	90.00	$42.28	$3,805.20
		EA	7	1	390.00	$30.00	$11,700.00
		EA	11	1	360.00	$23.73	$8,542.80
		EA	12	1	66.00	$24.00	$1,584.00
	Unit Sub Total	**EA**		**5**	**1,006.00**	**$27.96**	**$28,132.00**
	Item Code 208465 Total No. of Proj.			**5**		**Total Amount**	**$28,132.00**
208466	SPRINKLER (TYPE A-6)	EA	3	1	290.00	$35.00	$10,150.00
		EA	4	2	80.00	$30.38	$2,430.00
		EA	11	3	216.00	$55.91	$12,076.12
		EA	12	1	23.00	$28.00	$644.00
	Unit Sub Total	**EA**		**7**	**609.00**	**$41.54**	**$25,300.12**
	Item Code 208466 Total No. of Proj.			**7**		**Total Amount**	**$25,300.12**
208467	SPRINKLER (TYPE A-7)	EA	4	1	30.00	$28.00	$840.00
		EA	7	1	23.00	$30.00	$690.00
		EA	11	1	660.00	$23.73	$15,661.80
	Unit Sub Total	**EA**		**3**	**713.00**	**$24.11**	**$17,191.80**
	Item Code 208467 Total No. of Proj.			**3**		**Total Amount**	**$17,191.80**
208468	SPRINKLER (TYPE A-8)	EA	4	1	57.00	$21.00	$1,197.00
		EA	11	3	167.00	$55.85	$9,326.45
	Unit Sub Total	**EA**		**4**	**224.00**	**$46.98**	**$10,523.45**
	Item Code 208468 Total No. of Proj.			**4**		**Total Amount**	**$10,523.45**
208471	SPRINKLER (TYPE B-1)	EA	3	1	31.00	$10.00	$310.00
		EA	5	1	63.00	$23.00	$1,449.00
		EA	12	1	98.00	$24.00	$2,352.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**3**	**192.00**	**$21.41**	**$4,111.00**
	Item Code 208471	**Total No. of Proj.**			**3**		**Total Amount**	**$4,111.00**
208472	SPRINKLER (TYPE B-2)		EA	3	1	180.00	$25.00	$4,500.00
			EA	5	1	140.00	$20.45	$2,863.00
			EA	7	1	33.00	$25.00	$825.00
			EA	11	2	340.00	$33.59	$11,420.60
		Unit Sub Total	**EA**		**5**	**693.00**	**$28.30**	**$19,608.60**
	Item Code 208472	**Total No. of Proj.**			**5**		**Total Amount**	**$19,608.60**
208474	SPRINKLER (TYPE B-4)		EA	5	1	4.00	$19.45	$77.80
			EA	11	1	76.00	$42.00	$3,192.00
		Unit Sub Total	**EA**		**2**	**80.00**	**$40.87**	**$3,269.80**
	Item Code 208474	**Total No. of Proj.**			**2**		**Total Amount**	**$3,269.80**
208476	SPRINKLER (TYPE B-6)		EA	4	1	28.00	$22.00	$616.00
		Unit Sub Total	**EA**		**1**	**28.00**	**$22.00**	**$616.00**
	Item Code 208476	**Total No. of Proj.**			**1**		**Total Amount**	**$616.00**
208480	SPRINKLER (TYPE C-2 MOD)		EA	11	1	1,360.00	$17.90	$24,344.00
		Unit Sub Total	**EA**		**1**	**1,360.00**	**$17.90**	**$24,344.00**
	Item Code 208480	**Total No. of Proj.**			**1**		**Total Amount**	**$24,344.00**
208481	SPRINKLER (TYPE C-1)		EA	5	1	430.00	$11.00	$4,730.00
		Unit Sub Total	**EA**		**1**	**430.00**	**$11.00**	**$4,730.00**
	Item Code 208481	**Total No. of Proj.**			**1**		**Total Amount**	**$4,730.00**
208482	SPRINKLER (TYPE C-2)		EA	3	1	1,120.00	$11.00	$12,320.00
			EA	4	3	4,090.00	$10.73	$43,900.00
			EA	5	2	2,120.00	$15.75	$33,400.00
			EA	7	1	750.00	$20.00	$15,000.00
			EA	8	1	92.00	$20.00	$1,840.00
			EA	10	1	620.00	$10.00	$6,200.00
			EA	11	1	370.00	$10.00	$3,700.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**10**	**9,162.00**	**$12.70**	**$116,360.00**
	Item Code 208482	**Total No. of Proj.**			**10**		**Total Amount**	**$116,360.00**
208488	25 MM GATE VALVE		EA	3	1	5.00	$165.00	$825.00
		Unit Sub Total	**EA**		**1**	**5.00**	**$165.00**	**$825.00**
	Item Code 208488	**Total No. of Proj.**			**1**		**Total Amount**	**$825.00**
208490	40 MM GATE VALVE		EA	3	1	11.00	$190.00	$2,090.00
		Unit Sub Total	**EA**		**1**	**11.00**	**$190.00**	**$2,090.00**
	Item Code 208490	**Total No. of Proj.**			**1**		**Total Amount**	**$2,090.00**
208491	50 MM GATE VALVE		EA	3	1	7.00	$200.00	$1,400.00
			EA	4	1	8.00	$175.00	$1,400.00
			EA	11	1	45.00	$209.52	$9,428.40
		Unit Sub Total	**EA**		**3**	**60.00**	**$203.81**	**$12,228.40**
	Item Code 208491	**Total No. of Proj.**			**3**		**Total Amount**	**$12,228.40**
208492	65 MM GATE VALVE		EA	3	1	9.00	$325.00	$2,925.00
			EA	4	1	4.00	$300.00	$1,200.00
		Unit Sub Total	**EA**		**2**	**13.00**	**$317.31**	**$4,125.00**
	Item Code 208492	**Total No. of Proj.**			**2**		**Total Amount**	**$4,125.00**
208493	75 MM GATE VALVE		EA	11	1	6.00	$595.88	$3,575.28
		Unit Sub Total	**EA**		**1**	**6.00**	**$595.88**	**$3,575.28**
	Item Code 208493	**Total No. of Proj.**			**1**		**Total Amount**	**$3,575.28**
208502	50 MM PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)		M	8	1	19.00	$58.00	$1,102.00
		Unit Sub Total	**M**		**1**	**19.00**	**$58.00**	**$1,102.00**
	Item Code 208502	**Total No. of Proj.**			**1**		**Total Amount**	**$1,102.00**
208505	25 MM MANUAL CONTROL VALVE		EA	3	1	1.00	$160.00	$160.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$160.00**	**$160.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208505	**Total No. of Proj.**			**1**		**Total Amount**	**$160.00**
208509	25 MM WYE STRAINER		EA	4	1	2.00	$100.00	$200.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$100.00**	**$200.00**
	Item Code 208509	**Total No. of Proj.**			**1**		**Total Amount**	**$200.00**
208510	32 MM WYE STRAINER		EA	4	1	3.00	$145.00	$435.00
		Unit Sub Total	**EA**		**1**	**3.00**	**$145.00**	**$435.00**
	Item Code 208510	**Total No. of Proj.**			**1**		**Total Amount**	**$435.00**
208511	40 MM WYE STRAINER		EA	4	1	2.00	$150.00	$300.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$150.00**	**$300.00**
	Item Code 208511	**Total No. of Proj.**			**1**		**Total Amount**	**$300.00**
208526	SPRINKLER (TYPE D-1)		EA	4	1	9,350.00	$6.10	$57,035.00
			EA	5	1	580.00	$10.74	$6,229.20
		Unit Sub Total	**EA**		**2**	**9,930.00**	**$6.37**	**$63,264.20**
	Item Code 208526	**Total No. of Proj.**			**2**		**Total Amount**	**$63,264.20**
208560	FILTER ASSEMBLY UNIT		EA	10	1	2.00	$600.00	$1,200.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$600.00**	**$1,200.00**
	Item Code 208560	**Total No. of Proj.**			**1**		**Total Amount**	**$1,200.00**
208562	CAM COUPLER ASSEMBLY		EA	4	2	2.00	$395.00	$790.00
			EA	5	1	4.00	$350.00	$1,400.00
			EA	10	1	1.00	$250.00	$250.00
		Unit Sub Total	**EA**		**4**	**7.00**	**$348.57**	**$2,440.00**
	Item Code 208562	**Total No. of Proj.**			**4**		**Total Amount**	**$2,440.00**
208565	REPLACE VALVE BOX COVER		EA	11	2	63.00	$15.19	$957.00
		Unit Sub Total	**EA**		**2**	**63.00**	**$15.19**	**$957.00**
	Item Code 208565	**Total No. of Proj.**			**2**		**Total Amount**	**$957.00**
208572	1" GATE VALVE		EA	4	1	5.00	$120.50	$602.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**5.00**	**$120.50**	**$602.50**
	Item Code 208572	**Total No. of Proj.**			**1**		**Total Amount**	**$602.50**
208573	1 1/4" GATE VALVE		EA	4	1	1.00	$150.00	$150.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$150.00**	**$150.00**
	Item Code 208573	**Total No. of Proj.**			**1**		**Total Amount**	**$150.00**
208574	1 1/2" GATE VALVE		EA	4	1	1.00	$165.00	$165.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$165.00**	**$165.00**
	Item Code 208574	**Total No. of Proj.**			**1**		**Total Amount**	**$165.00**
208575	2" GATE VALVE		EA	4	1	8.00	$200.00	$1,600.00
			EA	5	1	7.00	$236.55	$1,655.85
			EA	11	2	35.00	$151.94	$5,317.85
		Unit Sub Total	**EA**		**4**	**50.00**	**$171.47**	**$8,573.70**
	Item Code 208575	**Total No. of Proj.**			**4**		**Total Amount**	**$8,573.70**
208576	2 1/2" GATE VALVE		EA	4	1	14.00	$260.00	$3,640.00
			EA	5	1	3.00	$417.15	$1,251.45
			EA	10	1	2.00	$300.00	$600.00
		Unit Sub Total	**EA**		**3**	**19.00**	**$289.02**	**$5,491.45**
	Item Code 208576	**Total No. of Proj.**			**3**		**Total Amount**	**$5,491.45**
208588	3" GATE VALVE		EA	4	1	14.00	$310.00	$4,340.00
			EA	5	2	24.00	$488.11	$11,714.74
			EA	7	1	5.00	$750.00	$3,750.00
			EA	10	1	4.00	$350.00	$1,400.00
			EA	11	1	14.00	$450.00	$6,300.00
			EA	12	1	1.00	$450.00	$450.00
		Unit Sub Total	**EA**		**7**	**62.00**	**$450.88**	**$27,954.74**
	Item Code 208588	**Total No. of Proj.**			**7**		**Total Amount**	**$27,954.74**
208589	4" GATE VALVE		EA	5	1	5.00	$550.00	$2,750.00
		Unit Sub Total	**EA**		**1**	**5.00**	**$550.00**	**$2,750.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208589 Total No. of Proj.			**1**		**Total Amount**	**$2,750.00**
208591	8" GATE VALVE	EA	3	1	2.00	$1,900.00	$3,800.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,900.00**	**$3,800.00**
	Item Code 208591 Total No. of Proj.			**1**		**Total Amount**	**$3,800.00**
208594	3/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	4	1	1,270.00	$2.00	$2,540.00
	Unit Sub Total	**LF**		**1**	**1,270.00**	**$2.00**	**$2,540.00**
	Item Code 208594 Total No. of Proj.			**1**		**Total Amount**	**$2,540.00**
208595	1" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	4	1	310.00	$3.00	$930.00
	Unit Sub Total	**LF**		**1**	**310.00**	**$3.00**	**$930.00**
	Item Code 208595 Total No. of Proj.			**1**		**Total Amount**	**$930.00**
208596	1 1/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	4	1	95.00	$4.00	$380.00
		LF	8	1	40.00	$10.00	$400.00
	Unit Sub Total	**LF**		**2**	**135.00**	**$5.78**	**$780.00**
	Item Code 208596 Total No. of Proj.			**2**		**Total Amount**	**$780.00**
208598	2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	4	1	20.00	$5.00	$100.00
	Unit Sub Total	**LF**		**1**	**20.00**	**$5.00**	**$100.00**
	Item Code 208598 Total No. of Proj.			**1**		**Total Amount**	**$100.00**
208618	1" MANUAL CONTROL VALVE	EA	4	1	3.00	$250.00	$750.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$250.00**	**$750.00**
	Item Code 208618 Total No. of Proj.			**1**		**Total Amount**	**$750.00**
208626	1" WYE STRAINER	EA	4	2	14.00	$124.64	$1,745.00
	Unit Sub Total	**EA**		**2**	**14.00**	**$124.64**	**$1,745.00**
	Item Code 208626 Total No. of Proj.			**2**		**Total Amount**	**$1,745.00**
208628	1 1/2" WYE STRAINER	EA	4	1	14.00	$195.00	$2,730.00
	Unit Sub Total	**EA**		**1**	**14.00**	**$195.00**	**$2,730.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208628	**Total No. of Proj.**			**1**		**Total Amount**	**$2,730.00**
208645	3/4" QUICK COUPLING VALVE		EA	4	1	27.00	$150.00	$4,050.00
		Unit Sub Total	**EA**		**1**	**27.00**	**$150.00**	**$4,050.00**
	Item Code 208645	**Total No. of Proj.**			**1**		**Total Amount**	**$4,050.00**
208649	QUICK COUPLING VALVE		EA	4	1	2.00	$180.00	$360.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$180.00**	**$360.00**
	Item Code 208649	**Total No. of Proj.**			**1**		**Total Amount**	**$360.00**
208670	CHECK VALVE		EA	7	1	3.00	$150.00	$450.00
		Unit Sub Total	**EA**		**1**	**3.00**	**$150.00**	**$450.00**
	Item Code 208670	**Total No. of Proj.**			**1**		**Total Amount**	**$450.00**
208683	BALL VALVE		EA	4	1	12.00	$90.00	$1,080.00
			EA	5	1	4.00	$150.00	$600.00
			EA	7	1	15.00	$200.00	$3,000.00
			EA	12	1	6.00	$100.00	$600.00
		Unit Sub Total	**EA**		**4**	**37.00**	**$142.70**	**$5,280.00**
	Item Code 208683	**Total No. of Proj.**			**4**		**Total Amount**	**$5,280.00**
208724	200 MM ALTERNATIVE CONDUIT		M	3	1	240.00	$202.00	$48,480.00
			M	5	1	88.00	$20.00	$1,760.00
		Unit Sub Total	**M**		**2**	**328.00**	**$153.17**	**$50,240.00**
	Item Code 208724	**Total No. of Proj.**			**2**		**Total Amount**	**$50,240.00**
208731	200 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT		M	2	1	120.00	$89.00	$10,680.00
			M	3	1	20.00	$79.00	$1,580.00
			M	4	6	589.00	$120.97	$71,249.00
			M	6	1	8.00	$87.00	$696.00
			M	7	2	182.00	$152.90	$27,828.00
			M	11	2	1,210.00	$106.20	$128,500.00
		Unit Sub Total	**M**		**13**	**2,129.00**	**$112.98**	**$240,533.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208731 Total No. of Proj.			**13**		**Total Amount**	**$240,533.00**
208732	250 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	M	5	1	110.00	$176.00	$19,360.00
		M	6	1	86.00	$50.00	$4,300.00
		M	7	1	240.00	$190.00	$45,600.00
		M	11	1	180.00	$195.00	$35,100.00
	Unit Sub Total	**M**		**4**	**616.00**	**$169.42**	**$104,360.00**
	Item Code 208732 Total No. of Proj.			**4**		**Total Amount**	**$104,360.00**
208733	300 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	M	8	1	140.00	$65.00	$9,100.00
	Unit Sub Total	**M**		**1**	**140.00**	**$65.00**	**$9,100.00**
	Item Code 208733 Total No. of Proj.			**1**		**Total Amount**	**$9,100.00**
208738	8" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	4	3	774.00	$26.78	$20,725.00
		LF	11	1	40.00	$100.00	$4,000.00
	Unit Sub Total	**LF**		**4**	**814.00**	**$30.37**	**$24,725.00**
	Item Code 208738 Total No. of Proj.			**4**		**Total Amount**	**$24,725.00**
208739	10" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	4	1	75.00	$70.00	$5,250.00
		LF	5	1	32.00	$36.00	$1,152.00
	Unit Sub Total	**LF**		**2**	**107.00**	**$59.83**	**$6,402.00**
	Item Code 208739 Total No. of Proj.			**2**		**Total Amount**	**$6,402.00**
208740	12" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	6	1	4,020.00	$20.00	$80,400.00
	Unit Sub Total	**LF**		**1**	**4,020.00**	**$20.00**	**$80,400.00**
	Item Code 208740 Total No. of Proj.			**1**		**Total Amount**	**$80,400.00**
208741	150 MM CORRUGATED STEEL PIPE CONDUIT (1.63 MM THICK)	M	6	1	60.00	$85.00	$5,100.00
		M	10	1	20.00	$612.00	$12,240.00
	Unit Sub Total	**M**		**2**	**80.00**	**$216.75**	**$17,340.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208741 Total No. of Proj.			**2**		**Total Amount**	**$17,340.00**
208743	250 MM CORRUGATED STEEL PIPE CONDUIT (1.63 MM THICK)	M	8	1	110.00	$137.00	$15,070.00
	Unit Sub Total	**M**		**1**	**110.00**	**$137.00**	**$15,070.00**
	Item Code 208743 Total No. of Proj.			**1**		**Total Amount**	**$15,070.00**
208744	300 MM CORRUGATED STEEL PIPE CONDUIT (1.63 MM THICK)	M	8	1	620.00	$166.00	$102,920.00
	Unit Sub Total	**M**		**1**	**620.00**	**$166.00**	**$102,920.00**
	Item Code 208744 Total No. of Proj.			**1**		**Total Amount**	**$102,920.00**
208747	250 MM BITUMINOUS COATED STEEL PIPE CONDUIT (1.63 MM THICK)	M	10	1	120.00	$390.00	$46,800.00
	Unit Sub Total	**M**		**1**	**120.00**	**$390.00**	**$46,800.00**
	Item Code 208747 Total No. of Proj.			**1**		**Total Amount**	**$46,800.00**
208765	8" BITUMINOUS COATED CORRUGATED STEEL PIPE CONDUIT (.064" THICK)	LF	6	1	30.00	$155.00	$4,650.00
	Unit Sub Total	**LF**		**1**	**30.00**	**$155.00**	**$4,650.00**
	Item Code 208765 Total No. of Proj.			**1**		**Total Amount**	**$4,650.00**
208796	100 MM WELDED STEEL PIPE CONDUIT (6.02 MM THICK)	M	3	1	40.00	$200.00	$8,000.00
	Unit Sub Total	**M**		**1**	**40.00**	**$200.00**	**$8,000.00**
	Item Code 208796 Total No. of Proj.			**1**		**Total Amount**	**$8,000.00**
208797	150 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	7	1	57.00	$215.00	$12,255.00
	Unit Sub Total	**M**		**1**	**57.00**	**$215.00**	**$12,255.00**
	Item Code 208797 Total No. of Proj.			**1**		**Total Amount**	**$12,255.00**
208798	200 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	3	1	200.00	$200.00	$40,000.00
		M	4	2	420.00	$214.64	$90,150.00
		M	6	1	33.00	$550.00	$18,150.00
		M	7	1	10.00	$1,200.00	$12,000.00
		M	11	1	58.00	$511.31	$29,655.98

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**6**	**721.00**	**$263.46**	**$189,955.98**
	Item Code 208798 Total No. of Proj.			**6**		**Total Amount**	**$189,955.98**
208799	250 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	8	1	65.00	$165.00	$10,725.00
		M	11	1	81.00	$642.01	$52,002.81
	Unit Sub Total	**M**		**2**	**146.00**	**$429.64**	**$62,727.81**
	Item Code 208799 Total No. of Proj.			**2**		**Total Amount**	**$62,727.81**
208800	300 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	8	1	230.00	$232.00	$53,360.00
	Unit Sub Total	**M**		**1**	**230.00**	**$232.00**	**$53,360.00**
	Item Code 208800 Total No. of Proj.			**1**		**Total Amount**	**$53,360.00**
208808	8" WELDED STEEL PIPE CONDUIT (.250" THICK)	LF	3	1	940.00	$100.00	$94,000.00
		LF	4	1	140.00	$100.00	$14,000.00
		LF	5	1	25.00	$144.00	$3,600.00
		LF	7	3	195.00	$154.87	$30,200.00
		LF	11	1	63.00	$135.00	$8,505.00
	Unit Sub Total	**LF**		**7**	**1,363.00**	**$110.28**	**$150,305.00**
	Item Code 208808 Total No. of Proj.			**7**		**Total Amount**	**$150,305.00**
208809	10" WELDED STEEL PIPE CONDUIT (.250" THICK)	LF	5	2	850.00	$101.05	$85,894.00
	Unit Sub Total	**LF**		**2**	**850.00**	**$101.05**	**$85,894.00**
	Item Code 208809 Total No. of Proj.			**2**		**Total Amount**	**$85,894.00**
208812	12" WELDED STEEL PIPE CONDUIT (.250" THICK)	LF	5	1	560.00	$126.25	$70,700.00
		LF	10	1	290.00	$55.00	$15,950.00
	Unit Sub Total	**LF**		**2**	**850.00**	**$101.94**	**$86,650.00**
	Item Code 208812 Total No. of Proj.			**2**		**Total Amount**	**$86,650.00**
208906	EXTEND 8" CONDUIT	LF	2	1	180.00	$23.00	$4,140.00
		LF	3	1	1,560.00	$40.00	$62,400.00
		LF	6	1	110.00	$35.00	$3,850.00
		LF	10	1	57.00	$50.00	$2,850.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208906	EXTEND 8" CONDUIT	LF	11	1	6.00	$420.00	$2,520.00
	Unit Sub Total	**LF**		**5**	**1,913.00**	**$39.60**	**$75,760.00**
	Item Code 208906 Total No. of Proj.			**5**		**Total Amount**	**$75,760.00**
208907	EXTEND 10" CONDUIT	LF	4	1	25.00	$110.00	$2,750.00
		LF	7	1	15.00	$100.00	$1,500.00
		LF	11	2	120.00	$223.33	$26,800.00
	Unit Sub Total	**LF**		**4**	**160.00**	**$194.06**	**$31,050.00**
	Item Code 208907 Total No. of Proj.			**4**		**Total Amount**	**$31,050.00**
208908	EXTEND 150 MM CONDUIT	M	3	1	50.00	$120.00	$6,000.00
	Unit Sub Total	**M**		**1**	**50.00**	**$120.00**	**$6,000.00**
	Item Code 208908 Total No. of Proj.			**1**		**Total Amount**	**$6,000.00**
208909	EXTEND 200 MM CONDUIT	M	6	1	11.00	$185.00	$2,035.00
	Unit Sub Total	**M**		**1**	**11.00**	**$185.00**	**$2,035.00**
	Item Code 208909 Total No. of Proj.			**1**		**Total Amount**	**$2,035.00**
208910	EXTEND 250 MM CONDUIT	M	7	1	6.00	$650.00	$3,900.00
		M	11	1	29.00	$530.00	$15,370.00
	Unit Sub Total	**M**		**2**	**35.00**	**$550.57**	**$19,270.00**
	Item Code 208910 Total No. of Proj.			**2**		**Total Amount**	**$19,270.00**
209202	RECYCLED WATER WARNING SIGNS	LS	12	1	1.00	$700.00	$700.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$700.00**	**$700.00**
	Item Code 209202 Total No. of Proj.			**1**		**Total Amount**	**$700.00**
209503	BOOSTER PUMP SYSTEM	EA	3	2	3.00	$15,000.00	$45,000.00
		EA	4	1	2.00	$16,000.00	$32,000.00
		EA	5	1	1.00	$15,000.00	$15,000.00
	Unit Sub Total	**EA**		**4**	**6.00**	**$15,333.33**	**$92,000.00**
	Item Code 209503 Total No. of Proj.			**4**		**Total Amount**	**$92,000.00**
209801	MAINTENANCE VEHICLE PULLOUT	EA	3	1	12.00	$5,000.00	$60,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**12.00**	**$5,000.00**	**$60,000.00**
	Item Code 209801	**Total No. of Proj.**			**1**		**Total Amount**	**$60,000.00**
220101	FINISHING ROADWAY		LS	3	1	1.00	$1,000.00	$1,000.00
			LS	4	1	1.00	$20,000.00	$20,000.00
			LS	5	1	1.00	$1,000.00	$1,000.00
			LS	6	1	1.00	$300,000.00	$300,000.00
			LS	9	1	1.00	$10,000.00	$10,000.00
		Unit Sub Total	**LS**		**5**	**5.00**	**$66,400.00**	**$332,000.00**
	Item Code 220101	**Total No. of Proj.**			**5**		**Total Amount**	**$332,000.00**
240100	LIME		TON	2	1	35.00	$171.00	$5,985.00
		Unit Sub Total	**TON**		**1**	**35.00**	**$171.00**	**$5,985.00**
240100	LIME		TONN	4	2	6,400.00	$145.84	$933,400.00
		Unit Sub Total	**TONN**		**2**	**6,400.00**	**$145.84**	**$933,400.00**
	Item Code 240100	**Total No. of Proj.**			**3**		**Total Amount**	**$939,385.00**
250101	CLASS 1 AGGREGATE SUBBASE		CY	6	2	113,310.00	$16.08	$1,821,640.00
		Unit Sub Total	**CY**		**2**	**113,310.00**	**$16.08**	**$1,821,640.00**
250101	CLASS 1 AGGREGATE SUBBASE		M3	5	1	43,100.00	$15.00	$646,500.00
		Unit Sub Total	**M3**		**1**	**43,100.00**	**$15.00**	**$646,500.00**
	Item Code 250101	**Total No. of Proj.**			**3**		**Total Amount**	**$2,468,140.00**
250201	CLASS 2 AGGREGATE SUBBASE		CY	4	1	50.00	$330.00	$16,500.00
			CY	12	3	23,417.00	$16.20	$379,250.00
		Unit Sub Total	**CY**		**4**	**23,467.00**	**$16.86**	**$395,750.00**
250201	CLASS 2 AGGREGATE SUBBASE		M3	3	1	840.00	$46.00	$38,640.00
			M3	6	1	44,100.00	$9.00	$396,900.00
		Unit Sub Total	**M3**		**2**	**44,940.00**	**$9.69**	**$435,540.00**
	Item Code 250201	**Total No. of Proj.**			**6**		**Total Amount**	**$831,290.00**
250301	CLASS 3 AGGREGATE SUBBASE		M3	6	1	2,250.00	$50.00	$112,500.00
		Unit Sub Total	**M3**		**1**	**2,250.00**	**$50.00**	**$112,500.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 250301	**Total No. of Proj.**			**1**		**Total Amount**	**$112,500.00**
250401	CLASS 4 AGGREGATE SUBBASE		CY	4	4	9,500.00	$25.46	$241,910.00
			CY	5	1	260.00	$76.00	$19,760.00
		Unit Sub Total	**CY**		**5**	**9,760.00**	**$26.81**	**$261,670.00**
250401	CLASS 4 AGGREGATE SUBBASE		M3	4	10	158,343.00	$20.45	$3,238,160.00
			M3	11	2	105,700.00	$9.24	$976,300.00
		Unit Sub Total	**M3**		**12**	**264,043.00**	**$15.96**	**$4,214,460.00**
	Item Code 250401	**Total No. of Proj.**			**17**		**Total Amount**	**$4,476,130.00**
260200	AGGREGATE BASE		CY	3	1	150.00	$50.00	$7,500.00
			CY	12	1	210.00	$73.70	$15,477.00
		Unit Sub Total	**CY**		**2**	**360.00**	**$63.83**	**$22,977.00**
	Item Code 260200	**Total No. of Proj.**			**2**		**Total Amount**	**$22,977.00**
260201	CLASS 2 AGGREGATE BASE		CY	1	18	12,683.00	$44.98	$570,522.00
			CY	2	22	53,636.00	$32.03	$1,717,796.00
			CY	3	11	150,520.00	$25.25	$3,800,291.00
			CY	4	2	147.00	$93.74	$13,780.20
			CY	5	9	22,111.00	$39.00	$862,326.20
			CY	6	9	50,943.00	$27.66	$1,409,264.00
			CY	7	1	160.00	$80.00	$12,800.00
			CY	8	18	14,685.00	$50.45	$740,828.30
			CY	10	4	4,180.00	$50.59	$211,480.00
			CY	11	8	8,467.00	$56.46	$478,078.00
			CY	12	6	6,886.00	$26.72	$184,013.00
		Unit Sub Total	**CY**		**108**	**324,418.00**	**$30.83**	**$10,001,178.70**
260201	CLASS 2 AGGREGATE BASE		M3	1	4	772.30	$101.94	$78,725.00
			M3	2	4	14,960.00	$68.87	$1,030,267.00
			M3	3	5	142,500.00	$36.38	$5,184,000.00
			M3	4	1	310.00	$125.00	$38,750.00
			M3	5	3	22,031.00	$38.84	$855,778.15
			M3	6	6	163,250.00	$41.50	$6,774,420.00
			M3	7	2	1,916.00	$42.06	$80,580.00
			M3	8	3	47,200.00	$31.67	$1,494,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
260201	CLASS 2 AGGREGATE BASE	M3	9	2	2,110.00	$75.56	$159,430.00
		M3	10	10	60,570.00	$41.30	$2,501,397.00
		M3	11	2	88,350.00	$21.72	$1,919,000.00
	Unit Sub Total	**M3**		**42**	**543,969.30**	**$36.98**	**$20,117,247.15**
	Item Code 260201 Total No. of Proj.			**150**		**Total Amount**	**$30,118,425.85**
260210	AGGREGATE BASE (APPROACH SLAB)	CY	2	2	90.00	$73.78	$6,640.00
		CY	3	3	84.00	$255.95	$21,500.00
		CY	4	5	157.00	$134.59	$21,130.00
		CY	6	1	35.00	$400.00	$14,000.00
		CY	7	7	323.00	$345.00	$111,435.00
		CY	8	2	37.00	$222.30	$8,225.00
		CY	10	3	44.00	$359.77	$15,830.00
		CY	11	2	29.00	$650.00	$18,850.00
		CY	12	1	19.00	$280.00	$5,320.00
	Unit Sub Total	**CY**		**26**	**818.00**	**$272.53**	**$222,930.00**
260210	AGGREGATE BASE (APPROACH SLAB)	M3	7	3	14.70	$277.21	$4,075.00
		M3	8	1	190.00	$250.00	$47,500.00
		M3	11	1	3.00	$620.00	$1,860.00
	Unit Sub Total	**M3**		**5**	**207.70**	**$257.27**	**$53,435.00**
	Item Code 260210 Total No. of Proj.			**31**		**Total Amount**	**$276,365.00**
260301	CLASS 3 AGGREGATE BASE	CY	4	7	4,861.00	$44.50	$216,336.46
		CY	7	11	6,738.40	$47.08	$317,254.00
	Unit Sub Total	**CY**		**18**	**11,599.40**	**$46.00**	**$533,590.46**
260301	CLASS 3 AGGREGATE BASE	M3	4	9	56,034.00	$39.91	$2,236,137.00
		M3	7	5	48,980.00	$42.53	$2,083,150.00
		M3	9	1	5,190.00	$70.00	$363,300.00
	Unit Sub Total	**M3**		**15**	**110,204.00**	**$42.49**	**$4,682,587.00**
	Item Code 260301 Total No. of Proj.			**33**		**Total Amount**	**$5,216,177.46**
270011	CEMENT TREATED BASE (PLANT-MIXED, CLASS A)	M3	4	2	15,390.00	$72.82	$1,120,700.00
		M3	5	1	1,470.00	$90.00	$132,300.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**3**	**16,860.00**	**$74.32**	**$1,253,000.00**
	Item Code 270011	**Total No. of Proj.**			**3**		**Total Amount**	**$1,253,000.00**
270065	ASPHALTIC EMULSION (CURING SEAL)		TON	4	1	6.00	$600.00	$3,600.00
		Unit Sub Total	**TON**		**1**	**6.00**	**$600.00**	**$3,600.00**
270065	ASPHALTIC EMULSION (CURING SEAL)		TONN	4	3	84.00	$688.10	$57,800.00
		Unit Sub Total	**TONN**		**3**	**84.00**	**$688.10**	**$57,800.00**
	Item Code 270065	**Total No. of Proj.**			**4**		**Total Amount**	**$61,400.00**
280000	LEAN CONCRETE BASE		CY	2	1	15,300.00	$100.00	$1,530,000.00
			CY	4	2	3,370.00	$128.77	$433,950.00
			CY	6	1	70,200.00	$70.00	$4,914,000.00
			CY	7	4	4,081.80	$139.80	$570,650.00
			CY	8	1	350.00	$140.00	$49,000.00
			CY	12	1	14,100.00	$120.00	$1,692,000.00
		Unit Sub Total	**CY**		**10**	**107,401.80**	**$85.56**	**$9,189,600.00**
280000	LEAN CONCRETE BASE		M3	4	8	78,161.00	$150.02	$11,725,530.00
			M3	6	2	31,270.00	$74.13	$2,317,900.00
			M3	7	5	29,730.00	$114.43	$3,401,860.00
			M3	8	2	17,030.00	$114.69	$1,953,150.00
		Unit Sub Total	**M3**		**17**	**156,191.00**	**$124.20**	**$19,398,440.00**
	Item Code 280000	**Total No. of Proj.**			**27**		**Total Amount**	**$28,588,040.00**
290201	ASPHALT TREATED PERMEABLE BASE		CY	1	3	360.00	$188.78	$67,960.00
			CY	3	1	1,170.00	$80.00	$93,600.00
			CY	4	1	550.00	$135.00	$74,250.00
			CY	8	1	4.00	$225.00	$900.00
		Unit Sub Total	**CY**		**6**	**2,084.00**	**$113.58**	**$236,710.00**
290201	ASPHALT TREATED PERMEABLE BASE		M3	1	1	54.00	$242.00	$13,068.00
			M3	4	1	160.00	$160.00	$25,600.00
		Unit Sub Total	**M3**		**2**	**214.00**	**$180.69**	**$38,668.00**
	Item Code 290201	**Total No. of Proj.**			**8**		**Total Amount**	**$275,378.00**
290301	CEMENT TREATED PERMEABLE BASE		M3	2	1	4,450.00	$86.00	$382,700.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**1**	**4,450.00**	**$86.00**	**$382,700.00**
	Item Code 290301	**Total No. of Proj.**			**1**		**Total Amount**	**$382,700.00**
365001	SAND COVER		CY	5	1	6,970.00	$88.00	$613,360.00
		Unit Sub Total	**CY**		**1**	**6,970.00**	**$88.00**	**$613,360.00**
365001	SAND COVER		TON	1	2	560.00	$31.34	$17,550.00
			TON	2	4	1,678.00	$125.04	$209,810.00
			TON	3	2	1,090.00	$30.91	$33,695.00
			TON	5	3	587.00	$57.03	$33,475.00
			TON	6	11	2,855.00	$39.84	$113,745.00
			TON	7	1	140.00	$100.00	$14,000.00
			TON	8	2	660.00	$65.64	$43,320.00
			TON	9	3	2,158.00	$129.68	$279,850.00
			TON	10	2	670.00	$95.22	$63,800.00
			TON	11	1	1,990.00	$125.00	$248,750.00
		Unit Sub Total	**TON**		**31**	**12,388.00**	**$85.40**	**$1,057,995.00**
	Item Code 365001	**Total No. of Proj.**			**32**		**Total Amount**	**$1,671,355.00**
370120	ASPHALT-RUBBER BINDER		TON	2	2	1,460.00	$873.64	$1,275,520.00
			TON	7	1	250.00	$327.00	$81,750.00
			TON	8	1	520.00	$800.00	$416,000.00
			TON	9	1	1,570.00	$857.00	$1,345,490.00
			TON	12	1	6.00	$560.00	$3,360.00
		Unit Sub Total	**TON**		**6**	**3,806.00**	**$820.32**	**$3,122,120.00**
	Item Code 370120	**Total No. of Proj.**			**6**		**Total Amount**	**$3,122,120.00**
370125	ASPHALT BINDER (POLYMER MODIFIED)		TON	6	1	420.00	$534.00	$224,280.00
		Unit Sub Total	**TON**		**1**	**420.00**	**$534.00**	**$224,280.00**
	Item Code 370125	**Total No. of Proj.**			**1**		**Total Amount**	**$224,280.00**
374002	ASPHALTIC EMULSION (FOG SEAL COAT)		TON	1	2	96.00	$450.44	$43,242.00
			TON	2	6	318.00	$579.17	$184,175.00
			TON	3	4	163.00	$474.79	$77,390.00
			TON	4	1	80.00	$100.00	$8,000.00
			TON	5	12	115.90	$628.72	$72,869.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
374002	ASPHALTIC EMULSION (FOG SEAL COAT)	TON	6	16	673.00	$545.55	$367,158.00
		TON	7	4	684.00	$278.84	$190,725.00
		TON	8	10	719.00	$572.66	$411,744.80
		TON	9	4	266.00	$675.09	$179,575.00
		TON	10	4	207.00	$251.65	$52,092.00
		TON	11	13	275.40	$469.44	$129,284.00
	Unit Sub Total	**TON**		**76**	**3,597.30**	**$477.10**	**$1,716,254.80**
374002	ASPHALTIC EMULSION (FOG SEAL COAT)	TONN	9	1	1.20	$3,000.00	$3,600.00
		TONN	10	1	5.00	$900.00	$4,500.00
		TONN	11	3	46.10	$1,144.25	$52,750.00
	Unit Sub Total	**TONN**		**5**	**52.30**	**$1,163.48**	**$60,850.00**
	Item Code 374002 Total No. of Proj.			**81**		**Total Amount**	**$1,777,104.80**
374206	SEAL RANDOM CRACKS	LNKM	3	1	6.00	$8,000.00	$48,000.00
		LNKM	4	1	4.10	$5,000.00	$20,500.00
		LNKM	7	1	0.50	$6,000.00	$3,000.00
		LNKM	9	2	27.10	$1,837.45	$49,795.00
	Unit Sub Total	**LNKM**		**5**	**37.70**	**$3,217.37**	**$121,295.00**
374206	SEAL RANDOM CRACKS	LNMI	1	1	1.10	$8,600.00	$9,460.00
		LNMI	2	1	3.00	$2,850.00	$8,550.00
		LNMI	3	6	223.70	$1,840.72	$411,770.00
		LNMI	4	16	121.20	$3,004.74	$364,175.00
		LNMI	10	1	10.00	$4,200.00	$42,000.00
	Unit Sub Total	**LNMI**		**25**	**359.00**	**$2,328.57**	**$835,955.00**
374206	SEAL RANDOM CRACKS	LS	12	1	1.00	$500.00	$500.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$500.00**	**$500.00**
	Item Code 374206 Total No. of Proj.			**31**		**Total Amount**	**$957,750.00**
374492	ASPHALTIC EMULSION (POLYMER MODIFIED)	TON	1	2	450.00	$502.84	$226,280.00
		TON	3	2	1,060.00	$528.65	$560,370.00
		TON	5	2	375.00	$428.67	$160,750.00
		TON	6	8	1,900.00	$469.44	$891,930.00
		TON	8	1	230.00	$412.00	$94,760.00
		TON	10	2	590.00	$402.80	$237,650.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
374492	ASPHALTIC EMULSION (POLYMER MODIFIED)	TON	11	1	1,330.00	$430.00	$571,900.00
	Unit Sub Total	**TON**		**18**	**5,935.00**	**$462.28**	**$2,743,640.00**
	Item Code 374492 Total No. of Proj.			**18**		**Total Amount**	**$2,743,640.00**
375021	SCREENINGS (MEDIUM FINE)	TON	1	2	3,780.00	$32.97	$124,640.00
	Unit Sub Total	**TON**		**2**	**3,780.00**	**$32.97**	**$124,640.00**
	Item Code 375021 Total No. of Proj.			**2**		**Total Amount**	**$124,640.00**
375022	SCREENINGS (MEDIUM)	TON	3	2	9,510.00	$31.38	$298,380.00
		TON	5	2	3,880.00	$23.08	$89,566.00
		TON	6	7	15,310.00	$61.11	$935,610.00
		TON	8	1	2,070.00	$22.00	$45,540.00
		TON	10	2	5,180.00	$17.91	$92,780.00
		TON	11	1	11,900.00	$28.00	$333,200.00
	Unit Sub Total	**TON**		**15**	**47,850.00**	**$37.51**	**$1,795,076.00**
	Item Code 375022 Total No. of Proj.			**15**		**Total Amount**	**$1,795,076.00**
375023	SCREENINGS (COARSE)	TON	6	2	1,300.00	$28.46	$37,000.00
	Unit Sub Total	**TON**		**2**	**1,300.00**	**$28.46**	**$37,000.00**
	Item Code 375023 Total No. of Proj.			**2**		**Total Amount**	**$37,000.00**
375030	SCREENINGS (HOT-APPLIED)	TON	2	2	10,310.00	$39.88	$411,205.00
		TON	6	2	5,840.00	$58.41	$341,110.00
		TON	7	1	1,540.00	$76.25	$117,425.00
		TON	8	1	3,790.00	$145.00	$549,550.00
		TON	9	2	18,640.00	$58.17	$1,084,260.00
		TON	12	1	18.00	$1,225.00	$22,050.00
	Unit Sub Total	**TON**		**9**	**40,138.00**	**$62.92**	**$2,525,600.00**
	Item Code 375030 Total No. of Proj.			**9**		**Total Amount**	**$2,525,600.00**
377501	SLURRY SEAL	TON	2	1	180.00	$335.00	$60,300.00
		TON	3	1	240.00	$150.00	$36,000.00
		TON	5	1	580.00	$164.00	$95,120.00
		TON	7	2	8,570.00	$116.17	$995,608.90
		TON	8	3	6,100.00	$148.26	$904,413.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
377501	SLURRY SEAL	TON	10	1	130.00	$185.00	$24,050.00
		TON	11	2	52.00	$827.40	$43,025.00
		TON	12	2	4,110.00	$117.95	$484,755.00
	Unit Sub Total	**TON**		**13**	**19,962.00**	**$132.42**	**$2,643,272.40**
	Item Code 377501 Total No. of Proj.			**13**		**Total Amount**	**$2,643,272.40**
378000	MICRO-SURFACING	TON	7	1	2,930.00	$149.91	$439,236.30
	Unit Sub Total	**TON**		**1**	**2,930.00**	**$149.91**	**$439,236.30**
	Item Code 378000 Total No. of Proj.			**1**		**Total Amount**	**$439,236.30**
390095	REPLACE ASPHALT CONCRETE SURFACING	CY	1	7	7,278.00	$188.49	$1,371,829.50
		CY	2	14	9,870.00	$254.81	$2,514,956.40
		CY	3	10	7,829.00	$168.18	$1,316,695.00
		CY	4	15	5,231.70	$236.00	$1,234,688.00
		CY	6	4	143.00	$426.92	$61,050.00
		CY	7	9	321.50	$397.55	$127,813.00
		CY	8	20	16,517.00	$220.21	$3,637,149.29
		CY	10	1	29.00	$425.00	$12,325.00
	Unit Sub Total	**CY**		**80**	**47,219.20**	**$217.63**	**$10,276,506.19**
390095	REPLACE ASPHALT CONCRETE SURFACING	M3	3	2	2,499.00	$206.86	$516,950.00
		M3	4	3	1,130.00	$244.60	$276,400.00
		M3	6	2	5,865.00	$177.42	$1,040,555.00
		M3	10	1	470.00	$200.00	$94,000.00
	Unit Sub Total	**M3**		**8**	**9,964.00**	**$193.49**	**$1,927,905.00**
	Item Code 390095 Total No. of Proj.			**88**		**Total Amount**	**$12,204,411.19**
390102	ASPHALT CONCRETE (TYPE A)	TON	8	1	290.00	$110.00	$31,900.00
		TON	9	1	190.00	$145.00	$27,550.00
	Unit Sub Total	**TON**		**2**	**480.00**	**$123.85**	**$59,450.00**
390102	ASPHALT CONCRETE (TYPE A)	TONN	3	1	25,900.00	$64.00	$1,657,600.00
		TONN	4	1	28,600.00	$82.10	$2,348,060.00
		TONN	8	1	94,800.00	$64.05	$6,071,940.00
		TONN	10	1	1,540.00	$120.00	$184,800.00
	Unit Sub Total	**TONN**		**4**	**150,840.00**	**$68.04**	**$10,262,400.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 390102 Total No. of Proj.			**6**		**Total Amount**	**$10,321,850.00**
390104	ASPHALT CONCRETE	TONN	4	1	76,000.00	$66.00	$5,016,000.00
	Unit Sub Total	**TONN**		**1**	**76,000.00**	**$66.00**	**$5,016,000.00**
	Item Code 390104 Total No. of Proj.			**1**		**Total Amount**	**$5,016,000.00**
390106	ASPHALT CONCRETE (OPEN GRADED)	TONN	4	1	3,100.00	$107.00	$331,700.00
	Unit Sub Total	**TONN**		**1**	**3,100.00**	**$107.00**	**$331,700.00**
	Item Code 390106 Total No. of Proj.			**1**		**Total Amount**	**$331,700.00**
390107	ASPHALT CONCRETE (LEVELING)	TON	3	1	400.00	$162.00	$64,800.00
	Unit Sub Total	**TON**		**1**	**400.00**	**$162.00**	**$64,800.00**
	Item Code 390107 Total No. of Proj.			**1**		**Total Amount**	**$64,800.00**
390126	RUBBERIZED ASPHALT CONCRETE (TYPE G)	TONN	4	1	29,100.00	$90.00	$2,619,000.00
		TONN	10	1	15,600.00	$85.00	$1,326,000.00
	Unit Sub Total	**TONN**		**2**	**44,700.00**	**$88.26**	**$3,945,000.00**
	Item Code 390126 Total No. of Proj.			**2**		**Total Amount**	**$3,945,000.00**
390127	RUBBERIZED ASPHALT CONCRETE (TYPE O)	TONN	3	1	110.00	$120.00	$13,200.00
		TONN	4	1	19,800.00	$9.00	$178,200.00
	Unit Sub Total	**TONN**		**2**	**19,910.00**	**$9.61**	**$191,400.00**
	Item Code 390127 Total No. of Proj.			**2**		**Total Amount**	**$191,400.00**
390130	HOT MIX ASPHALT	TON	8	1	610.00	$115.00	$70,150.00
	Unit Sub Total	**TON**		**1**	**610.00**	**$115.00**	**$70,150.00**
390130	HOT MIX ASPHALT	TONN	4	1	5,710.00	$130.00	$742,300.00
	Unit Sub Total	**TONN**		**1**	**5,710.00**	**$130.00**	**$742,300.00**
	Item Code 390130 Total No. of Proj.			**2**		**Total Amount**	**$812,450.00**
390131	HOT MIX ASPHALT	TON	2	1	15,500.00	$93.00	$1,441,500.00
		TON	3	3	207,300.00	$59.48	$12,330,025.00
		TON	4	2	79,900.00	$65.03	$5,195,500.00
		TON	5	1	24,600.00	$75.00	$1,845,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
390131	HOT MIX ASPHALT		TON	6	1	73,600.00	$70.00	$5,152,000.00
			TON	8	3	71,800.00	$60.83	$4,367,847.00
			TON	10	1	14,000.00	$60.00	$840,000.00
		Unit Sub Total	**TON**		**12**	**486,700.00**	**$64.05**	**$31,171,872.00**
390131	HOT MIX ASPHALT		TONN	2	1	30,400.00	$82.00	$2,492,800.00
			TONN	3	3	132,900.00	$62.11	$8,254,100.00
			TONN	4	7	379,100.00	$85.71	$32,492,440.00
			TONN	5	1	41,600.00	$70.00	$2,912,000.00
			TONN	6	3	264,300.00	$65.86	$17,406,400.00
			TONN	7	1	40,900.00	$70.00	$2,863,000.00
			TONN	8	2	78,800.00	$89.17	$7,026,800.00
			TONN	9	1	12,500.00	$95.00	$1,187,500.00
			TONN	10	1	23,900.00	$65.00	$1,553,500.00
			TONN	11	2	252,300.00	$69.34	$17,494,500.00
		Unit Sub Total	**TONN**		**22**	**1,256,700.00**	**$74.55**	**$93,683,040.00**
	Item Code 390131	**Total No. of Proj.**			**34**		**Total Amount**	**$124,854,912.00**
390132	HOT MIX ASPHALT (TYPE A)		TON	1	26	22,239.00	$123.19	$2,739,528.00
			TON	2	25	179,030.00	$89.04	$15,940,607.20
			TON	3	14	20,320.00	$84.24	$1,711,667.00
			TON	4	21	51,681.00	$89.67	$4,634,343.50
			TON	5	17	25,070.00	$88.33	$2,214,405.50
			TON	6	20	57,520.00	$77.55	$4,460,485.00
			TON	7	2	7,557.00	$85.12	$643,216.00
			TON	8	18	31,641.00	$91.07	$2,881,511.70
			TON	9	4	13,600.00	$105.32	$1,432,410.00
			TON	10	2	1,170.00	$110.26	$129,000.00
			TON	11	7	12,177.00	$84.45	$1,028,368.00
			TON	12	14	27,409.80	$74.86	$2,051,825.00
		Unit Sub Total	**TON**		**170**	**449,414.80**	**$88.71**	**$39,867,366.90**
390132	HOT MIX ASPHALT (TYPE A)		TONN	1	5	22,054.00	$111.60	$2,461,210.00
			TONN	3	1	12,800.00	$79.00	$1,011,200.00
			TONN	4	4	18,050.00	$103.18	$1,862,410.00
			TONN	5	2	5,570.00	$123.61	$688,533.50
			TONN	6	4	10,093.00	$65.80	$664,110.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
390132	HOT MIX ASPHALT (TYPE A)	TONN	9	2	5,690.00	$122.60	$697,570.00
		TONN	10	2	7,360.00	$80.29	$590,924.00
		TONN	11	1	3,490.00	$90.00	$314,100.00
		TONN	12	1	30.00	$150.00	$4,500.00
	Unit Sub Total	**TONN**		**22**	**85,137.00**	**$97.43**	**$8,294,557.50**
	Item Code 390132 Total No. of Proj.			**192**		**Total Amount**	**$48,161,924.40**
390133	HOT MIX ASPHALT (TYPE B)	TON	4	1	2,317.00	$92.00	$213,164.00
		TON	7	15	26,894.50	$76.37	$2,054,044.50
		TON	10	11	6,701.00	$83.67	$560,660.00
		TON	12	1	3.00	$800.00	$2,400.00
	Unit Sub Total	**TON**		**28**	**35,915.50**	**$78.80**	**$2,830,268.50**
390133	HOT MIX ASPHALT (TYPE B)	TONN	7	4	10,860.00	$95.36	$1,035,640.00
		TONN	10	7	23,640.00	$85.41	$2,019,145.00
	Unit Sub Total	**TONN**		**11**	**34,500.00**	**$88.54**	**$3,054,785.00**
	Item Code 390133 Total No. of Proj.			**39**		**Total Amount**	**$5,885,053.50**
390134	HOT MIX ASPHALT (OPEN GRADED)	TON	1	12	5,262.00	$127.91	$673,049.00
		TON	2	1	910.00	$96.00	$87,360.00
		TON	3	2	380.00	$126.08	$47,910.00
		TON	4	2	85,700.00	$72.31	$6,197,100.00
		TON	5	3	19,810.00	$88.77	$1,758,550.00
		TON	6	1	830.00	$110.00	$91,300.00
		TON	9	2	10,850.00	$94.90	$1,029,700.00
		TON	12	3	2,860.00	$82.05	$234,650.00
	Unit Sub Total	**TON**		**26**	**126,602.00**	**$79.93**	**$10,119,619.00**
390134	HOT MIX ASPHALT (OPEN GRADED)	TONN	1	1	2,700.00	$125.00	$337,500.00
		TONN	3	1	4,030.00	$50.00	$201,500.00
		TONN	4	3	23,710.00	$103.52	$2,454,540.00
		TONN	8	1	850.00	$100.00	$85,000.00
	Unit Sub Total	**TONN**		**6**	**31,290.00**	**$98.39**	**$3,078,540.00**
	Item Code 390134 Total No. of Proj.			**32**		**Total Amount**	**$13,198,159.00**
390135	HOT MIX ASPHALT (LEVELING)	TON	3	2	3,035.00	$113.39	$344,130.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
390135	HOT MIX ASPHALT (LEVELING)		TON	7	1	2,340.00	$90.00	$210,600.00
		Unit Sub Total	**TON**		**3**	**5,375.00**	**$103.21**	**$554,730.00**
	Item Code 390135	**Total No. of Proj.**			**3**		**Total Amount**	**$554,730.00**
390136	MINOR HOT MIX ASPHALT		TON	1	4	281.00	$207.44	$58,291.00
			TON	2	9	2,208.00	$129.57	$286,085.00
			TON	3	7	305.00	$127.45	$38,871.40
			TON	4	7	2,039.40	$97.95	$199,758.84
			TON	5	4	299.50	$239.64	$71,772.00
			TON	6	4	367.70	$138.56	$50,950.00
			TON	7	2	21.00	$240.95	$5,060.00
			TON	8	6	326.60	$153.89	$50,261.98
			TON	10	1	99.00	$116.50	$11,533.50
			TON	11	12	2,480.00	$110.38	$273,741.50
			TON	12	1	120.00	$140.00	$16,800.00
		Unit Sub Total	**TON**		**57**	**8,547.20**	**$124.38**	**$1,063,125.22**
390136	MINOR HOT MIX ASPHALT		TONN	2	2	76.00	$505.49	$38,416.86
		Unit Sub Total	**TONN**		**2**	**76.00**	**$505.49**	**$38,416.86**
	Item Code 390136	**Total No. of Proj.**			**59**		**Total Amount**	**$1,101,542.08**
390137	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)		TON	4	5	27,670.00	$107.60	$2,977,250.00
			TON	6	4	28,480.00	$87.88	$2,502,948.00
			TON	7	14	63,340.00	$90.64	$5,741,179.50
			TON	8	2	5,180.00	$88.42	$458,040.00
			TON	10	3	19,780.00	$86.72	$1,715,357.50
			TON	11	1	6,880.00	$104.00	$715,520.00
			TON	12	4	41,900.00	$75.27	$3,153,763.00
		Unit Sub Total	**TON**		**33**	**193,230.00**	**$89.34**	**$17,264,058.00**
390137	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)		TONN	4	2	12,850.00	$107.12	$1,376,480.00
			TONN	7	1	170.00	$68.00	$11,560.00
		Unit Sub Total	**TONN**		**3**	**13,020.00**	**$106.61**	**$1,388,040.00**
	Item Code 390137	**Total No. of Proj.**			**36**		**Total Amount**	**$18,652,098.00**
390138	RUBBERIZED HOT MIX ASPHALT (OPEN GRADED)		TON	3	3	93,130.00	$64.46	$6,003,050.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
390138	RUBBERIZED HOT MIX ASPHALT (OPEN GRADED)	TON	6	3	38,500.00	$85.28	$3,283,125.00
		TON	8	6	156,000.00	$81.26	$12,676,119.00
		TON	11	2	16,210.00	$91.39	$1,481,486.60
		TON	12	2	95,900.00	$71.73	$6,878,750.00
	Unit Sub Total	**TON**		**16**	**399,740.00**	**$75.86**	**$30,322,530.60**
390138	RUBBERIZED HOT MIX ASPHALT (OPEN GRADED)	TONN	3	2	17,020.00	$97.32	$1,656,400.00
		TONN	4	1	6,410.00	$50.00	$320,500.00
		TONN	10	1	730.00	$118.00	$86,140.00
	Unit Sub Total	**TONN**		**4**	**24,160.00**	**$85.39**	**$2,063,040.00**
	Item Code 390138 Total No. of Proj.			**20**		**Total Amount**	**$32,385,570.60**
390139	RUBBERIZED HOT MIX ASPHALT (OPEN GRADED HIGH BINDER)	TON	5	3	35,900.00	$107.38	$3,855,052.00
		TON	6	1	19,600.00	$86.50	$1,695,400.00
	Unit Sub Total	**TON**		**4**	**55,500.00**	**$100.01**	**$5,550,452.00**
	Item Code 390139 Total No. of Proj.			**4**		**Total Amount**	**$5,550,452.00**
390140	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TON	4	7	257,400.00	$91.46	$23,540,720.00
		TON	6	4	78,300.00	$82.48	$6,457,900.00
		TON	7	3	39,210.00	$94.70	$3,713,325.00
		TON	8	1	10,300.00	$87.00	$896,100.00
		TON	10	6	96,430.00	$81.63	$7,871,500.00
		TON	12	1	11,500.00	$60.00	$690,000.00
	Unit Sub Total	**TON**		**22**	**493,140.00**	**$87.54**	**$43,169,545.00**
390140	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TONN	4	3	53,130.00	$121.07	$6,432,560.00
		TONN	7	1	14,000.00	$100.35	$1,404,900.00
		TONN	9	1	23,000.00	$100.00	$2,300,000.00
		TONN	10	2	18,680.00	$101.54	$1,896,800.00
	Unit Sub Total	**TONN**		**7**	**108,810.00**	**$110.60**	**$12,034,260.00**
	Item Code 390140 Total No. of Proj.			**29**		**Total Amount**	**$55,203,805.00**
390141	HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	TON	3	3	52,600.00	$103.14	$5,425,400.00
		TON	5	1	2,200.00	$154.00	$338,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
390141	HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	TON	7	1	9,400.00	$136.00	$1,278,400.00
	Unit Sub Total	**TON**		**5**	**64,200.00**	**$109.70**	**$7,042,600.00**
	Item Code 390141 Total No. of Proj.			**5**		**Total Amount**	**$7,042,600.00**
390142	HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	TON	3	1	6,140.00	$121.00	$742,940.00
		TON	6	2	48,600.00	$120.18	$5,840,600.00
	Unit Sub Total	**TON**		**3**	**54,740.00**	**$120.27**	**$6,583,540.00**
	Item Code 390142 Total No. of Proj.			**3**		**Total Amount**	**$6,583,540.00**
390149	ASPHALTIC EMULSION MEMBRANE (BONDED WEARING COURSE)	TON	1	1	300.00	$456.00	$136,800.00
		TON	3	5	929.00	$849.24	$788,940.00
		TON	5	1	40.00	$910.00	$36,400.00
		TON	6	3	900.00	$1,459.22	$1,313,300.00
		TON	7	1	91.00	$874.00	$79,534.00
		TON	11	1	120.00	$650.00	$78,000.00
	Unit Sub Total	**TON**		**12**	**2,380.00**	**$1,022.26**	**$2,432,974.00**
	Item Code 390149 Total No. of Proj.			**12**		**Total Amount**	**$2,432,974.00**
390156	RUBBERIZED HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	TON	11	1	13,300.00	$117.00	$1,556,100.00
	Unit Sub Total	**TON**		**1**	**13,300.00**	**$117.00**	**$1,556,100.00**
	Item Code 390156 Total No. of Proj.			**1**		**Total Amount**	**$1,556,100.00**
390158	HOT MIX ASPHALT (BONDED WEARING COURSE-OPEN GRADED)	TON	1	1	15,000.00	$100.00	$1,500,000.00
		TON	3	1	6,500.00	$114.00	$741,000.00
	Unit Sub Total	**TON**		**2**	**21,500.00**	**$104.23**	**$2,241,000.00**
	Item Code 390158 Total No. of Proj.			**2**		**Total Amount**	**$2,241,000.00**
390159	RUBBERIZED HOT MIX ASPHALT (BONDED WEARING COURSE-OPEN GRADED)	TON	6	1	24,600.00	$79.60	$1,958,160.00
	Unit Sub Total	**TON**		**1**	**24,600.00**	**$79.60**	**$1,958,160.00**
	Item Code 390159 Total No. of Proj.			**1**		**Total Amount**	**$1,958,160.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
391003	PAVING ASPHALT (PAINT BINDER)	TON	8	1	0.50	$1,200.00	$600.00
	Unit Sub Total	**TON**		**1**	**0.50**	**$1,200.00**	**$600.00**
	Item Code 391003 Total No. of Proj.			**1**		**Total Amount**	**$600.00**
391005	PAVING ASPHALT (BINDER-PAVEMENT REINFORCING FABRIC)	TONN	4	1	170.00	$1.00	$170.00
	Unit Sub Total	**TONN**		**1**	**170.00**	**$1.00**	**$170.00**
	Item Code 391005 Total No. of Proj.			**1**		**Total Amount**	**$170.00**
391007	PAVING ASPHALT (BINDER, GEOSYNTHETIC PAVEMENT INTERLAYER)	TON	1	11	4.00	$1,562.00	$6,248.00
		TON	2	2	28.20	$382.98	$10,800.00
		TON	3	1	8.00	$1,200.00	$9,600.00
		TON	6	2	130.60	$400.11	$52,255.00
		TON	9	1	8.00	$300.00	$2,400.00
	Unit Sub Total	**TON**		**17**	**178.80**	**$454.71**	**$81,303.00**
391007	PAVING ASPHALT (BINDER, GEOSYNTHETIC PAVEMENT INTERLAYER)	TONN	1	1	1.00	$1.00	$1.00
		TONN	3	2	16.10	$555.90	$8,950.00
		TONN	4	1	7.00	$100.00	$700.00
		TONN	11	1	1.00	$1,500.00	$1,500.00
	Unit Sub Total	**TONN**		**5**	**25.10**	**$444.26**	**$11,151.00**
	Item Code 391007 Total No. of Proj.			**22**		**Total Amount**	**$92,454.00**
393001	PAVEMENT REINFORCING FABRIC	M2	4	3	154,370.00	$1.29	$198,790.00
	Unit Sub Total	**M2**		**3**	**154,370.00**	**$1.29**	**$198,790.00**
393001	PAVEMENT REINFORCING FABRIC	SQYD	4	2	427,870.00	$0.98	$420,955.00
	Unit Sub Total	**SQYD**		**2**	**427,870.00**	**$0.98**	**$420,955.00**
	Item Code 393001 Total No. of Proj.			**5**		**Total Amount**	**$619,745.00**
393003	GEOSYNTHETIC PAVEMENT INTERLAYER	LF	1	1	360.00	$2.05	$738.00
	Unit Sub Total	**LF**		**1**	**360.00**	**$2.05**	**$738.00**
393003	GEOSYNTHETIC PAVEMENT INTERLAYER	M2	1	1	330.00	$10.00	$3,300.00
		M2	3	2	12,840.00	$1.68	$21,515.00
		M2	4	2	6,570.00	$3.12	$20,520.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
393003	GEOSYNTHETIC PAVEMENT INTERLAYER	M2	7	1	9,200.00	$2.00	$18,400.00
		M2	11	1	3,570.00	$3.50	$12,495.00
	Unit Sub Total	**M2**		**7**	**32,510.00**	**$2.34**	**$76,230.00**
393003	GEOSYNTHETIC PAVEMENT INTERLAYER	SQYD	1	11	2,892.00	$8.86	$25,626.00
		SQYD	2	2	240.00	$13.00	$3,120.00
		SQYD	3	1	31,000.00	$1.40	$43,400.00
		SQYD	6	2	110,540.00	$1.09	$120,825.00
		SQYD	7	1	123,000.00	$0.80	$98,400.00
		SQYD	9	1	6,940.00	$1.00	$6,940.00
	Unit Sub Total	**SQYD**		**18**	**274,612.00**	**$1.09**	**$298,311.00**
	Item Code 393003 Total No. of Proj.			**26**		**Total Amount**	**$375,279.00**
394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	M2	3	1	25.00	$104.00	$2,600.00
		M2	4	2	4,590.00	$10.44	$47,925.00
		M2	5	1	130.00	$49.25	$6,402.50
		M2	8	1	58.00	$45.00	$2,610.00
	Unit Sub Total	**M2**		**5**	**4,803.00**	**$12.40**	**$59,537.50**
394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	SQFT	9	1	580.00	$20.00	$11,600.00
	Unit Sub Total	**SQFT**		**1**	**580.00**	**$20.00**	**$11,600.00**
394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	SQYD	10	1	1,300.00	$6.00	$7,800.00
	Unit Sub Total	**SQYD**		**1**	**1,300.00**	**$6.00**	**$7,800.00**
	Item Code 394002 Total No. of Proj.			**7**		**Total Amount**	**$78,937.50**
394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	LF	7	1	290.00	$12.00	$3,480.00
	Unit Sub Total	**LF**		**1**	**290.00**	**$12.00**	**$3,480.00**
394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	M	3	1	130.00	$3.50	$455.00
		M	4	1	240.00	$10.00	$2,400.00
		M	10	1	320.00	$15.00	$4,800.00
	Unit Sub Total	**M**		**3**	**690.00**	**$11.09**	**$7,655.00**
	Item Code 394040 Total No. of Proj.			**4**		**Total Amount**	**$11,135.00**
394044	PLACE ASPHALT CONCRETE DIKE (TYPE C)	LF	2	1	50.00	$104.17	$5,208.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394044	PLACE ASPHALT CONCRETE DIKE (TYPE C)	LF	5	1	38.00	$4.00	$152.00
		LF	6	1	38.00	$10.00	$380.00
		LF	8	1	75.00	$27.00	$2,025.00
		LF	10	1	100.00	$6.00	$600.00
	Unit Sub Total	**LF**		**5**	**301.00**	**$27.79**	**$8,365.50**
394044	PLACE ASPHALT CONCRETE DIKE (TYPE C)	M	3	1	30.00	$3.50	$105.00
		M	4	2	710.00	$9.18	$6,520.00
		M	8	1	250.00	$4.50	$1,125.00
	Unit Sub Total	**M**		**4**	**990.00**	**$7.83**	**$7,750.00**
	Item Code 394044 Total No. of Proj.			**9**		**Total Amount**	**$16,115.50**
394046	PLACE ASPHALT CONCRETE DIKE (TYPE D)	M	4	1	46.00	$10.00	$460.00
		M	8	1	7,370.00	$4.50	$33,165.00
	Unit Sub Total	**M**		**2**	**7,416.00**	**$4.53**	**$33,625.00**
	Item Code 394046 Total No. of Proj.			**2**		**Total Amount**	**$33,625.00**
394048	PLACE ASPHALT CONCRETE DIKE (TYPE E)	LF	2	1	3,900.00	$4.76	$18,564.00
		LF	5	1	180.00	$4.00	$720.00
		LF	8	1	2,240.00	$1.00	$2,240.00
	Unit Sub Total	**LF**		**3**	**6,320.00**	**$3.41**	**$21,524.00**
394048	PLACE ASPHALT CONCRETE DIKE (TYPE E)	M	3	1	940.00	$3.50	$3,290.00
		M	4	2	1,610.00	$8.29	$13,340.00
	Unit Sub Total	**M**		**3**	**2,550.00**	**$6.52**	**$16,630.00**
	Item Code 394048 Total No. of Proj.			**6**		**Total Amount**	**$38,154.00**
394049	PLACE ASPHALT CONCRETE DIKE (TYPE F)	LF	2	2	4,490.00	$3.12	$14,021.70
		LF	5	1	200.00	$25.00	$5,000.00
		LF	8	2	355.00	$7.76	$2,755.00
		LF	10	1	550.00	$6.00	$3,300.00
	Unit Sub Total	**LF**		**6**	**5,595.00**	**$4.48**	**$25,076.70**
394049	PLACE ASPHALT CONCRETE DIKE (TYPE F)	M	4	1	88.00	$8.00	$704.00
		M	8	1	3,760.00	$4.50	$16,920.00
	Unit Sub Total	**M**		**2**	**3,848.00**	**$4.58**	**$17,624.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 394049 Total No. of Proj.			**8**		**Total Amount**	**$42,700.70**
394050	RUMBLE STRIP	STA	2	1	330.00	$18.10	$5,973.00
		STA	5	1	903.00	$26.00	$23,478.00
		STA	6	1	310.00	$35.00	$10,850.00
		STA	10	1	48.00	$60.00	$2,880.00
		STA	11	1	350.00	$37.00	$12,950.00
	Unit Sub Total	**STA**		**5**	**1,941.00**	**$28.92**	**$56,131.00**
	Item Code 394050 Total No. of Proj.			**5**		**Total Amount**	**$56,131.00**
394051	SHOULDER RUMBLE STRIP (HMA,ROLLED-IN INDENTATIONS)	M	10	1	18,500.00	$0.30	$5,550.00
	Unit Sub Total	**M**		**1**	**18,500.00**	**$0.30**	**$5,550.00**
394051	SHOULDER RUMBLE STRIP (HMA,ROLLED-IN INDENTATIONS)	STA	6	1	450.00	$12.00	$5,400.00
		STA	10	2	190.00	$53.37	$10,140.00
	Unit Sub Total	**STA**		**3**	**640.00**	**$24.28**	**$15,540.00**
	Item Code 394051 Total No. of Proj.			**4**		**Total Amount**	**$21,090.00**
394053	SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	LF	2	2	4,040.00	$0.92	$3,733.00
		LF	3	1	92,400.00	$0.12	$11,088.00
		LF	4	1	34,900.00	$0.20	$6,980.00
	Unit Sub Total	**LF**		**4**	**131,340.00**	**$0.17**	**$21,801.00**
394053	SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	M	8	1	3,350.00	$1.00	$3,350.00
	Unit Sub Total	**M**		**1**	**3,350.00**	**$1.00**	**$3,350.00**
394053	SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	STA	2	6	3,784.00	$25.19	$95,306.00
		STA	3	4	2,633.00	$11.78	$31,009.00
		STA	4	1	97.00	$72.00	$6,984.00
		STA	5	1	43.00	$100.00	$4,300.00
		STA	6	2	850.00	$25.35	$21,550.00
		STA	8	3	1,319.00	$31.05	$40,960.00
		STA	9	2	259.00	$151.60	$39,265.00
	Unit Sub Total	**STA**		**19**	**8,985.00**	**$26.64**	**$239,374.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 394053 Total No. of Proj.			**24**		**Total Amount**	**$264,525.00**
394054	SHOULDER RUMBLE STRIP (AC, GROUND-IN INDENTATIONS)	LF	2	1	75.00	$44.00	$3,300.00
	Unit Sub Total	**LF**		**1**	**75.00**	**$44.00**	**$3,300.00**
394054	SHOULDER RUMBLE STRIP (AC, GROUND-IN INDENTATIONS)	STA	1	1	390.00	$30.00	$11,700.00
		STA	2	1	39.00	$55.00	$2,145.00
		STA	3	2	4,800.00	$18.67	$89,600.00
		STA	5	4	4,730.00	$14.54	$68,762.00
		STA	8	2	184.00	$38.91	$7,160.00
		STA	9	1	2,250.00	$17.00	$38,250.00
		STA	10	1	26.00	$190.00	$4,940.00
	Unit Sub Total	**STA**		**12**	**12,419.00**	**$17.92**	**$222,557.00**
	Item Code 394054 Total No. of Proj.			**13**		**Total Amount**	**$225,857.00**
394060	DATA CORE	EA	12	1	6.00	$550.00	$3,300.00
	Unit Sub Total	**EA**		**1**	**6.00**	**$550.00**	**$3,300.00**
394060	DATA CORE	LS	1	10	10.00	$1,970.00	$19,700.00
		LS	2	5	5.00	$4,184.00	$20,920.00
		LS	3	5	5.00	$8,350.00	$41,750.00
		LS	4	13	13.00	$4,417.31	$57,425.00
		LS	5	5	5.00	$3,700.00	$18,500.00
		LS	6	11	11.00	$17,640.91	$194,050.00
		LS	7	5	5.00	$3,125.00	$15,625.00
		LS	8	9	9.00	$4,073.28	$36,659.55
		LS	9	3	3.00	$2,000.00	$6,000.00
		LS	10	10	10.00	$4,201.10	$42,011.00
		LS	11	2	2.00	$21,850.00	$43,700.00
		LS	12	4	4.00	$8,400.00	$33,600.00
	Unit Sub Total	**LS**		**82**	**82.00**	**$6,462.69**	**$529,940.55**
	Item Code 394060 Total No. of Proj.			**83**		**Total Amount**	**$533,240.55**
394071	PLACE HOT MIX ASPHALT DIKE	LF	3	1	60.00	$60.00	$3,600.00
		LF	11	10	66,420.00	$1.43	$94,853.60

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**11**	**66,480.00**	**$1.48**	**$98,453.60**
394071	PLACE HOT MIX ASPHALT DIKE		M	6	1	190.00	$15.00	$2,850.00
			M	7	3	2,580.00	$10.80	$27,870.00
			M	11	3	9,000.00	$7.67	$69,000.00
		Unit Sub Total	**M**		**7**	**11,770.00**	**$8.47**	**$99,720.00**
	Item Code 394071	**Total No. of Proj.**			**18**		**Total Amount**	**$198,173.60**
394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)		LF	1	9	5,992.00	$4.74	$28,420.00
			LF	2	8	4,559.00	$5.52	$25,146.50
			LF	3	3	2,209.00	$3.33	$7,350.00
			LF	4	5	570.00	$11.51	$6,560.00
			LF	5	1	40.00	$4.00	$160.00
			LF	6	1	780.00	$3.70	$2,886.00
			LF	7	2	3,110.00	$1.97	$6,134.00
			LF	8	1	500.00	$11.00	$5,500.00
			LF	10	1	310.00	$6.50	$2,015.00
			LF	11	1	75.00	$29.00	$2,175.00
			LF	12	3	3,230.00	$11.33	$36,600.00
		Unit Sub Total	**LF**		**35**	**21,375.00**	**$5.75**	**$122,946.50**
394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)		M	1	3	1,433.00	$6.18	$8,852.50
			M	2	1	620.00	$40.00	$24,800.00
			M	6	4	1,077.00	$9.05	$9,749.00
			M	7	1	600.00	$8.30	$4,980.00
			M	8	1	61.00	$4.00	$244.00
			M	9	1	360.00	$4.00	$1,440.00
			M	10	2	645.00	$8.56	$5,520.00
		Unit Sub Total	**M**		**13**	**4,796.00**	**$11.59**	**$55,585.50**
	Item Code 394073	**Total No. of Proj.**			**48**		**Total Amount**	**$178,532.00**
394074	PLACE HOT MIX ASPHALT DIKE (TYPE C)		LF	1	2	173.00	$33.15	$5,735.00
			LF	2	4	1,269.00	$1.73	$2,199.50
			LF	3	5	1,720.00	$5.25	$9,032.00
			LF	4	5	3,420.00	$8.15	$27,865.00
			LF	5	2	1,230.00	$1.94	$2,382.00
			LF	6	1	280.00	$2.00	$560.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394074	PLACE HOT MIX ASPHALT DIKE (TYPE C)	LF	7	4	1,085.00	$5.28	$5,729.00
		LF	8	3	588.00	$2.12	$1,249.00
		LF	12	4	833.00	$9.37	$7,808.00
	Unit Sub Total	**LF**		**30**	**10,598.00**	**$5.90**	**$62,559.50**
394074	PLACE HOT MIX ASPHALT DIKE (TYPE C)	M	1	2	135.00	$14.77	$1,994.00
		M	2	1	46.00	$50.00	$2,300.00
		M	3	2	218.00	$4.17	$910.00
		M	4	9	1,160.00	$5.41	$6,281.00
		M	5	2	298.00	$9.53	$2,840.00
		M	6	1	120.00	$20.00	$2,400.00
		M	7	1	79.00	$8.30	$655.70
		M	8	2	446.00	$14.12	$6,299.00
		M	9	1	440.00	$3.00	$1,320.00
		M	10	1	26.00	$56.00	$1,456.00
	Unit Sub Total	**M**		**22**	**2,968.00**	**$8.91**	**$26,455.70**
	Item Code 394074 Total No. of Proj.			**52**		**Total Amount**	**$89,015.20**
394075	PLACE HOT MIX ASPHALT DIKE (TYPE D)	LF	1	2	490.00	$14.29	$7,000.00
		LF	2	1	60.00	$1.00	$60.00
		LF	3	1	17,600.00	$1.00	$17,600.00
		LF	4	5	2,990.00	$5.65	$16,900.00
		LF	7	1	20.00	$20.00	$400.00
		LF	8	4	7,420.00	$3.06	$22,700.00
	Unit Sub Total	**LF**		**14**	**28,580.00**	**$2.26**	**$64,660.00**
394075	PLACE HOT MIX ASPHALT DIKE (TYPE D)	M	1	1	240.00	$3.75	$900.00
		M	4	1	4.00	$100.00	$400.00
		M	8	1	1,710.00	$14.50	$24,795.00
		M	10	1	420.00	$4.00	$1,680.00
	Unit Sub Total	**M**		**4**	**2,374.00**	**$11.70**	**$27,775.00**
	Item Code 394075 Total No. of Proj.			**18**		**Total Amount**	**$92,435.00**
394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	LF	1	5	1,606.00	$8.38	$13,464.00
		LF	2	8	35,950.00	$1.54	$55,241.60
		LF	3	8	24,860.00	$1.44	$35,808.50
		LF	4	5	81,535.00	$1.90	$154,590.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	LF	5	2	632.00	$4.56	$2,880.00
		LF	6	1	1,010.00	$2.00	$2,020.00
		LF	7	2	20,080.00	$1.15	$23,110.00
		LF	8	2	7,240.00	$1.79	$12,988.50
		LF	9	1	6,300.00	$2.50	$15,750.00
		LF	10	2	1,140.00	$7.21	$8,220.00
		LF	12	1	610.00	$17.00	$10,370.00
	Unit Sub Total	**LF**		**37**	**180,963.00**	**$1.85**	**$334,442.60**
394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	M	1	2	641.00	$5.63	$3,609.50
		M	3	3	2,240.00	$5.41	$12,110.00
		M	4	7	14,980.00	$3.97	$59,476.50
		M	5	2	800.00	$9.44	$7,550.00
		M	6	1	2,560.00	$2.50	$6,400.00
		M	8	2	2,490.00	$6.99	$17,415.00
		M	9	2	8,250.00	$4.50	$37,090.00
		M	10	3	4,135.00	$5.18	$21,425.00
	Unit Sub Total	**M**		**22**	**36,096.00**	**$4.57**	**$165,076.00**
	Item Code 394076 **Total No. of Proj.**			**59**		**Total Amount**	**$499,518.60**
394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	LF	1	5	2,460.00	$9.35	$22,990.00
		LF	2	9	4,176.00	$6.02	$25,132.10
		LF	3	8	6,632.00	$2.42	$16,050.40
		LF	4	7	15,230.00	$2.16	$32,863.50
		LF	5	3	10,530.00	$2.17	$22,862.00
		LF	6	4	612.00	$13.01	$7,960.00
		LF	7	5	1,780.00	$5.64	$10,035.00
		LF	8	5	8,970.00	$2.25	$20,227.10
		LF	12	4	865.00	$9.54	$8,252.00
	Unit Sub Total	**LF**		**50**	**51,255.00**	**$3.25**	**$166,372.10**
394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	M	1	2	55.00	$13.95	$767.00
		M	2	1	160.00	$50.00	$8,000.00
		M	3	2	345.00	$4.04	$1,395.00
		M	4	9	5,535.00	$3.88	$21,459.50
		M	5	3	2,500.00	$8.90	$22,240.00
		M	6	1	40.00	$20.00	$800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	M	7	1	840.00	$8.30	$6,972.00
		M	8	2	1,020.00	$13.37	$13,635.00
		M	9	1	4,930.00	$3.25	$16,022.50
		M	10	2	302.00	$6.26	$1,892.00
	Unit Sub Total	**M**		**24**	**15,727.00**	**$5.93**	**$93,183.00**
	Item Code 394077 Total No. of Proj.			**74**		**Total Amount**	**$259,555.10**
394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	M2	1	4	778.00	$40.49	$31,500.00
		M2	2	1	38.00	$26.00	$988.00
		M2	3	3	3,785.00	$14.92	$56,470.00
		M2	4	4	667.00	$35.19	$23,475.00
		M2	5	2	133.00	$50.00	$6,650.00
		M2	6	5	3,094.00	$19.43	$60,116.00
		M2	7	2	888.00	$21.28	$18,900.00
		M2	8	2	91.00	$149.78	$13,630.00
		M2	9	1	510.00	$100.00	$51,000.00
		M2	10	4	3,083.00	$4.22	$13,002.00
		M2	11	2	658.00	$16.85	$11,090.00
	Unit Sub Total	**M2**		**30**	**13,725.00**	**$20.90**	**$286,821.00**
394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	1	13	1,226.50	$21.15	$25,945.25
		SQYD	2	12	3,267.40	$20.30	$66,338.99
		SQYD	3	11	5,727.00	$16.31	$93,399.00
		SQYD	4	7	2,564.00	$26.36	$67,595.00
		SQYD	5	3	84.00	$157.98	$13,270.00
		SQYD	6	4	2,105.00	$11.14	$23,450.00
		SQYD	7	6	459.00	$54.33	$24,936.00
		SQYD	8	3	392.00	$25.15	$9,860.00
		SQYD	9	1	14.00	$100.00	$1,400.00
		SQYD	10	2	40.20	$59.20	$2,380.00
		SQYD	11	6	6,539.00	$11.53	$75,405.90
		SQYD	12	2	780.00	$33.28	$25,960.00
	Unit Sub Total	**SQYD**		**70**	**23,198.10**	**$18.53**	**$429,940.14**
	Item Code 394090 Total No. of Proj.			**100**		**Total Amount**	**$716,761.14**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394095	ROADSIDE PAVING (MISCELLANEOUS AREAS)	SQYD	5	2	582.00	$74.61	$43,421.00
		SQYD	7	1	180.00	$50.00	$9,000.00
		SQYD	11	1	650.00	$39.97	$25,980.50
		SQYD	12	1	180.00	$35.00	$6,300.00
	Unit Sub Total	**SQYD**		**5**	**1,592.00**	**$53.20**	**$84,701.50**
	Item Code 394095 Total No. of Proj.			**5**		**Total Amount**	**$84,701.50**
395000	LIQUID ASPHALT (PRIME COAT)	TON	8	5	63.60	$649.03	$41,278.00
	Unit Sub Total	**TON**		**5**	**63.60**	**$649.03**	**$41,278.00**
395000	LIQUID ASPHALT (PRIME COAT)	TONN	8	1	70.00	$850.00	$59,500.00
	Unit Sub Total	**TONN**		**1**	**70.00**	**$850.00**	**$59,500.00**
	Item Code 395000 Total No. of Proj.			**6**		**Total Amount**	**$100,778.00**
395501	LIQUID ASPHALT, MC-70 (PRIME COAT)	TONN	8	1	190.00	$690.00	$131,100.00
	Unit Sub Total	**TONN**		**1**	**190.00**	**$690.00**	**$131,100.00**
	Item Code 395501 Total No. of Proj.			**1**		**Total Amount**	**$131,100.00**
397001	ASPHALTIC EMULSION (PAINT BINDER)	TON	3	2	161.00	$226.09	$36,400.00
		TON	4	1	40.00	$1.00	$40.00
	Unit Sub Total	**TON**		**3**	**201.00**	**$181.29**	**$36,440.00**
397001	ASPHALTIC EMULSION (PAINT BINDER)	TONN	8	1	310.00	$690.00	$213,900.00
		TONN	10	1	60.00	$1.00	$60.00
	Unit Sub Total	**TONN**		**2**	**370.00**	**$578.27**	**$213,960.00**
	Item Code 397001 Total No. of Proj.			**5**		**Total Amount**	**$250,400.00**
397005	TACK COAT	TON	1	13	19.20	$864.19	$16,592.50
		TON	2	9	151.50	$641.16	$97,136.00
		TON	3	7	220.80	$556.61	$122,900.00
		TON	4	21	2,669.40	$228.15	$609,015.25
		TON	5	13	754.10	$378.89	$285,720.50
		TON	6	21	1,222.10	$422.99	$516,939.80
		TON	7	9	1,526.00	$594.17	$906,700.00
		TON	8	20	1,464.40	$497.63	$728,724.90
		TON	9	3	133.00	$179.58	$23,884.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
397005	TACK COAT	TON	10	10	730.10	$94.23	$68,798.00
		TON	11	8	189.40	$764.74	$144,841.00
		TON	12	14	549.00	$485.73	$266,664.00
	Unit Sub Total	**TON**		**148**	**9,629.00**	**$393.39**	**$3,787,915.95**
397005	TACK COAT	TONN	1	1	25.00	$780.00	$19,500.00
		TONN	4	6	476.00	$664.79	$316,440.00
		TONN	5	2	44.00	$1,025.00	$45,100.00
		TONN	6	4	444.00	$427.07	$189,620.00
		TONN	7	2	3.20	$842.81	$2,697.00
		TONN	8	1	29.00	$550.00	$15,950.00
		TONN	10	8	90.80	$446.21	$40,516.00
		TONN	11	3	209.90	$995.86	$209,030.00
	Unit Sub Total	**TONN**		**27**	**1,321.90**	**$634.58**	**$838,853.00**
	Item Code 397005 Total No. of Proj.			**175**		**Total Amount**	**$4,626,768.95**
400050	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT	CY	4	1	500.00	$275.00	$137,500.00
		CY	6	1	400.00	$323.00	$129,200.00
	Unit Sub Total	**CY**		**2**	**900.00**	**$296.33**	**$266,700.00**
	Item Code 400050 Total No. of Proj.			**2**		**Total Amount**	**$266,700.00**
400060	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT)	LF	6	1	68.00	$37.00	$2,516.00
	Unit Sub Total	**LF**		**1**	**68.00**	**$37.00**	**$2,516.00**
	Item Code 400060 Total No. of Proj.			**1**		**Total Amount**	**$2,516.00**
400065	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE E)	LF	4	1	120.00	$40.00	$4,800.00
	Unit Sub Total	**LF**		**1**	**120.00**	**$40.00**	**$4,800.00**
	Item Code 400065 Total No. of Proj.			**1**		**Total Amount**	**$4,800.00**
401000	CONCRETE PAVEMENT	CY	2	2	26,810.00	$146.75	$3,934,450.00
		CY	6	1	120,000.00	$98.00	$11,760,000.00
		CY	7	3	10,420.00	$182.82	$1,905,000.00
		CY	11	1	1,760.00	$285.00	$501,600.00
		CY	12	1	29,800.00	$150.00	$4,470,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**CY**		**8**	**188,790.00**	**$119.56**	**$22,571,050.00**
401000	CONCRETE PAVEMENT	M3	4	3	13,257.00	$281.73	$3,734,900.00
		M3	6	2	65,830.00	$114.72	$7,551,730.00
		M3	7	4	51,450.00	$172.21	$8,860,150.00
		M3	8	3	45,840.00	$190.17	$8,717,400.00
		M3	11	2	30,550.00	$190.52	$5,820,500.00
	Unit Sub Total	**M3**		**14**	**206,927.00**	**$167.62**	**$34,684,680.00**
	Item Code 401000 Total No. of Proj.			**22**		**Total Amount**	**$57,255,730.00**
401050	JOINTED PLAIN CONCRETE PAVEMENT	CY	8	1	724.00	$170.00	$123,080.00
	Unit Sub Total	**CY**		**1**	**724.00**	**$170.00**	**$123,080.00**
401050	JOINTED PLAIN CONCRETE PAVEMENT	M3	11	1	140.00	$500.00	$70,000.00
	Unit Sub Total	**M3**		**1**	**140.00**	**$500.00**	**$70,000.00**
	Item Code 401050 Total No. of Proj.			**2**		**Total Amount**	**$193,080.00**
401066	CONCRETE PAVEMENT (RAMP TERMINI)	M3	7	1	170.00	$250.00	$42,500.00
		M3	8	2	1,280.00	$230.78	$295,400.00
	Unit Sub Total	**M3**		**3**	**1,450.00**	**$233.03**	**$337,900.00**
	Item Code 401066 Total No. of Proj.			**3**		**Total Amount**	**$337,900.00**
401082	SHOULDER RUMBLE STRIP (PCC, GROUND-IN INDENTATIONS)	STA	2	1	180.00	$55.00	$9,900.00
	Unit Sub Total	**STA**		**1**	**180.00**	**$55.00**	**$9,900.00**
	Item Code 401082 Total No. of Proj.			**1**		**Total Amount**	**$9,900.00**
401102	CONCRETE PAVEMENT (WEIGH-IN-MOTION)	CY	2	1	340.00	$260.00	$88,400.00
	Unit Sub Total	**CY**		**1**	**340.00**	**$260.00**	**$88,400.00**
	Item Code 401102 Total No. of Proj.			**1**		**Total Amount**	**$88,400.00**
401108	REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	CY	2	1	18,900.00	$353.00	$6,671,700.00
		CY	3	2	4,690.00	$408.96	$1,918,000.00
		CY	4	5	5,580.00	$530.04	$2,957,640.00
		CY	6	4	2,220.00	$616.77	$1,369,220.00
		CY	7	6	11,538.00	$408.53	$4,713,670.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
401108	REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	CY	12	3	528.00	$560.61	$296,000.00
	Unit Sub Total	**CY**		**21**	**43,456.00**	**$412.51**	**$17,926,230.00**
401108	REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	M3	4	3	943.00	$704.14	$664,000.00
		M3	8	1	37,800.00	$315.00	$11,907,000.00
	Unit Sub Total	**M3**		**4**	**38,743.00**	**$324.47**	**$12,571,000.00**
	Item Code 401108 Total No. of Proj.			**25**		**Total Amount**	**$30,497,230.00**
404092	SEAL PAVEMENT JOINT	LF	2	3	104,800.00	$3.17	$331,882.50
		LF	4	2	4,924.00	$9.19	$45,264.00
		LF	6	1	422,000.00	$3.25	$1,371,500.00
		LF	7	6	64,260.00	$7.02	$450,954.00
		LF	8	1	3,000.00	$4.00	$12,000.00
		LF	11	1	8,570.00	$2.30	$19,711.00
		LF	12	1	103,000.00	$1.50	$154,500.00
	Unit Sub Total	**LF**		**15**	**710,554.00**	**$3.36**	**$2,385,811.50**
404092	SEAL PAVEMENT JOINT	M	4	3	6,279.00	$20.21	$126,910.00
		M	6	2	130,310.00	$9.82	$1,279,205.00
		M	7	4	65,390.00	$13.09	$855,630.00
		M	8	3	111,490.00	$8.10	$903,200.00
		M	11	3	69,650.00	$3.12	$217,360.00
	Unit Sub Total	**M**		**15**	**383,119.00**	**$8.83**	**$3,382,305.00**
	Item Code 404092 Total No. of Proj.			**30**		**Total Amount**	**$5,768,116.50**
404094	SEAL LONGITUDINAL ISOLATION JOINT	LF	2	2	82,100.00	$1.53	$125,700.00
		LF	7	3	6,430.00	$14.26	$91,696.00
		LF	8	1	1,550.00	$18.00	$27,900.00
		LF	11	1	3,370.00	$8.50	$28,645.00
		LF	12	1	21,700.00	$3.00	$65,100.00
	Unit Sub Total	**LF**		**8**	**115,150.00**	**$2.94**	**$339,041.00**
404094	SEAL LONGITUDINAL ISOLATION JOINT	M	4	1	7,700.00	$13.00	$100,100.00
		M	6	1	140.00	$16.00	$2,240.00
		M	7	4	38,330.00	$23.47	$899,750.00
		M	8	3	32,940.00	$8.17	$269,280.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
404094	SEAL LONGITUDINAL ISOLATION JOINT	M	11	1	1,580.00	$17.00	$26,860.00
	Unit Sub Total	**M**		**10**	**80,690.00**	**$16.09**	**$1,298,230.00**
	Item Code 404094 Total No. of Proj.			**18**		**Total Amount**	**$1,637,271.00**
405030	PORTLAND CEMENT CONCRETE BASE	CY	4	1	1,170.00	$170.00	$198,900.00
	Unit Sub Total	**CY**		**1**	**1,170.00**	**$170.00**	**$198,900.00**
	Item Code 405030 Total No. of Proj.			**1**		**Total Amount**	**$198,900.00**
406001	TIE BAR	EA	7	1	27,700.00	$8.00	$221,600.00
	Unit Sub Total	**EA**		**1**	**27,700.00**	**$8.00**	**$221,600.00**
	Item Code 406001 Total No. of Proj.			**1**		**Total Amount**	**$221,600.00**
406003	TIE BAR (DRILL AND BOND)	EA	7	1	4,690.00	$13.00	$60,970.00
		EA	12	1	220.00	$13.00	$2,860.00
	Unit Sub Total	**EA**		**2**	**4,910.00**	**$13.00**	**$63,830.00**
	Item Code 406003 Total No. of Proj.			**2**		**Total Amount**	**$63,830.00**
406050	DOWEL BAR (DRILL AND BOND)	EA	4	1	3,400.00	$21.00	$71,400.00
		EA	7	2	26,560.00	$10.84	$287,790.00
		EA	12	1	400.00	$25.00	$10,000.00
	Unit Sub Total	**EA**		**4**	**30,360.00**	**$12.16**	**$369,190.00**
	Item Code 406050 Total No. of Proj.			**4**		**Total Amount**	**$369,190.00**
406100	DOWEL BAR RETROFIT	EA	3	1	61,200.00	$60.00	$3,672,000.00
	Unit Sub Total	**EA**		**1**	**61,200.00**	**$60.00**	**$3,672,000.00**
	Item Code 406100 Total No. of Proj.			**1**		**Total Amount**	**$3,672,000.00**
413111	REPAIR SPALLED JOINTS	M2	4	2	128.50	$599.38	$77,020.00
		M2	11	1	5.00	$1,700.00	$8,500.00
	Unit Sub Total	**M2**		**3**	**133.50**	**$640.60**	**$85,520.00**
413111	REPAIR SPALLED JOINTS	SQYD	3	2	54.00	$1,546.30	$83,500.00
		SQYD	8	1	18.00	$100.00	$1,800.00
	Unit Sub Total	**SQYD**		**3**	**72.00**	**$1,184.72**	**$85,300.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 413111 Total No. of Proj.			**6**		**Total Amount**	**$170,820.00**
413115	SEAL JOINT (EXISTING CONCRETE PAVEMENT)	LF	3	2	142,000.00	$1.53	$217,500.00
		LF	7	1	298,000.00	$2.11	$628,780.00
	Unit Sub Total	**LF**		**3**	**440,000.00**	**$1.92**	**$846,280.00**
	Item Code 413115 Total No. of Proj.			**3**		**Total Amount**	**$846,280.00**
414091	SEAL LONGITUDINAL JOINT	M	4	1	3,720.00	$13.00	$48,360.00
	Unit Sub Total	**M**		**1**	**3,720.00**	**$13.00**	**$48,360.00**
	Item Code 414091 Total No. of Proj.			**1**		**Total Amount**	**$48,360.00**
415101	CRACK EXISTING CONCRETE PAVEMENT	M2	4	2	142,740.00	$0.63	$89,345.00
	Unit Sub Total	**M2**		**2**	**142,740.00**	**$0.63**	**$89,345.00**
415101	CRACK EXISTING CONCRETE PAVEMENT	SQYD	4	1	184,000.00	$0.42	$77,280.00
		SQYD	6	1	3,050.00	$2.78	$8,479.00
		SQYD	7	1	102,000.00	$0.75	$76,500.00
	Unit Sub Total	**SQYD**		**3**	**289,050.00**	**$0.56**	**$162,259.00**
	Item Code 415101 Total No. of Proj.			**5**		**Total Amount**	**$251,604.00**
416101	PAVEMENT TRANSITION TAPER	M2	4	1	1,470.00	$35.00	$51,450.00
	Unit Sub Total	**M2**		**1**	**1,470.00**	**$35.00**	**$51,450.00**
416101	PAVEMENT TRANSITION TAPER	SQYD	3	1	1,680.00	$14.00	$23,520.00
	Unit Sub Total	**SQYD**		**1**	**1,680.00**	**$14.00**	**$23,520.00**
	Item Code 416101 Total No. of Proj.			**2**		**Total Amount**	**$74,970.00**
420102	GROOVE EXISTING CONCRETE PAVEMENT	M2	4	1	16,400.00	$5.00	$82,000.00
	Unit Sub Total	**M2**		**1**	**16,400.00**	**$5.00**	**$82,000.00**
420102	GROOVE EXISTING CONCRETE PAVEMENT	SQYD	12	2	229,470.00	$1.76	$403,390.00
	Unit Sub Total	**SQYD**		**2**	**229,470.00**	**$1.76**	**$403,390.00**
	Item Code 420102 Total No. of Proj.			**3**		**Total Amount**	**$485,390.00**
420201	GRIND EXISTING CONCRETE PAVEMENT	M2	4	4	5,760.00	$28.50	$164,160.00
		M2	7	1	1,860.00	$12.00	$22,320.00
		M2	8	1	192,000.00	$4.72	$906,240.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
420201	GRIND EXISTING CONCRETE PAVEMENT	M2	11	1	1,870.00	$6.00	$11,220.00
	Unit Sub Total	**M2**		**7**	**201,490.00**	**$5.48**	**$1,103,940.00**
420201	GRIND EXISTING CONCRETE PAVEMENT	SQYD	2	1	167,000.00	$3.10	$517,700.00
		SQYD	3	4	412,670.00	$3.88	$1,602,213.70
		SQYD	4	1	164,000.00	$4.35	$713,400.00
		SQYD	6	5	1,563,000.00	$3.15	$4,918,400.00
		SQYD	7	6	1,148,400.00	$3.25	$3,731,720.00
		SQYD	8	1	2,070.00	$5.00	$10,350.00
		SQYD	11	1	4,470.00	$7.00	$31,290.00
		SQYD	12	2	8,100.00	$6.43	$52,120.00
	Unit Sub Total	**SQYD**		**21**	**3,469,710.00**	**$3.34**	**$11,577,193.70**
	Item Code 420201 **Total No. of Proj.**			**28**		**Total Amount**	**$12,681,133.70**
490380	SHEET PILING	SQFT	7	1	352.00	$100.00	$35,200.00
	Unit Sub Total	**SQFT**		**1**	**352.00**	**$100.00**	**$35,200.00**
	Item Code 490380 **Total No. of Proj.**			**1**		**Total Amount**	**$35,200.00**
490505	FURNISH STEEL PILING (HP 250 X 62)	M	2	1	278.00	$75.00	$20,850.00
		M	8	1	1,658.00	$63.00	$104,454.00
		M	11	1	264.00	$80.00	$21,120.00
	Unit Sub Total	**M**		**3**	**2,200.00**	**$66.56**	**$146,424.00**
	Item Code 490505 **Total No. of Proj.**			**3**		**Total Amount**	**$146,424.00**
490506	DRIVE STEEL PILE (HP 250 X 62)	EA	2	1	38.00	$3,200.00	$121,600.00
		EA	8	1	136.00	$700.00	$95,200.00
		EA	11	1	8.00	$2,900.00	$23,200.00
	Unit Sub Total	**EA**		**3**	**182.00**	**$1,318.68**	**$240,000.00**
	Item Code 490506 **Total No. of Proj.**			**3**		**Total Amount**	**$240,000.00**
490511	FURNISH STEEL PILING (HP 250 X 85)	M	3	1	377.00	$110.00	$41,470.00
		M	8	1	1,891.00	$85.00	$160,735.00
		M	10	1	7,537.00	$106.00	$798,922.00
	Unit Sub Total	**M**		**3**	**9,805.00**	**$102.10**	**$1,001,127.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 490511 Total No. of Proj.			**3**		**Total Amount**	**$1,001,127.00**
490512	DRIVE STEEL PILE (HP 250 X 85)	EA	3	1	24.00	$2,500.00	$60,000.00
		EA	8	1	161.00	$700.00	$112,700.00
		EA	10	1	420.00	$745.00	$312,900.00
	Unit Sub Total	**EA**		**3**	**605.00**	**$802.64**	**$485,600.00**
	Item Code 490512 Total No. of Proj.			**3**		**Total Amount**	**$485,600.00**
490520	FURNISH STEEL PILING (HP 12 X 84)	LF	11	1	3,661.00	$36.00	$131,796.00
	Unit Sub Total	**LF**		**1**	**3,661.00**	**$36.00**	**$131,796.00**
	Item Code 490520 Total No. of Proj.			**1**		**Total Amount**	**$131,796.00**
490521	DRIVE STEEL PILE (HP 12 X 84)	EA	11	1	96.00	$1,135.00	$108,960.00
	Unit Sub Total	**EA**		**1**	**96.00**	**$1,135.00**	**$108,960.00**
	Item Code 490521 Total No. of Proj.			**1**		**Total Amount**	**$108,960.00**
490538	FURNISH STEEL PILING (HP 14 X 117)	LF	6	1	3,681.00	$55.00	$202,455.00
	Unit Sub Total	**LF**		**1**	**3,681.00**	**$55.00**	**$202,455.00**
	Item Code 490538 Total No. of Proj.			**1**		**Total Amount**	**$202,455.00**
490539	DRIVE STEEL PILE (HP 14 X 117)	EA	6	1	84.00	$2,450.00	$205,800.00
	Unit Sub Total	**EA**		**1**	**84.00**	**$2,450.00**	**$205,800.00**
	Item Code 490539 Total No. of Proj.			**1**		**Total Amount**	**$205,800.00**
490566	FURNISH STEEL PILING (HP 360 X 132)	M	8	1	10,532.00	$131.00	$1,379,692.00
		M	11	1	4,500.00	$145.00	$652,500.00
	Unit Sub Total	**M**		**2**	**15,032.00**	**$135.19**	**$2,032,192.00**
	Item Code 490566 Total No. of Proj.			**2**		**Total Amount**	**$2,032,192.00**
490567	DRIVE STEEL PILE (HP 360 X 132)	EA	8	1	781.00	$800.00	$624,800.00
		EA	11	1	232.00	$1,600.00	$371,200.00
	Unit Sub Total	**EA**		**2**	**1,013.00**	**$983.22**	**$996,000.00**
	Item Code 490567 Total No. of Proj.			**2**		**Total Amount**	**$996,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
490595	108" PERMANENT STEEL CASING	LF	4	1	43.00	$1,250.00	$53,750.00
	Unit Sub Total	**LF**		**1**	**43.00**	**$1,250.00**	**$53,750.00**
	Item Code 490595 Total No. of Proj.			**1**		**Total Amount**	**$53,750.00**
490601	16" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	4	1	195.00	$72.00	$14,040.00
	Unit Sub Total	**LF**		**1**	**195.00**	**$72.00**	**$14,040.00**
	Item Code 490601 Total No. of Proj.			**1**		**Total Amount**	**$14,040.00**
490603	24" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	2	1	42.00	$125.00	$5,250.00
		LF	4	3	2,226.00	$48.76	$108,540.00
		LF	7	1	168.00	$95.00	$15,960.00
		LF	12	2	607.00	$221.43	$134,410.00
	Unit Sub Total	**LF**		**7**	**3,043.00**	**$86.81**	**$264,160.00**
	Item Code 490603 Total No. of Proj.			**7**		**Total Amount**	**$264,160.00**
490604	30" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	4	1	5,000.00	$125.00	$625,000.00
		LF	5	2	727.00	$387.31	$281,575.00
	Unit Sub Total	**LF**		**3**	**5,727.00**	**$158.30**	**$906,575.00**
	Item Code 490604 Total No. of Proj.			**3**		**Total Amount**	**$906,575.00**
490607	48" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	6	1	1,862.00	$655.00	$1,219,610.00
	Unit Sub Total	**LF**		**1**	**1,862.00**	**$655.00**	**$1,219,610.00**
	Item Code 490607 Total No. of Proj.			**1**		**Total Amount**	**$1,219,610.00**
490608	54" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	5	1	216.00	$900.00	$194,400.00
	Unit Sub Total	**LF**		**1**	**216.00**	**$900.00**	**$194,400.00**
	Item Code 490608 Total No. of Proj.			**1**		**Total Amount**	**$194,400.00**
490610	66" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	5	1	216.00	$1,100.00	$237,600.00
	Unit Sub Total	**LF**		**1**	**216.00**	**$1,100.00**	**$237,600.00**
	Item Code 490610 Total No. of Proj.			**1**		**Total Amount**	**$237,600.00**
490615	18" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	5	1	392.00	$110.00	$43,120.00
	Unit Sub Total	**LF**		**1**	**392.00**	**$110.00**	**$43,120.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 490615 Total No. of Proj.			**1**		**Total Amount**	**$43,120.00**
490620	108" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	4	1	43.00	$1,200.00	$51,600.00
	Unit Sub Total	**LF**		**1**	**43.00**	**$1,200.00**	**$51,600.00**
	Item Code 490620 Total No. of Proj.			**1**		**Total Amount**	**$51,600.00**
490655	400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	4	1	1,460.00	$112.00	$163,520.00
		M	5	1	30.50	$802.00	$24,461.00
		M	7	1	7,530.00	$93.00	$700,290.00
		M	8	1	955.00	$317.00	$302,735.00
	Unit Sub Total	**M**		**4**	**9,975.50**	**$119.39**	**$1,191,006.00**
	Item Code 490655 Total No. of Proj.			**4**		**Total Amount**	**$1,191,006.00**
490657	600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	1	1	348.00	$1,200.00	$417,600.00
		M	2	1	429.00	$4,050.00	$1,737,450.00
		M	3	1	108.00	$160.00	$17,280.00
		M	4	2	185.00	$191.22	$35,375.00
		M	5	1	981.00	$180.00	$176,580.00
		M	7	3	5,814.00	$187.66	$1,091,051.00
		M	8	2	549.00	$294.22	$161,526.00
	Unit Sub Total	**M**		**11**	**8,414.00**	**$432.24**	**$3,636,862.00**
	Item Code 490657 Total No. of Proj.			**11**		**Total Amount**	**$3,636,862.00**
490658	750 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	4	1	166.00	$800.00	$132,800.00
	Unit Sub Total	**M**		**1**	**166.00**	**$800.00**	**$132,800.00**
	Item Code 490658 Total No. of Proj.			**1**		**Total Amount**	**$132,800.00**
490661	1.2 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	1	1	293.00	$2,150.00	$629,950.00
		M	4	1	1,410.00	$1,200.00	$1,692,000.00
		M	11	1	77.00	$1,100.00	$84,700.00
	Unit Sub Total	**M**		**3**	**1,780.00**	**$1,352.05**	**$2,406,650.00**
	Item Code 490661 Total No. of Proj.			**3**		**Total Amount**	**$2,406,650.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
490663	1.5 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	4	1	16.00	$6,000.00	$96,000.00
		M	7	1	22.00	$1,200.00	$26,400.00
		M	11	1	219.00	$1,200.00	$262,800.00
	Unit Sub Total	**M**		**3**	**257.00**	**$1,498.83**	**$385,200.00**
	Item Code 490663 Total No. of Proj.			**3**		**Total Amount**	**$385,200.00**
490665	1.8 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	4	2	282.00	$1,758.16	$495,800.00
		M	7	2	434.00	$2,693.13	$1,168,820.00
		M	11	1	75.00	$1,600.00	$120,000.00
	Unit Sub Total	**M**		**5**	**791.00**	**$2,256.16**	**$1,784,620.00**
	Item Code 490665 Total No. of Proj.			**5**		**Total Amount**	**$1,784,620.00**
490667	2.0 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	7	1	69.00	$1,500.00	$103,500.00
	Unit Sub Total	**M**		**1**	**69.00**	**$1,500.00**	**$103,500.00**
	Item Code 490667 Total No. of Proj.			**1**		**Total Amount**	**$103,500.00**
490669	2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	8	1	91.00	$1,800.00	$163,800.00
		M	11	1	117.00	$1,800.00	$210,600.00
	Unit Sub Total	**M**		**2**	**208.00**	**$1,800.00**	**$374,400.00**
	Item Code 490669 Total No. of Proj.			**2**		**Total Amount**	**$374,400.00**
490671	2.4 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	4	1	1,912.00	$2,500.00	$4,780,000.00
		M	8	1	450.00	$2,000.00	$900,000.00
		M	11	1	26.00	$2,300.00	$59,800.00
	Unit Sub Total	**M**		**3**	**2,388.00**	**$2,403.60**	**$5,739,800.00**
	Item Code 490671 Total No. of Proj.			**3**		**Total Amount**	**$5,739,800.00**
490676	600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	M	3	1	137.00	$150.00	$20,550.00
	Unit Sub Total	**M**		**1**	**137.00**	**$150.00**	**$20,550.00**
	Item Code 490676 Total No. of Proj.			**1**		**Total Amount**	**$20,550.00**
490677	1.2 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	M	11	1	72.00	$3,000.00	$216,000.00
	Unit Sub Total	**M**		**1**	**72.00**	**$3,000.00**	**$216,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 490677 Total No. of Proj.			**1**		**Total Amount**	**$216,000.00**
490679	1.8 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	M	11	1	47.00	$40,000.00	$1,880,000.00
	Unit Sub Total	**M**		**1**	**47.00**	**$40,000.00**	**$1,880,000.00**
	Item Code 490679 Total No. of Proj.			**1**		**Total Amount**	**$1,880,000.00**
490681	2.4 M CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	M	11	1	31.00	$60,000.00	$1,860,000.00
	Unit Sub Total	**M**		**1**	**31.00**	**$60,000.00**	**$1,860,000.00**
	Item Code 490681 Total No. of Proj.			**1**		**Total Amount**	**$1,860,000.00**
490683	24" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	LF	4	3	1,979.00	$58.11	$114,990.00
		LF	5	1	675.00	$675.00	$455,625.00
	Unit Sub Total	**LF**		**4**	**2,654.00**	**$215.00**	**$570,615.00**
	Item Code 490683 Total No. of Proj.			**4**		**Total Amount**	**$570,615.00**
490684	48" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	LF	5	1	330.00	$575.00	$189,750.00
	Unit Sub Total	**LF**		**1**	**330.00**	**$575.00**	**$189,750.00**
	Item Code 490684 Total No. of Proj.			**1**		**Total Amount**	**$189,750.00**
490685	60" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	LF	5	1	590.00	$550.00	$324,500.00
	Unit Sub Total	**LF**		**1**	**590.00**	**$550.00**	**$324,500.00**
	Item Code 490685 Total No. of Proj.			**1**		**Total Amount**	**$324,500.00**
490700	FURNISH PILING (CLASS 900) (ALTERNATIVE W)	M	4	2	2,869.00	$133.75	$383,730.00
		M	5	1	265.00	$160.00	$42,400.00
	Unit Sub Total	**M**		**3**	**3,134.00**	**$135.97**	**$426,130.00**
	Item Code 490700 Total No. of Proj.			**3**		**Total Amount**	**$426,130.00**
490701	DRIVE PILE (CLASS 900) (ALTERNATIVE W)	EA	4	2	176.00	$1,181.82	$208,000.00
		EA	5	1	32.00	$625.00	$20,000.00
	Unit Sub Total	**EA**		**3**	**208.00**	**$1,096.15**	**$228,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 490701 Total No. of Proj.			**3**		**Total Amount**	**$228,000.00**
490736	FURNISH PILING (CLASS 90)	LF	4	1	850.00	$35.00	$29,750.00
	Unit Sub Total	**LF**		**1**	**850.00**	**$35.00**	**$29,750.00**
	Item Code 490736 Total No. of Proj.			**1**		**Total Amount**	**$29,750.00**
490737	DRIVE PILE (CLASS 90)	EA	4	1	15.00	$1,100.00	$16,500.00
	Unit Sub Total	**EA**		**1**	**15.00**	**$1,100.00**	**$16,500.00**
	Item Code 490737 Total No. of Proj.			**1**		**Total Amount**	**$16,500.00**
490740	FURNISH PILING (CLASS 90) (ALTERNATIVE V)	LF	4	1	19,470.00	$32.00	$623,040.00
		LF	8	1	249.00	$23.48	$5,846.52
	Unit Sub Total	**LF**		**2**	**19,719.00**	**$31.89**	**$628,886.52**
	Item Code 490740 Total No. of Proj.			**2**		**Total Amount**	**$628,886.52**
490741	DRIVE PILE (CLASS 90) (ALTERNATIVE V)	EA	4	1	252.00	$1,850.00	$466,200.00
		EA	8	1	12.00	$5,170.00	$62,040.00
	Unit Sub Total	**EA**		**2**	**264.00**	**$2,000.91**	**$528,240.00**
	Item Code 490741 Total No. of Proj.			**2**		**Total Amount**	**$528,240.00**
490744	FURNISH PILING (CLASS 140) (ALTERNATIVE V)	LF	12	1	1,168.00	$11.50	$13,432.00
	Unit Sub Total	**LF**		**1**	**1,168.00**	**$11.50**	**$13,432.00**
	Item Code 490744 Total No. of Proj.			**1**		**Total Amount**	**$13,432.00**
490745	DRIVE PILE (CLASS 140) (ALTERNATIVE V)	EA	12	1	20.00	$3,000.00	$60,000.00
	Unit Sub Total	**EA**		**1**	**20.00**	**$3,000.00**	**$60,000.00**
	Item Code 490745 Total No. of Proj.			**1**		**Total Amount**	**$60,000.00**
490770	FURNISH PILING (CLASS 625) (ALTERNATIVE V)	M	4	2	5,729.00	$151.61	$868,600.00
	Unit Sub Total	**M**		**2**	**5,729.00**	**$151.61**	**$868,600.00**
	Item Code 490770 Total No. of Proj.			**2**		**Total Amount**	**$868,600.00**
490771	DRIVE PILE (CLASS 625) (ALTERNATIVE V)	EA	4	2	296.00	$1,666.22	$493,200.00
	Unit Sub Total	**EA**		**2**	**296.00**	**$1,666.22**	**$493,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 490771 Total No. of Proj.			**2**		**Total Amount**	**$493,200.00**
490772	FURNISH PILING (CLASS 625) (ALTERNATIVE W)	M	4	1	517.00	$200.00	$103,400.00
		M	5	1	827.00	$130.00	$107,510.00
	Unit Sub Total	**M**		**2**	**1,344.00**	**$156.93**	**$210,910.00**
	Item Code 490772 Total No. of Proj.			**2**		**Total Amount**	**$210,910.00**
490773	DRIVE PILE (CLASS 625) (ALTERNATIVE W)	EA	4	1	20.00	$2,800.00	$56,000.00
		EA	5	1	60.00	$900.00	$54,000.00
	Unit Sub Total	**EA**		**2**	**80.00**	**$1,375.00**	**$110,000.00**
	Item Code 490773 Total No. of Proj.			**2**		**Total Amount**	**$110,000.00**
491007	FURNISH PILING (CLASS 400)	M	4	1	61.00	$140.00	$8,540.00
	Unit Sub Total	**M**		**1**	**61.00**	**$140.00**	**$8,540.00**
	Item Code 491007 Total No. of Proj.			**1**		**Total Amount**	**$8,540.00**
491008	DRIVE PILE (CLASS 400)	EA	4	1	8.00	$3,000.00	$24,000.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$3,000.00**	**$24,000.00**
	Item Code 491008 Total No. of Proj.			**1**		**Total Amount**	**$24,000.00**
491012	FURNISH PILING (CLASS 400) (ALTERNATIVE W)	M	1	1	332.00	$80.00	$26,560.00
		M	4	1	1,923.00	$207.00	$398,061.00
	Unit Sub Total	**M**		**2**	**2,255.00**	**$188.30**	**$424,621.00**
	Item Code 491012 Total No. of Proj.			**2**		**Total Amount**	**$424,621.00**
491013	DRIVE PILE (CLASS 400) (ALTERNATIVE W)	EA	1	1	40.00	$3,600.00	$144,000.00
		EA	4	1	128.00	$2,500.00	$320,000.00
	Unit Sub Total	**EA**		**2**	**168.00**	**$2,761.90**	**$464,000.00**
	Item Code 491013 Total No. of Proj.			**2**		**Total Amount**	**$464,000.00**
493486	2.1 M PERMANENT STEEL CASING	M	11	1	117.00	$1,700.00	$198,900.00
	Unit Sub Total	**M**		**1**	**117.00**	**$1,700.00**	**$198,900.00**
	Item Code 493486 Total No. of Proj.			**1**		**Total Amount**	**$198,900.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
495103	FURNISH 16" CAST-IN-STEEL SHELL CONCRETE PILING	LF	8	1	759.00	$19.90	$15,104.10
	Unit Sub Total	**LF**		**1**	**759.00**	**$19.90**	**$15,104.10**
	Item Code 495103 Total No. of Proj.			**1**		**Total Amount**	**$15,104.10**
495104	DRIVE 16" CAST-IN-STEEL SHELL CONCRETE PILE	EA	8	1	12.00	$5,170.00	$62,040.00
	Unit Sub Total	**EA**		**1**	**12.00**	**$5,170.00**	**$62,040.00**
	Item Code 495104 Total No. of Proj.			**1**		**Total Amount**	**$62,040.00**
498016	16" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	LF	3	1	36,300.00	$35.00	$1,270,500.00
		LF	7	1	2,400.00	$50.00	$120,000.00
	Unit Sub Total	**LF**		**2**	**38,700.00**	**$35.93**	**$1,390,500.00**
	Item Code 498016 Total No. of Proj.			**2**		**Total Amount**	**$1,390,500.00**
498022	24" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	LF	3	1	870.00	$40.00	$34,800.00
	Unit Sub Total	**LF**		**1**	**870.00**	**$40.00**	**$34,800.00**
	Item Code 498022 Total No. of Proj.			**1**		**Total Amount**	**$34,800.00**
498027	400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	M	3	1	630.00	$130.00	$81,900.00
		M	4	1	5,780.00	$195.00	$1,127,100.00
		M	7	2	8,490.00	$120.00	$1,018,800.00
		M	8	1	1,080.00	$100.00	$108,000.00
		M	11	1	1,990.00	$150.00	$298,500.00
	Unit Sub Total	**M**		**6**	**17,970.00**	**$146.59**	**$2,634,300.00**
	Item Code 498027 Total No. of Proj.			**6**		**Total Amount**	**$2,634,300.00**
498030	600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	M	3	1	1,160.00	$80.00	$92,800.00
		M	4	1	88.00	$400.00	$35,200.00
		M	7	1	27.00	$80.00	$2,160.00
	Unit Sub Total	**M**		**3**	**1,275.00**	**$102.09**	**$130,160.00**
	Item Code 498030 Total No. of Proj.			**3**		**Total Amount**	**$130,160.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
499010	24" CAST-IN-DRILLED-HOLE CONCRETE PILING (RETAINING WALL)	LF	5	1	198.00	$140.00	$27,720.00
	Unit Sub Total	**LF**		**1**	**198.00**	**$140.00**	**$27,720.00**
	Item Code 499010 Total No. of Proj.			**1**		**Total Amount**	**$27,720.00**
499042	FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (914 MM)	M	8	1	498.00	$530.00	$263,940.00
	Unit Sub Total	**M**		**1**	**498.00**	**$530.00**	**$263,940.00**
	Item Code 499042 Total No. of Proj.			**1**		**Total Amount**	**$263,940.00**
499043	DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (914 MM)	EA	8	1	20.00	$12,000.00	$240,000.00
	Unit Sub Total	**EA**		**1**	**20.00**	**$12,000.00**	**$240,000.00**
	Item Code 499043 Total No. of Proj.			**1**		**Total Amount**	**$240,000.00**
499054	FURNISH CAST-IN-STEEL-SHELL CONCRETE PILING (1524 MM)	M	4	1	168.00	$1,800.00	$302,400.00
	Unit Sub Total	**M**		**1**	**168.00**	**$1,800.00**	**$302,400.00**
	Item Code 499054 Total No. of Proj.			**1**		**Total Amount**	**$302,400.00**
499055	DRIVE CAST-IN-STEEL-SHELL CONCRETE PILE (1524 MM)	EA	4	1	6.00	$36,500.00	$219,000.00
	Unit Sub Total	**EA**		**1**	**6.00**	**$36,500.00**	**$219,000.00**
	Item Code 499055 Total No. of Proj.			**1**		**Total Amount**	**$219,000.00**
500001	PRESTRESSING CAST-IN-PLACE CONCRETE	LS	1	1	1.00	$68,000.00	$68,000.00
		LS	3	2	2.00	$85,000.00	$170,000.00
		LS	4	8	8.00	$545,575.00	$4,364,600.00
		LS	5	2	2.00	$77,500.00	$155,000.00
		LS	6	1	1.00	$55,000.00	$55,000.00
		LS	7	2	2.00	$140,000.00	$280,000.00
		LS	8	3	3.00	$424,000.00	$1,272,000.00
		LS	10	1	1.00	$275,000.00	$275,000.00
		LS	11	3	3.00	$358,000.00	$1,074,000.00
		LS	12	1	1.00	$200,000.00	$200,000.00
	Unit Sub Total	**LS**		**24**	**24.00**	**$329,733.33**	**$7,913,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 500001 Total No. of Proj.			**24**		**Total Amount**	**$7,913,600.00**
500010	PRESTRESSING	LS	2	1	1.00	$45,000.00	$45,000.00
		LS	4	1	1.00	$9,500.00	$9,500.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$27,250.00**	**$54,500.00**
	Item Code 500010 Total No. of Proj.			**2**		**Total Amount**	**$54,500.00**
500050	TIEBACK ANCHOR	EA	1	6	311.00	$3,226.56	$1,003,460.00
		EA	2	1	30.00	$3,150.00	$94,500.00
		EA	3	2	678.00	$1,584.66	$1,074,400.00
		EA	4	3	229.00	$4,121.31	$943,780.00
		EA	5	1	51.00	$7,000.00	$357,000.00
		EA	7	1	104.00	$3,500.00	$364,000.00
	Unit Sub Total	**EA**		**14**	**1,403.00**	**$2,734.95**	**$3,837,140.00**
	Item Code 500050 Total No. of Proj.			**14**		**Total Amount**	**$3,837,140.00**
510000	SEAL COURSE CONCRETE	M3	1	1	15.00	$250.00	$3,750.00
		M3	4	2	190.00	$190.95	$36,280.00
	Unit Sub Total	**M3**		**3**	**205.00**	**$195.27**	**$40,030.00**
	Item Code 510000 Total No. of Proj.			**3**		**Total Amount**	**$40,030.00**
510050	STRUCTURAL CONCRETE	CY	3	1	59.00	$660.00	$38,940.00
		CY	4	3	130.00	$763.91	$99,308.16
		CY	10	1	22.00	$660.00	$14,520.00
	Unit Sub Total	**CY**		**5**	**211.00**	**$724.02**	**$152,768.16**
	Item Code 510050 Total No. of Proj.			**5**		**Total Amount**	**$152,768.16**
510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	CY	3	1	601.00	$375.00	$225,375.00
		CY	4	4	1,302.00	$273.04	$355,500.00
		CY	5	1	370.00	$750.00	$277,500.00
		CY	6	2	225.00	$301.31	$67,794.00
		CY	8	1	102.00	$300.00	$30,600.00
		CY	11	1	165.00	$340.00	$56,100.00
		CY	12	1	485.00	$250.00	$121,250.00
	Unit Sub Total	**CY**		**11**	**3,250.00**	**$348.96**	**$1,134,119.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	M3	1	1	76.00	$450.00	$34,200.00
		M3	2	1	355.00	$1,000.00	$355,000.00
		M3	3	2	168.00	$543.45	$91,300.00
		M3	4	8	2,960.00	$382.43	$1,131,990.00
		M3	5	2	425.00	$533.65	$226,800.00
		M3	6	1	450.00	$350.00	$157,500.00
		M3	7	4	2,415.00	$658.76	$1,590,915.00
		M3	8	3	2,659.00	$361.38	$960,900.00
		M3	10	1	750.00	$240.00	$180,000.00
		M3	11	3	2,086.00	$391.25	$816,150.00
	Unit Sub Total	**M3**		**26**	**12,344.00**	**$449.19**	**$5,544,755.00**
	Item Code 510051 Total No. of Proj.			**37**		**Total Amount**	**$6,678,874.00**
510053	STRUCTURAL CONCRETE, BRIDGE	CF	4	1	25.00	$300.00	$7,500.00
	Unit Sub Total	**CF**		**1**	**25.00**	**$300.00**	**$7,500.00**
510053	STRUCTURAL CONCRETE, BRIDGE	CY	1	1	0.50	$4,000.00	$2,000.00
		CY	2	3	367.00	$933.11	$342,450.00
		CY	3	3	3,056.00	$1,043.67	$3,189,470.00
		CY	4	10	27,579.00	$330.38	$9,111,500.00
		CY	5	2	40.00	$768.75	$30,750.00
		CY	6	4	3,838.10	$424.96	$1,631,025.00
		CY	7	2	38.00	$2,782.11	$105,720.00
		CY	8	4	862.00	$613.79	$529,090.00
		CY	10	2	48.00	$2,176.25	$104,460.00
		CY	11	3	1,015.00	$803.55	$815,600.00
		CY	12	2	3,816.20	$635.84	$2,426,485.00
	Unit Sub Total	**CY**		**36**	**40,659.80**	**$449.79**	**$18,288,550.00**
510053	STRUCTURAL CONCRETE, BRIDGE	M3	1	2	2,760.00	$1,596.91	$4,407,472.00
		M3	2	1	3,080.00	$1,144.00	$3,523,520.00
		M3	3	2	937.00	$904.83	$847,830.00
		M3	4	8	62,658.00	$779.20	$48,822,873.00
		M3	5	2	2,636.00	$559.41	$1,474,600.00
		M3	6	2	1,124.00	$848.60	$953,830.00
		M3	7	4	10,076.00	$781.38	$7,873,185.00
		M3	8	3	24,273.00	$544.07	$13,206,140.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510053	STRUCTURAL CONCRETE, BRIDGE	M3	10	1	6,150.00	$490.00	$3,013,500.00
		M3	11	3	15,345.00	$614.08	$9,423,050.00
	Unit Sub Total	**M3**		**28**	**129,039.00**	**$724.94**	**$93,546,000.00**
	Item Code 510053 Total No. of Proj.			**65**		**Total Amount**	**$111,842,050.00**
510060	STRUCTURAL CONCRETE, RETAINING WALL	CY	1	3	408.00	$801.23	$326,900.00
		CY	2	1	46.00	$975.00	$44,850.00
		CY	3	1	593.00	$830.00	$492,190.00
		CY	4	6	4,126.00	$399.09	$1,646,644.60
		CY	5	1	37.00	$500.00	$18,500.00
		CY	6	2	1,188.00	$397.52	$472,256.00
		CY	7	2	1,233.00	$514.55	$634,445.00
		CY	8	1	43.00	$700.00	$30,100.00
		CY	12	2	4,204.00	$401.86	$1,689,430.00
	Unit Sub Total	**CY**		**19**	**11,878.00**	**$450.86**	**$5,355,315.60**
510060	STRUCTURAL CONCRETE, RETAINING WALL	M3	2	1	138.00	$1,300.00	$179,400.00
		M3	3	2	2,990.00	$414.39	$1,239,020.00
		M3	4	8	9,164.00	$706.09	$6,470,638.00
		M3	7	3	12,654.00	$454.23	$5,747,810.00
		M3	8	2	5,846.00	$504.15	$2,947,270.00
		M3	10	1	6,714.00	$287.00	$1,926,918.00
		M3	11	2	1,231.00	$500.00	$615,500.00
	Unit Sub Total	**M3**		**19**	**38,737.00**	**$493.75**	**$19,126,556.00**
	Item Code 510060 Total No. of Proj.			**38**		**Total Amount**	**$24,481,871.60**
510069	STRUCTURE CONCRETE (PUMPING PLANT)	M3	4	1	170.00	$900.00	$153,000.00
	Unit Sub Total	**M3**		**1**	**170.00**	**$900.00**	**$153,000.00**
	Item Code 510069 Total No. of Proj.			**1**		**Total Amount**	**$153,000.00**
510072	STRUCTURAL CONCRETE, BARRIER SLAB	CY	1	5	479.00	$638.38	$305,782.00
		CY	2	2	346.00	$453.18	$156,800.00
		CY	5	3	2,045.00	$186.14	$380,665.00
		CY	6	1	550.00	$436.00	$239,800.00
	Unit Sub Total	**CY**		**11**	**3,420.00**	**$316.68**	**$1,083,047.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510072	STRUCTURAL CONCRETE, BARRIER SLAB	M3	4	3	1,174.00	$489.61	$574,800.00
	Unit Sub Total	**M3**		**3**	**1,174.00**	**$489.61**	**$574,800.00**
	Item Code 510072 Total No. of Proj.			**14**		**Total Amount**	**$1,657,847.00**
510085	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ)	CY	5	1	3.00	$1,000.00	$3,000.00
	Unit Sub Total	**CY**		**1**	**3.00**	**$1,000.00**	**$3,000.00**
510085	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ)	M3	1	1	21.00	$700.00	$14,700.00
		M3	4	2	96.00	$846.67	$81,280.00
		M3	5	1	59.00	$1,200.00	$70,800.00
		M3	7	2	32.00	$1,525.00	$48,800.00
	Unit Sub Total	**M3**		**6**	**208.00**	**$1,036.44**	**$215,580.00**
	Item Code 510085 Total No. of Proj.			**7**		**Total Amount**	**$218,580.00**
510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	CY	4	4	323.00	$372.88	$120,440.00
		CY	5	1	80.00	$1,200.00	$96,000.00
		CY	6	2	291.00	$637.48	$185,506.00
		CY	12	1	280.00	$650.00	$182,000.00
	Unit Sub Total	**CY**		**8**	**974.00**	**$599.53**	**$583,946.00**
510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	M3	4	6	1,673.00	$726.99	$1,216,250.00
		M3	7	4	1,018.00	$790.10	$804,320.00
		M3	8	3	1,368.00	$535.60	$732,700.00
		M3	10	1	210.00	$670.00	$140,700.00
		M3	11	3	1,134.00	$718.65	$814,950.00
	Unit Sub Total	**M3**		**17**	**5,403.00**	**$686.46**	**$3,708,920.00**
	Item Code 510086 Total No. of Proj.			**25**		**Total Amount**	**$4,292,866.00**
510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	CY	2	2	898.00	$701.08	$629,570.00
		CY	3	3	828.00	$852.96	$706,255.00
		CY	4	4	1,369.00	$852.99	$1,167,750.00
		CY	6	1	354.00	$925.00	$327,450.00
		CY	7	7	1,919.00	$857.40	$1,645,360.00
		CY	8	1	96.00	$750.00	$72,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	CY	10	3	425.00	$1,144.47	$486,400.00
		CY	11	2	287.00	$1,500.00	$430,500.00
		CY	12	1	183.00	$540.00	$98,820.00
	Unit Sub Total	**CY**		**24**	**6,359.00**	**$875.00**	**$5,564,105.00**
510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	M3	7	3	136.00	$764.71	$104,000.00
		M3	8	1	1,920.00	$1,230.00	$2,361,600.00
		M3	11	1	26.00	$1,600.00	$41,600.00
	Unit Sub Total	**M3**		**5**	**2,082.00**	**$1,204.23**	**$2,507,200.00**
	Item Code 510087 Total No. of Proj.			**29**		**Total Amount**	**$8,071,305.00**
510088	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N MODIFIED)	CY	4	1	705.00	$600.00	$423,000.00
		CY	11	1	69.00	$500.00	$34,500.00
	Unit Sub Total	**CY**		**2**	**774.00**	**$591.09**	**$457,500.00**
510088	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N MODIFIED)	M3	2	1	210.00	$700.00	$147,000.00
	Unit Sub Total	**M3**		**1**	**210.00**	**$700.00**	**$147,000.00**
	Item Code 510088 Total No. of Proj.			**3**		**Total Amount**	**$604,500.00**
510126	CLASS 2 CONCRETE (MINOR STRUCTURE)	CY	11	1	30.00	$2,186.00	$65,580.00
	Unit Sub Total	**CY**		**1**	**30.00**	**$2,186.00**	**$65,580.00**
510126	CLASS 2 CONCRETE (MINOR STRUCTURE)	M3	9	1	13.00	$2,000.00	$26,000.00
		M3	11	2	276.00	$810.00	$223,560.00
	Unit Sub Total	**M3**		**3**	**289.00**	**$863.53**	**$249,560.00**
	Item Code 510126 Total No. of Proj.			**4**		**Total Amount**	**$315,140.00**
510127	CLASS 2 CONCRETE (STRUCTURE)	CY	8	1	700.00	$448.00	$313,600.00
	Unit Sub Total	**CY**		**1**	**700.00**	**$448.00**	**$313,600.00**
510127	CLASS 2 CONCRETE (STRUCTURE)	M3	7	1	19.00	$700.00	$13,300.00
	Unit Sub Total	**M3**		**1**	**19.00**	**$700.00**	**$13,300.00**
	Item Code 510127 Total No. of Proj.			**2**		**Total Amount**	**$326,900.00**
510129	CLASS 2 CONCRETE (BOX CULVERT)	M3	4	2	29.00	$1,536.21	$44,550.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M3**		**2**	**29.00**	**$1,536.21**	**$44,550.00**
	Item Code 510129 Total No. of Proj.			**2**		**Total Amount**	**$44,550.00**
510132	CLASS 2 CONCRETE (RETAINING WALL FOOTING)	CY	8	1	3.00	$630.00	$1,890.00
	Unit Sub Total	**CY**		**1**	**3.00**	**$630.00**	**$1,890.00**
	Item Code 510132 Total No. of Proj.			**1**		**Total Amount**	**$1,890.00**
510135	CLASS 2 CONCRETE (HEADWALL)	M3	4	2	16.00	$3,687.50	$59,000.00
		M3	7	1	38.00	$1,000.00	$38,000.00
	Unit Sub Total	**M3**		**3**	**54.00**	**$1,796.30**	**$97,000.00**
	Item Code 510135 Total No. of Proj.			**3**		**Total Amount**	**$97,000.00**
510138	CLASS 2 CONCRETE (WINGWALLS)	M3	3	1	14.00	$1,250.00	$17,500.00
	Unit Sub Total	**M3**		**1**	**14.00**	**$1,250.00**	**$17,500.00**
	Item Code 510138 Total No. of Proj.			**1**		**Total Amount**	**$17,500.00**
510217	CLASS 3 CONCRETE	CY	4	1	22.00	$206.63	$4,545.86
	Unit Sub Total	**CY**		**1**	**22.00**	**$206.63**	**$4,545.86**
	Item Code 510217 Total No. of Proj.			**1**		**Total Amount**	**$4,545.86**
510220	CLASS 3 CONCRETE (BACKFILL)	CY	1	4	368.00	$250.75	$92,276.50
	Unit Sub Total	**CY**		**4**	**368.00**	**$250.75**	**$92,276.50**
510220	CLASS 3 CONCRETE (BACKFILL)	M3	11	1	35.00	$300.00	$10,500.00
	Unit Sub Total	**M3**		**1**	**35.00**	**$300.00**	**$10,500.00**
	Item Code 510220 Total No. of Proj.			**5**		**Total Amount**	**$102,776.50**
510314	CLASS 4 CONCRETE (BACKFILL)	CY	8	1	1.50	$550.00	$825.00
		CY	10	1	5.00	$750.00	$3,750.00
		CY	11	1	8.00	$175.00	$1,400.00
	Unit Sub Total	**CY**		**3**	**14.50**	**$412.07**	**$5,975.00**
510314	CLASS 4 CONCRETE (BACKFILL)	M3	3	2	88.40	$124.78	$11,030.60
		M3	11	1	130.00	$170.00	$22,100.00
	Unit Sub Total	**M3**		**3**	**218.40**	**$151.70**	**$33,130.60**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 510314 Total No. of Proj.			**6**		**Total Amount**	**$39,105.60**
510408	CLASS 1 CONCRETE (RETAINING WALL)	CY	11	1	593.00	$450.00	$266,850.00
	Unit Sub Total	**CY**		**1**	**593.00**	**$450.00**	**$266,850.00**
510408	CLASS 1 CONCRETE (RETAINING WALL)	M3	11	1	870.00	$700.00	$609,000.00
	Unit Sub Total	**M3**		**1**	**870.00**	**$700.00**	**$609,000.00**
	Item Code 510408 Total No. of Proj.			**2**		**Total Amount**	**$875,850.00**
510409	CLASS 1 CONCRETE (MINOR STRUCTURE)	CY	2	2	30.00	$1,680.93	$50,428.00
	Unit Sub Total	**CY**		**2**	**30.00**	**$1,680.93**	**$50,428.00**
510409	CLASS 1 CONCRETE (MINOR STRUCTURE)	M3	2	2	78.00	$1,281.24	$99,936.72
		M3	10	1	101.00	$1,600.00	$161,600.00
	Unit Sub Total	**M3**		**3**	**179.00**	**$1,461.10**	**$261,536.72**
	Item Code 510409 Total No. of Proj.			**5**		**Total Amount**	**$311,964.72**
510410	CLASS 1 CONCRETE (STRUCTURE)	CY	1	1	9.00	$3,800.00	$34,200.00
		CY	8	1	29.30	$970.00	$28,421.00
	Unit Sub Total	**CY**		**2**	**38.30**	**$1,635.01**	**$62,621.00**
510410	CLASS 1 CONCRETE (STRUCTURE)	M3	8	1	560.00	$500.00	$280,000.00
	Unit Sub Total	**M3**		**1**	**560.00**	**$500.00**	**$280,000.00**
	Item Code 510410 Total No. of Proj.			**3**		**Total Amount**	**$342,621.00**
510413	CLASS 1 CONCRETE (BOX CULVERT)	CY	2	1	266.00	$495.00	$131,670.00
	Unit Sub Total	**CY**		**1**	**266.00**	**$495.00**	**$131,670.00**
510413	CLASS 1 CONCRETE (BOX CULVERT)	M3	3	2	572.10	$914.91	$523,420.90
		M3	4	2	232.00	$1,192.24	$276,600.00
		M3	11	1	470.00	$850.00	$399,500.00
	Unit Sub Total	**M3**		**5**	**1,274.10**	**$941.47**	**$1,199,520.90**
	Item Code 510413 Total No. of Proj.			**6**		**Total Amount**	**$1,331,190.90**
510414	CLASS 1 CONCRETE (BACKFILL)	CY	10	1	9.00	$1,000.00	$9,000.00
	Unit Sub Total	**CY**		**1**	**9.00**	**$1,000.00**	**$9,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 510414	**Total No. of Proj.**			**1**		**Total Amount**	**$9,000.00**
510501	MINOR CONCRETE		CY	7	1	35.00	$385.00	$13,475.00
		Unit Sub Total	**CY**		**1**	**35.00**	**$385.00**	**$13,475.00**
510501	MINOR CONCRETE		M3	4	1	190.00	$320.00	$60,800.00
		Unit Sub Total	**M3**		**1**	**190.00**	**$320.00**	**$60,800.00**
	Item Code 510501	**Total No. of Proj.**			**2**		**Total Amount**	**$74,275.00**
510502	MINOR CONCRETE (MINOR STRUCTURE)		CF	8	1	270.00	$100.00	$27,000.00
		Unit Sub Total	**CF**		**1**	**270.00**	**$100.00**	**$27,000.00**
510502	MINOR CONCRETE (MINOR STRUCTURE)		CY	1	11	59.40	$1,503.11	$89,285.00
			CY	2	20	270.80	$1,598.31	$432,821.90
			CY	3	13	2,865.70	$716.08	$2,052,080.18
			CY	4	12	386.20	$1,005.88	$388,469.04
			CY	5	11	201.40	$1,490.41	$300,168.00
			CY	6	8	196.60	$602.04	$118,362.00
			CY	7	14	761.30	$1,399.50	$1,065,442.00
			CY	8	7	82.50	$1,309.70	$108,050.00
			CY	9	1	5.00	$2,200.00	$11,000.00
			CY	10	5	59.00	$1,035.34	$61,085.00
			CY	11	4	74.00	$1,895.95	$140,300.00
			CY	12	8	253.30	$1,039.77	$263,375.00
		Unit Sub Total	**CY**		**114**	**5,215.20**	**$964.57**	**$5,030,438.12**
510502	MINOR CONCRETE (MINOR STRUCTURE)		M3	1	2	30.00	$1,913.33	$57,400.00
			M3	2	1	51.60	$3,000.00	$154,800.00
			M3	3	5	315.10	$982.22	$309,499.00
			M3	4	11	1,461.40	$1,177.37	$1,720,615.00
			M3	5	3	91.10	$2,804.52	$255,491.49
			M3	6	5	119.80	$1,439.94	$172,505.00
			M3	7	4	465.30	$1,390.93	$647,200.00
			M3	8	3	535.00	$985.47	$527,225.00
			M3	9	1	15.70	$1,700.00	$26,690.00
			M3	10	7	200.10	$1,131.06	$226,325.00
			M3	11	3	922.00	$1,069.31	$985,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**45**	**4,207.10**	**$1,208.35**	**$5,083,650.49**
	Item Code 510502	**Total No. of Proj.**			**160**		**Total Amount**	**$10,141,088.61**
510510	MINOR CONCRETE (INVERT PAVING)		CY	2	1	6.00	$1,500.00	$9,000.00
		Unit Sub Total	**CY**		**1**	**6.00**	**$1,500.00**	**$9,000.00**
510510	MINOR CONCRETE (INVERT PAVING)		LF	1	1	990.00	$25.00	$24,750.00
		Unit Sub Total	**LF**		**1**	**990.00**	**$25.00**	**$24,750.00**
510510	MINOR CONCRETE (INVERT PAVING)		M3	3	1	10.00	$3,470.00	$34,700.00
		Unit Sub Total	**M3**		**1**	**10.00**	**$3,470.00**	**$34,700.00**
	Item Code 510510	**Total No. of Proj.**			**3**		**Total Amount**	**$68,450.00**
510524	MINOR CONCRETE (SOUND WALL)		CY	3	1	1,180.00	$365.00	$430,700.00
			CY	7	1	42.00	$150.00	$6,300.00
		Unit Sub Total	**CY**		**2**	**1,222.00**	**$357.61**	**$437,000.00**
510524	MINOR CONCRETE (SOUND WALL)		M3	3	2	590.00	$450.00	$265,500.00
			M3	4	1	175.00	$1,415.00	$247,625.00
			M3	7	1	4.00	$600.00	$2,400.00
			M3	8	1	10.00	$700.00	$7,000.00
			M3	11	2	478.00	$837.20	$400,180.00
		Unit Sub Total	**M3**		**7**	**1,257.00**	**$734.05**	**$922,705.00**
	Item Code 510524	**Total No. of Proj.**			**9**		**Total Amount**	**$1,359,705.00**
510526	MINOR CONCRETE (BACKFILL)		CY	2	4	213.70	$181.47	$38,780.00
			CY	3	1	10.00	$200.00	$2,000.00
			CY	4	4	212.00	$157.77	$33,446.91
			CY	6	1	13.00	$171.00	$2,223.00
			CY	7	3	408.00	$86.95	$35,475.00
			CY	9	1	5.00	$600.00	$3,000.00
			CY	12	2	60.00	$271.83	$16,310.00
		Unit Sub Total	**CY**		**16**	**921.70**	**$142.38**	**$131,234.91**
510526	MINOR CONCRETE (BACKFILL)		M3	1	2	98.00	$212.24	$20,800.00
			M3	3	1	180.00	$130.00	$23,400.00
			M3	4	7	1,013.00	$206.32	$209,004.00
			M3	5	1	16.00	$175.00	$2,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510526	MINOR CONCRETE (BACKFILL)		M3	6	1	27.00	$420.00	$11,340.00
			M3	7	2	40.00	$188.50	$7,540.00
			M3	9	1	46.00	$500.00	$23,000.00
		Unit Sub Total	**M3**		**15**	**1,420.00**	**$209.78**	**$297,884.00**
	Item Code 510526	**Total No. of Proj.**			**31**		**Total Amount**	**$429,118.91**
510800	PAVING NOTCH EXTENSION		CY	2	1	9.00	$1,650.00	$14,850.00
			CY	3	3	26.00	$3,361.54	$87,400.00
			CY	4	2	28.50	$3,419.30	$97,450.00
			CY	7	7	52.20	$3,335.69	$174,123.00
			CY	8	1	3.00	$3,425.00	$10,275.00
			CY	10	2	5.90	$2,559.32	$15,100.00
			CY	11	1	4.00	$3,300.00	$13,200.00
			CY	12	1	8.00	$2,400.00	$19,200.00
		Unit Sub Total	**CY**		**18**	**136.60**	**$3,159.58**	**$431,598.00**
510800	PAVING NOTCH EXTENSION		M3	7	2	3.60	$4,750.00	$17,100.00
			M3	8	1	50.00	$7,875.00	$393,750.00
		Unit Sub Total	**M3**		**3**	**53.60**	**$7,665.11**	**$410,850.00**
	Item Code 510800	**Total No. of Proj.**			**21**		**Total Amount**	**$842,448.00**
510805	DIAPHRAGM BOLSTER		EA	7	1	43.00	$1,800.00	$77,400.00
			EA	10	1	16.00	$5,800.00	$92,800.00
		Unit Sub Total	**EA**		**2**	**59.00**	**$2,884.75**	**$170,200.00**
	Item Code 510805	**Total No. of Proj.**			**2**		**Total Amount**	**$170,200.00**
511001	LIGHTWEIGHT CONCRETE		CY	2	1	11.00	$1,800.00	$19,800.00
		Unit Sub Total	**CY**		**1**	**11.00**	**$1,800.00**	**$19,800.00**
	Item Code 511001	**Total No. of Proj.**			**1**		**Total Amount**	**$19,800.00**
511035	ARCHITECTURAL TREATMENT		M2	2	2	126.00	$178.42	$22,480.29
			M2	4	3	6,969.00	$41.35	$288,195.00
		Unit Sub Total	**M2**		**5**	**7,095.00**	**$43.79**	**$310,675.29**
511035	ARCHITECTURAL TREATMENT		SQFT	6	1	7,332.00	$13.50	$98,982.00
		Unit Sub Total	**SQFT**		**1**	**7,332.00**	**$13.50**	**$98,982.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 511035	**Total No. of Proj.**			**6**		**Total Amount**	**$409,657.29**
511045	EXPOSED AGGREGATE FINISH		SQFT	11	1	1,559.00	$21.00	$32,739.00
		Unit Sub Total	**SQFT**		**1**	**1,559.00**	**$21.00**	**$32,739.00**
	Item Code 511045	**Total No. of Proj.**			**1**		**Total Amount**	**$32,739.00**
511046	HEAVY BLAST TEXTURE		M2	4	1	2,270.00	$30.00	$68,100.00
		Unit Sub Total	**M2**		**1**	**2,270.00**	**$30.00**	**$68,100.00**
	Item Code 511046	**Total No. of Proj.**			**1**		**Total Amount**	**$68,100.00**
511047	ANTI-GRAFFITI COATING		M2	2	2	126.00	$72.30	$9,109.80
			M2	4	2	14,481.00	$5.58	$80,848.00
		Unit Sub Total	**M2**		**4**	**14,607.00**	**$6.16**	**$89,957.80**
511047	ANTI-GRAFFITI COATING		SQFT	4	2	77,756.00	$1.00	$77,756.00
			SQFT	5	1	240.00	$4.00	$960.00
			SQFT	12	1	4,480.00	$1.40	$6,272.00
		Unit Sub Total	**SQFT**		**4**	**82,476.00**	**$1.03**	**$84,988.00**
	Item Code 511047	**Total No. of Proj.**			**8**		**Total Amount**	**$174,945.80**
511063	FRACTURED FIN TEXTURE		M2	4	1	470.00	$72.00	$33,840.00
		Unit Sub Total	**M2**		**1**	**470.00**	**$72.00**	**$33,840.00**
	Item Code 511063	**Total No. of Proj.**			**1**		**Total Amount**	**$33,840.00**
511064	FRACTURED RIB TEXTURE		M2	4	2	223.00	$172.40	$38,445.00
			M2	5	1	30.00	$200.00	$6,000.00
			M2	8	1	5,514.00	$12.00	$66,168.00
			M2	11	1	1,840.00	$43.00	$79,120.00
		Unit Sub Total	**M2**		**5**	**7,607.00**	**$24.94**	**$189,733.00**
511064	FRACTURED RIB TEXTURE		SQFT	3	1	15,970.00	$15.00	$239,550.00
			SQFT	4	1	10,505.00	$6.00	$63,030.00
			SQFT	11	1	3,843.00	$15.00	$57,645.00
			SQFT	12	1	2,570.00	$7.00	$17,990.00
		Unit Sub Total	**SQFT**		**4**	**32,888.00**	**$11.50**	**$378,215.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 511064 Total No. of Proj.			**9**		**Total Amount**	**$567,948.00**
511106	DRILL AND BOND DOWEL	LF	2	4	518.00	$59.85	$31,000.00
		LF	3	1	90.00	$30.00	$2,700.00
		LF	4	4	3,307.00	$12.43	$41,090.00
		LF	5	1	120.00	$45.00	$5,400.00
		LF	6	1	350.00	$20.00	$7,000.00
		LF	7	1	470.00	$51.00	$23,970.00
		LF	8	2	2,449.00	$21.11	$51,710.00
		LF	10	2	361.00	$44.52	$16,070.00
		LF	12	1	580.00	$24.00	$13,920.00
	Unit Sub Total	**LF**		**17**	**8,245.00**	**$23.39**	**$192,860.00**
511106	DRILL AND BOND DOWEL	M	3	1	7.00	$100.00	$700.00
		M	4	4	277.00	$118.25	$32,756.00
		M	5	1	39.00	$98.49	$3,841.11
		M	6	1	166.00	$120.00	$19,920.00
		M	7	4	1,260.00	$39.30	$49,515.00
		M	8	1	140.00	$100.00	$14,000.00
		M	11	1	97.00	$95.00	$9,215.00
	Unit Sub Total	**M**		**13**	**1,986.00**	**$65.43**	**$129,947.11**
	Item Code 511106 Total No. of Proj.			**30**		**Total Amount**	**$322,807.11**
511109	DRILL AND BOND DOWEL (EPOXY CARTRIDGE)	EA	4	1	480.00	$30.00	$14,400.00
	Unit Sub Total	**EA**		**1**	**480.00**	**$30.00**	**$14,400.00**
	Item Code 511109 Total No. of Proj.			**1**		**Total Amount**	**$14,400.00**
511110	DRILL AND BOND DOWEL (CHEMICAL ADHESIVE)	EA	4	1	204.00	$60.00	$12,240.00
		EA	7	3	46.00	$146.96	$6,760.00
	Unit Sub Total	**EA**		**4**	**250.00**	**$76.00**	**$19,000.00**
	Item Code 511110 Total No. of Proj.			**4**		**Total Amount**	**$19,000.00**
511118	CLEAN EXPANSION JOINT	LF	1	4	1,163.00	$14.03	$16,320.00
		LF	2	3	2,092.00	$4.32	$9,045.00
		LF	3	8	7,097.00	$21.00	$149,019.44
		LF	4	18	28,523.00	$12.83	$366,021.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
511118	CLEAN EXPANSION JOINT	LF	5	1	196.00	$5.00	$980.00
		LF	6	3	1,021.50	$8.97	$9,165.00
		LF	7	18	29,987.00	$11.09	$332,558.60
		LF	8	8	6,345.00	$13.88	$88,095.00
		LF	10	4	5,093.00	$14.65	$74,626.00
		LF	11	5	5,653.00	$22.53	$127,360.00
		LF	12	3	1,679.00	$21.42	$35,957.00
	Unit Sub Total	**LF**		**75**	**88,849.50**	**$13.61**	**$1,209,147.04**
511118	CLEAN EXPANSION JOINT	M	4	1	33.00	$95.00	$3,135.00
		M	6	1	33.00	$63.00	$2,079.00
	Unit Sub Total	**M**		**2**	**66.00**	**$79.00**	**$5,214.00**
	Item Code 511118 Total No. of Proj.			**77**		**Total Amount**	**$1,214,361.04**
511124	RAPID SETTING CONCRETE (PATCH)	CF	1	5	678.00	$49.43	$33,512.00
		CF	2	3	1,301.00	$68.37	$88,946.00
		CF	3	7	4,285.00	$26.40	$113,107.40
		CF	4	16	13,841.00	$32.83	$454,423.00
		CF	6	1	753.00	$29.00	$21,837.00
		CF	7	17	7,211.00	$25.09	$180,914.00
		CF	8	10	2,986.00	$31.59	$94,322.00
		CF	10	4	2,355.00	$38.01	$89,517.00
		CF	11	6	7,294.00	$19.56	$142,688.00
		CF	12	1	645.00	$35.00	$22,575.00
	Unit Sub Total	**CF**		**70**	**41,349.00**	**$30.03**	**$1,241,841.40**
	Item Code 511124 Total No. of Proj.			**70**		**Total Amount**	**$1,241,841.40**
512225	FURNISH PRECAST PRESTRESSED CONCRETE BOX GIRDER (80'-90')	EA	12	1	1.00	$53,000.00	$53,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$53,000.00**	**$53,000.00**
	Item Code 512225 Total No. of Proj.			**1**		**Total Amount**	**$53,000.00**
512229	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (5 M - 10 M)	EA	7	1	2.00	$9,000.00	$18,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$9,000.00**	**$18,000.00**
	Item Code 512229 Total No. of Proj.			**1**		**Total Amount**	**$18,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
512230	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (10 M - 15 M)	EA	6	1	20.00	$6,000.00	$120,000.00
		EA	7	1	1.00	$13,000.00	$13,000.00
	Unit Sub Total	**EA**		**2**	**21.00**	**$6,333.33**	**$133,000.00**
	Item Code 512230 Total No. of Proj.			**2**		**Total Amount**	**$133,000.00**
512231	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (15 M - 20 M)	EA	7	2	3.00	$21,183.33	$63,550.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$21,183.33**	**$63,550.00**
	Item Code 512231 Total No. of Proj.			**2**		**Total Amount**	**$63,550.00**
512232	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (20 M - 25 M)	EA	6	1	20.00	$10,000.00	$200,000.00
		EA	7	1	16.00	$8,820.00	$141,120.00
	Unit Sub Total	**EA**		**2**	**36.00**	**$9,475.56**	**$341,120.00**
	Item Code 512232 Total No. of Proj.			**2**		**Total Amount**	**$341,120.00**
512235	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (35 M - 40 M)	EA	7	1	4.00	$35,000.00	$140,000.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$35,000.00**	**$140,000.00**
	Item Code 512235 Total No. of Proj.			**1**		**Total Amount**	**$140,000.00**
512280	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (110'-120')	EA	4	1	5.00	$24,000.00	$120,000.00
	Unit Sub Total	**EA**		**1**	**5.00**	**$24,000.00**	**$120,000.00**
	Item Code 512280 Total No. of Proj.			**1**		**Total Amount**	**$120,000.00**
512281	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (120'-130')	EA	12	1	2.00	$35,000.00	$70,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$35,000.00**	**$70,000.00**
	Item Code 512281 Total No. of Proj.			**1**		**Total Amount**	**$70,000.00**
512290	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (60'-70')	EA	6	1	20.00	$13,500.00	$270,000.00
	Unit Sub Total	**EA**		**1**	**20.00**	**$13,500.00**	**$270,000.00**
	Item Code 512290 Total No. of Proj.			**1**		**Total Amount**	**$270,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
512291	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (70'-80')	EA	6	1	50.00	$21,600.00	$1,080,000.00
	Unit Sub Total	**EA**		**1**	**50.00**	**$21,600.00**	**$1,080,000.00**
	Item Code 512291 Total No. of Proj.			**1**		**Total Amount**	**$1,080,000.00**
512500	ERECT PRECAST PRESTRESSED CONCRETE GIRDER	EA	4	1	5.00	$4,300.00	$21,500.00
		EA	6	2	110.00	$2,109.64	$232,060.00
		EA	7	3	26.00	$5,295.38	$137,680.00
		EA	12	1	2.00	$11,000.00	$22,000.00
	Unit Sub Total	**EA**		**7**	**143.00**	**$2,889.79**	**$413,240.00**
	Item Code 512500 Total No. of Proj.			**7**		**Total Amount**	**$413,240.00**
512502	ERECT PRECAST PRESTRESSED CONCRETE BOX GIRDER	EA	12	1	1.00	$13,500.00	$13,500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$13,500.00**	**$13,500.00**
	Item Code 512502 Total No. of Proj.			**1**		**Total Amount**	**$13,500.00**
512510	ERECT PRECAST PRESTRESSED CONCRETE DECK UNIT	M2	7	1	255.00	$214.00	$54,570.00
	Unit Sub Total	**M2**		**1**	**255.00**	**$214.00**	**$54,570.00**
	Item Code 512510 Total No. of Proj.			**1**		**Total Amount**	**$54,570.00**
513501	CONCRETE CLOSURE WALL	M2	7	1	373.00	$380.00	$141,740.00
	Unit Sub Total	**M2**		**1**	**373.00**	**$380.00**	**$141,740.00**
	Item Code 513501 Total No. of Proj.			**1**		**Total Amount**	**$141,740.00**
513551	RETAINING WALL STEM (TYPE 6)	SQFT	5	1	160.00	$40.00	$6,400.00
		SQFT	8	3	437.00	$81.84	$35,765.00
	Unit Sub Total	**SQFT**		**4**	**597.00**	**$70.63**	**$42,165.00**
	Item Code 513551 Total No. of Proj.			**4**		**Total Amount**	**$42,165.00**
513570	CONCRETE BLOCK WALL	M2	6	1	3.10	$885.00	$2,743.50
	Unit Sub Total	**M2**		**1**	**3.10**	**$885.00**	**$2,743.50**
	Item Code 513570 Total No. of Proj.			**1**		**Total Amount**	**$2,743.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
513601	REINFORCED CONCRETE CRIB WALL (TYPE A)	M2	11	1	25.00	$490.00	$12,250.00
	Unit Sub Total	**M2**		**1**	**25.00**	**$490.00**	**$12,250.00**
	Item Code 513601 Total No. of Proj.			**1**		**Total Amount**	**$12,250.00**
513602	REINFORCED CONCRETE CRIB WALL (TYPE B)	M2	11	1	70.00	$560.00	$39,200.00
	Unit Sub Total	**M2**		**1**	**70.00**	**$560.00**	**$39,200.00**
	Item Code 513602 Total No. of Proj.			**1**		**Total Amount**	**$39,200.00**
513603	REINFORCED CONCRETE CRIB WALL (TYPE C)	M2	11	1	440.00	$590.00	$259,600.00
	Unit Sub Total	**M2**		**1**	**440.00**	**$590.00**	**$259,600.00**
	Item Code 513603 Total No. of Proj.			**1**		**Total Amount**	**$259,600.00**
513604	REINFORCED CONCRETE CRIB WALL (TYPE D)	M2	11	1	830.00	$116.00	$96,280.00
	Unit Sub Total	**M2**		**1**	**830.00**	**$116.00**	**$96,280.00**
	Item Code 513604 Total No. of Proj.			**1**		**Total Amount**	**$96,280.00**
515010	INSTALL STUD CONNECTORS	EA	4	1	120.00	$15.00	$1,800.00
	Unit Sub Total	**EA**		**1**	**120.00**	**$15.00**	**$1,800.00**
	Item Code 515010 Total No. of Proj.			**1**		**Total Amount**	**$1,800.00**
515020	REFINISH BRIDGE DECK	M2	4	2	15.00	$383.33	$5,750.00
		M2	7	3	471.00	$189.71	$89,355.00
	Unit Sub Total	**M2**		**5**	**486.00**	**$195.69**	**$95,105.00**
515020	REFINISH BRIDGE DECK	SQFT	5	1	190.00	$25.00	$4,750.00
		SQFT	6	1	335.00	$56.00	$18,760.00
		SQFT	7	1	1,728.00	$5.40	$9,331.20
		SQFT	10	1	634.00	$15.00	$9,510.00
	Unit Sub Total	**SQFT**		**4**	**2,887.00**	**$14.67**	**$42,351.20**
	Item Code 515020 Total No. of Proj.			**9**		**Total Amount**	**$137,456.20**
515028	REPAIR SPALLED SURFACE AREA	SQFT	4	1	13.00	$500.00	$6,500.00
	Unit Sub Total	**SQFT**		**1**	**13.00**	**$500.00**	**$6,500.00**
	Item Code 515028 Total No. of Proj.			**1**		**Total Amount**	**$6,500.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
515041	FURNISH POLYESTER CONCRETE OVERLAY	CF	1	2	2,802.00	$75.92	$212,740.00
		CF	2	4	26,577.00	$76.64	$2,036,811.18
		CF	3	6	28,025.00	$77.28	$2,165,703.44
		CF	4	4	28,341.00	$58.19	$1,649,029.00
		CF	5	1	13.00	$47.00	$611.00
		CF	7	3	7,666.00	$71.25	$546,210.00
		CF	8	8	23,345.00	$64.52	$1,506,144.00
		CF	12	1	580.00	$50.00	$29,000.00
	Unit Sub Total	**CF**		**29**	**117,349.00**	**$69.42**	**$8,146,248.62**
515041	FURNISH POLYESTER CONCRETE OVERLAY	M3	2	1	370.00	$2,785.00	$1,030,450.00
		M3	6	1	5.00	$4,095.00	$20,475.00
		M3	7	2	32.00	$2,986.41	$95,565.00
	Unit Sub Total	**M3**		**4**	**407.00**	**$2,816.93**	**$1,146,490.00**
	Item Code 515041 Total No. of Proj.			**33**		**Total Amount**	**$9,292,738.62**
515042	PLACE POLYESTER CONCRETE OVERLAY	M2	2	1	18,400.00	$15.00	$276,000.00
		M2	6	1	230.00	$68.00	$15,640.00
		M2	7	2	1,062.00	$61.23	$65,022.00
	Unit Sub Total	**M2**		**4**	**19,692.00**	**$18.11**	**$356,662.00**
515042	PLACE POLYESTER CONCRETE OVERLAY	SQFT	1	2	25,246.00	$3.14	$79,194.00
		SQFT	2	4	304,352.00	$1.06	$323,386.45
		SQFT	3	6	398,681.00	$2.05	$819,185.40
		SQFT	4	4	208,267.00	$3.12	$649,621.50
		SQFT	5	1	54.00	$40.00	$2,160.00
		SQFT	7	3	64,480.00	$2.97	$191,646.00
		SQFT	8	8	142,654.00	$4.75	$677,054.40
		SQFT	12	1	9,300.00	$3.50	$32,550.00
	Unit Sub Total	**SQFT**		**29**	**1,153,034.00**	**$2.41**	**$2,774,797.75**
	Item Code 515042 Total No. of Proj.			**33**		**Total Amount**	**$3,131,459.75**
515060	CORE CONCRETE (1")	LF	7	1	700.00	$58.00	$40,600.00
	Unit Sub Total	**LF**		**1**	**700.00**	**$58.00**	**$40,600.00**
	Item Code 515060 Total No. of Proj.			**1**		**Total Amount**	**$40,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
515067	CORE CONCRETE (8")	LF	7	1	3.00	$305.00	$915.00
	Unit Sub Total	**LF**		**1**	**3.00**	**$305.00**	**$915.00**
	Item Code 515067 Total No. of Proj.			**1**		**Total Amount**	**$915.00**
515072	CORE CONCRETE (0 - 50 MM)	M	4	1	3.00	$1,500.00	$4,500.00
	Unit Sub Total	**M**		**1**	**3.00**	**$1,500.00**	**$4,500.00**
	Item Code 515072 Total No. of Proj.			**1**		**Total Amount**	**$4,500.00**
515074	CORE CONCRETE (101 MM - 150 MM)	M	7	1	42.00	$75.00	$3,150.00
	Unit Sub Total	**M**		**1**	**42.00**	**$75.00**	**$3,150.00**
	Item Code 515074 Total No. of Proj.			**1**		**Total Amount**	**$3,150.00**
515075	CORE CONCRETE (151 MM - 200 MM)	M	7	1	34.00	$200.00	$6,800.00
	Unit Sub Total	**M**		**1**	**34.00**	**$200.00**	**$6,800.00**
	Item Code 515075 Total No. of Proj.			**1**		**Total Amount**	**$6,800.00**
515076	CORE CONCRETE (201 MM - 250 MM)	M	8	1	2.40	$250.00	$600.00
	Unit Sub Total	**M**		**1**	**2.40**	**$250.00**	**$600.00**
	Item Code 515076 Total No. of Proj.			**1**		**Total Amount**	**$600.00**
515077	CORE CONCRETE (251 MM - 300 MM)	M	7	1	10.00	$125.00	$1,250.00
		M	10	1	9.00	$450.00	$4,050.00
	Unit Sub Total	**M**		**2**	**19.00**	**$278.95**	**$5,300.00**
	Item Code 515077 Total No. of Proj.			**2**		**Total Amount**	**$5,300.00**
515160	CORE CONCRETE (1 1/2")	LF	4	1	50.00	$50.00	$2,500.00
	Unit Sub Total	**LF**		**1**	**50.00**	**$50.00**	**$2,500.00**
	Item Code 515160 Total No. of Proj.			**1**		**Total Amount**	**$2,500.00**
517961	SOUND WALL (BARRIER) (MASONRY BLOCK)	M2	4	1	4,680.00	$179.00	$837,720.00
		M2	8	2	1,380.00	$145.65	$201,000.00
	Unit Sub Total	**M2**		**3**	**6,060.00**	**$171.41**	**$1,038,720.00**
	Item Code 517961 Total No. of Proj.			**3**		**Total Amount**	**$1,038,720.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
518002	SOUND WALL (MASONRY BLOCK)	M2	3	2	7,405.00	$148.90	$1,102,584.00
		M2	4	3	5,003.00	$183.27	$916,883.00
		M2	7	3	26,732.00	$155.33	$4,152,268.00
		M2	8	1	1,207.00	$150.00	$181,050.00
		M2	11	2	6,505.00	$170.91	$1,111,775.00
	Unit Sub Total	**M2**		**11**	**46,852.00**	**$159.32**	**$7,464,560.00**
518002	SOUND WALL (MASONRY BLOCK)	SQFT	3	1	224,434.00	$14.75	$3,310,401.50
		SQFT	7	1	6,888.00	$30.00	$206,640.00
	Unit Sub Total	**SQFT**		**2**	**231,322.00**	**$15.20**	**$3,517,041.50**
	Item Code 518002	**Total No. of Proj.**		**13**		**Total Amount**	**$10,981,601.50**
518040	REPLACE BEARING PAD	EA	6	1	10.00	$3,700.00	$37,000.00
		EA	10	2	20.00	$6,740.00	$134,800.00
	Unit Sub Total	**EA**		**3**	**30.00**	**$5,726.67**	**$171,800.00**
	Item Code 518040	**Total No. of Proj.**		**3**		**Total Amount**	**$171,800.00**
518050	PTFE BEARING	EA	4	1	2.00	$7,600.00	$15,200.00
		EA	8	1	5.00	$2,000.00	$10,000.00
	Unit Sub Total	**EA**		**2**	**7.00**	**$3,600.00**	**$25,200.00**
	Item Code 518050	**Total No. of Proj.**		**2**		**Total Amount**	**$25,200.00**
518051	PTFE SPHERICAL BEARING	EA	2	1	8.00	$29,000.00	$232,000.00
		EA	4	4	116.00	$5,000.00	$580,000.00
		EA	5	1	4.00	$10,000.00	$40,000.00
		EA	7	1	21.00	$4,000.00	$84,000.00
		EA	8	1	10.00	$4,500.00	$45,000.00
		EA	11	1	10.00	$6,000.00	$60,000.00
	Unit Sub Total	**EA**		**9**	**169.00**	**$6,159.76**	**$1,041,000.00**
	Item Code 518051	**Total No. of Proj.**		**9**		**Total Amount**	**$1,041,000.00**
518201	MASONRY BLOCK WALL	M2	8	1	32.00	$120.00	$3,840.00
	Unit Sub Total	**M2**		**1**	**32.00**	**$120.00**	**$3,840.00**
	Item Code 518201	**Total No. of Proj.**		**1**		**Total Amount**	**$3,840.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
519050	EXPANSION DAM		CF	7	2	569.00	$129.35	$73,600.00
		Unit Sub Total	**CF**		**2**	**569.00**	**$129.35**	**$73,600.00**
	Item Code 519050	**Total No. of Proj.**			**2**		**Total Amount**	**$73,600.00**
519078	SNOWPLOW DEFLECTOR		EA	2	1	98.00	$296.00	$29,008.00
		Unit Sub Total	**EA**		**1**	**98.00**	**$296.00**	**$29,008.00**
	Item Code 519078	**Total No. of Proj.**			**1**		**Total Amount**	**$29,008.00**
519081	JOINT SEAL (MR 1/2")		LF	1	3	727.00	$20.83	$15,140.00
			LF	2	3	621.00	$24.67	$15,320.00
			LF	3	6	3,853.00	$29.03	$111,860.34
			LF	4	16	16,553.00	$22.60	$374,067.60
			LF	5	2	204.00	$28.10	$5,732.00
			LF	6	2	294.00	$51.89	$15,255.00
			LF	7	12	16,066.00	$17.48	$280,809.00
			LF	8	8	2,900.00	$22.04	$63,919.04
			LF	10	4	2,066.00	$20.66	$42,688.00
			LF	11	5	2,932.00	$22.02	$64,574.00
			LF	12	1	10.00	$140.00	$1,400.00
		Unit Sub Total	**LF**		**62**	**46,226.00**	**$21.43**	**$990,764.98**
	Item Code 519081	**Total No. of Proj.**			**62**		**Total Amount**	**$990,764.98**
519088	JOINT SEAL (MR 1")		LF	1	1	193.00	$20.00	$3,860.00
			LF	2	2	1,126.00	$16.77	$18,884.00
			LF	3	6	2,013.00	$21.01	$42,302.00
			LF	4	17	9,634.00	$30.56	$294,383.00
			LF	6	1	185.00	$30.00	$5,550.00
			LF	7	16	11,499.00	$18.22	$209,518.00
			LF	8	6	2,955.00	$18.89	$55,832.00
			LF	10	4	1,743.00	$21.66	$37,750.00
			LF	11	3	1,675.00	$21.55	$36,098.00
			LF	12	3	459.00	$57.16	$26,235.00
		Unit Sub Total	**LF**		**59**	**31,482.00**	**$23.20**	**$730,412.00**
	Item Code 519088	**Total No. of Proj.**			**59**		**Total Amount**	**$730,412.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
519091	JOINT SEAL (MR 1 1/2")	LF	1	1	27.00	$45.00	$1,215.00
		LF	2	1	520.00	$50.00	$26,000.00
		LF	3	4	544.00	$50.80	$27,634.00
		LF	4	10	2,977.00	$50.11	$149,170.00
		LF	6	1	315.00	$46.00	$14,490.00
		LF	7	7	2,775.00	$34.48	$95,682.00
		LF	8	3	862.00	$47.71	$41,124.00
		LF	10	3	575.00	$47.16	$27,114.50
		LF	11	1	1,000.00	$38.00	$38,000.00
		LF	12	2	459.00	$50.72	$23,280.00
	Unit Sub Total	**LF**		**33**	**10,054.00**	**$44.13**	**$443,709.50**
	Item Code 519091 Total No. of Proj.			**33**		**Total Amount**	**$443,709.50**
519092	JOINT SEAL ASSEMBLY (MR 2 1/2")	LF	4	4	358.00	$229.76	$82,255.00
		LF	6	1	445.00	$280.00	$124,600.00
		LF	7	2	56.00	$150.00	$8,400.00
		LF	11	2	617.00	$222.30	$137,160.00
	Unit Sub Total	**LF**		**9**	**1,476.00**	**$238.76**	**$352,415.00**
	Item Code 519092 Total No. of Proj.			**9**		**Total Amount**	**$352,415.00**
519093	JOINT SEAL ASSEMBLY (MR 3")	LF	2	1	100.00	$160.00	$16,000.00
		LF	3	2	727.00	$382.88	$278,356.00
		LF	4	2	273.00	$233.77	$63,820.00
		LF	6	1	37.50	$180.00	$6,750.00
		LF	7	2	28.00	$180.00	$5,040.00
		LF	10	1	168.00	$225.00	$37,800.00
	Unit Sub Total	**LF**		**9**	**1,333.50**	**$305.79**	**$407,766.00**
	Item Code 519093 Total No. of Proj.			**9**		**Total Amount**	**$407,766.00**
519094	JOINT SEAL ASSEMBLY (MR 3 1/2")	LF	4	2	207.00	$245.02	$50,720.00
		LF	7	2	28.00	$185.00	$5,180.00
		LF	11	1	220.00	$110.00	$24,200.00
	Unit Sub Total	**LF**		**5**	**455.00**	**$176.04**	**$80,100.00**
	Item Code 519094 Total No. of Proj.			**5**		**Total Amount**	**$80,100.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
519095	JOINT SEAL ASSEMBLY (MR 4")	LF	3	1	158.00	$225.00	$35,550.00
		LF	4	1	255.00	$260.00	$66,300.00
		LF	5	1	72.00	$150.00	$10,800.00
		LF	11	1	177.00	$110.00	$19,470.00
	Unit Sub Total	**LF**		**4**	**662.00**	**$199.58**	**$132,120.00**
	Item Code 519095 Total No. of Proj.			**4**		**Total Amount**	**$132,120.00**
519100	JOINT SEAL (MR 2")	LF	1	2	216.00	$60.00	$12,960.00
		LF	2	2	881.00	$46.27	$40,760.00
		LF	3	5	1,254.00	$79.35	$99,500.00
		LF	4	6	1,059.00	$60.86	$64,450.00
		LF	6	3	542.00	$63.79	$34,575.00
		LF	7	1	1,287.00	$45.00	$57,915.00
		LF	8	1	70.00	$75.00	$5,250.00
		LF	10	1	197.00	$46.00	$9,062.00
		LF	11	3	403.00	$87.12	$35,110.00
		LF	12	2	1,532.00	$57.02	$87,352.00
	Unit Sub Total	**LF**		**26**	**7,441.00**	**$60.06**	**$446,934.00**
	Item Code 519100 Total No. of Proj.			**26**		**Total Amount**	**$446,934.00**
519102	JOINT SEAL (TYPE AL)	LF	3	1	33.00	$25.00	$825.00
		LF	4	1	512.00	$35.00	$17,920.00
		LF	10	1	433.00	$20.00	$8,660.00
	Unit Sub Total	**LF**		**3**	**978.00**	**$28.02**	**$27,405.00**
519102	JOINT SEAL (TYPE AL)	M	4	1	2,104.00	$125.00	$263,000.00
		M	7	1	62.00	$85.00	$5,270.00
	Unit Sub Total	**M**		**2**	**2,166.00**	**$123.86**	**$268,270.00**
	Item Code 519102 Total No. of Proj.			**5**		**Total Amount**	**$295,675.00**
519117	JOINT SEAL (MR 30 MM)	M	4	1	30.00	$125.00	$3,750.00
		M	7	2	192.00	$163.13	$31,320.00
		M	8	1	780.00	$152.00	$118,560.00
		M	11	1	78.00	$200.00	$15,600.00
	Unit Sub Total	**M**		**5**	**1,080.00**	**$156.69**	**$169,230.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 519117 Total No. of Proj.			**5**		**Total Amount**	**$169,230.00**
519120	JOINT SEAL (MR 15 MM)	M	4	2	48.00	$192.08	$9,220.00
		M	7	2	80.00	$147.81	$11,825.00
		M	8	1	70.00	$236.00	$16,520.00
	Unit Sub Total	**M**		**5**	**198.00**	**$189.72**	**$37,565.00**
	Item Code 519120 Total No. of Proj.			**5**		**Total Amount**	**$37,565.00**
519124	JOINT SEAL ASSEMBLY (MR 60 MM)	M	8	1	13.00	$270.00	$3,510.00
	Unit Sub Total	**M**		**1**	**13.00**	**$270.00**	**$3,510.00**
	Item Code 519124 Total No. of Proj.			**1**		**Total Amount**	**$3,510.00**
519125	JOINT SEAL ASSEMBLY (MR 70 MM)	M	8	1	13.00	$270.00	$3,510.00
		M	11	2	102.00	$900.00	$91,800.00
	Unit Sub Total	**M**		**3**	**115.00**	**$828.78**	**$95,310.00**
	Item Code 519125 Total No. of Proj.			**3**		**Total Amount**	**$95,310.00**
519126	JOINT SEAL ASSEMBLY (MR 80 MM)	M	4	3	230.00	$655.24	$150,705.00
		M	8	1	65.00	$270.00	$17,550.00
	Unit Sub Total	**M**		**4**	**295.00**	**$570.36**	**$168,255.00**
	Item Code 519126 Total No. of Proj.			**4**		**Total Amount**	**$168,255.00**
519127	JOINT SEAL ASSEMBLY (MR 90 MM)	M	4	2	60.00	$700.00	$42,000.00
		M	8	1	12.00	$270.00	$3,240.00
	Unit Sub Total	**M**		**3**	**72.00**	**$628.33**	**$45,240.00**
	Item Code 519127 Total No. of Proj.			**3**		**Total Amount**	**$45,240.00**
519128	JOINT SEAL ASSEMBLY (MR 100 MM)	M	1	1	27.00	$1,000.00	$27,000.00
		M	4	1	9.00	$450.00	$4,050.00
		M	8	1	12.00	$270.00	$3,240.00
	Unit Sub Total	**M**		**3**	**48.00**	**$714.38**	**$34,290.00**
	Item Code 519128 Total No. of Proj.			**3**		**Total Amount**	**$34,290.00**
519129	JOINT SEAL ASSEMBLY (MR 101 MM - 160 MM)	M	4	1	187.00	$4,000.00	$748,000.00
		M	8	1	56.00	$2,200.00	$123,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
519129	JOINT SEAL ASSEMBLY (MR 101 MM - 160 MM)	M	10	1	146.00	$2,900.00	$423,400.00
		M	11	1	17.00	$2,600.00	$44,200.00
	Unit Sub Total	**M**		**4**	**406.00**	**$3,297.54**	**$1,338,800.00**
	Item Code 519129 Total No. of Proj.			**4**		**Total Amount**	**$1,338,800.00**
519130	JOINT SEAL ASSEMBLY (MR 161 MM - 240 MM)	M	4	1	25.00	$4,100.00	$102,500.00
		M	8	1	68.00	$3,600.00	$244,800.00
		M	11	1	13.00	$4,200.00	$54,600.00
	Unit Sub Total	**M**		**3**	**106.00**	**$3,791.51**	**$401,900.00**
	Item Code 519130 Total No. of Proj.			**3**		**Total Amount**	**$401,900.00**
519131	JOINT SEAL ASSEMBLY (MR 241 MM - 320 MM)	M	2	1	63.00	$5,000.00	$315,000.00
		M	4	1	90.00	$5,100.00	$459,000.00
	Unit Sub Total	**M**		**2**	**153.00**	**$5,058.82**	**$774,000.00**
	Item Code 519131 Total No. of Proj.			**2**		**Total Amount**	**$774,000.00**
519132	JOINT SEAL ASSEMBLY (MR 321 MM - 400 MM)	M	4	1	94.00	$5,500.00	$517,000.00
	Unit Sub Total	**M**		**1**	**94.00**	**$5,500.00**	**$517,000.00**
	Item Code 519132 Total No. of Proj.			**1**		**Total Amount**	**$517,000.00**
519133	JOINT SEAL (ASPHALTIC PLUG)	LF	4	1	92.00	$200.00	$18,400.00
	Unit Sub Total	**LF**		**1**	**92.00**	**$200.00**	**$18,400.00**
	Item Code 519133 Total No. of Proj.			**1**		**Total Amount**	**$18,400.00**
519142	JOINT SEAL (MR 40 MM)	M	4	2	151.00	$329.93	$49,820.00
		M	5	1	43.00	$125.00	$5,375.00
		M	8	2	105.00	$276.19	$29,000.00
		M	11	1	48.00	$230.00	$11,040.00
	Unit Sub Total	**M**		**6**	**347.00**	**$274.45**	**$95,235.00**
	Item Code 519142 Total No. of Proj.			**6**		**Total Amount**	**$95,235.00**
519144	JOINT SEAL (MR 50 MM)	M	3	1	30.00	$230.00	$6,900.00
		M	4	4	154.00	$236.69	$36,450.00
		M	5	2	80.00	$150.00	$12,000.00
		M	7	2	111.00	$224.32	$24,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
519144	JOINT SEAL (MR 50 MM)	M	8	1	84.00	$350.00	$29,400.00
		M	11	1	48.00	$285.00	$13,680.00
	Unit Sub Total	**M**		**11**	**507.00**	**$243.25**	**$123,330.00**
	Item Code 519144 Total No. of Proj.			**11**		**Total Amount**	**$123,330.00**
520101	BAR REINFORCING STEEL	KG	1	1	3,684.00	$3.16	$11,641.44
		KG	3	2	40,395.00	$2.04	$82,575.00
		KG	4	3	41,793.00	$1.72	$71,741.10
		KG	7	1	2,575.00	$1.32	$3,399.00
		KG	8	2	69,124.00	$1.40	$96,964.00
	Unit Sub Total	**KG**		**9**	**157,571.00**	**$1.69**	**$266,320.54**
520101	BAR REINFORCING STEEL	LB	1	1	603.00	$3.00	$1,809.00
		LB	2	1	80,659.00	$0.75	$60,494.25
		LB	4	3	17,840.00	$0.93	$16,604.60
		LB	6	1	346,220.00	$0.56	$193,883.20
		LB	7	3	274,847.00	$0.75	$205,063.95
		LB	8	1	1,505.00	$2.00	$3,010.00
		LB	12	1	333,800.00	$0.70	$233,660.00
	Unit Sub Total	**LB**		**11**	**1,055,474.00**	**$0.68**	**$714,525.00**
	Item Code 520101 Total No. of Proj.			**20**		**Total Amount**	**$980,845.54**
520102	BAR REINFORCING STEEL (BRIDGE)	KG	1	2	633,200.00	$1.79	$1,133,200.00
		KG	2	1	1,670,000.00	$1.26	$2,104,200.00
		KG	3	2	162,070.00	$1.60	$259,312.00
		KG	4	8	14,013,065.00	$1.26	$17,645,851.00
		KG	5	2	423,100.00	$1.42	$599,960.00
		KG	6	2	282,900.00	$1.27	$358,659.00
		KG	7	4	2,307,851.00	$1.29	$2,968,843.60
		KG	8	3	5,437,050.00	$1.27	$6,924,250.50
		KG	10	1	860,000.00	$1.50	$1,290,000.00
		KG	11	3	2,987,176.00	$1.24	$3,714,505.20
	Unit Sub Total	**KG**		**28**	**28,776,412.00**	**$1.29**	**$36,998,781.30**
520102	BAR REINFORCING STEEL (BRIDGE)	LB	1	1	185.00	$3.00	$555.00
		LB	2	1	19,896.00	$1.00	$19,896.00
		LB	3	2	1,038,000.00	$0.60	$626,300.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
520102	BAR REINFORCING STEEL (BRIDGE)	LB	4	13	11,911,737.80	$0.43	$5,075,150.83
		LB	5	2	26,064.00	$2.44	$63,564.00
		LB	6	3	1,470,050.00	$0.74	$1,082,423.50
		LB	7	3	8,320.00	$2.80	$23,317.00
		LB	8	4	189,338.00	$0.85	$160,299.00
		LB	10	3	7,020.00	$2.02	$14,159.50
		LB	11	3	358,180.00	$0.55	$195,710.50
		LB	12	2	1,239,030.00	$0.66	$811,889.00
	Unit Sub Total	**LB**		**37**	**16,267,820.80**	**$0.50**	**$8,073,264.33**
	Item Code 520102 Total No. of Proj.			**65**		**Total Amount**	**$45,072,045.63**
520103	BAR REINFORCING STEEL (RETAINING WALL)	KG	2	1	9,960.00	$1.65	$16,434.00
		KG	3	2	259,731.00	$1.63	$423,672.00
		KG	4	8	809,491.00	$1.84	$1,489,770.00
		KG	7	3	934,181.00	$1.62	$1,510,029.98
		KG	8	2	572,975.00	$1.20	$688,995.00
		KG	10	1	789,864.00	$1.05	$829,357.20
		KG	11	3	99,924.00	$1.82	$182,048.60
	Unit Sub Total	**KG**		**20**	**3,476,126.00**	**$1.48**	**$5,140,306.78**
520103	BAR REINFORCING STEEL (RETAINING WALL)	LB	1	2	36,000.00	$1.02	$36,590.00
		LB	2	2	41,892.00	$1.59	$66,420.00
		LB	3	1	471,405.00	$0.80	$377,124.00
		LB	4	6	699,740.00	$0.74	$520,735.00
		LB	5	3	100,931.00	$0.84	$84,885.50
		LB	6	2	382,642.00	$0.49	$188,312.40
		LB	7	2	76,262.00	$1.34	$102,031.85
		LB	8	4	33,820.00	$1.25	$42,395.00
		LB	11	3	108,286.00	$1.18	$127,432.00
		LB	12	2	595,090.00	$0.75	$447,682.50
	Unit Sub Total	**LB**		**27**	**2,546,068.00**	**$0.78**	**$1,993,608.25**
	Item Code 520103 Total No. of Proj.			**47**		**Total Amount**	**$7,133,915.03**
520105	BAR REINFORCING STEEL (SOUND WALL)	KG	3	1	57,737.00	$1.30	$75,058.10
	Unit Sub Total	**KG**		**1**	**57,737.00**	**$1.30**	**$75,058.10**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 520105 Total No. of Proj.			**1**		**Total Amount**	**$75,058.10**
520106	BAR REINFORCING STEEL (EPOXY COATED)	KG	4	1	5,440.00	$2.10	$11,424.00
	Unit Sub Total	**KG**		**1**	**5,440.00**	**$2.10**	**$11,424.00**
520106	BAR REINFORCING STEEL (EPOXY COATED)	LB	1	1	19,500.00	$1.50	$29,250.00
		LB	2	1	9,130.00	$4.40	$40,172.00
		LB	3	2	22,302.00	$1.97	$43,998.00
		LB	5	1	7,110.00	$2.00	$14,220.00
		LB	12	1	19,500.00	$1.60	$31,200.00
	Unit Sub Total	**LB**		**6**	**77,542.00**	**$2.05**	**$158,840.00**
	Item Code 520106 Total No. of Proj.			**7**		**Total Amount**	**$170,264.00**
520107	BAR REINFORCING STEEL (BOX CULVERT)	KG	3	2	89,419.00	$0.41	$37,088.50
		KG	4	2	37,995.00	$1.32	$50,128.95
		KG	7	1	7,975.00	$1.50	$11,962.50
		KG	8	1	5,950.00	$1.50	$8,925.00
		KG	11	1	131,000.00	$1.55	$203,050.00
	Unit Sub Total	**KG**		**7**	**272,339.00**	**$1.14**	**$311,154.95**
520107	BAR REINFORCING STEEL (BOX CULVERT)	LB	2	1	89,246.00	$0.88	$78,536.48
		LB	12	1	51,944.00	$0.75	$38,958.00
	Unit Sub Total	**LB**		**2**	**141,190.00**	**$0.83**	**$117,494.48**
	Item Code 520107 Total No. of Proj.			**9**		**Total Amount**	**$428,649.43**
520110	BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	KG	2	1	1,593,000.00	$2.02	$3,217,860.00
		KG	4	1	723,000.00	$2.50	$1,807,500.00
	Unit Sub Total	**KG**		**2**	**2,316,000.00**	**$2.17**	**$5,025,360.00**
520110	BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	LB	2	3	63,475.00	$1.06	$67,093.00
	Unit Sub Total	**LB**		**3**	**63,475.00**	**$1.06**	**$67,093.00**
	Item Code 520110 Total No. of Proj.			**5**		**Total Amount**	**$5,092,453.00**
520113	BAR REINFORCING STEEL (PUMPING PLANT)	KG	4	1	26,300.00	$1.25	$32,875.00
	Unit Sub Total	**KG**		**1**	**26,300.00**	**$1.25**	**$32,875.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 520113	**Total No. of Proj.**			**1**		**Total Amount**	**$32,875.00**
520120	HEADED BAR REINFORCEMENT		EA	2	1	9,190.00	$36.00	$330,840.00
			EA	4	6	58,914.00	$10.49	$618,140.00
			EA	5	1	26.00	$60.00	$1,560.00
			EA	7	2	2,456.00	$7.92	$19,460.00
			EA	8	1	114.00	$37.00	$4,218.00
			EA	11	3	3,522.00	$32.15	$113,220.00
		Unit Sub Total	**EA**		**14**	**74,222.00**	**$14.65**	**$1,087,438.00**
	Item Code 520120	**Total No. of Proj.**			**14**		**Total Amount**	**$1,087,438.00**
530100	SHOTCRETE		CF	7	1	307.00	$80.00	$24,560.00
		Unit Sub Total	**CF**		**1**	**307.00**	**$80.00**	**$24,560.00**
530100	SHOTCRETE		CY	3	1	451.00	$350.00	$157,850.00
			CY	4	1	38.00	$805.00	$30,590.00
			CY	5	2	69.00	$702.90	$48,500.00
			CY	6	1	340.00	$545.00	$185,300.00
			CY	12	1	3,225.00	$600.00	$1,935,000.00
		Unit Sub Total	**CY**		**6**	**4,123.00**	**$571.73**	**$2,357,240.00**
530100	SHOTCRETE		M3	3	1	436.00	$510.00	$222,360.00
			M3	4	6	3,497.00	$486.10	$1,699,878.00
			M3	6	1	13.00	$1,500.00	$19,500.00
			M3	7	1	137.00	$550.00	$75,350.00
		Unit Sub Total	**M3**		**9**	**4,083.00**	**$494.02**	**$2,017,088.00**
	Item Code 530100	**Total No. of Proj.**			**16**		**Total Amount**	**$4,398,888.00**
540101	ASPHALT MEMBRANE WATERPROOFING		M2	7	1	33.00	$195.00	$6,435.00
		Unit Sub Total	**M2**		**1**	**33.00**	**$195.00**	**$6,435.00**
	Item Code 540101	**Total No. of Proj.**			**1**		**Total Amount**	**$6,435.00**
540102	TREAT BRIDGE DECK		M2	6	1	643.00	$3.35	$2,154.05
			M2	8	1	39,200.00	$2.12	$83,104.00
		Unit Sub Total	**M2**		**2**	**39,843.00**	**$2.14**	**$85,258.05**
540102	TREAT BRIDGE DECK		SQFT	1	5	102,750.00	$0.19	$19,064.92

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
540102	TREAT BRIDGE DECK	SQFT	2	2	10,792.00	$0.84	$9,082.00
		SQFT	3	7	1,267,479.00	$0.24	$307,375.64
		SQFT	4	16	6,118,964.00	$0.16	$986,284.68
		SQFT	6	1	223,000.00	$0.20	$44,600.00
		SQFT	7	17	2,196,231.00	$0.19	$416,589.79
		SQFT	8	7	873,192.00	$0.19	$167,438.99
		SQFT	10	4	702,063.00	$0.15	$107,290.75
		SQFT	11	6	2,144,311.00	$0.23	$485,607.97
		SQFT	12	1	254,135.00	$0.20	$50,827.00
	Unit Sub Total	**SQFT**		**66**	**13,892,917.00**	**$0.19**	**$2,594,161.74**
	Item Code 540102 Total No. of Proj.			**68**		**Total Amount**	**$2,679,419.79**
540108	FURNISH BRIDGE DECK TREATMENT MATERIAL	GAL	1	5	1,148.00	$68.36	$78,476.00
		GAL	2	2	120.00	$67.08	$8,050.00
		GAL	3	7	14,329.00	$55.99	$802,312.00
		GAL	4	16	69,538.00	$60.43	$4,202,102.50
		GAL	7	17	26,618.00	$56.00	$1,490,654.00
		GAL	8	7	10,073.00	$55.50	$559,010.00
		GAL	10	4	7,812.00	$63.11	$493,004.00
		GAL	11	6	26,421.00	$62.13	$1,641,570.00
		GAL	12	1	3,177.00	$48.00	$152,496.00
	Unit Sub Total	**GAL**		**65**	**159,236.00**	**$59.21**	**$9,427,674.50**
540108	FURNISH BRIDGE DECK TREATMENT MATERIAL	L	6	1	262.00	$30.00	$7,860.00
		L	8	1	15,870.00	$20.95	$332,476.50
	Unit Sub Total	**L**		**2**	**16,132.00**	**$21.10**	**$340,336.50**
	Item Code 540108 Total No. of Proj.			**67**		**Total Amount**	**$9,768,011.00**
540109	FURNISH BRIDGE DECK TREATMENT MATERIAL (LOW ODOR)	GAL	6	1	2,480.00	$60.95	$151,156.00
	Unit Sub Total	**GAL**		**1**	**2,480.00**	**$60.95**	**$151,156.00**
	Item Code 540109 Total No. of Proj.			**1**		**Total Amount**	**$151,156.00**
550102	STRUCTURAL STEEL (BRIDGE)	KG	4	2	2,910.00	$43.90	$127,750.00
		KG	7	1	716,690.00	$3.00	$2,150,070.00
	Unit Sub Total	**KG**		**3**	**719,600.00**	**$3.17**	**$2,277,820.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
550102	STRUCTURAL STEEL (BRIDGE)	LB	2	2	99,956.00	$7.51	$750,736.00
		LB	4	3	1,011,000.00	$1.34	$1,352,500.00
		LB	10	2	1,010.00	$26.29	$26,550.00
	Unit Sub Total	**LB**		**7**	**1,111,966.00**	**$1.92**	**$2,129,786.00**
	Item Code 550102 Total No. of Proj.			**10**		**Total Amount**	**$4,407,606.00**
550110	COLUMN CASING	KG	7	1	15,863.00	$13.60	$215,736.80
	Unit Sub Total	**KG**		**1**	**15,863.00**	**$13.60**	**$215,736.80**
	Item Code 550110 Total No. of Proj.			**1**		**Total Amount**	**$215,736.80**
550203	FURNISH STRUCTURAL STEEL (BRIDGE)	LB	3	1	7,000.00	$7.36	$51,499.70
	Unit Sub Total	**LB**		**1**	**7,000.00**	**$7.36**	**$51,499.70**
	Item Code 550203 Total No. of Proj.			**1**		**Total Amount**	**$51,499.70**
550204	ERECT STRUCTURAL STEEL (BRIDGE)	LB	3	1	7,000.00	$5.71	$40,000.10
	Unit Sub Total	**LB**		**1**	**7,000.00**	**$5.71**	**$40,000.10**
	Item Code 550204 Total No. of Proj.			**1**		**Total Amount**	**$40,000.10**
560203	FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	KG	3	2	14,540.00	$15.00	$218,100.00
		KG	4	1	5,500.00	$12.00	$66,000.00
		KG	6	1	1,032.00	$25.00	$25,800.00
		KG	7	2	12,612.00	$15.16	$191,138.00
		KG	8	1	1,844.00	$21.00	$38,724.00
		KG	11	1	1,440.00	$30.00	$43,200.00
	Unit Sub Total	**KG**		**8**	**36,968.00**	**$15.77**	**$582,962.00**
560203	FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	LB	2	1	11,094.00	$7.15	$79,322.10
		LB	3	1	2,964.00	$5.00	$14,820.00
		LB	7	1	12,400.00	$7.00	$86,800.00
	Unit Sub Total	**LB**		**3**	**26,458.00**	**$6.84**	**$180,942.10**
	Item Code 560203 Total No. of Proj.			**11**		**Total Amount**	**$763,904.10**
560204	INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	KG	3	2	14,540.00	$4.52	$65,770.00
		KG	4	1	5,500.00	$3.00	$16,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560204	INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	KG	6	1	1,032.00	$6.20	$6,398.40
		KG	7	2	12,612.00	$2.54	$32,019.50
		KG	8	1	1,844.00	$3.25	$5,993.00
		KG	11	1	1,440.00	$5.00	$7,200.00
	Unit Sub Total	**KG**		**8**	**36,968.00**	**$3.62**	**$133,880.90**
560204	INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	LB	2	1	11,094.00	$1.54	$17,084.76
		LB	3	1	2,964.00	$5.00	$14,820.00
		LB	7	1	12,400.00	$2.00	$24,800.00
	Unit Sub Total	**LB**		**3**	**26,458.00**	**$2.14**	**$56,704.76**
	Item Code 560204 Total No. of Proj.			**11**		**Total Amount**	**$190,585.66**
560208	FURNISH SIGN STRUCTURE (TUBULAR)	KG	8	2	215,684.00	$12.33	$2,660,310.05
	Unit Sub Total	**KG**		**2**	**215,684.00**	**$12.33**	**$2,660,310.05**
560208	FURNISH SIGN STRUCTURE (TUBULAR)	LB	4	1	38,370.00	$4.50	$172,665.00
		LB	6	1	19,669.00	$5.15	$101,295.35
		LB	8	1	29,200.00	$5.50	$160,600.00
	Unit Sub Total	**LB**		**3**	**87,239.00**	**$4.98**	**$434,560.35**
	Item Code 560208 Total No. of Proj.			**5**		**Total Amount**	**$3,094,870.40**
560209	INSTALL SIGN STRUCTURE (TUBULAR)	KG	8	2	215,684.00	$0.59	$127,278.75
	Unit Sub Total	**KG**		**2**	**215,684.00**	**$0.59**	**$127,278.75**
560209	INSTALL SIGN STRUCTURE (TUBULAR)	LB	4	1	38,370.00	$0.50	$19,185.00
		LB	6	1	19,669.00	$0.45	$8,851.05
		LB	8	1	29,200.00	$0.30	$8,760.00
	Unit Sub Total	**LB**		**3**	**87,239.00**	**$0.42**	**$36,796.05**
	Item Code 560209 Total No. of Proj.			**5**		**Total Amount**	**$164,074.80**
560213	FURNISH SIGN STRUCTURE (LIGHTWEIGHT)	KG	7	1	6,045.00	$6.00	$36,270.00
		KG	8	1	9,921.00	$14.00	$138,894.00
		KG	11	1	5,720.00	$12.00	$68,640.00
	Unit Sub Total	**KG**		**3**	**21,686.00**	**$11.24**	**$243,804.00**
	Item Code 560213 Total No. of Proj.			**3**		**Total Amount**	**$243,804.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560214	INSTALL SIGN STRUCTURE (LIGHTWEIGHT)	KG	7	1	6,045.00	$1.00	$6,045.00
		KG	8	1	9,921.00	$1.50	$14,881.50
		KG	11	1	5,720.00	$1.50	$8,580.00
	Unit Sub Total	**KG**		**3**	**21,686.00**	**$1.36**	**$29,506.50**
	Item Code 560214 Total No. of Proj.			**3**		**Total Amount**	**$29,506.50**
560218	FURNISH SIGN STRUCTURE (TRUSS)	KG	3	2	231,580.00	$10.81	$2,502,530.00
		KG	4	8	383,870.00	$9.38	$3,600,155.00
		KG	6	3	22,118.00	$12.00	$265,416.00
		KG	7	4	391,198.00	$9.25	$3,616,787.10
		KG	8	1	18,600.00	$13.00	$241,800.00
		KG	11	2	113,400.00	$11.80	$1,337,725.00
	Unit Sub Total	**KG**		**20**	**1,160,766.00**	**$9.96**	**$11,564,413.10**
560218	FURNISH SIGN STRUCTURE (TRUSS)	LB	2	1	66,400.00	$5.00	$332,000.00
		LB	3	2	677,315.00	$4.45	$3,012,235.40
		LB	4	3	117,093.00	$4.65	$544,148.50
		LB	6	1	28,304.00	$5.25	$148,596.00
		LB	7	4	254,299.00	$5.50	$1,399,174.00
		LB	8	2	89,484.00	$5.85	$523,206.00
		LB	11	2	57,275.00	$5.45	$311,962.00
		LB	12	3	194,868.00	$2.21	$431,385.00
	Unit Sub Total	**LB**		**18**	**1,485,038.00**	**$4.51**	**$6,702,706.90**
	Item Code 560218 Total No. of Proj.			**38**		**Total Amount**	**$18,267,120.00**
560219	INSTALL SIGN STRUCTURE (TRUSS)	KG	3	2	231,580.00	$0.47	$109,817.25
		KG	4	8	383,870.00	$0.53	$202,778.10
		KG	6	3	22,118.00	$0.81	$17,935.65
		KG	7	4	391,198.00	$0.37	$145,277.40
		KG	8	1	18,600.00	$0.30	$5,580.00
		KG	11	2	113,400.00	$0.34	$38,635.00
	Unit Sub Total	**KG**		**20**	**1,160,766.00**	**$0.45**	**$520,023.40**
560219	INSTALL SIGN STRUCTURE (TRUSS)	LB	2	1	66,400.00	$0.25	$16,600.00
		LB	3	2	676,987.00	$0.42	$284,390.75
		LB	4	3	140,063.00	$0.26	$35,803.90
		LB	6	1	28,304.00	$0.20	$5,660.80

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560219	INSTALL SIGN STRUCTURE (TRUSS)	LB	7	3	247,290.00	$0.19	$47,081.90
		LB	8	2	89,484.00	$0.37	$33,237.60
		LB	11	2	57,275.00	$0.30	$17,182.50
		LB	12	3	194,868.00	$0.40	$77,134.50
	Unit Sub Total	**LB**		**17**	**1,500,671.00**	**$0.34**	**$517,091.95**
	Item Code 560219 Total No. of Proj.			**37**		**Total Amount**	**$1,037,115.35**
560223	FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY)	LB	4	1	390.00	$12.00	$4,680.00
	Unit Sub Total	**LB**		**1**	**390.00**	**$12.00**	**$4,680.00**
	Item Code 560223 Total No. of Proj.			**1**		**Total Amount**	**$4,680.00**
560224	INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITHOUT WALKWAY)	LB	4	1	390.00	$8.00	$3,120.00
	Unit Sub Total	**LB**		**1**	**390.00**	**$8.00**	**$3,120.00**
	Item Code 560224 Total No. of Proj.			**1**		**Total Amount**	**$3,120.00**
560233	FURNISH FORMED PANEL SIGN (OVERHEAD)	M2	4	8	1,026.00	$118.85	$121,935.00
		M2	7	4	1,031.00	$91.97	$94,825.00
		M2	11	1	40.00	$100.00	$4,000.00
	Unit Sub Total	**M2**		**13**	**2,097.00**	**$105.27**	**$220,760.00**
560233	FURNISH FORMED PANEL SIGN (OVERHEAD)	SQFT	2	1	440.00	$14.00	$6,160.00
		SQFT	4	2	1,220.00	$10.51	$12,820.00
		SQFT	7	4	9,440.00	$9.73	$91,808.00
		SQFT	8	1	890.00	$12.00	$10,680.00
		SQFT	11	1	300.00	$14.00	$4,200.00
	Unit Sub Total	**SQFT**		**9**	**12,290.00**	**$10.23**	**$125,668.00**
	Item Code 560233 Total No. of Proj.			**22**		**Total Amount**	**$346,428.00**
560234	FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE A)	M2	3	2	825.00	$163.15	$134,600.00
		M2	4	1	18.00	$230.00	$4,140.00
		M2	6	1	12.00	$230.00	$2,760.00
		M2	7	1	86.00	$120.00	$10,320.00
		M2	8	3	716.00	$187.30	$134,110.00
		M2	11	2	747.00	$132.53	$99,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M2**		**10**	**2,404.00**	**$160.12**	**$384,930.00**
	Item Code 560234 Total No. of Proj.			**10**		**Total Amount**	**$384,930.00**
560235	FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE B)	M2	3	2	29.00	$160.34	$4,650.00
		M2	7	1	22.00	$195.00	$4,290.00
		M2	8	2	23.00	$184.35	$4,240.00
		M2	11	1	60.00	$135.00	$8,100.00
	Unit Sub Total	**M2**		**6**	**134.00**	**$158.81**	**$21,280.00**
	Item Code 560235 Total No. of Proj.			**6**		**Total Amount**	**$21,280.00**
560236	FURNISH LAMINATED PANEL SIGN (63.5 MM-TYPE B)	M2	2	1	64.00	$170.00	$10,880.00
		M2	4	1	8.00	$190.00	$1,520.00
		M2	7	1	13.00	$230.00	$2,990.00
		M2	8	1	12.00	$170.00	$2,040.00
	Unit Sub Total	**M2**		**4**	**97.00**	**$179.69**	**$17,430.00**
	Item Code 560236 Total No. of Proj.			**4**		**Total Amount**	**$17,430.00**
560237	FURNISH LAMINATED PANEL SIGN (63.5 MM-TYPE H)	M2	11	1	11.00	$163.00	$1,793.00
	Unit Sub Total	**M2**		**1**	**11.00**	**$163.00**	**$1,793.00**
	Item Code 560237 Total No. of Proj.			**1**		**Total Amount**	**$1,793.00**
560238	FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-UNFRAMED)	M2	1	2	5.90	$191.53	$1,130.00
		M2	2	1	6.00	$100.00	$600.00
		M2	3	6	137.60	$121.60	$16,732.00
		M2	4	8	312.00	$92.09	$28,733.00
		M2	5	3	88.30	$84.95	$7,501.20
		M2	6	6	241.00	$100.56	$24,236.00
		M2	7	4	81.00	$73.20	$5,929.00
		M2	8	2	106.00	$85.00	$9,010.00
		M2	9	2	44.60	$116.05	$5,176.00
		M2	10	6	69.50	$191.19	$13,288.00
		M2	11	3	480.00	$78.96	$37,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M2**		**43**	**1,571.90**	**$95.58**	**$150,235.20**
560238	FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-UNFRAMED)	SQFT	3	1	58.00	$9.00	$522.00
		SQFT	8	2	77.00	$15.00	$1,155.00
	Unit Sub Total	**SQFT**		**3**	**135.00**	**$12.42**	**$1,677.00**
	Item Code 560238 Total No. of Proj.			**46**		**Total Amount**	**$151,912.20**
560239	FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-UNFRAMED)	M2	2	1	5.00	$110.00	$550.00
		M2	3	6	165.20	$114.64	$18,939.00
		M2	4	8	271.10	$106.17	$28,783.90
		M2	5	1	18.00	$100.00	$1,800.00
		M2	6	2	159.00	$91.98	$14,625.00
		M2	7	3	92.00	$76.24	$7,014.00
		M2	8	2	132.00	$88.48	$11,680.00
		M2	9	1	55.00	$118.00	$6,490.00
		M2	10	5	22.50	$184.89	$4,160.00
		M2	11	3	216.00	$82.44	$17,808.00
	Unit Sub Total	**M2**		**32**	**1,135.80**	**$98.48**	**$111,849.90**
560239	FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-UNFRAMED)	SQFT	3	1	288.00	$10.00	$2,880.00
	Unit Sub Total	**SQFT**		**1**	**288.00**	**$10.00**	**$2,880.00**
	Item Code 560239 Total No. of Proj.			**33**		**Total Amount**	**$114,729.90**
560241	FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-FRAMED)	M2	2	1	6.00	$150.00	$900.00
		M2	3	4	15.50	$156.74	$2,429.50
		M2	4	6	58.70	$122.15	$7,170.00
		M2	5	2	22.00	$110.18	$2,424.00
		M2	6	1	5.00	$155.00	$775.00
		M2	7	1	26.00	$143.00	$3,718.00
		M2	8	2	12.00	$103.33	$1,240.00
		M2	9	2	11.00	$163.27	$1,796.00
		M2	10	3	20.30	$227.96	$4,627.50
		M2	11	2	109.00	$84.66	$9,228.00
	Unit Sub Total	**M2**		**24**	**285.50**	**$120.17**	**$34,308.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 560241 Total No. of Proj.			**24**		**Total Amount**	**$34,308.00**
560242	FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-FRAMED)	M2	2	1	17.00	$160.00	$2,720.00
		M2	3	4	73.00	$163.08	$11,905.00
		M2	4	7	141.50	$125.68	$17,784.10
		M2	5	2	37.00	$125.54	$4,645.00
		M2	6	2	31.00	$130.16	$4,035.00
		M2	7	2	37.00	$174.05	$6,440.00
		M2	8	2	25.60	$119.84	$3,068.00
		M2	10	1	3.00	$300.00	$900.00
		M2	11	3	236.00	$98.14	$23,160.00
	Unit Sub Total	**M2**		**24**	**601.10**	**$124.20**	**$74,657.10**
	Item Code 560242 Total No. of Proj.			**24**		**Total Amount**	**$74,657.10**
560243	FURNISH FIBERGLASS REINFORCED PLASTIC PANEL SIGN (3.4 MM)	M2	4	1	7.00	$115.00	$805.00
	Unit Sub Total	**M2**		**1**	**7.00**	**$115.00**	**$805.00**
	Item Code 560243 Total No. of Proj.			**1**		**Total Amount**	**$805.00**
560244	FURNISH LAMINATED PANEL SIGN (1"-TYPE A)	SQFT	3	1	7,000.00	$15.00	$105,000.00
		SQFT	4	1	60.00	$19.00	$1,140.00
		SQFT	6	1	240.00	$17.00	$4,080.00
		SQFT	7	3	4,403.00	$13.92	$61,281.00
		SQFT	8	2	2,750.00	$14.14	$38,880.00
		SQFT	11	1	420.00	$16.50	$6,930.00
		SQFT	12	3	2,590.00	$13.45	$34,846.00
	Unit Sub Total	**SQFT**		**12**	**17,463.00**	**$14.44**	**$252,157.00**
	Item Code 560244 Total No. of Proj.			**12**		**Total Amount**	**$252,157.00**
560245	FURNISH LAMINATED PANEL SIGN (1"-TYPE B)	SQFT	2	2	231.00	$22.21	$5,131.00
		SQFT	3	1	180.00	$15.00	$2,700.00
		SQFT	7	1	81.00	$14.00	$1,134.00
		SQFT	8	2	2,680.00	$16.87	$45,200.00
		SQFT	11	1	60.00	$22.00	$1,320.00
		SQFT	12	1	78.00	$13.00	$1,014.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**SQFT**		**8**	**3,310.00**	**$17.07**	**$56,499.00**
	Item Code 560245 Total No. of Proj.			**8**		**Total Amount**	**$56,499.00**
560246	FURNISH LAMINATED PANEL SIGN (2 1/2"-TYPE B)	SQFT	2	1	91.00	$15.00	$1,365.00
		SQFT	7	1	65.30	$28.00	$1,828.40
		SQFT	8	1	1,190.00	$15.00	$17,850.00
	Unit Sub Total	**SQFT**		**3**	**1,346.30**	**$15.63**	**$21,043.40**
	Item Code 560246 Total No. of Proj.			**3**		**Total Amount**	**$21,043.40**
560248	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	SQFT	1	1	62.00	$35.00	$2,170.00
		SQFT	2	8	636.50	$12.51	$7,963.25
		SQFT	3	8	1,583.00	$11.97	$18,949.57
		SQFT	4	7	627.00	$11.67	$7,314.00
		SQFT	5	5	1,083.30	$14.12	$15,292.30
		SQFT	6	5	1,655.00	$9.99	$16,536.24
		SQFT	7	13	50,346.00	$6.59	$331,947.00
		SQFT	8	12	482.10	$13.65	$6,578.30
		SQFT	9	3	277.00	$13.30	$3,683.00
		SQFT	10	5	403.00	$13.19	$5,315.00
		SQFT	11	7	724.00	$13.00	$9,409.05
		SQFT	12	16	2,696.00	$9.36	$25,237.50
	Unit Sub Total	**SQFT**		**90**	**60,574.90**	**$7.44**	**$450,395.21**
	Item Code 560248 Total No. of Proj.			**90**		**Total Amount**	**$450,395.21**
560249	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED)	SQFT	2	3	213.00	$15.72	$3,348.00
		SQFT	3	7	1,585.00	$10.90	$17,273.80
		SQFT	4	5	399.00	$13.15	$5,246.00
		SQFT	5	2	43.00	$53.37	$2,295.00
		SQFT	6	1	3,510.00	$9.00	$31,590.00
		SQFT	7	5	14,300.00	$9.03	$129,068.00
		SQFT	8	10	1,504.00	$9.21	$13,853.45
		SQFT	9	1	9.00	$20.00	$180.00
		SQFT	10	3	177.00	$9.19	$1,626.00
		SQFT	11	6	2,068.00	$9.67	$20,007.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560249	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED)	SQFT	12	6	708.00	$10.40	$7,361.20
	Unit Sub Total	**SQFT**		**49**	**24,516.00**	**$9.46**	**$231,848.45**
	Item Code 560249 Total No. of Proj.			**49**		**Total Amount**	**$231,848.45**
560250	FURNISH SINGLE SHEET ALUMINUM SIGN (0.125"-UNFRAMED)	SQFT	8	1	34.00	$21.60	$734.40
	Unit Sub Total	**SQFT**		**1**	**34.00**	**$21.60**	**$734.40**
	Item Code 560250 Total No. of Proj.			**1**		**Total Amount**	**$734.40**
560251	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED)	SQFT	3	2	380.00	$10.71	$4,070.00
		SQFT	4	2	108.00	$11.67	$1,260.00
		SQFT	5	2	52.00	$34.40	$1,788.58
		SQFT	6	1	68.00	$19.00	$1,292.00
		SQFT	7	1	240.00	$9.00	$2,160.00
		SQFT	8	2	70.00	$10.11	$707.60
		SQFT	10	3	82.00	$11.95	$980.00
		SQFT	11	3	326.00	$14.66	$4,780.00
		SQFT	12	3	158.00	$11.22	$1,772.00
	Unit Sub Total	**SQFT**		**19**	**1,484.00**	**$12.68**	**$18,810.18**
	Item Code 560251 Total No. of Proj.			**19**		**Total Amount**	**$18,810.18**
560252	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED)	SQFT	2	3	406.00	$17.22	$6,990.00
		SQFT	3	3	394.00	$12.74	$5,020.00
		SQFT	4	3	292.00	$14.54	$4,245.00
		SQFT	7	1	710.00	$9.60	$6,816.00
		SQFT	8	2	55.00	$12.00	$660.00
		SQFT	9	1	100.00	$17.60	$1,760.00
		SQFT	11	1	120.00	$15.00	$1,800.00
		SQFT	12	2	290.00	$12.69	$3,679.60
	Unit Sub Total	**SQFT**		**16**	**2,367.00**	**$13.08**	**$30,970.60**
	Item Code 560252 Total No. of Proj.			**16**		**Total Amount**	**$30,970.60**
561003	24" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	3	1	49.00	$300.00	$14,700.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**1**	**49.00**	**$300.00**	**$14,700.00**
	Item Code 561003 Total No. of Proj.			**1**		**Total Amount**	**$14,700.00**
561006	42" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	3	1	40.00	$330.00	$13,200.00
	Unit Sub Total	**LF**		**1**	**40.00**	**$330.00**	**$13,200.00**
	Item Code 561006 Total No. of Proj.			**1**		**Total Amount**	**$13,200.00**
561008	760 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	8	1	3.40	$2,250.00	$7,650.00
	Unit Sub Total	**M**		**1**	**3.40**	**$2,250.00**	**$7,650.00**
	Item Code 561008 Total No. of Proj.			**1**		**Total Amount**	**$7,650.00**
561009	920 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	7	1	19.00	$2,600.00	$49,400.00
		M	8	1	20.00	$2,800.00	$56,000.00
		M	11	1	17.00	$1,800.00	$30,600.00
	Unit Sub Total	**M**		**3**	**56.00**	**$2,428.57**	**$136,000.00**
	Item Code 561009 Total No. of Proj.			**3**		**Total Amount**	**$136,000.00**
561011	48" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	3	1	22.00	$550.00	$12,100.00
		LF	8	1	24.00	$2,000.00	$48,000.00
	Unit Sub Total	**LF**		**2**	**46.00**	**$1,306.52**	**$60,100.00**
	Item Code 561011 Total No. of Proj.			**2**		**Total Amount**	**$60,100.00**
561013	1372 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	3	2	30.20	$2,000.00	$60,400.00
		M	8	1	6.00	$4,400.00	$26,400.00
		M	11	1	5.00	$2,600.00	$13,000.00
	Unit Sub Total	**M**		**4**	**41.20**	**$2,422.33**	**$99,800.00**
	Item Code 561013 Total No. of Proj.			**4**		**Total Amount**	**$99,800.00**
561014	54" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	3	1	280.00	$550.00	$154,000.00
		LF	12	1	19.00	$950.00	$18,050.00
	Unit Sub Total	**LF**		**2**	**299.00**	**$575.42**	**$172,050.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 561014 Total No. of Proj.			**2**		**Total Amount**	**$172,050.00**
561015	1524 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	3	2	188.50	$2,194.83	$413,725.00
		M	4	7	281.20	$2,509.03	$705,540.00
		M	6	3	21.00	$3,066.67	$64,400.00
		M	7	4	226.00	$2,624.27	$593,085.00
		M	8	3	276.00	$2,137.32	$589,900.00
		M	11	2	85.00	$2,320.00	$197,200.00
	Unit Sub Total	**M**		**21**	**1,077.70**	**$2,379.00**	**$2,563,850.00**
	Item Code 561015 Total No. of Proj.			**21**		**Total Amount**	**$2,563,850.00**
561016	60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	2	1	90.00	$1,200.00	$108,000.00
		LF	3	2	750.00	$620.00	$465,000.00
		LF	4	2	198.00	$2,400.00	$475,200.00
		LF	6	1	99.00	$675.00	$66,825.00
		LF	7	3	305.00	$717.70	$218,900.00
		LF	8	2	160.00	$694.00	$111,040.00
		LF	11	2	72.00	$1,180.00	$84,960.00
		LF	12	3	268.00	$742.01	$198,860.00
	Unit Sub Total	**LF**		**16**	**1,942.00**	**$890.21**	**$1,728,785.00**
	Item Code 561016 Total No. of Proj.			**16**		**Total Amount**	**$1,728,785.00**
562001	METAL (ROADSIDE SIGN)	KG	4	2	262.00	$45.60	$11,948.00
	Unit Sub Total	**KG**		**2**	**262.00**	**$45.60**	**$11,948.00**
	Item Code 562001 Total No. of Proj.			**2**		**Total Amount**	**$11,948.00**
562002	METAL (BARRIER MOUNTED SIGN)	KG	4	1	12.00	$70.00	$840.00
		KG	7	4	3,210.00	$20.63	$66,225.00
		KG	11	1	200.00	$25.00	$5,000.00
	Unit Sub Total	**KG**		**6**	**3,422.00**	**$21.06**	**$72,065.00**
562002	METAL (BARRIER MOUNTED SIGN)	LB	2	1	350.00	$11.00	$3,850.00
	Unit Sub Total	**LB**		**1**	**350.00**	**$11.00**	**$3,850.00**
	Item Code 562002 Total No. of Proj.			**7**		**Total Amount**	**$75,915.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
562004	METAL (RAIL MOUNTED SIGN)		KG	4	4	5,450.00	$14.97	$81,560.00
			KG	11	1	1,360.00	$32.00	$43,520.00
		Unit Sub Total	**KG**		**5**	**6,810.00**	**$18.37**	**$125,080.00**
562004	METAL (RAIL MOUNTED SIGN)		LB	4	2	1,390.00	$13.45	$18,690.00
			LB	7	2	580.00	$9.72	$5,640.00
			LB	10	1	210.00	$15.00	$3,150.00
			LB	11	1	720.00	$14.00	$10,080.00
			LB	12	1	170.00	$13.00	$2,210.00
		Unit Sub Total	**LB**		**7**	**3,070.00**	**$12.95**	**$39,770.00**
	Item Code 562004	**Total No. of Proj.**			**12**		**Total Amount**	**$164,850.00**
566011	ROADSIDE SIGN - ONE POST		EA	1	6	39.00	$286.41	$11,170.04
			EA	2	11	83.00	$289.88	$24,060.00
			EA	3	14	334.00	$187.74	$62,705.00
			EA	4	17	384.00	$179.36	$68,875.00
			EA	5	7	166.00	$230.09	$38,195.40
			EA	6	12	647.00	$192.02	$124,237.00
			EA	7	11	3,222.00	$228.73	$736,966.00
			EA	8	18	306.00	$233.68	$71,505.00
			EA	9	2	64.00	$255.47	$16,350.00
			EA	10	12	97.00	$215.81	$20,934.00
			EA	11	8	415.00	$336.82	$139,780.00
			EA	12	15	171.00	$209.93	$35,897.20
		Unit Sub Total	**EA**		**133**	**5,928.00**	**$227.85**	**$1,350,674.64**
	Item Code 566011	**Total No. of Proj.**			**133**		**Total Amount**	**$1,350,674.64**
566012	ROADSIDE SIGN - TWO POST		EA	2	5	19.00	$588.95	$11,190.00
			EA	3	7	55.00	$323.00	$17,765.00
			EA	4	10	61.00	$343.77	$20,970.00
			EA	5	4	20.00	$350.70	$7,014.00
			EA	6	4	40.00	$277.25	$11,090.00
			EA	7	9	297.00	$567.83	$168,645.00
			EA	8	6	32.00	$613.94	$19,646.00
			EA	9	3	10.00	$576.00	$5,760.00
			EA	10	4	16.00	$265.44	$4,247.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
566012	ROADSIDE SIGN - TWO POST	EA	11	6	70.00	$930.36	$65,125.00
		EA	12	6	19.00	$534.71	$10,159.52
	Unit Sub Total	**EA**		**64**	**639.00**	**$534.60**	**$341,611.52**
	Item Code 566012 Total No. of Proj.			**64**		**Total Amount**	**$341,611.52**
568001	INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	2	1	1.00	$50.00	$50.00
		EA	3	8	103.00	$82.77	$8,525.00
		EA	4	8	81.00	$73.27	$5,935.00
		EA	7	14	172.00	$133.80	$23,013.00
		EA	8	2	11.00	$171.82	$1,890.00
		EA	9	1	23.00	$75.00	$1,725.00
		EA	10	4	7.00	$112.71	$789.00
		EA	11	7	102.00	$103.24	$10,530.00
		EA	12	5	29.00	$118.69	$3,442.00
	Unit Sub Total	**EA**		**50**	**529.00**	**$105.67**	**$55,899.00**
	Item Code 568001 Total No. of Proj.			**50**		**Total Amount**	**$55,899.00**
568007	INSTALL SIGN OVERLAY	M2	4	3	15.30	$182.68	$2,795.00
		M2	7	1	1.10	$220.00	$242.00
		M2	11	1	1.00	$100.00	$100.00
	Unit Sub Total	**M2**		**5**	**17.40**	**$180.29**	**$3,137.00**
568007	INSTALL SIGN OVERLAY	SQFT	6	1	40.00	$10.70	$428.00
		SQFT	7	1	150.00	$6.00	$900.00
		SQFT	8	1	78.00	$20.00	$1,560.00
	Unit Sub Total	**SQFT**		**3**	**268.00**	**$10.78**	**$2,888.00**
	Item Code 568007 Total No. of Proj.			**8**		**Total Amount**	**$6,025.00**
568015	INSTALL SIGN (MAST-ARM HANGER METHOD)	EA	7	1	8.00	$500.00	$4,000.00
		EA	11	1	2.00	$230.00	$460.00
	Unit Sub Total	**EA**		**2**	**10.00**	**$446.00**	**$4,460.00**
	Item Code 568015 Total No. of Proj.			**2**		**Total Amount**	**$4,460.00**
568016	INSTALL SIGN PANEL ON EXISTING FRAME	EA	2	1	2.00	$500.00	$1,000.00
		EA	8	2	21.00	$749.52	$15,740.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**3**	**23.00**	**$727.83**	**$16,740.00**
568016	INSTALL SIGN PANEL ON EXISTING FRAME		M2	3	1	16.00	$60.00	$960.00
			M2	4	5	290.00	$335.29	$97,235.00
			M2	7	2	104.00	$40.31	$4,192.00
			M2	11	1	40.00	$110.00	$4,400.00
		Unit Sub Total	**M2**		**9**	**450.00**	**$237.30**	**$106,787.00**
568016	INSTALL SIGN PANEL ON EXISTING FRAME		SQFT	3	1	210.00	$40.00	$8,400.00
			SQFT	7	2	10,110.00	$7.06	$71,412.00
			SQFT	8	1	320.00	$22.00	$7,040.00
			SQFT	11	1	300.00	$17.00	$5,100.00
			SQFT	12	1	840.00	$3.00	$2,520.00
		Unit Sub Total	**SQFT**		**6**	**11,780.00**	**$8.02**	**$94,472.00**
	Item Code 568016	**Total No. of Proj.**			**18**		**Total Amount**	**$217,999.00**
568017	INSTALL ROADSIDE SIGN PANEL ON EXISTING POST		EA	3	3	3.00	$146.00	$438.00
			EA	4	2	32.00	$137.19	$4,390.00
			EA	5	2	3.00	$165.17	$495.50
			EA	7	1	69.00	$150.00	$10,350.00
			EA	8	3	10.00	$170.00	$1,700.00
			EA	10	2	5.00	$125.00	$625.00
			EA	11	6	170.00	$112.65	$19,150.00
			EA	12	7	108.00	$70.33	$7,595.50
		Unit Sub Total	**EA**		**26**	**400.00**	**$111.86**	**$44,744.00**
	Item Code 568017	**Total No. of Proj.**			**26**		**Total Amount**	**$44,744.00**
568023	INSTALL ROADSIDE SIGN (LAMINATED WOOD BOX POST)		EA	2	3	12.00	$1,500.00	$18,000.00
			EA	4	1	2.00	$1,000.00	$2,000.00
			EA	5	1	3.00	$3,000.00	$9,000.00
			EA	7	2	22.00	$728.41	$16,025.00
			EA	8	4	44.00	$2,639.55	$116,140.00
			EA	11	1	1.00	$1,900.00	$1,900.00
			EA	12	1	1.00	$3,800.00	$3,800.00
		Unit Sub Total	**EA**		**13**	**85.00**	**$1,963.12**	**$166,865.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 568023	**Total No. of Proj.**			**13**		**Total Amount**	**$166,865.00**
575004	TIMBER LAGGING		M3	4	1	133.10	$2,000.00	$266,200.00
		Unit Sub Total	**M3**		**1**	**133.10**	**$2,000.00**	**$266,200.00**
575004	TIMBER LAGGING		MFBM	1	4	52.20	$2,925.38	$152,705.00
			MFBM	2	1	15.00	$3,450.00	$51,750.00
			MFBM	5	4	87.00	$2,896.55	$252,000.00
			MFBM	7	2	28.00	$2,804.50	$78,526.00
			MFBM	10	1	3.30	$5,000.00	$16,500.00
		Unit Sub Total	**MFBM**		**12**	**185.50**	**$2,972.94**	**$551,481.00**
	Item Code 575004	**Total No. of Proj.**			**13**		**Total Amount**	**$817,681.00**
590106	CLEAN STRUCTURAL STEEL (EXISTING BRIDGE)		LS	2	2	2.00	$78,000.00	$156,000.00
			LS	3	2	2.00	$480,977.50	$961,955.00
			LS	6	1	1.00	$77,700.00	$77,700.00
			LS	10	3	3.00	$34,023.33	$102,070.00
		Unit Sub Total	**LS**		**8**	**8.00**	**$162,215.63**	**$1,297,725.00**
	Item Code 590106	**Total No. of Proj.**			**8**		**Total Amount**	**$1,297,725.00**
590111	PAINT STRUCTURAL STEEL (EXISTING BRIDGE)		LS	2	2	2.00	$256,000.00	$512,000.00
			LS	3	2	2.00	$181,412.50	$362,825.00
			LS	6	1	1.00	$529,900.00	$529,900.00
			LS	10	4	4.00	$67,310.00	$269,240.00
		Unit Sub Total	**LS**		**9**	**9.00**	**$185,996.11**	**$1,673,965.00**
	Item Code 590111	**Total No. of Proj.**			**9**		**Total Amount**	**$1,673,965.00**
590115	CLEAN AND PAINT STRUCTURAL STEEL		LS	2	2	2.00	$67,500.00	$135,000.00
			LS	3	1	1.00	$35,000.00	$35,000.00
			LS	4	4	4.00	$51,250.00	$205,000.00
			LS	5	1	1.00	$3,400.00	$3,400.00
			LS	7	1	1.00	$100,000.00	$100,000.00
			LS	10	2	2.00	$3,000.00	$6,000.00
		Unit Sub Total	**LS**		**11**	**11.00**	**$44,036.36**	**$484,400.00**
	Item Code 590115	**Total No. of Proj.**			**11**		**Total Amount**	**$484,400.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
590116	CLEAN AND PAINT STRUCTURAL STEEL (EXISTING BRIDGE)	LS	3	1	1.00	$297,566.00	$297,566.00
		LS	4	1	1.00	$5,000.00	$5,000.00
		LS	12	1	1.00	$965,063.00	$965,063.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$422,543.00**	**$1,267,629.00**
	Item Code 590116 Total No. of Proj.			**3**		**Total Amount**	**$1,267,629.00**
590135	SPOT BLAST CLEAN AND PAINT UNDERCOAT	SQFT	2	2	14,930.00	$27.58	$411,748.00
		SQFT	3	1	10,395.00	$35.00	$363,825.00
		SQFT	6	1	8,292.00	$26.00	$215,592.00
		SQFT	10	4	6,054.00	$101.89	$616,830.00
	Unit Sub Total	**SQFT**		**8**	**39,671.00**	**$40.53**	**$1,607,995.00**
	Item Code 590135 Total No. of Proj.			**8**		**Total Amount**	**$1,607,995.00**
590136	SPOT BLAST CLEAN AND PAINT UNDERCOAT (LOCATION A)	SQFT	12	1	2,457.00	$25.00	$61,425.00
	Unit Sub Total	**SQFT**		**1**	**2,457.00**	**$25.00**	**$61,425.00**
	Item Code 590136 Total No. of Proj.			**1**		**Total Amount**	**$61,425.00**
590137	SPOT BLAST CLEAN AND PAINT UNDERCOAT (LOCATION B)	SQFT	12	1	1,462.00	$25.00	$36,550.00
	Unit Sub Total	**SQFT**		**1**	**1,462.00**	**$25.00**	**$36,550.00**
	Item Code 590137 Total No. of Proj.			**1**		**Total Amount**	**$36,550.00**
590280	PAINT CONCRETE SURFACES	SQFT	8	1	1.00	$25.00	$25.00
		SQFT	12	2	3,180.00	$1.60	$5,092.00
	Unit Sub Total	**SQFT**		**3**	**3,181.00**	**$1.61**	**$5,117.00**
	Item Code 590280 Total No. of Proj.			**3**		**Total Amount**	**$5,117.00**
590301	WORK AREA MONITORING	LS	2	3	3.00	$9,666.67	$29,000.00
		LS	3	4	4.00	$4,733.75	$18,935.00
		LS	4	1	1.00	$4,000.00	$4,000.00
		LS	6	1	1.00	$40,500.00	$40,500.00
		LS	10	4	4.00	$3,000.00	$12,000.00
		LS	12	1	1.00	$12,784.00	$12,784.00
	Unit Sub Total	**LS**		**14**	**14.00**	**$8,372.79**	**$117,219.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 590301	**Total No. of Proj.**			**14**		**Total Amount**	**$117,219.00**
597401	PAINT CURB (2-COAT)		LF	2	1	33.00	$55.00	$1,815.00
			LF	9	1	66.00	$10.00	$660.00
		Unit Sub Total	**LF**		**2**	**99.00**	**$25.00**	**$2,475.00**
597401	PAINT CURB (2-COAT)		SQFT	4	1	250.00	$1.00	$250.00
			SQFT	7	2	295.00	$1.13	$332.50
			SQFT	12	1	2,670.00	$0.55	$1,468.50
		Unit Sub Total	**SQFT**		**4**	**3,215.00**	**$0.64**	**$2,051.00**
	Item Code 597401	**Total No. of Proj.**			**6**		**Total Amount**	**$4,526.00**
597600	PREPARE AND PAINT CONCRETE		M2	2	1	379.00	$75.00	$28,425.00
			M2	3	1	751.00	$60.00	$45,060.00
			M2	11	1	340.00	$24.00	$8,160.00
		Unit Sub Total	**M2**		**3**	**1,470.00**	**$55.54**	**$81,645.00**
	Item Code 597600	**Total No. of Proj.**			**3**		**Total Amount**	**$81,645.00**
597601	PREPARE AND STAIN CONCRETE		LS	8	1	1.00	$110,000.00	$110,000.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$110,000.00**	**$110,000.00**
597601	PREPARE AND STAIN CONCRETE		M2	4	1	3,425.00	$13.50	$46,237.50
			M2	10	1	7,100.00	$43.00	$305,300.00
		Unit Sub Total	**M2**		**2**	**10,525.00**	**$33.40**	**$351,537.50**
597601	PREPARE AND STAIN CONCRETE		SQFT	2	2	7,665.00	$3.59	$27,554.00
			SQFT	3	1	24,415.00	$4.00	$97,660.00
			SQFT	5	1	55,000.00	$7.25	$398,750.00
			SQFT	12	1	57,400.00	$1.00	$57,400.00
		Unit Sub Total	**SQFT**		**5**	**144,480.00**	**$4.02**	**$581,364.00**
	Item Code 597601	**Total No. of Proj.**			**8**		**Total Amount**	**$1,042,901.50**
620020	8" ALTERNATIVE PIPE CULVERT		LF	2	1	62.00	$46.50	$2,883.00
		Unit Sub Total	**LF**		**1**	**62.00**	**$46.50**	**$2,883.00**
	Item Code 620020	**Total No. of Proj.**			**1**		**Total Amount**	**$2,883.00**
620060	12" ALTERNATIVE PIPE CULVERT		LF	3	1	40.00	$40.00	$1,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
620060	12" ALTERNATIVE PIPE CULVERT	LF	4	2	450.00	$59.33	$26,700.00
		LF	5	1	30.00	$105.00	$3,150.00
	Unit Sub Total	**LF**		**4**	**520.00**	**$60.48**	**$31,450.00**
	Item Code 620060 Total No. of Proj.			**4**		**Total Amount**	**$31,450.00**
620080	15" ALTERNATIVE PIPE CULVERT	LF	4	1	62.00	$100.00	$6,200.00
	Unit Sub Total	**LF**		**1**	**62.00**	**$100.00**	**$6,200.00**
	Item Code 620080 Total No. of Proj.			**1**		**Total Amount**	**$6,200.00**
620100	18" ALTERNATIVE PIPE CULVERT	LF	1	1	52.00	$70.00	$3,640.00
		LF	2	1	24.00	$103.75	$2,490.00
		LF	3	1	3,500.00	$80.00	$280,000.00
		LF	4	4	5,397.00	$63.12	$340,675.72
		LF	5	4	3,063.00	$34.20	$104,769.00
	Unit Sub Total	**LF**		**11**	**12,036.00**	**$60.78**	**$731,574.72**
	Item Code 620100 Total No. of Proj.			**11**		**Total Amount**	**$731,574.72**
620101	18" ALTERNATIVE PIPE CULVERT (TYPE A)	LF	4	1	410.00	$52.00	$21,320.00
	Unit Sub Total	**LF**		**1**	**410.00**	**$52.00**	**$21,320.00**
	Item Code 620101 Total No. of Proj.			**1**		**Total Amount**	**$21,320.00**
620120	21" ALTERNATIVE PIPE CULVERT	LF	4	1	63.00	$70.00	$4,410.00
	Unit Sub Total	**LF**		**1**	**63.00**	**$70.00**	**$4,410.00**
	Item Code 620120 Total No. of Proj.			**1**		**Total Amount**	**$4,410.00**
620140	24" ALTERNATIVE PIPE CULVERT	LF	1	2	168.00	$75.21	$12,635.00
		LF	2	4	1,397.00	$72.51	$101,295.00
		LF	3	1	540.00	$90.00	$48,600.00
		LF	4	1	110.00	$75.00	$8,250.00
		LF	5	3	686.00	$37.58	$25,780.00
		LF	6	2	2,672.00	$45.45	$121,450.00
		LF	11	1	2,030.00	$67.00	$136,010.00
		LF	12	1	9,030.00	$44.00	$397,320.00
	Unit Sub Total	**LF**		**15**	**16,633.00**	**$51.18**	**$851,340.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 620140 Total No. of Proj.			**15**		**Total Amount**	**$851,340.00**
620180	30" ALTERNATIVE PIPE CULVERT	LF	2	1	84.00	$165.00	$13,860.00
		LF	3	1	24.00	$100.00	$2,400.00
		LF	4	1	490.00	$125.00	$61,250.00
		LF	5	2	81.00	$105.19	$8,520.00
	Unit Sub Total	**LF**		**5**	**679.00**	**$126.70**	**$86,030.00**
	Item Code 620180 Total No. of Proj.			**5**		**Total Amount**	**$86,030.00**
620220	36" ALTERNATIVE PIPE CULVERT	LF	12	1	180.00	$146.00	$26,280.00
	Unit Sub Total	**LF**		**1**	**180.00**	**$146.00**	**$26,280.00**
	Item Code 620220 Total No. of Proj.			**1**		**Total Amount**	**$26,280.00**
620260	42" ALTERNATIVE PIPE CULVERT	LF	3	1	80.00	$170.00	$13,600.00
	Unit Sub Total	**LF**		**1**	**80.00**	**$170.00**	**$13,600.00**
	Item Code 620260 Total No. of Proj.			**1**		**Total Amount**	**$13,600.00**
620300	48" ALTERNATIVE PIPE CULVERT	LF	3	1	46.00	$220.00	$10,120.00
		LF	12	1	16.00	$350.00	$5,600.00
	Unit Sub Total	**LF**		**2**	**62.00**	**$253.55**	**$15,720.00**
	Item Code 620300 Total No. of Proj.			**2**		**Total Amount**	**$15,720.00**
620340	54" ALTERNATIVE PIPE CULVERT	LF	4	1	410.00	$180.00	$73,800.00
	Unit Sub Total	**LF**		**1**	**410.00**	**$180.00**	**$73,800.00**
	Item Code 620340 Total No. of Proj.			**1**		**Total Amount**	**$73,800.00**
620901	150 MM ALTERNATIVE PIPE CULVERT	M	5	1	40.00	$150.00	$6,000.00
	Unit Sub Total	**M**		**1**	**40.00**	**$150.00**	**$6,000.00**
	Item Code 620901 Total No. of Proj.			**1**		**Total Amount**	**$6,000.00**
620904	300 MM ALTERNATIVE PIPE CULVERT	M	4	2	155.00	$193.87	$30,050.00
		M	6	1	55.00	$300.00	$16,500.00
		M	8	1	110.00	$262.00	$28,820.00
		M	10	2	111.00	$47.16	$5,235.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**6**	**431.00**	**$187.02**	**$80,605.00**
	Item Code 620904 Total No. of Proj.			**6**		**Total Amount**	**$80,605.00**
620905	300 MM ALTERNATIVE PIPE CULVERT (TYPE A)	M	4	3	211.30	$79.91	$16,885.00
	Unit Sub Total	**M**		**3**	**211.30**	**$79.91**	**$16,885.00**
	Item Code 620905 Total No. of Proj.			**3**		**Total Amount**	**$16,885.00**
620906	300 MM ALTERNATIVE PIPE CULVERT (TYPE B)	M	4	2	354.00	$185.51	$65,670.00
	Unit Sub Total	**M**		**2**	**354.00**	**$185.51**	**$65,670.00**
	Item Code 620906 Total No. of Proj.			**2**		**Total Amount**	**$65,670.00**
620908	375 MM ALTERNATIVE PIPE CULVERT	M	3	1	13.00	$125.00	$1,625.00
		M	4	2	169.00	$100.23	$16,939.00
		M	8	1	320.00	$308.00	$98,560.00
		M	10	1	6.00	$70.00	$420.00
	Unit Sub Total	**M**		**5**	**508.00**	**$231.39**	**$117,544.00**
	Item Code 620908 Total No. of Proj.			**5**		**Total Amount**	**$117,544.00**
620909	450 MM ALTERNATIVE PIPE CULVERT	M	1	1	11.00	$250.00	$2,750.00
		M	2	1	3.00	$600.00	$1,800.00
		M	3	4	1,980.00	$93.51	$185,150.00
		M	4	3	4,027.00	$154.54	$622,320.00
		M	5	2	370.00	$212.43	$78,600.00
		M	6	2	441.00	$196.28	$86,560.00
		M	8	3	4,520.00	$137.01	$619,300.00
		M	10	1	22.00	$100.00	$2,200.00
		M	11	2	1,270.00	$90.53	$114,970.00
	Unit Sub Total	**M**		**19**	**12,644.00**	**$135.53**	**$1,713,650.00**
	Item Code 620909 Total No. of Proj.			**19**		**Total Amount**	**$1,713,650.00**
620910	450 MM ALTERNATIVE PIPE CULVERT (TYPE A)	M	4	6	5,670.00	$163.70	$928,170.00
	Unit Sub Total	**M**		**6**	**5,670.00**	**$163.70**	**$928,170.00**
	Item Code 620910 Total No. of Proj.			**6**		**Total Amount**	**$928,170.00**
620911	450 MM ALTERNATIVE PIPE CULVERT (TYPE B)	M	4	5	1,400.00	$172.96	$242,140.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**5**	**1,400.00**	**$172.96**	**$242,140.00**
	Item Code 620911 Total No. of Proj.			**5**		**Total Amount**	**$242,140.00**
620913	600 MM ALTERNATIVE PIPE CULVERT	M	1	2	550.00	$380.15	$209,080.00
		M	2	1	540.00	$400.00	$216,000.00
		M	3	4	513.00	$155.65	$79,850.00
		M	4	4	2,857.00	$213.83	$610,925.00
		M	5	1	1,150.00	$180.00	$207,000.00
		M	6	2	3,030.00	$155.96	$472,550.00
		M	8	3	1,572.00	$120.25	$189,040.00
		M	10	1	71.00	$250.00	$17,750.00
		M	11	2	3,920.00	$106.86	$418,880.00
	Unit Sub Total	**M**		**20**	**14,203.00**	**$170.46**	**$2,421,075.00**
	Item Code 620913 Total No. of Proj.			**20**		**Total Amount**	**$2,421,075.00**
620914	600 MM ALTERNATIVE PIPE CULVERT (TYPE A)	M	4	5	778.00	$227.60	$177,072.00
		M	9	1	25.00	$300.00	$7,500.00
	Unit Sub Total	**M**		**6**	**803.00**	**$229.85**	**$184,572.00**
	Item Code 620914 Total No. of Proj.			**6**		**Total Amount**	**$184,572.00**
620915	600 MM ALTERNATIVE PIPE CULVERT (TYPE B)	M	4	4	534.00	$279.87	$149,452.00
	Unit Sub Total	**M**		**4**	**534.00**	**$279.87**	**$149,452.00**
	Item Code 620915 Total No. of Proj.			**4**		**Total Amount**	**$149,452.00**
620916	600 MM ALTERNATIVE PIPE CULVERT (TYPE C)	M	4	1	330.00	$416.00	$137,280.00
	Unit Sub Total	**M**		**1**	**330.00**	**$416.00**	**$137,280.00**
	Item Code 620916 Total No. of Proj.			**1**		**Total Amount**	**$137,280.00**
620919	750 MM ALTERNATIVE PIPE CULVERT	M	2	1	170.00	$900.00	$153,000.00
		M	3	2	183.00	$281.97	$51,600.00
		M	4	6	892.00	$277.14	$247,205.00
		M	6	1	930.00	$150.00	$139,500.00
		M	8	1	190.00	$165.00	$31,350.00
		M	11	1	850.00	$140.00	$119,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**12**	**3,215.00**	**$230.69**	**$741,655.00**
	Item Code 620919 Total No. of Proj.			**12**		**Total Amount**	**$741,655.00**
620920	750 MM ALTERNATIVE PIPE CULVERT (TYPE A)	M	4	1	290.00	$185.00	$53,650.00
	Unit Sub Total	**M**		**1**	**290.00**	**$185.00**	**$53,650.00**
	Item Code 620920 Total No. of Proj.			**1**		**Total Amount**	**$53,650.00**
620921	750 MM ALTERNATIVE PIPE CULVERT (TYPE B)	M	4	1	360.00	$120.00	$43,200.00
	Unit Sub Total	**M**		**1**	**360.00**	**$120.00**	**$43,200.00**
	Item Code 620921 Total No. of Proj.			**1**		**Total Amount**	**$43,200.00**
620924	900 MM ALTERNATIVE PIPE CULVERT	M	2	1	57.00	$460.00	$26,220.00
		M	3	1	14.00	$295.00	$4,130.00
		M	4	4	352.00	$298.74	$105,157.00
		M	5	1	170.00	$200.00	$34,000.00
		M	6	1	49.00	$250.00	$12,250.00
		M	8	1	400.00	$172.00	$68,800.00
		M	10	1	36.00	$350.00	$12,600.00
		M	11	1	140.00	$180.00	$25,200.00
	Unit Sub Total	**M**		**11**	**1,218.00**	**$236.75**	**$288,357.00**
	Item Code 620924 Total No. of Proj.			**11**		**Total Amount**	**$288,357.00**
620925	900 MM ALTERNATIVE PIPE CULVERT (TYPE A)	M	4	1	260.00	$220.00	$57,200.00
	Unit Sub Total	**M**		**1**	**260.00**	**$220.00**	**$57,200.00**
	Item Code 620925 Total No. of Proj.			**1**		**Total Amount**	**$57,200.00**
620930	1050 MM ALTERNATIVE PIPE CULVERT	M	2	1	24.00	$600.00	$14,400.00
		M	11	1	92.00	$220.00	$20,240.00
	Unit Sub Total	**M**		**2**	**116.00**	**$298.62**	**$34,640.00**
	Item Code 620930 Total No. of Proj.			**2**		**Total Amount**	**$34,640.00**
620933	1200 MM ALTERNATIVE PIPE CULVERT	M	3	1	31.00	$310.00	$9,610.00
		M	4	1	36.00	$284.00	$10,224.00
		M	11	1	88.00	$110.00	$9,680.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**3**	**155.00**	**$190.41**	**$29,514.00**
	Item Code 620933 Total No. of Proj.			**3**		**Total Amount**	**$29,514.00**
620938	1350 MM ALTERNATIVE PIPE CULVERT	M	8	1	46.00	$235.00	$10,810.00
	Unit Sub Total	**M**		**1**	**46.00**	**$235.00**	**$10,810.00**
	Item Code 620938 Total No. of Proj.			**1**		**Total Amount**	**$10,810.00**
620940	1500 MM ALTERNATIVE PIPE CULVERT	M	11	1	83.00	$530.00	$43,990.00
	Unit Sub Total	**M**		**1**	**83.00**	**$530.00**	**$43,990.00**
	Item Code 620940 Total No. of Proj.			**1**		**Total Amount**	**$43,990.00**
625299	42" X 29" ALTERNATIVE PIPE ARCH CULVERT	LF	2	2	940.00	$97.04	$91,216.00
	Unit Sub Total	**LF**		**2**	**940.00**	**$97.04**	**$91,216.00**
	Item Code 625299 Total No. of Proj.			**2**		**Total Amount**	**$91,216.00**
625319	49" X 33" ALTERNATIVE PIPE ARCH CULVERT	LF	2	1	66.00	$151.50	$9,999.00
	Unit Sub Total	**LF**		**1**	**66.00**	**$151.50**	**$9,999.00**
	Item Code 625319 Total No. of Proj.			**1**		**Total Amount**	**$9,999.00**
625382	525 MM X 375 MM ALTERNATIVE PIPE ARCH CULVERT	M	3	1	16.00	$220.00	$3,520.00
	Unit Sub Total	**M**		**1**	**16.00**	**$220.00**	**$3,520.00**
	Item Code 625382 Total No. of Proj.			**1**		**Total Amount**	**$3,520.00**
625391	875 MM X 600 MM ALTERNATIVE PIPE ARCH CULVERT	M	3	1	50.00	$310.00	$15,500.00
		M	5	1	27.00	$400.00	$10,800.00
	Unit Sub Total	**M**		**2**	**77.00**	**$341.56**	**$26,300.00**
	Item Code 625391 Total No. of Proj.			**2**		**Total Amount**	**$26,300.00**
625392	1050 MM X 725 MM ALTERNATIVE PIPE ARCH CULVERT	M	3	1	60.00	$450.00	$27,000.00
	Unit Sub Total	**M**		**1**	**60.00**	**$450.00**	**$27,000.00**
	Item Code 625392 Total No. of Proj.			**1**		**Total Amount**	**$27,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
641101	12" PLASTIC PIPE	LF	3	1	8.00	$100.00	$800.00
		LF	7	1	120.00	$45.00	$5,400.00
	Unit Sub Total	**LF**		**2**	**128.00**	**$48.44**	**$6,200.00**
	Item Code 641101 Total No. of Proj.			**2**		**Total Amount**	**$6,200.00**
641104	15" PLASTIC PIPE	LF	4	1	4.00	$385.00	$1,540.00
	Unit Sub Total	**LF**		**1**	**4.00**	**$385.00**	**$1,540.00**
	Item Code 641104 Total No. of Proj.			**1**		**Total Amount**	**$1,540.00**
641107	18" PLASTIC PIPE	LF	2	1	240.00	$108.00	$25,920.00
		LF	3	1	180.00	$100.00	$18,000.00
		LF	4	1	75.00	$106.03	$7,952.25
		LF	5	2	3,190.00	$36.00	$114,850.00
		LF	6	1	260.00	$60.00	$15,600.00
	Unit Sub Total	**LF**		**6**	**3,945.00**	**$46.22**	**$182,322.25**
	Item Code 641107 Total No. of Proj.			**6**		**Total Amount**	**$182,322.25**
641113	24" PLASTIC PIPE	LF	4	1	37.00	$114.97	$4,253.89
		LF	5	1	1,530.00	$30.00	$45,900.00
		LF	7	1	17.00	$120.00	$2,040.00
	Unit Sub Total	**LF**		**3**	**1,584.00**	**$32.95**	**$52,193.89**
	Item Code 641113 Total No. of Proj.			**3**		**Total Amount**	**$52,193.89**
641119	30" PLASTIC PIPE	LF	4	1	38.00	$139.69	$5,308.22
	Unit Sub Total	**LF**		**1**	**38.00**	**$139.69**	**$5,308.22**
	Item Code 641119 Total No. of Proj.			**1**		**Total Amount**	**$5,308.22**
641132	300 MM PLASTIC PIPE	M	3	1	32.00	$70.00	$2,240.00
	Unit Sub Total	**M**		**1**	**32.00**	**$70.00**	**$2,240.00**
	Item Code 641132 Total No. of Proj.			**1**		**Total Amount**	**$2,240.00**
641133	375 MM PLASTIC PIPE	M	3	1	44.00	$75.00	$3,300.00
	Unit Sub Total	**M**		**1**	**44.00**	**$75.00**	**$3,300.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 641133 Total No. of Proj.			**1**		**Total Amount**	**$3,300.00**
641134	450 MM PLASTIC PIPE	M	3	1	43.00	$100.00	$4,300.00
		M	4	1	87.00	$136.00	$11,832.00
	Unit Sub Total	**M**		**2**	**130.00**	**$124.09**	**$16,132.00**
	Item Code 641134 Total No. of Proj.			**2**		**Total Amount**	**$16,132.00**
641136	600 MM PLASTIC PIPE	M	4	1	4.00	$500.00	$2,000.00
	Unit Sub Total	**M**		**1**	**4.00**	**$500.00**	**$2,000.00**
	Item Code 641136 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
650010	12" REINFORCED CONCRETE PIPE	LF	1	1	70.00	$86.00	$6,020.00
		LF	2	1	35.00	$75.00	$2,625.00
		LF	12	2	37.00	$218.65	$8,090.00
	Unit Sub Total	**LF**		**4**	**142.00**	**$117.85**	**$16,735.00**
	Item Code 650010 Total No. of Proj.			**4**		**Total Amount**	**$16,735.00**
650012	15" REINFORCED CONCRETE PIPE	LF	4	1	18.00	$165.00	$2,970.00
	Unit Sub Total	**LF**		**1**	**18.00**	**$165.00**	**$2,970.00**
	Item Code 650012 Total No. of Proj.			**1**		**Total Amount**	**$2,970.00**
650014	18" REINFORCED CONCRETE PIPE	LF	2	3	165.00	$161.67	$26,675.00
		LF	4	2	24.00	$228.33	$5,480.00
		LF	6	3	257.00	$98.64	$25,350.00
		LF	7	5	2,377.00	$76.75	$182,444.00
		LF	10	3	1,715.00	$55.95	$95,947.00
		LF	12	4	990.00	$160.53	$158,920.00
	Unit Sub Total	**LF**		**20**	**5,528.00**	**$89.51**	**$494,816.00**
	Item Code 650014 Total No. of Proj.			**20**		**Total Amount**	**$494,816.00**
650018	24" REINFORCED CONCRETE PIPE	LF	2	2	106.00	$249.06	$26,400.00
		LF	3	1	310.00	$120.00	$37,200.00
		LF	4	1	60.00	$80.00	$4,800.00
		LF	5	2	212.00	$60.38	$12,800.00
		LF	7	7	9,094.00	$78.08	$710,040.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
650018	24" REINFORCED CONCRETE PIPE	LF	8	1	200.00	$82.00	$16,400.00
		LF	11	2	420.00	$115.24	$48,400.00
		LF	12	3	564.00	$283.00	$159,610.00
	Unit Sub Total	**LF**		**19**	**10,966.00**	**$92.62**	**$1,015,650.00**
	Item Code 650018 Total No. of Proj.			**19**		**Total Amount**	**$1,015,650.00**
650019	27" REINFORCED CONCRETE PIPE	LF	7	1	570.00	$100.00	$57,000.00
	Unit Sub Total	**LF**		**1**	**570.00**	**$100.00**	**$57,000.00**
	Item Code 650019 Total No. of Proj.			**1**		**Total Amount**	**$57,000.00**
650022	30" REINFORCED CONCRETE PIPE	LF	2	2	78.00	$148.08	$11,550.00
		LF	7	1	780.00	$110.00	$85,800.00
	Unit Sub Total	**LF**		**3**	**858.00**	**$113.46**	**$97,350.00**
	Item Code 650022 Total No. of Proj.			**3**		**Total Amount**	**$97,350.00**
650024	33" REINFORCED CONCRETE PIPE	LF	7	1	100.00	$120.00	$12,000.00
	Unit Sub Total	**LF**		**1**	**100.00**	**$120.00**	**$12,000.00**
	Item Code 650024 Total No. of Proj.			**1**		**Total Amount**	**$12,000.00**
650026	36" REINFORCED CONCRETE PIPE	LF	2	2	41.00	$358.84	$14,712.50
		LF	7	2	460.00	$116.52	$53,600.00
		LF	12	1	44.00	$133.00	$5,852.00
	Unit Sub Total	**LF**		**5**	**545.00**	**$136.08**	**$74,164.50**
	Item Code 650026 Total No. of Proj.			**5**		**Total Amount**	**$74,164.50**
650028	39" REINFORCED CONCRETE PIPE	LF	7	1	130.00	$135.00	$17,550.00
	Unit Sub Total	**LF**		**1**	**130.00**	**$135.00**	**$17,550.00**
	Item Code 650028 Total No. of Proj.			**1**		**Total Amount**	**$17,550.00**
650030	42" REINFORCED CONCRETE PIPE	LF	2	1	20.00	$530.00	$10,600.00
		LF	7	1	120.00	$120.00	$14,400.00
		LF	11	1	30.00	$210.00	$6,300.00
	Unit Sub Total	**LF**		**3**	**170.00**	**$184.12**	**$31,300.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 650030 Total No. of Proj.			**3**		**Total Amount**	**$31,300.00**
650034	48" REINFORCED CONCRETE PIPE	LF	2	1	380.00	$200.00	$76,000.00
		LF	11	1	3,450.00	$116.00	$400,200.00
		LF	12	1	140.00	$123.00	$17,220.00
	Unit Sub Total	**LF**		**3**	**3,970.00**	**$124.29**	**$493,420.00**
	Item Code 650034 Total No. of Proj.			**3**		**Total Amount**	**$493,420.00**
650038	54" REINFORCED CONCRETE PIPE	LF	12	1	260.00	$194.00	$50,440.00
	Unit Sub Total	**LF**		**1**	**260.00**	**$194.00**	**$50,440.00**
	Item Code 650038 Total No. of Proj.			**1**		**Total Amount**	**$50,440.00**
650067	300 MM REINFORCED CONCRETE PIPE	M	4	3	25.00	$212.80	$5,320.00
		M	6	1	2.50	$180.00	$450.00
		M	7	1	72.00	$225.00	$16,200.00
	Unit Sub Total	**M**		**5**	**99.50**	**$220.80**	**$21,970.00**
	Item Code 650067 Total No. of Proj.			**5**		**Total Amount**	**$21,970.00**
650068	375 MM REINFORCED CONCRETE PIPE	M	4	1	50.00	$155.00	$7,750.00
		M	6	1	2.30	$220.00	$506.00
		M	7	2	16.00	$353.75	$5,660.00
		M	11	1	4.70	$500.00	$2,350.00
	Unit Sub Total	**M**		**5**	**73.00**	**$222.82**	**$16,266.00**
	Item Code 650068 Total No. of Proj.			**5**		**Total Amount**	**$16,266.00**
650069	450 MM REINFORCED CONCRETE PIPE	M	3	2	690.00	$228.32	$157,540.00
		M	4	3	137.00	$189.42	$25,950.00
		M	5	1	30.00	$275.00	$8,250.00
		M	6	3	244.00	$192.95	$47,080.00
		M	7	4	1,730.00	$180.09	$311,550.00
		M	8	2	350.00	$119.71	$41,900.00
		M	10	4	398.00	$231.81	$92,260.00
		M	11	3	1,130.00	$173.93	$196,540.00
	Unit Sub Total	**M**		**22**	**4,709.00**	**$187.10**	**$881,070.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 650069 Total No. of Proj.			**22**		**Total Amount**	**$881,070.00**
650073	600 MM REINFORCED CONCRETE PIPE (SPECIAL)	M	4	1	41.00	$330.00	$13,530.00
	Unit Sub Total	**M**		**1**	**41.00**	**$330.00**	**$13,530.00**
	Item Code 650073 Total No. of Proj.			**1**		**Total Amount**	**$13,530.00**
650075	600 MM REINFORCED CONCRETE PIPE	M	1	1	56.00	$400.00	$22,400.00
		M	3	3	873.00	$197.69	$172,580.00
		M	6	3	302.00	$210.26	$63,500.00
		M	7	3	1,080.00	$264.26	$285,400.00
		M	8	1	63.00	$126.00	$7,938.00
		M	10	2	381.00	$208.40	$79,400.00
		M	11	3	3,235.00	$191.64	$619,950.00
	Unit Sub Total	**M**		**16**	**5,990.00**	**$208.88**	**$1,251,168.00**
	Item Code 650075 Total No. of Proj.			**16**		**Total Amount**	**$1,251,168.00**
650077	750 MM REINFORCED CONCRETE PIPE	M	3	2	14.00	$865.00	$12,110.00
		M	4	1	9.00	$225.00	$2,025.00
		M	6	1	30.00	$200.00	$6,000.00
		M	7	1	9.00	$900.00	$8,100.00
		M	8	1	200.00	$135.00	$27,000.00
		M	10	1	3.60	$410.00	$1,476.00
		M	11	2	500.00	$264.96	$132,480.00
	Unit Sub Total	**M**		**9**	**765.60**	**$247.11**	**$189,191.00**
	Item Code 650077 Total No. of Proj.			**9**		**Total Amount**	**$189,191.00**
650079	900 MM REINFORCED CONCRETE PIPE	M	3	3	72.00	$651.39	$46,900.00
		M	4	2	22.00	$518.18	$11,400.00
		M	6	1	2.00	$500.00	$1,000.00
		M	7	1	5.00	$1,500.00	$7,500.00
		M	8	1	27.00	$142.00	$3,834.00
		M	10	1	19.00	$453.00	$8,607.00
		M	11	2	100.00	$333.68	$33,368.00
	Unit Sub Total	**M**		**11**	**247.00**	**$455.91**	**$112,609.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 650079 Total No. of Proj.			**11**		**Total Amount**	**$112,609.00**
650081	1050 MM REINFORCED CONCRETE PIPE	M	11	1	63.00	$989.00	$62,307.00
	Unit Sub Total	**M**		**1**	**63.00**	**$989.00**	**$62,307.00**
	Item Code 650081 Total No. of Proj.			**1**		**Total Amount**	**$62,307.00**
650084	1200 MM REINFORCED CONCRETE PIPE	M	6	1	91.00	$550.00	$50,050.00
		M	8	1	32.00	$235.00	$7,520.00
		M	10	1	15.00	$500.00	$7,500.00
		M	11	2	249.00	$478.55	$119,160.00
	Unit Sub Total	**M**		**5**	**387.00**	**$476.05**	**$184,230.00**
	Item Code 650084 Total No. of Proj.			**5**		**Total Amount**	**$184,230.00**
650086	1350 MM REINFORCED CONCRETE PIPE	M	8	1	56.00	$352.00	$19,712.00
	Unit Sub Total	**M**		**1**	**56.00**	**$352.00**	**$19,712.00**
	Item Code 650086 Total No. of Proj.			**1**		**Total Amount**	**$19,712.00**
650089	1500 MM REINFORCED CONCRETE PIPE	M	8	1	120.00	$369.00	$44,280.00
	Unit Sub Total	**M**		**1**	**120.00**	**$369.00**	**$44,280.00**
	Item Code 650089 Total No. of Proj.			**1**		**Total Amount**	**$44,280.00**
650091	1650 MM REINFORCED CONCRETE PIPE	M	11	1	68.00	$861.00	$58,548.00
	Unit Sub Total	**M**		**1**	**68.00**	**$861.00**	**$58,548.00**
	Item Code 650091 Total No. of Proj.			**1**		**Total Amount**	**$58,548.00**
650094	2100 MM REINFORCED CONCRETE PIPE	M	11	1	96.00	$1,200.00	$115,200.00
	Unit Sub Total	**M**		**1**	**96.00**	**$1,200.00**	**$115,200.00**
	Item Code 650094 Total No. of Proj.			**1**		**Total Amount**	**$115,200.00**
650105	18" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	LF	6	1	28.00	$130.00	$3,640.00
		LF	10	2	460.00	$132.83	$61,100.00
	Unit Sub Total	**LF**		**3**	**488.00**	**$132.66**	**$64,740.00**
	Item Code 650105 Total No. of Proj.			**3**		**Total Amount**	**$64,740.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
650107	24" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	LF	6	1	1,630.00	$50.00	$81,500.00
	Unit Sub Total	**LF**		**1**	**1,630.00**	**$50.00**	**$81,500.00**
	Item Code 650107 Total No. of Proj.			**1**		**Total Amount**	**$81,500.00**
650127	450 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	6	1	450.00	$130.00	$58,500.00
		M	10	2	1,240.00	$215.32	$267,000.00
	Unit Sub Total	**M**		**3**	**1,690.00**	**$192.60**	**$325,500.00**
	Item Code 650127 Total No. of Proj.			**3**		**Total Amount**	**$325,500.00**
650128	600 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	10	3	427.00	$185.08	$79,030.00
	Unit Sub Total	**M**		**3**	**427.00**	**$185.08**	**$79,030.00**
	Item Code 650128 Total No. of Proj.			**3**		**Total Amount**	**$79,030.00**
650129	750 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	6	1	100.00	$225.00	$22,500.00
	Unit Sub Total	**M**		**1**	**100.00**	**$225.00**	**$22,500.00**
	Item Code 650129 Total No. of Proj.			**1**		**Total Amount**	**$22,500.00**
650130	900 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	10	1	44.00	$300.00	$13,200.00
	Unit Sub Total	**M**		**1**	**44.00**	**$300.00**	**$13,200.00**
	Item Code 650130 Total No. of Proj.			**1**		**Total Amount**	**$13,200.00**
650131	1050 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	6	1	1,880.00	$280.00	$526,400.00
		M	10	1	24.00	$900.00	$21,600.00
	Unit Sub Total	**M**		**2**	**1,904.00**	**$287.82**	**$548,000.00**
	Item Code 650131 Total No. of Proj.			**2**		**Total Amount**	**$548,000.00**
650132	1200 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	6	1	240.00	$475.00	$114,000.00
	Unit Sub Total	**M**		**1**	**240.00**	**$475.00**	**$114,000.00**
	Item Code 650132 Total No. of Proj.			**1**		**Total Amount**	**$114,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
650220	30" REINFORCED CONCRETE PIPE (CLASS II)	LF	3	1	1,130.00	$60.00	$67,800.00
	Unit Sub Total	**LF**		**1**	**1,130.00**	**$60.00**	**$67,800.00**
	Item Code 650220 Total No. of Proj.			**1**		**Total Amount**	**$67,800.00**
650224	36" REINFORCED CONCRETE PIPE (CLASS II)	LF	3	1	170.00	$70.00	$11,900.00
	Unit Sub Total	**LF**		**1**	**170.00**	**$70.00**	**$11,900.00**
	Item Code 650224 Total No. of Proj.			**1**		**Total Amount**	**$11,900.00**
650311	18" REINFORCED CONCRETE PIPE (CLASS III)	LF	2	1	18.00	$108.00	$1,944.00
	Unit Sub Total	**LF**		**1**	**18.00**	**$108.00**	**$1,944.00**
	Item Code 650311 Total No. of Proj.			**1**		**Total Amount**	**$1,944.00**
650411	18" REINFORCED CONCRETE PIPE (CLASS IV)	LF	2	1	140.00	$63.00	$8,820.00
	Unit Sub Total	**LF**		**1**	**140.00**	**$63.00**	**$8,820.00**
	Item Code 650411 Total No. of Proj.			**1**		**Total Amount**	**$8,820.00**
650440	60" REINFORCED CONCRETE PIPE (CLASS IV)	LF	5	1	11.00	$450.00	$4,950.00
	Unit Sub Total	**LF**		**1**	**11.00**	**$450.00**	**$4,950.00**
	Item Code 650440 Total No. of Proj.			**1**		**Total Amount**	**$4,950.00**
650470	450 MM REINFORCED CONCRETE PIPE (CLASS IV)	M	4	1	28.00	$300.00	$8,400.00
	Unit Sub Total	**M**		**1**	**28.00**	**$300.00**	**$8,400.00**
	Item Code 650470 Total No. of Proj.			**1**		**Total Amount**	**$8,400.00**
650574	450 MM REINFORCED CONCRETE PIPE (CLASS V)	M	6	1	13.00	$140.00	$1,820.00
	Unit Sub Total	**M**		**1**	**13.00**	**$140.00**	**$1,820.00**
	Item Code 650574 Total No. of Proj.			**1**		**Total Amount**	**$1,820.00**
652215	24" REINFORCED CONCRETE PIPE (CLASS II, RUBBER GASKET JOINT)	LF	3	1	5,840.00	$50.00	$292,000.00
	Unit Sub Total	**LF**		**1**	**5,840.00**	**$50.00**	**$292,000.00**
	Item Code 652215 Total No. of Proj.			**1**		**Total Amount**	**$292,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
655212	JACKED 24" REINFORCED CONCRETE PIPE (CLASS II)	LF	7	1	230.00	$700.00	$161,000.00
	Unit Sub Total	**LF**		**1**	**230.00**	**$700.00**	**$161,000.00**
	Item Code 655212 Total No. of Proj.			**1**		**Total Amount**	**$161,000.00**
655256	JACKED 600 MM REINFORCED CONCRETE PIPE (CLASS II)	M	3	1	37.00	$2,800.00	$103,600.00
	Unit Sub Total	**M**		**1**	**37.00**	**$2,800.00**	**$103,600.00**
	Item Code 655256 Total No. of Proj.			**1**		**Total Amount**	**$103,600.00**
655257	JACKED 750 MM REINFORCED CONCRETE PIPE (CLASS II)	M	4	1	39.00	$1,050.00	$40,950.00
	Unit Sub Total	**M**		**1**	**39.00**	**$1,050.00**	**$40,950.00**
	Item Code 655257 Total No. of Proj.			**1**		**Total Amount**	**$40,950.00**
655311	JACKED 18" REINFORCED CONCRETE PIPE (CLASS III)	LF	10	1	190.00	$480.00	$91,200.00
	Unit Sub Total	**LF**		**1**	**190.00**	**$480.00**	**$91,200.00**
	Item Code 655311 Total No. of Proj.			**1**		**Total Amount**	**$91,200.00**
655365	JACKED 450 MM REINFORCED CONCRETE PIPE (CLASS III)	M	4	1	200.00	$1,800.00	$360,000.00
	Unit Sub Total	**M**		**1**	**200.00**	**$1,800.00**	**$360,000.00**
	Item Code 655365 Total No. of Proj.			**1**		**Total Amount**	**$360,000.00**
655432	JACKED 48" REINFORCED CONCRETE PIPE (CLASS IV)	LF	6	1	40.00	$360.00	$14,400.00
	Unit Sub Total	**LF**		**1**	**40.00**	**$360.00**	**$14,400.00**
	Item Code 655432 Total No. of Proj.			**1**		**Total Amount**	**$14,400.00**
655516	JACKED 24" REINFORCED CONCRETE PIPE (CLASS V)	LF	8	1	80.00	$395.00	$31,600.00
	Unit Sub Total	**LF**		**1**	**80.00**	**$395.00**	**$31,600.00**
	Item Code 655516 Total No. of Proj.			**1**		**Total Amount**	**$31,600.00**
655574	JACKED 600 MM REINFORCED CONCRETE PIPE (CLASS V)	M	7	1	25.00	$1,350.00	$33,750.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**1**	**25.00**	**$1,350.00**	**$33,750.00**
	Item Code 655574 Total No. of Proj.			**1**		**Total Amount**	**$33,750.00**
657343	365 MM X 575 MM OVAL SHAPED REINFORCED CONCRETE PIPE (CLASS III, RUBBER GASKET JOINT)	M	10	1	150.00	$220.00	$33,000.00
	Unit Sub Total	**M**		**1**	**150.00**	**$220.00**	**$33,000.00**
	Item Code 657343 Total No. of Proj.			**1**		**Total Amount**	**$33,000.00**
664008	300 MM CORRUGATED STEEL PIPE	M	4	2	550.00	$80.47	$44,260.00
	Unit Sub Total	**M**		**2**	**550.00**	**$80.47**	**$44,260.00**
	Item Code 664008 Total No. of Proj.			**2**		**Total Amount**	**$44,260.00**
664010	300 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	10	1	120.00	$78.00	$9,360.00
	Unit Sub Total	**M**		**1**	**120.00**	**$78.00**	**$9,360.00**
	Item Code 664010 Total No. of Proj.			**1**		**Total Amount**	**$9,360.00**
664014	450 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	3	1	6.00	$200.00	$1,200.00
	Unit Sub Total	**M**		**1**	**6.00**	**$200.00**	**$1,200.00**
	Item Code 664014 Total No. of Proj.			**1**		**Total Amount**	**$1,200.00**
664015	450 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	4	1	54.00	$183.00	$9,882.00
		M	7	2	273.00	$253.85	$69,300.00
		M	10	2	14.00	$173.86	$2,434.00
	Unit Sub Total	**M**		**5**	**341.00**	**$239.34**	**$81,616.00**
	Item Code 664015 Total No. of Proj.			**5**		**Total Amount**	**$81,616.00**
664016	450 MM CORRUGATED STEEL PIPE (2.77 MM THICK)	M	4	1	59.00	$125.00	$7,375.00
		M	9	1	59.00	$440.00	$25,960.00
		M	10	1	11.00	$240.00	$2,640.00
	Unit Sub Total	**M**		**3**	**129.00**	**$278.88**	**$35,975.00**
	Item Code 664016 Total No. of Proj.			**3**		**Total Amount**	**$35,975.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
664019	600 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	3	1	6.00	$180.00	$1,080.00
	Unit Sub Total	**M**		**1**	**6.00**	**$180.00**	**$1,080.00**
	Item Code 664019 Total No. of Proj.			**1**		**Total Amount**	**$1,080.00**
664020	600 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	7	1	66.00	$285.00	$18,810.00
		M	8	1	5.00	$800.00	$4,000.00
		M	10	1	43.00	$180.00	$7,740.00
	Unit Sub Total	**M**		**3**	**114.00**	**$267.98**	**$30,550.00**
	Item Code 664020 Total No. of Proj.			**3**		**Total Amount**	**$30,550.00**
664021	600 MM CORRUGATED STEEL PIPE (2.77 MM THICK)	M	9	1	59.00	$400.00	$23,600.00
	Unit Sub Total	**M**		**1**	**59.00**	**$400.00**	**$23,600.00**
	Item Code 664021 Total No. of Proj.			**1**		**Total Amount**	**$23,600.00**
664022	600 MM CORRUGATED STEEL PIPE (3.51 MM THICK)	M	1	1	16.00	$360.00	$5,760.00
	Unit Sub Total	**M**		**1**	**16.00**	**$360.00**	**$5,760.00**
	Item Code 664022 Total No. of Proj.			**1**		**Total Amount**	**$5,760.00**
664028	750 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	10	1	7.00	$338.00	$2,366.00
	Unit Sub Total	**M**		**1**	**7.00**	**$338.00**	**$2,366.00**
	Item Code 664028 Total No. of Proj.			**1**		**Total Amount**	**$2,366.00**
664033	900 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	8	2	73.00	$290.75	$21,225.00
		M	10	1	7.00	$395.00	$2,765.00
	Unit Sub Total	**M**		**3**	**80.00**	**$299.88**	**$23,990.00**
	Item Code 664033 Total No. of Proj.			**3**		**Total Amount**	**$23,990.00**
664034	900 MM CORRUGATED STEEL PIPE (2.77 MM THICK)	M	9	1	4.20	$440.00	$1,848.00
	Unit Sub Total	**M**		**1**	**4.20**	**$440.00**	**$1,848.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 664034 Total No. of Proj.			**1**		**Total Amount**	**$1,848.00**
664037	1050 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	6	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**M**		**1**	**1.00**	**$1,000.00**	**$1,000.00**
	Item Code 664037 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
664044	1200 MM CORRUGATED STEEL PIPE (2.77 MM THICK)	M	9	1	6.00	$540.00	$3,240.00
	Unit Sub Total	**M**		**1**	**6.00**	**$540.00**	**$3,240.00**
	Item Code 664044 Total No. of Proj.			**1**		**Total Amount**	**$3,240.00**
664052	1500 MM CORRUGATED STEEL PIPE (2.77 MM THICK)	M	9	1	7.00	$700.00	$4,900.00
	Unit Sub Total	**M**		**1**	**7.00**	**$700.00**	**$4,900.00**
	Item Code 664052 Total No. of Proj.			**1**		**Total Amount**	**$4,900.00**
664064	2100 MM CORRUGATED STEEL PIPE (4.27 MM THICK)	M	10	1	5.00	$860.00	$4,300.00
	Unit Sub Total	**M**		**1**	**5.00**	**$860.00**	**$4,300.00**
	Item Code 664064 Total No. of Proj.			**1**		**Total Amount**	**$4,300.00**
664068	450 MM CORRUGATED STEEL PIPE (3.51 MM THICK)	M	4	1	12.00	$300.00	$3,600.00
	Unit Sub Total	**M**		**1**	**12.00**	**$300.00**	**$3,600.00**
	Item Code 664068 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
664084	300 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (1.63 MM THICK)	M	4	1	40.00	$258.00	$10,320.00
	Unit Sub Total	**M**		**1**	**40.00**	**$258.00**	**$10,320.00**
	Item Code 664084 Total No. of Proj.			**1**		**Total Amount**	**$10,320.00**
664091	450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK)	M	11	1	80.00	$370.00	$29,600.00
	Unit Sub Total	**M**		**1**	**80.00**	**$370.00**	**$29,600.00**
	Item Code 664091 Total No. of Proj.			**1**		**Total Amount**	**$29,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
664097	600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK)	M	11	1	50.00	$500.00	$25,000.00
	Unit Sub Total	**M**		**1**	**50.00**	**$500.00**	**$25,000.00**
	Item Code 664097 Total No. of Proj.			**1**		**Total Amount**	**$25,000.00**
664110	900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.77 MM THICK)	M	11	1	1.00	$2,850.00	$2,850.00
	Unit Sub Total	**M**		**1**	**1.00**	**$2,850.00**	**$2,850.00**
	Item Code 664110 Total No. of Proj.			**1**		**Total Amount**	**$2,850.00**
665006	8" CORRUGATED STEEL PIPE (.079" THICK)	LF	1	1	90.00	$80.00	$7,200.00
	Unit Sub Total	**LF**		**1**	**90.00**	**$80.00**	**$7,200.00**
	Item Code 665006 Total No. of Proj.			**1**		**Total Amount**	**$7,200.00**
665010	12" CORRUGATED STEEL PIPE	LF	2	1	12.00	$120.00	$1,440.00
		LF	4	1	58.00	$65.00	$3,770.00
	Unit Sub Total	**LF**		**2**	**70.00**	**$74.43**	**$5,210.00**
	Item Code 665010 Total No. of Proj.			**2**		**Total Amount**	**$5,210.00**
665011	12" CORRUGATED STEEL PIPE (.064" THICK)	LF	3	1	14.00	$200.00	$2,800.00
		LF	4	1	30.00	$73.00	$2,190.00
	Unit Sub Total	**LF**		**2**	**44.00**	**$113.41**	**$4,990.00**
	Item Code 665011 Total No. of Proj.			**2**		**Total Amount**	**$4,990.00**
665012	12" CORRUGATED STEEL PIPE (.079" THICK)	LF	1	1	44.00	$52.00	$2,288.00
		LF	3	1	200.00	$60.00	$12,000.00
		LF	4	3	282.00	$79.26	$22,350.00
		LF	5	1	2.00	$150.00	$300.00
		LF	6	1	98.00	$120.00	$11,760.00
	Unit Sub Total	**LF**		**7**	**626.00**	**$77.79**	**$48,698.00**
	Item Code 665012 Total No. of Proj.			**7**		**Total Amount**	**$48,698.00**
665015	15" CORRUGATED STEEL PIPE (.109" THICK)	LF	12	1	120.00	$100.00	$12,000.00
	Unit Sub Total	**LF**		**1**	**120.00**	**$100.00**	**$12,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 665015 Total No. of Proj.			**1**		**Total Amount**	**$12,000.00**
665016	18" CORRUGATED STEEL PIPE (.064" THICK)	LF	3	1	56.00	$200.00	$11,200.00
		LF	4	2	60.00	$105.35	$6,321.00
	Unit Sub Total	**LF**		**3**	**116.00**	**$151.04**	**$17,521.00**
	Item Code 665016 Total No. of Proj.			**3**		**Total Amount**	**$17,521.00**
665017	18" CORRUGATED STEEL PIPE (.079" THICK)	LF	2	1	130.00	$60.00	$7,800.00
		LF	4	2	512.00	$94.06	$48,160.00
		LF	6	2	256.00	$132.34	$33,880.00
		LF	7	3	281.00	$60.22	$16,922.00
		LF	8	2	860.00	$74.14	$63,760.00
	Unit Sub Total	**LF**		**10**	**2,039.00**	**$83.63**	**$170,522.00**
	Item Code 665017 Total No. of Proj.			**10**		**Total Amount**	**$170,522.00**
665018	18" CORRUGATED STEEL PIPE (.109" THICK)	LF	2	5	144.00	$107.60	$15,494.00
		LF	7	3	122.00	$119.59	$14,590.00
		LF	10	1	33.00	$110.00	$3,630.00
	Unit Sub Total	**LF**		**9**	**299.00**	**$112.76**	**$33,714.00**
	Item Code 665018 Total No. of Proj.			**9**		**Total Amount**	**$33,714.00**
665023	24" CORRUGATED STEEL PIPE (.079" THICK)	LF	2	2	95.00	$153.16	$14,550.00
		LF	3	1	14.00	$200.00	$2,800.00
		LF	4	1	68.00	$135.00	$9,180.00
		LF	6	1	8.00	$180.00	$1,440.00
		LF	7	1	16.00	$130.00	$2,080.00
		LF	8	1	180.00	$41.30	$7,434.00
	Unit Sub Total	**LF**		**7**	**381.00**	**$98.38**	**$37,484.00**
	Item Code 665023 Total No. of Proj.			**7**		**Total Amount**	**$37,484.00**
665024	24" CORRUGATED STEEL PIPE (.109" THICK)	LF	1	2	180.00	$136.78	$24,620.00
		LF	2	2	96.00	$112.50	$10,800.00
		LF	3	1	1,770.00	$50.00	$88,500.00
		LF	10	1	30.00	$160.00	$4,800.00
	Unit Sub Total	**LF**		**6**	**2,076.00**	**$62.00**	**$128,720.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 665024 Total No. of Proj.			**6**		**Total Amount**	**$128,720.00**
665025	24" CORRUGATED STEEL PIPE (.138" THICK)	LF	1	3	681.00	$235.46	$160,350.00
		LF	3	1	2.00	$250.00	$500.00
		LF	5	1	13.00	$65.00	$845.00
		LF	7	4	142.00	$127.55	$18,112.50
	Unit Sub Total	**LF**		**9**	**838.00**	**$214.57**	**$179,807.50**
	Item Code 665025 Total No. of Proj.			**9**		**Total Amount**	**$179,807.50**
665031	30" CORRUGATED STEEL PIPE (.079" THICK)	LF	2	1	50.00	$165.00	$8,250.00
		LF	3	1	4.00	$250.00	$1,000.00
		LF	4	1	190.00	$140.00	$26,600.00
		LF	8	1	10.00	$100.00	$1,000.00
	Unit Sub Total	**LF**		**4**	**254.00**	**$145.08**	**$36,850.00**
	Item Code 665031 Total No. of Proj.			**4**		**Total Amount**	**$36,850.00**
665032	30" CORRUGATED STEEL PIPE (.109" THICK)	LF	1	2	83.00	$126.87	$10,530.00
	Unit Sub Total	**LF**		**2**	**83.00**	**$126.87**	**$10,530.00**
	Item Code 665032 Total No. of Proj.			**2**		**Total Amount**	**$10,530.00**
665033	30" CORRUGATED STEEL PIPE (.138" THICK)	LF	7	2	20.00	$189.00	$3,780.00
	Unit Sub Total	**LF**		**2**	**20.00**	**$189.00**	**$3,780.00**
	Item Code 665033 Total No. of Proj.			**2**		**Total Amount**	**$3,780.00**
665036	36" CORRUGATED STEEL PIPE (.079" THICK)	LF	1	1	310.00	$120.00	$37,200.00
		LF	4	1	5.00	$250.00	$1,250.00
	Unit Sub Total	**LF**		**2**	**315.00**	**$122.06**	**$38,450.00**
	Item Code 665036 Total No. of Proj.			**2**		**Total Amount**	**$38,450.00**
665037	36" CORRUGATED STEEL PIPE (.109" THICK)	LF	4	1	13.00	$600.00	$7,800.00
	Unit Sub Total	**LF**		**1**	**13.00**	**$600.00**	**$7,800.00**
	Item Code 665037 Total No. of Proj.			**1**		**Total Amount**	**$7,800.00**
665038	36" CORRUGATED STEEL PIPE (.138" THICK)	LF	3	1	24.00	$230.00	$5,520.00
		LF	10	1	2.10	$1,300.00	$2,730.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**2**	**26.10**	**$316.09**	**$8,250.00**
	Item Code 665038 Total No. of Proj.			**2**		**Total Amount**	**$8,250.00**
665039	36" CORRUGATED STEEL PIPE (.168" THICK)	LF	1	1	61.00	$250.00	$15,250.00
		LF	7	2	20.00	$93.88	$1,877.50
	Unit Sub Total	**LF**		**3**	**81.00**	**$211.45**	**$17,127.50**
	Item Code 665039 Total No. of Proj.			**3**		**Total Amount**	**$17,127.50**
665046	48" CORRUGATED STEEL PIPE (.079" THICK)	LF	7	1	270.00	$104.00	$28,080.00
	Unit Sub Total	**LF**		**1**	**270.00**	**$104.00**	**$28,080.00**
	Item Code 665046 Total No. of Proj.			**1**		**Total Amount**	**$28,080.00**
665047	48" CORRUGATED STEEL PIPE (.109" THICK)	LF	8	1	110.00	$110.00	$12,100.00
		LF	9	1	6.00	$400.00	$2,400.00
	Unit Sub Total	**LF**		**2**	**116.00**	**$125.00**	**$14,500.00**
	Item Code 665047 Total No. of Proj.			**2**		**Total Amount**	**$14,500.00**
665049	48" CORRUGATED STEEL PIPE (.168" THICK)	LF	7	1	2.00	$790.00	$1,580.00
	Unit Sub Total	**LF**		**1**	**2.00**	**$790.00**	**$1,580.00**
	Item Code 665049 Total No. of Proj.			**1**		**Total Amount**	**$1,580.00**
665075	18" CORRUGATED STEEL PIPE (.138" THICK)	LF	1	2	70.00	$242.86	$17,000.00
		LF	2	1	61.00	$163.00	$9,943.00
		LF	3	1	32.00	$172.00	$5,504.00
	Unit Sub Total	**LF**		**4**	**163.00**	**$199.06**	**$32,447.00**
	Item Code 665075 Total No. of Proj.			**4**		**Total Amount**	**$32,447.00**
665117	18" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	LF	12	1	290.00	$72.00	$20,880.00
	Unit Sub Total	**LF**		**1**	**290.00**	**$72.00**	**$20,880.00**
	Item Code 665117 Total No. of Proj.			**1**		**Total Amount**	**$20,880.00**
665118	18" BITUMINOUS COATED CORRUGATED STEEL PIPE (.109" THICK)	LF	8	1	170.00	$55.00	$9,350.00
	Unit Sub Total	**LF**		**1**	**170.00**	**$55.00**	**$9,350.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 665118 Total No. of Proj.			**1**		**Total Amount**	**$9,350.00**
665137	36" BITUMINOUS COATED CORRUGATED STEEL PIPE (.109" THICK)	LF	8	1	470.00	$100.00	$47,000.00
	Unit Sub Total	**LF**		**1**	**470.00**	**$100.00**	**$47,000.00**
	Item Code 665137 Total No. of Proj.			**1**		**Total Amount**	**$47,000.00**
665717	18" SLOTTED CORRUGATED STEEL PIPE (.079" THICK)	LF	2	1	170.00	$77.00	$13,090.00
		LF	7	2	420.00	$107.14	$45,000.00
	Unit Sub Total	**LF**		**3**	**590.00**	**$98.46**	**$58,090.00**
	Item Code 665717 Total No. of Proj.			**3**		**Total Amount**	**$58,090.00**
665732	450 MM SLOTTED CORRUGATED STEEL PIPE (1.63 MM THICK)	M	4	3	376.00	$270.74	$101,800.00
	Unit Sub Total	**M**		**3**	**376.00**	**$270.74**	**$101,800.00**
	Item Code 665732 Total No. of Proj.			**3**		**Total Amount**	**$101,800.00**
665733	450 MM SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK)	M	7	2	720.00	$307.78	$221,600.00
	Unit Sub Total	**M**		**2**	**720.00**	**$307.78**	**$221,600.00**
	Item Code 665733 Total No. of Proj.			**2**		**Total Amount**	**$221,600.00**
667006	21" X 15" CORRUGATED STEEL PIPE ARCH (.109" THICK)	LF	2	1	32.00	$100.00	$3,200.00
	Unit Sub Total	**LF**		**1**	**32.00**	**$100.00**	**$3,200.00**
	Item Code 667006 Total No. of Proj.			**1**		**Total Amount**	**$3,200.00**
667059	875 MM X 600 MM CORRUGATED STEEL PIPE ARCH (3.51 MM THICK)	M	9	1	120.00	$255.00	$30,600.00
	Unit Sub Total	**M**		**1**	**120.00**	**$255.00**	**$30,600.00**
	Item Code 667059 Total No. of Proj.			**1**		**Total Amount**	**$30,600.00**
680207	3" PLASTIC PIPE	LF	4	1	37.00	$65.00	$2,405.00
		LF	12	1	20.00	$100.00	$2,000.00
	Unit Sub Total	**LF**		**2**	**57.00**	**$77.28**	**$4,405.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 680207 Total No. of Proj.			**2**		**Total Amount**	**$4,405.00**
680259	80 MM SLOTTED PLASTIC PIPE	M	4	1	18.00	$200.00	$3,600.00
	Unit Sub Total	**M**		**1**	**18.00**	**$200.00**	**$3,600.00**
	Item Code 680259 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
680285	4" PLASTIC PIPE UNDERDRAIN	LF	2	1	120.00	$23.82	$2,858.40
		LF	4	1	20.00	$5.00	$100.00
		LF	7	1	160.00	$5.00	$800.00
	Unit Sub Total	**LF**		**3**	**300.00**	**$12.53**	**$3,758.40**
	Item Code 680285 Total No. of Proj.			**3**		**Total Amount**	**$3,758.40**
680404	8" PERFORATED STEEL PIPE UNDERDRAIN	LF	1	1	1,550.00	$35.45	$54,947.50
	Unit Sub Total	**LF**		**1**	**1,550.00**	**$35.45**	**$54,947.50**
	Item Code 680404 Total No. of Proj.			**1**		**Total Amount**	**$54,947.50**
680405	8" PERFORATED STEEL PIPE UNDERDRAIN (.064" THICK)	LF	7	1	100.00	$15.00	$1,500.00
	Unit Sub Total	**LF**		**1**	**100.00**	**$15.00**	**$1,500.00**
	Item Code 680405 Total No. of Proj.			**1**		**Total Amount**	**$1,500.00**
680412	12" PERFORATED STEEL PIPE UNDERDRAIN (.079" THICK)	LF	1	1	370.00	$52.00	$19,240.00
	Unit Sub Total	**LF**		**1**	**370.00**	**$52.00**	**$19,240.00**
	Item Code 680412 Total No. of Proj.			**1**		**Total Amount**	**$19,240.00**
680465	200 MM PERFORATED STEEL PIPE UNDERDRAIN (1.63 MM THICK)	M	8	1	82.00	$80.00	$6,560.00
	Unit Sub Total	**M**		**1**	**82.00**	**$80.00**	**$6,560.00**
	Item Code 680465 Total No. of Proj.			**1**		**Total Amount**	**$6,560.00**
680469	300 MM PERFORATED STEEL PIPE UNDERDRAIN (2.01 MM THICK)	M	1	1	59.00	$82.00	$4,838.00
	Unit Sub Total	**M**		**1**	**59.00**	**$82.00**	**$4,838.00**
	Item Code 680469 Total No. of Proj.			**1**		**Total Amount**	**$4,838.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
680902	6" PERFORATED PLASTIC PIPE UNDERDRAIN	LF	1	1	116.00	$135.00	$15,660.00
		LF	4	2	1,010.00	$11.39	$11,500.00
		LF	5	1	15.00	$35.00	$525.00
		LF	7	2	3,600.00	$28.05	$100,980.00
	Unit Sub Total	**LF**		**6**	**4,741.00**	**$27.14**	**$128,665.00**
	Item Code 680902 Total No. of Proj.			**6**		**Total Amount**	**$128,665.00**
680903	6" NON-PERFORATED PLASTIC PIPE UNDERDRAIN	LF	5	1	16.00	$35.00	$560.00
		LF	7	1	41.00	$14.00	$574.00
	Unit Sub Total	**LF**		**2**	**57.00**	**$19.89**	**$1,134.00**
	Item Code 680903 Total No. of Proj.			**2**		**Total Amount**	**$1,134.00**
680905	8" PERFORATED PLASTIC PIPE UNDERDRAIN	LF	1	2	250.00	$55.20	$13,800.00
		LF	2	3	1,050.00	$36.00	$37,800.00
		LF	3	2	3,128.00	$30.72	$96,100.00
		LF	4	1	300.00	$29.15	$8,745.00
		LF	7	1	580.00	$8.50	$4,930.00
	Unit Sub Total	**LF**		**9**	**5,308.00**	**$30.40**	**$161,375.00**
	Item Code 680905 Total No. of Proj.			**9**		**Total Amount**	**$161,375.00**
680931	150 MM PERFORATED PLASTIC PIPE UNDERDRAIN	M	4	1	81.00	$150.00	$12,150.00
		M	5	1	2.00	$50.00	$100.00
	Unit Sub Total	**M**		**2**	**83.00**	**$147.59**	**$12,250.00**
	Item Code 680931 Total No. of Proj.			**2**		**Total Amount**	**$12,250.00**
680932	150 MM NON-PERFORATED PLASTIC PIPE UNDERDRAIN	M	7	1	11.00	$40.00	$440.00
	Unit Sub Total	**M**		**1**	**11.00**	**$40.00**	**$440.00**
	Item Code 680932 Total No. of Proj.			**1**		**Total Amount**	**$440.00**
680933	200 MM PERFORATED PLASTIC PIPE UNDERDRAIN	M	2	1	2,370.00	$100.00	$237,000.00
		M	3	1	140.00	$70.00	$9,800.00
		M	4	2	5,570.00	$87.01	$484,640.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**4**	**8,080.00**	**$90.52**	**$731,440.00**
	Item Code 680933	**Total No. of Proj.**			**4**		**Total Amount**	**$731,440.00**
681023	6" PLASTIC PIPE		LF	1	1	99.00	$15.00	$1,485.00
			LF	4	1	450.00	$38.00	$17,100.00
			LF	7	3	350.00	$35.00	$12,250.00
		Unit Sub Total	**LF**		**5**	**899.00**	**$34.30**	**$30,835.00**
	Item Code 681023	**Total No. of Proj.**			**5**		**Total Amount**	**$30,835.00**
681066	150 MM PLASTIC PIPE		M	5	1	11.00	$200.00	$2,200.00
			M	6	1	3.20	$15.00	$48.00
			M	8	1	180.00	$39.00	$7,020.00
		Unit Sub Total	**M**		**3**	**194.20**	**$47.72**	**$9,268.00**
	Item Code 681066	**Total No. of Proj.**			**3**		**Total Amount**	**$9,268.00**
681103	3" PLASTIC PIPE (EDGE DRAIN)		LF	1	2	571.00	$19.32	$11,032.00
			LF	2	3	677.00	$46.62	$31,562.50
			LF	3	1	360.00	$20.00	$7,200.00
			LF	4	1	1,550.00	$3.00	$4,650.00
		Unit Sub Total	**LF**		**7**	**3,158.00**	**$17.24**	**$54,444.50**
	Item Code 681103	**Total No. of Proj.**			**7**		**Total Amount**	**$54,444.50**
681107	3" PLASTIC PIPE (EDGE DRAIN OUTLET)		LF	1	1	32.00	$48.00	$1,536.00
			LF	2	2	1,060.00	$24.18	$25,630.00
		Unit Sub Total	**LF**		**3**	**1,092.00**	**$24.88**	**$27,166.00**
	Item Code 681107	**Total No. of Proj.**			**3**		**Total Amount**	**$27,166.00**
681108	6" PLASTIC PIPE (EDGE DRAIN)		LF	3	1	4,890.00	$15.00	$73,350.00
		Unit Sub Total	**LF**		**1**	**4,890.00**	**$15.00**	**$73,350.00**
	Item Code 681108	**Total No. of Proj.**			**1**		**Total Amount**	**$73,350.00**
681111	CLEANOUT ASSEMBLY (EDGE DRAIN)		EA	3	1	22.00	$100.00	$2,200.00
		Unit Sub Total	**EA**		**1**	**22.00**	**$100.00**	**$2,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 681111 Total No. of Proj.			**1**		**Total Amount**	**$2,200.00**
681113	6" PLASTIC PIPE (EDGE DRAIN OUTLET)	LF	2	1	60.00	$85.00	$5,100.00
		LF	3	1	410.00	$20.00	$8,200.00
	Unit Sub Total	**LF**		**2**	**470.00**	**$28.30**	**$13,300.00**
	Item Code 681113 Total No. of Proj.			**2**		**Total Amount**	**$13,300.00**
681132	GEOCOMPOSITE DRAIN	LF	12	1	840.00	$3.00	$2,520.00
	Unit Sub Total	**LF**		**1**	**840.00**	**$3.00**	**$2,520.00**
681132	GEOCOMPOSITE DRAIN	M2	4	2	1,308.00	$36.28	$47,448.00
	Unit Sub Total	**M2**		**2**	**1,308.00**	**$36.28**	**$47,448.00**
681132	GEOCOMPOSITE DRAIN	SQYD	5	1	370.00	$11.00	$4,070.00
	Unit Sub Total	**SQYD**		**1**	**370.00**	**$11.00**	**$4,070.00**
	Item Code 681132 Total No. of Proj.			**4**		**Total Amount**	**$54,038.00**
681134	80 MM PLASTIC PIPE (EDGE DRAIN)	M	2	1	1,700.00	$43.00	$73,100.00
		M	4	1	330.00	$13.00	$4,290.00
		M	7	1	94.00	$30.00	$2,820.00
	Unit Sub Total	**M**		**3**	**2,124.00**	**$37.76**	**$80,210.00**
	Item Code 681134 Total No. of Proj.			**3**		**Total Amount**	**$80,210.00**
681137	80 MM PLASTIC PIPE (EDGE DRAIN OUTLET)	M	1	1	98.00	$170.00	$16,660.00
		M	2	1	160.00	$94.00	$15,040.00
		M	4	2	31.00	$58.45	$1,812.00
		M	7	1	12.00	$250.00	$3,000.00
	Unit Sub Total	**M**		**5**	**301.00**	**$121.30**	**$36,512.00**
	Item Code 681137 Total No. of Proj.			**5**		**Total Amount**	**$36,512.00**
681501	FURNISH AND INSTALL DRAIN PIPE (HORIZONTAL DRAIN)	LF	1	3	3,010.00	$6.79	$20,427.50
		LF	2	1	6,420.00	$1.65	$10,593.00
		LF	5	1	3,200.00	$10.50	$33,600.00
	Unit Sub Total	**LF**		**5**	**12,630.00**	**$5.12**	**$64,620.50**
681501	FURNISH AND INSTALL DRAIN PIPE (HORIZONTAL DRAIN)	M	4	3	1,696.00	$33.58	$56,945.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**3**	**1,696.00**	**$33.58**	**$56,945.00**
	Item Code 681501	**Total No. of Proj.**			**8**		**Total Amount**	**$121,565.50**
681502	DRILL HOLE (HORIZONTAL DRAIN)		LF	1	3	2,840.00	$17.85	$50,700.00
			LF	2	1	6,420.00	$19.15	$122,943.00
			LF	5	1	3,200.00	$18.75	$60,000.00
		Unit Sub Total	**LF**		**5**	**12,460.00**	**$18.75**	**$233,643.00**
681502	DRILL HOLE (HORIZONTAL DRAIN)		M	4	2	635.00	$100.00	$63,500.00
		Unit Sub Total	**M**		**2**	**635.00**	**$100.00**	**$63,500.00**
	Item Code 681502	**Total No. of Proj.**			**7**		**Total Amount**	**$297,143.00**
681510	HORIZONTAL DRAIN CONNECTOR UNIT		EA	1	1	15.00	$90.00	$1,350.00
		Unit Sub Total	**EA**		**1**	**15.00**	**$90.00**	**$1,350.00**
	Item Code 681510	**Total No. of Proj.**			**1**		**Total Amount**	**$1,350.00**
681988	FILTER FABRIC (UNDERDRAIN)		SQYD	5	1	260.00	$1.10	$286.00
		Unit Sub Total	**SQYD**		**1**	**260.00**	**$1.10**	**$286.00**
	Item Code 681988	**Total No. of Proj.**			**1**		**Total Amount**	**$286.00**
681990	FILTER FABRIC		M2	1	1	4,150.00	$2.70	$11,205.00
			M2	10	1	58,300.00	$0.90	$52,470.00
		Unit Sub Total	**M2**		**2**	**62,450.00**	**$1.02**	**$63,675.00**
681990	FILTER FABRIC		SQFT	7	1	228.00	$1.50	$342.00
		Unit Sub Total	**SQFT**		**1**	**228.00**	**$1.50**	**$342.00**
681990	FILTER FABRIC		SQYD	1	1	290.00	$2.00	$580.00
			SQYD	2	1	52.00	$2.50	$130.00
			SQYD	3	1	8,810.00	$1.00	$8,810.00
			SQYD	7	1	80.00	$10.00	$800.00
		Unit Sub Total	**SQYD**		**4**	**9,232.00**	**$1.12**	**$10,320.00**
	Item Code 681990	**Total No. of Proj.**			**7**		**Total Amount**	**$74,337.00**
682001	PERMEABLE MATERIAL		CY	3	2	255.00	$58.90	$15,020.00
			CY	7	2	259.00	$65.56	$16,980.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**CY**		**4**	**514.00**	**$62.26**	**$32,000.00**
	Item Code 682001	**Total No. of Proj.**			**4**		**Total Amount**	**$32,000.00**
682007	IMPERMEABLE MEMBRANE		SQYD	5	1	360.00	$6.00	$2,160.00
		Unit Sub Total	**SQYD**		**1**	**360.00**	**$6.00**	**$2,160.00**
	Item Code 682007	**Total No. of Proj.**			**1**		**Total Amount**	**$2,160.00**
682008	PERMEABLE MATERIAL (BLANKET)		CY	2	1	52.00	$80.00	$4,160.00
		Unit Sub Total	**CY**		**1**	**52.00**	**$80.00**	**$4,160.00**
682008	PERMEABLE MATERIAL (BLANKET)		M3	4	3	17,830.00	$56.60	$1,009,255.00
		Unit Sub Total	**M3**		**3**	**17,830.00**	**$56.60**	**$1,009,255.00**
	Item Code 682008	**Total No. of Proj.**			**4**		**Total Amount**	**$1,013,415.00**
682020	CLASS 1 PERMEABLE MATERIAL		CY	1	3	154.00	$109.87	$16,920.00
			CY	3	1	3,020.00	$35.00	$105,700.00
		Unit Sub Total	**CY**		**4**	**3,174.00**	**$38.63**	**$122,620.00**
682020	CLASS 1 PERMEABLE MATERIAL		M3	1	1	1,160.00	$67.00	$77,720.00
			M3	4	1	6,230.00	$65.00	$404,950.00
			M3	5	1	4.80	$250.00	$1,200.00
		Unit Sub Total	**M3**		**3**	**7,394.80**	**$65.43**	**$483,870.00**
	Item Code 682020	**Total No. of Proj.**			**7**		**Total Amount**	**$606,490.00**
682021	CLASS 1 PERMEABLE MATERIAL (STABILIZATION)		CY	1	1	40.00	$140.00	$5,600.00
		Unit Sub Total	**CY**		**1**	**40.00**	**$140.00**	**$5,600.00**
	Item Code 682021	**Total No. of Proj.**			**1**		**Total Amount**	**$5,600.00**
682041	CLASS 2 PERMEABLE MATERIAL (UNDERDRAIN)		CY	5	1	16.00	$100.00	$1,600.00
		Unit Sub Total	**CY**		**1**	**16.00**	**$100.00**	**$1,600.00**
	Item Code 682041	**Total No. of Proj.**			**1**		**Total Amount**	**$1,600.00**
682045	CLASS 3 PERMEABLE MATERIAL		CY	1	1	440.00	$65.00	$28,600.00
			CY	2	3	915.00	$41.17	$37,672.00
		Unit Sub Total	**CY**		**4**	**1,355.00**	**$48.91**	**$66,272.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
682045	CLASS 3 PERMEABLE MATERIAL	M3	10	1	17,000.00	$27.00	$459,000.00
	Unit Sub Total	**M3**		**1**	**17,000.00**	**$27.00**	**$459,000.00**
	Item Code 682045 Total No. of Proj.			**5**		**Total Amount**	**$525,272.00**
682048	CLASS 3 PERMEABLE MATERIAL (UNDERDRAIN)	CY	5	1	46.00	$58.00	$2,668.00
	Unit Sub Total	**CY**		**1**	**46.00**	**$58.00**	**$2,668.00**
	Item Code 682048 Total No. of Proj.			**1**		**Total Amount**	**$2,668.00**
682049	CLASS 3 PERMEABLE MATERIAL (BLANKET)	M3	4	1	5,100.00	$81.00	$413,100.00
	Unit Sub Total	**M3**		**1**	**5,100.00**	**$81.00**	**$413,100.00**
	Item Code 682049 Total No. of Proj.			**1**		**Total Amount**	**$413,100.00**
685020	8" ALTERNATIVE PIPE UNDERDRAIN	LF	2	1	90.00	$75.00	$6,750.00
		LF	5	1	310.00	$16.00	$4,960.00
	Unit Sub Total	**LF**		**2**	**400.00**	**$29.28**	**$11,710.00**
	Item Code 685020 Total No. of Proj.			**2**		**Total Amount**	**$11,710.00**
685067	200 MM ALTERNATIVE PIPE UNDERDRAIN	M	4	3	7,480.00	$70.49	$527,260.00
	Unit Sub Total	**M**		**3**	**7,480.00**	**$70.49**	**$527,260.00**
	Item Code 685067 Total No. of Proj.			**3**		**Total Amount**	**$527,260.00**
690106	8" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	1	2	78.00	$54.23	$4,230.00
	Unit Sub Total	**LF**		**2**	**78.00**	**$54.23**	**$4,230.00**
	Item Code 690106 Total No. of Proj.			**2**		**Total Amount**	**$4,230.00**
690110	12" CORRUGATED STEEL PIPE DOWNDRAIN	LF	1	2	78.00	$44.10	$3,440.00
		LF	10	1	50.00	$80.00	$4,000.00
	Unit Sub Total	**LF**		**3**	**128.00**	**$58.13**	**$7,440.00**
	Item Code 690110 Total No. of Proj.			**3**		**Total Amount**	**$7,440.00**
690112	12" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	1	2	180.00	$23.22	$4,180.00
		LF	3	2	680.00	$42.94	$29,200.00
		LF	8	1	40.00	$115.00	$4,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
690112	12" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	10	1	20.00	$200.00	$4,000.00
	Unit Sub Total	**LF**		**6**	**920.00**	**$45.63**	**$41,980.00**
	Item Code 690112 Total No. of Proj.			**6**		**Total Amount**	**$41,980.00**
690116	18" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	LF	3	1	65.00	$80.00	$5,200.00
	Unit Sub Total	**LF**		**1**	**65.00**	**$80.00**	**$5,200.00**
	Item Code 690116 Total No. of Proj.			**1**		**Total Amount**	**$5,200.00**
690117	18" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	8	1	40.00	$90.00	$3,600.00
	Unit Sub Total	**LF**		**1**	**40.00**	**$90.00**	**$3,600.00**
	Item Code 690117 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
690118	18" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	7	1	60.00	$110.00	$6,600.00
	Unit Sub Total	**LF**		**1**	**60.00**	**$110.00**	**$6,600.00**
	Item Code 690118 Total No. of Proj.			**1**		**Total Amount**	**$6,600.00**
690123	24" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	1	2	128.00	$73.89	$9,458.00
	Unit Sub Total	**LF**		**2**	**128.00**	**$73.89**	**$9,458.00**
	Item Code 690123 Total No. of Proj.			**2**		**Total Amount**	**$9,458.00**
690124	24" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	1	2	135.00	$53.39	$7,207.50
		LF	7	1	340.00	$87.00	$29,580.00
	Unit Sub Total	**LF**		**3**	**475.00**	**$77.45**	**$36,787.50**
	Item Code 690124 Total No. of Proj.			**3**		**Total Amount**	**$36,787.50**
690125	24" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	LF	1	1	47.00	$100.00	$4,700.00
	Unit Sub Total	**LF**		**1**	**47.00**	**$100.00**	**$4,700.00**
	Item Code 690125 Total No. of Proj.			**1**		**Total Amount**	**$4,700.00**
690131	30" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	1	1	83.00	$50.00	$4,150.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
690131	30" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	2	1	30.00	$125.00	$3,750.00
	Unit Sub Total	**LF**		**2**	**113.00**	**$69.91**	**$7,900.00**
	Item Code 690131 Total No. of Proj.			**2**		**Total Amount**	**$7,900.00**
690137	36" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	1	1	50.00	$120.00	$6,000.00
		LF	7	1	410.00	$82.00	$33,620.00
	Unit Sub Total	**LF**		**2**	**460.00**	**$86.13**	**$39,620.00**
	Item Code 690137 Total No. of Proj.			**2**		**Total Amount**	**$39,620.00**
690148	48" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	LF	1	1	20.00	$109.00	$2,180.00
	Unit Sub Total	**LF**		**1**	**20.00**	**$109.00**	**$2,180.00**
	Item Code 690148 Total No. of Proj.			**1**		**Total Amount**	**$2,180.00**
690154	200 MM CORRUGATED STEEL PIPE DOWNDRAIN	M	5	1	12.00	$120.00	$1,440.00
	Unit Sub Total	**M**		**1**	**12.00**	**$120.00**	**$1,440.00**
	Item Code 690154 Total No. of Proj.			**1**		**Total Amount**	**$1,440.00**
690155	200 MM CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK)	M	8	1	78.00	$125.00	$9,750.00
	Unit Sub Total	**M**		**1**	**78.00**	**$125.00**	**$9,750.00**
	Item Code 690155 Total No. of Proj.			**1**		**Total Amount**	**$9,750.00**
690159	300 MM CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK)	M	5	2	54.00	$225.96	$12,202.00
	Unit Sub Total	**M**		**2**	**54.00**	**$225.96**	**$12,202.00**
	Item Code 690159 Total No. of Proj.			**2**		**Total Amount**	**$12,202.00**
690160	300 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	M	1	1	37.00	$120.00	$4,440.00
		M	9	1	51.00	$225.00	$11,475.00
	Unit Sub Total	**M**		**2**	**88.00**	**$180.85**	**$15,915.00**
	Item Code 690160 Total No. of Proj.			**2**		**Total Amount**	**$15,915.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
690165	450 MM CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK)	M	5	1	19.00	$200.00	$3,800.00
	Unit Sub Total	**M**		**1**	**19.00**	**$200.00**	**$3,800.00**
	Item Code 690165 Total No. of Proj.			**1**		**Total Amount**	**$3,800.00**
690166	450 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	M	3	1	96.00	$187.00	$17,952.00
		M	7	1	16.00	$250.00	$4,000.00
	Unit Sub Total	**M**		**2**	**112.00**	**$196.00**	**$21,952.00**
	Item Code 690166 Total No. of Proj.			**2**		**Total Amount**	**$21,952.00**
690170	600 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	M	3	1	87.00	$196.00	$17,052.00
		M	4	1	4.90	$500.00	$2,450.00
	Unit Sub Total	**M**		**2**	**91.90**	**$212.21**	**$19,502.00**
	Item Code 690170 Total No. of Proj.			**2**		**Total Amount**	**$19,502.00**
690172	600 MM CORRUGATED STEEL PIPE DOWNDRAIN (3.51 MM THICK)	M	1	1	6.00	$360.00	$2,160.00
	Unit Sub Total	**M**		**1**	**6.00**	**$360.00**	**$2,160.00**
	Item Code 690172 Total No. of Proj.			**1**		**Total Amount**	**$2,160.00**
690273	300 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	M	4	1	24.00	$325.00	$7,800.00
	Unit Sub Total	**M**		**1**	**24.00**	**$325.00**	**$7,800.00**
	Item Code 690273 Total No. of Proj.			**1**		**Total Amount**	**$7,800.00**
690276	450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	M	8	1	54.00	$275.00	$14,850.00
	Unit Sub Total	**M**		**1**	**54.00**	**$275.00**	**$14,850.00**
	Item Code 690276 Total No. of Proj.			**1**		**Total Amount**	**$14,850.00**
690277	450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK)	M	4	1	54.00	$270.00	$14,580.00
		M	11	1	48.00	$465.00	$22,320.00
	Unit Sub Total	**M**		**2**	**102.00**	**$361.76**	**$36,900.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 690277 Total No. of Proj.			**2**		**Total Amount**	**$36,900.00**
690281	600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK)	M	4	1	2.00	$600.00	$1,200.00
	Unit Sub Total	**M**		**1**	**2.00**	**$600.00**	**$1,200.00**
	Item Code 690281 Total No. of Proj.			**1**		**Total Amount**	**$1,200.00**
690282	600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (3.51 MM THICK)	M	11	1	230.00	$379.00	$87,170.00
	Unit Sub Total	**M**		**1**	**230.00**	**$379.00**	**$87,170.00**
	Item Code 690282 Total No. of Proj.			**1**		**Total Amount**	**$87,170.00**
690290	1050 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (2.77 MM THICK)	M	4	1	2.00	$700.00	$1,400.00
	Unit Sub Total	**M**		**1**	**2.00**	**$700.00**	**$1,400.00**
	Item Code 690290 Total No. of Proj.			**1**		**Total Amount**	**$1,400.00**
690294	750 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (3.51 MM THICK)	M	11	1	25.00	$644.00	$16,100.00
	Unit Sub Total	**M**		**1**	**25.00**	**$644.00**	**$16,100.00**
	Item Code 690294 Total No. of Proj.			**1**		**Total Amount**	**$16,100.00**
690297	450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (3.51 MM THICK)	M	11	1	13.00	$136.00	$1,768.00
	Unit Sub Total	**M**		**1**	**13.00**	**$136.00**	**$1,768.00**
	Item Code 690297 Total No. of Proj.			**1**		**Total Amount**	**$1,768.00**
691003	8" CORRUGATED STEEL FLUME DOWNDRAIN	LF	2	1	260.00	$22.00	$5,720.00
	Unit Sub Total	**LF**		**1**	**260.00**	**$22.00**	**$5,720.00**
	Item Code 691003 Total No. of Proj.			**1**		**Total Amount**	**$5,720.00**
691900	FLUME DOWNDRAIN	LF	7	1	40.00	$50.00	$2,000.00
	Unit Sub Total	**LF**		**1**	**40.00**	**$50.00**	**$2,000.00**
	Item Code 691900 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
692001	ENTRANCE TAPER	EA	1	2	3.00	$493.33	$1,480.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**2**	**3.00**	**$493.33**	**$1,480.00**
	Item Code 692001	**Total No. of Proj.**			**2**		**Total Amount**	**$1,480.00**
692005	12" ENTRANCE TAPER		EA	1	3	5.00	$300.00	$1,500.00
			EA	3	1	4.00	$500.00	$2,000.00
			EA	6	1	4.00	$400.00	$1,600.00
			EA	8	1	1.00	$700.00	$700.00
			EA	10	2	4.00	$400.00	$1,600.00
		Unit Sub Total	**EA**		**8**	**18.00**	**$411.11**	**$7,400.00**
	Item Code 692005	**Total No. of Proj.**			**8**		**Total Amount**	**$7,400.00**
692086	200 MM ENTRANCE TAPER		EA	4	1	8.00	$600.00	$4,800.00
		Unit Sub Total	**EA**		**1**	**8.00**	**$600.00**	**$4,800.00**
	Item Code 692086	**Total No. of Proj.**			**1**		**Total Amount**	**$4,800.00**
692088	300 MM ENTRANCE TAPER		EA	1	1	1.00	$800.00	$800.00
			EA	5	1	2.00	$300.00	$600.00
			EA	9	1	3.00	$600.00	$1,800.00
		Unit Sub Total	**EA**		**3**	**6.00**	**$533.33**	**$3,200.00**
	Item Code 692088	**Total No. of Proj.**			**3**		**Total Amount**	**$3,200.00**
692090	450 MM ENTRANCE TAPER		EA	8	1	3.00	$1,400.00	$4,200.00
		Unit Sub Total	**EA**		**1**	**3.00**	**$1,400.00**	**$4,200.00**
	Item Code 692090	**Total No. of Proj.**			**1**		**Total Amount**	**$4,200.00**
692091	600 MM ENTRANCE TAPER		EA	6	1	7.00	$160.00	$1,120.00
		Unit Sub Total	**EA**		**1**	**7.00**	**$160.00**	**$1,120.00**
	Item Code 692091	**Total No. of Proj.**			**1**		**Total Amount**	**$1,120.00**
692101	TAPERED INLET		EA	7	1	2.00	$500.00	$1,000.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$500.00**	**$1,000.00**
	Item Code 692101	**Total No. of Proj.**			**1**		**Total Amount**	**$1,000.00**
692107	18" TAPERED INLET		EA	2	1	7.00	$375.00	$2,625.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**1**	**7.00**	**$375.00**	**$2,625.00**
	Item Code 692107 Total No. of Proj.			**1**		**Total Amount**	**$2,625.00**
692205	12" DOWNDRAIN SLIP JOINT	EA	1	1	2.00	$250.00	$500.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$250.00**	**$500.00**
	Item Code 692205 Total No. of Proj.			**1**		**Total Amount**	**$500.00**
692207	18" DOWNDRAIN SLIP JOINT	EA	3	1	2.00	$450.00	$900.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$450.00**	**$900.00**
	Item Code 692207 Total No. of Proj.			**1**		**Total Amount**	**$900.00**
692244	200 MM DOWNDRAIN SLIP JOINT	EA	4	1	8.00	$25.00	$200.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$25.00**	**$200.00**
	Item Code 692244 Total No. of Proj.			**1**		**Total Amount**	**$200.00**
692245	300 MM DOWNDRAIN SLIP JOINT	EA	1	1	1.00	$750.00	$750.00
		EA	9	1	3.00	$950.00	$2,850.00
	Unit Sub Total	**EA**		**2**	**4.00**	**$900.00**	**$3,600.00**
	Item Code 692245 Total No. of Proj.			**2**		**Total Amount**	**$3,600.00**
692247	600 MM DOWNDRAIN SLIP JOINT	EA	2	1	3.00	$425.00	$1,275.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$425.00**	**$1,275.00**
	Item Code 692247 Total No. of Proj.			**1**		**Total Amount**	**$1,275.00**
692248	750 MM DOWNDRAIN SLIP JOINT	EA	2	1	1.00	$520.00	$520.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$520.00**	**$520.00**
	Item Code 692248 Total No. of Proj.			**1**		**Total Amount**	**$520.00**
692301	ANCHOR ASSEMBLY	EA	1	2	5.00	$1,003.20	$5,016.00
		EA	4	1	11.00	$800.00	$8,800.00
		EA	7	1	23.00	$290.00	$6,670.00
	Unit Sub Total	**EA**		**4**	**39.00**	**$525.28**	**$20,486.00**
	Item Code 692301 Total No. of Proj.			**4**		**Total Amount**	**$20,486.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
692303	8" ANCHOR ASSEMBLY	EA	1	1	2.00	$125.00	$250.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$125.00**	**$250.00**
	Item Code 692303 Total No. of Proj.			**1**		**Total Amount**	**$250.00**
692305	12" ANCHOR ASSEMBLY	EA	1	2	7.00	$428.57	$3,000.00
		EA	3	1	24.00	$400.00	$9,600.00
	Unit Sub Total	**EA**		**3**	**31.00**	**$406.45**	**$12,600.00**
	Item Code 692305 Total No. of Proj.			**3**		**Total Amount**	**$12,600.00**
692307	18" ANCHOR ASSEMBLY	EA	2	2	9.00	$323.89	$2,915.00
	Unit Sub Total	**EA**		**2**	**9.00**	**$323.89**	**$2,915.00**
	Item Code 692307 Total No. of Proj.			**2**		**Total Amount**	**$2,915.00**
692309	24" ANCHOR ASSEMBLY	EA	1	2	8.00	$187.50	$1,500.00
		EA	2	3	21.00	$296.43	$6,225.00
	Unit Sub Total	**EA**		**5**	**29.00**	**$266.38**	**$7,725.00**
	Item Code 692309 Total No. of Proj.			**5**		**Total Amount**	**$7,725.00**
692311	30" ANCHOR ASSEMBLY	EA	1	1	5.00	$285.00	$1,425.00
		EA	2	1	3.00	$400.00	$1,200.00
	Unit Sub Total	**EA**		**2**	**8.00**	**$328.13**	**$2,625.00**
	Item Code 692311 Total No. of Proj.			**2**		**Total Amount**	**$2,625.00**
692313	36" ANCHOR ASSEMBLY	EA	1	1	2.00	$175.00	$350.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$175.00**	**$350.00**
	Item Code 692313 Total No. of Proj.			**1**		**Total Amount**	**$350.00**
692361	FLUME ANCHOR ASSEMBLY	EA	2	1	27.00	$250.00	$6,750.00
	Unit Sub Total	**EA**		**1**	**27.00**	**$250.00**	**$6,750.00**
	Item Code 692361 Total No. of Proj.			**1**		**Total Amount**	**$6,750.00**
692383	300 MM ANCHOR ASSEMBLY	EA	4	1	52.00	$125.00	$6,500.00
		EA	5	1	2.00	$457.28	$914.56
		EA	9	1	3.00	$900.00	$2,700.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**3**	**57.00**	**$177.45**	**$10,114.56**
	Item Code 692383	**Total No. of Proj.**			**3**		**Total Amount**	**$10,114.56**
692385	450 MM ANCHOR ASSEMBLY		EA	3	1	18.00	$421.00	$7,578.00
			EA	4	3	16.00	$154.63	$2,474.00
		Unit Sub Total	**EA**		**4**	**34.00**	**$295.65**	**$10,052.00**
	Item Code 692385	**Total No. of Proj.**			**4**		**Total Amount**	**$10,052.00**
692386	600 MM ANCHOR ASSEMBLY		EA	2	1	24.00	$475.00	$11,400.00
			EA	3	1	12.00	$430.00	$5,160.00
		Unit Sub Total	**EA**		**2**	**36.00**	**$460.00**	**$16,560.00**
	Item Code 692386	**Total No. of Proj.**			**2**		**Total Amount**	**$16,560.00**
692387	750 MM ANCHOR ASSEMBLY		EA	2	1	5.00	$500.00	$2,500.00
		Unit Sub Total	**EA**		**1**	**5.00**	**$500.00**	**$2,500.00**
	Item Code 692387	**Total No. of Proj.**			**1**		**Total Amount**	**$2,500.00**
692409	CABLE ANCHORAGE SYSTEM		LF	1	2	119.00	$59.15	$7,039.00
		Unit Sub Total	**LF**		**2**	**119.00**	**$59.15**	**$7,039.00**
692409	CABLE ANCHORAGE SYSTEM		M	2	1	150.00	$143.00	$21,450.00
			M	3	1	19.00	$430.00	$8,170.00
		Unit Sub Total	**M**		**2**	**169.00**	**$175.27**	**$29,620.00**
	Item Code 692409	**Total No. of Proj.**			**4**		**Total Amount**	**$36,659.00**
698091	300 MM ALTERNATIVE PIPE DOWNDRAIN		M	1	1	1.00	$100.00	$100.00
			M	3	1	80.00	$135.00	$10,800.00
		Unit Sub Total	**M**		**2**	**81.00**	**$134.57**	**$10,900.00**
	Item Code 698091	**Total No. of Proj.**			**2**		**Total Amount**	**$10,900.00**
698162	450 MM ALTERNATIVE PIPE DOWNDRAIN		M	3	1	40.00	$230.00	$9,200.00
			M	10	1	160.00	$275.00	$44,000.00
			M	11	1	9.00	$140.00	$1,260.00
		Unit Sub Total	**M**		**3**	**209.00**	**$260.57**	**$54,460.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 698162 Total No. of Proj.			**3**		**Total Amount**	**$54,460.00**
698169	600 MM ALTERNATIVE PIPE DOWNDRAIN	M	1	1	17.00	$100.00	$1,700.00
		M	2	1	120.00	$206.00	$24,720.00
		M	6	1	61.00	$240.00	$14,640.00
		M	11	1	95.00	$120.00	$11,400.00
	Unit Sub Total	**M**		**4**	**293.00**	**$179.04**	**$52,460.00**
	Item Code 698169 Total No. of Proj.			**4**		**Total Amount**	**$52,460.00**
698176	750 MM ALTERNATIVE PIPE DOWNDRAIN	M	2	1	23.00	$340.00	$7,820.00
	Unit Sub Total	**M**		**1**	**23.00**	**$340.00**	**$7,820.00**
	Item Code 698176 Total No. of Proj.			**1**		**Total Amount**	**$7,820.00**
700617	DRAINAGE INLET MARKER	EA	3	3	75.00	$24.07	$1,805.00
		EA	4	7	104.00	$42.50	$4,420.00
		EA	5	1	8.00	$139.00	$1,112.00
		EA	6	3	22.00	$233.64	$5,140.00
		EA	8	1	13.00	$100.00	$1,300.00
		EA	11	2	30.00	$141.17	$4,235.00
	Unit Sub Total	**EA**		**17**	**252.00**	**$71.48**	**$18,012.00**
	Item Code 700617 Total No. of Proj.			**17**		**Total Amount**	**$18,012.00**
700638	36" CORRUGATED STEEL PIPE INLET (.079" THICK)	LF	2	3	31.00	$255.97	$7,935.00
	Unit Sub Total	**LF**		**3**	**31.00**	**$255.97**	**$7,935.00**
	Item Code 700638 Total No. of Proj.			**3**		**Total Amount**	**$7,935.00**
700639	36" CORRUGATED STEEL PIPE INLET (.109" THICK)	LF	1	2	52.00	$327.12	$17,010.00
		LF	2	1	6.00	$365.00	$2,190.00
		LF	5	1	3.00	$1,000.00	$3,000.00
	Unit Sub Total	**LF**		**4**	**61.00**	**$363.93**	**$22,200.00**
	Item Code 700639 Total No. of Proj.			**4**		**Total Amount**	**$22,200.00**
700640	36" CORRUGATED STEEL PIPE INLET (.138" THICK)	LF	1	1	10.00	$330.00	$3,300.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
700640	36" CORRUGATED STEEL PIPE INLET (.138" THICK)	LF	2	1	3.00	$575.00	$1,725.00
	Unit Sub Total	**LF**		**2**	**13.00**	**$386.54**	**$5,025.00**
	Item Code 700640 Total No. of Proj.			**2**		**Total Amount**	**$5,025.00**
700641	36" CORRUGATED STEEL PIPE INLET (.168" THICK)	LF	3	1	200.00	$800.00	$160,000.00
		LF	10	1	2.20	$1,000.00	$2,200.00
	Unit Sub Total	**LF**		**2**	**202.20**	**$802.18**	**$162,200.00**
	Item Code 700641 Total No. of Proj.			**2**		**Total Amount**	**$162,200.00**
700658	900 MM CORRUGATED STEEL PIPE INLET (2.01 MM THICK)	M	2	1	11.00	$1,200.00	$13,200.00
	Unit Sub Total	**M**		**1**	**11.00**	**$1,200.00**	**$13,200.00**
	Item Code 700658 Total No. of Proj.			**1**		**Total Amount**	**$13,200.00**
700659	900 MM CORRUGATED STEEL PIPE INLET (2.77 MM THICK)	M	4	2	17.00	$851.76	$14,480.00
		M	8	1	11.00	$465.00	$5,115.00
		M	10	1	1.40	$1,390.00	$1,946.00
	Unit Sub Total	**M**		**4**	**29.40**	**$732.69**	**$21,541.00**
	Item Code 700659 Total No. of Proj.			**4**		**Total Amount**	**$21,541.00**
700660	900 MM CORRUGATED STEEL PIPE INLET (3.51 MM THICK)	M	1	1	2.40	$500.00	$1,200.00
		M	5	1	18.00	$600.00	$10,800.00
		M	9	1	1.00	$2,250.00	$2,250.00
	Unit Sub Total	**M**		**3**	**21.40**	**$665.89**	**$14,250.00**
	Item Code 700660 Total No. of Proj.			**3**		**Total Amount**	**$14,250.00**
700858	900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE INLET (2.77 MM THICK)	M	4	1	6.00	$520.00	$3,120.00
		M	11	1	2.80	$2,000.00	$5,600.00
	Unit Sub Total	**M**		**2**	**8.80**	**$990.91**	**$8,720.00**
	Item Code 700858 Total No. of Proj.			**2**		**Total Amount**	**$8,720.00**
700859	900 MM BITUMINOUS COATED CORRUGATED STEEL PIPE INLET (3.51 MM THICK)	M	5	1	7.00	$300.00	$2,100.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**1**	**7.00**	**$300.00**	**$2,100.00**
	Item Code 700859	**Total No. of Proj.**			**1**		**Total Amount**	**$2,100.00**
702616	24" CORRUGATED STEEL PIPE ENERGY DISSIPATOR (.064" THICK)		EA	1	1	1.00	$500.00	$500.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$500.00**	**$500.00**
	Item Code 702616	**Total No. of Proj.**			**1**		**Total Amount**	**$500.00**
703233	GRATED LINE DRAIN		LF	4	1	170.00	$75.00	$12,750.00
			LF	6	1	310.00	$62.06	$19,238.60
			LF	7	3	1,210.00	$74.79	$90,500.00
			LF	12	1	96.00	$140.00	$13,440.00
		Unit Sub Total	**LF**		**6**	**1,786.00**	**$76.11**	**$135,928.60**
703233	GRATED LINE DRAIN		M	4	1	20.00	$550.00	$11,000.00
			M	7	2	400.00	$261.75	$104,700.00
			M	8	3	451.00	$302.21	$136,298.00
			M	11	2	170.00	$274.59	$46,680.00
		Unit Sub Total	**M**		**8**	**1,041.00**	**$286.91**	**$298,678.00**
	Item Code 703233	**Total No. of Proj.**			**14**		**Total Amount**	**$434,606.60**
703239	36" CORRUGATED STEEL PIPE RISER (.109" THICK)		LF	5	1	7.00	$1,400.00	$9,800.00
			LF	9	1	3.00	$800.00	$2,400.00
		Unit Sub Total	**LF**		**2**	**10.00**	**$1,220.00**	**$12,200.00**
	Item Code 703239	**Total No. of Proj.**			**2**		**Total Amount**	**$12,200.00**
703267	300 MM CORRUGATED STEEL PIPE RISER (1.63 MM THICK)		M	8	1	8.00	$1,092.00	$8,736.00
		Unit Sub Total	**M**		**1**	**8.00**	**$1,092.00**	**$8,736.00**
	Item Code 703267	**Total No. of Proj.**			**1**		**Total Amount**	**$8,736.00**
703284	900 MM CORRUGATED STEEL PIPE RISER (2.77 MM THICK)		M	11	1	3.20	$630.00	$2,016.00
		Unit Sub Total	**M**		**1**	**3.20**	**$630.00**	**$2,016.00**
	Item Code 703284	**Total No. of Proj.**			**1**		**Total Amount**	**$2,016.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
703285	900 MM CORRUGATED STEEL PIPE RISER (3.51 MM THICK)	M	9	1	1.30	$1,300.00	$1,690.00
	Unit Sub Total	**M**		**1**	**1.30**	**$1,300.00**	**$1,690.00**
	Item Code 703285 Total No. of Proj.			**1**		**Total Amount**	**$1,690.00**
703287	1200 MM CORRUGATED STEEL PIPE RISER (2.01 MM THICK)	M	8	2	2.80	$1,791.07	$5,015.00
	Unit Sub Total	**M**		**2**	**2.80**	**$1,791.07**	**$5,015.00**
	Item Code 703287 Total No. of Proj.			**2**		**Total Amount**	**$5,015.00**
703317	18" BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (.079" THICK)	LF	12	1	120.00	$380.00	$45,600.00
	Unit Sub Total	**LF**		**1**	**120.00**	**$380.00**	**$45,600.00**
	Item Code 703317 Total No. of Proj.			**1**		**Total Amount**	**$45,600.00**
703450	WELDED STEEL PIPE CASING (BRIDGE)	LF	12	1	595.00	$70.00	$41,650.00
	Unit Sub Total	**LF**		**1**	**595.00**	**$70.00**	**$41,650.00**
703450	WELDED STEEL PIPE CASING (BRIDGE)	M	2	1	62.00	$300.00	$18,600.00
		M	4	1	18.00	$400.00	$7,200.00
		M	7	1	9.00	$450.00	$4,050.00
		M	10	1	26.00	$195.00	$5,070.00
	Unit Sub Total	**M**		**4**	**115.00**	**$303.65**	**$34,920.00**
	Item Code 703450 Total No. of Proj.			**5**		**Total Amount**	**$76,570.00**
703460	24" WELDED STEEL PIPE CASING (BRIDGE)	LF	6	1	277.00	$160.00	$44,320.00
	Unit Sub Total	**LF**		**1**	**277.00**	**$160.00**	**$44,320.00**
	Item Code 703460 Total No. of Proj.			**1**		**Total Amount**	**$44,320.00**
703481	600 MM WELDED STEEL PIPE CASING (BRIDGE)	M	4	1	48.00	$16.00	$768.00
		M	11	1	48.00	$422.00	$20,256.00
	Unit Sub Total	**M**		**2**	**96.00**	**$219.00**	**$21,024.00**
	Item Code 703481 Total No. of Proj.			**2**		**Total Amount**	**$21,024.00**
703533	12" WELDED STEEL PIPE (.250" THICK)	LF	4	2	412.00	$91.46	$37,681.34
	Unit Sub Total	**LF**		**2**	**412.00**	**$91.46**	**$37,681.34**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 703533 Total No. of Proj.			**2**		**Total Amount**	**$37,681.34**
703542	300 MM WELDED STEEL PIPE (2.67 MM THICK)	M	4	1	6.00	$360.00	$2,160.00
	Unit Sub Total	**M**		**1**	**6.00**	**$360.00**	**$2,160.00**
	Item Code 703542 Total No. of Proj.			**1**		**Total Amount**	**$2,160.00**
703543	300 MM WELDED STEEL PIPE (3.40 MM THICK)	M	4	1	20.00	$620.00	$12,400.00
	Unit Sub Total	**M**		**1**	**20.00**	**$620.00**	**$12,400.00**
	Item Code 703543 Total No. of Proj.			**1**		**Total Amount**	**$12,400.00**
703545	300 MM WELDED STEEL PIPE (6.35 MM THICK)	M	4	1	4.00	$925.00	$3,700.00
	Unit Sub Total	**M**		**1**	**4.00**	**$925.00**	**$3,700.00**
	Item Code 703545 Total No. of Proj.			**1**		**Total Amount**	**$3,700.00**
703575	24" WELDED STEEL PIPE (.250" THICK)	LF	1	2	470.00	$317.40	$149,180.00
	Unit Sub Total	**LF**		**2**	**470.00**	**$317.40**	**$149,180.00**
	Item Code 703575 Total No. of Proj.			**2**		**Total Amount**	**$149,180.00**
703598	30" WELDED STEEL PIPE (.250" THICK)	LF	6	1	150.00	$133.75	$20,062.50
	Unit Sub Total	**LF**		**1**	**150.00**	**$133.75**	**$20,062.50**
	Item Code 703598 Total No. of Proj.			**1**		**Total Amount**	**$20,062.50**
703656	48" WELDED STEEL PIPE (.375" THICK)	LF	1	1	65.00	$320.00	$20,800.00
	Unit Sub Total	**LF**		**1**	**65.00**	**$320.00**	**$20,800.00**
	Item Code 703656 Total No. of Proj.			**1**		**Total Amount**	**$20,800.00**
704133	JACKED 12" WELDED STEEL PIPE (.250" THICK)	LF	1	1	50.00	$430.00	$21,500.00
	Unit Sub Total	**LF**		**1**	**50.00**	**$430.00**	**$21,500.00**
	Item Code 704133 Total No. of Proj.			**1**		**Total Amount**	**$21,500.00**
704175	JACKED 24" WELDED STEEL PIPE (.250" THICK)	LF	4	1	220.00	$1,010.00	$222,200.00
	Unit Sub Total	**LF**		**1**	**220.00**	**$1,010.00**	**$222,200.00**
	Item Code 704175 Total No. of Proj.			**1**		**Total Amount**	**$222,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
704196	JACKED 30" WELDED STEEL PIPE (.239" THICK)	LF	3	1	200.00	$700.00	$140,000.00
	Unit Sub Total	**LF**		**1**	**200.00**	**$700.00**	**$140,000.00**
	Item Code 704196 Total No. of Proj.			**1**		**Total Amount**	**$140,000.00**
705001	STEEL FLARED END SECTION	EA	2	1	2.00	$250.00	$500.00
		EA	4	1	2.00	$1,500.00	$3,000.00
		EA	6	1	10.00	$684.00	$6,840.00
	Unit Sub Total	**EA**		**3**	**14.00**	**$738.57**	**$10,340.00**
	Item Code 705001 Total No. of Proj.			**3**		**Total Amount**	**$10,340.00**
705007	12" STEEL FLARED END SECTION	EA	1	1	1.00	$500.00	$500.00
		EA	3	2	4.00	$335.00	$1,340.00
		EA	6	1	4.00	$78.00	$312.00
		EA	8	1	1.00	$700.00	$700.00
		EA	10	2	4.00	$375.00	$1,500.00
	Unit Sub Total	**EA**		**7**	**14.00**	**$310.86**	**$4,352.00**
	Item Code 705007 Total No. of Proj.			**7**		**Total Amount**	**$4,352.00**
705009	15" STEEL FLARED END SECTION	EA	12	1	1.00	$300.00	$300.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$300.00**	**$300.00**
	Item Code 705009 Total No. of Proj.			**1**		**Total Amount**	**$300.00**
705011	18" STEEL FLARED END SECTION	EA	2	2	5.00	$237.00	$1,185.00
		EA	3	2	11.00	$430.91	$4,740.00
		EA	4	1	1.00	$135.00	$135.00
		EA	6	3	10.00	$268.00	$2,680.00
		EA	7	2	2.00	$675.00	$1,350.00
	Unit Sub Total	**EA**		**10**	**29.00**	**$347.93**	**$10,090.00**
	Item Code 705011 Total No. of Proj.			**10**		**Total Amount**	**$10,090.00**
705015	24" STEEL FLARED END SECTION	EA	1	4	6.00	$399.00	$2,394.00
		EA	2	1	6.00	$290.00	$1,740.00
		EA	3	1	1.00	$500.00	$500.00
		EA	6	1	3.00	$935.00	$2,805.00
		EA	7	1	1.00	$600.00	$600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
705015	24" STEEL FLARED END SECTION	EA	8	1	4.00	$242.00	$968.00
	Unit Sub Total	**EA**		**9**	**21.00**	**$428.90**	**$9,007.00**
	Item Code 705015 Total No. of Proj.			**9**		**Total Amount**	**$9,007.00**
705019	30" STEEL FLARED END SECTION	EA	1	1	1.00	$460.00	$460.00
		EA	2	1	2.00	$350.00	$700.00
		EA	3	2	3.00	$733.33	$2,200.00
	Unit Sub Total	**EA**		**4**	**6.00**	**$560.00**	**$3,360.00**
	Item Code 705019 Total No. of Proj.			**4**		**Total Amount**	**$3,360.00**
705023	36" STEEL FLARED END SECTION	EA	1	2	2.00	$1,500.00	$3,000.00
		EA	7	1	1.00	$750.00	$750.00
	Unit Sub Total	**EA**		**3**	**3.00**	**$1,250.00**	**$3,750.00**
	Item Code 705023 Total No. of Proj.			**3**		**Total Amount**	**$3,750.00**
705042	300 MM STEEL FLARED END SECTION	EA	10	1	5.00	$92.00	$460.00
	Unit Sub Total	**EA**		**1**	**5.00**	**$92.00**	**$460.00**
	Item Code 705042 Total No. of Proj.			**1**		**Total Amount**	**$460.00**
705044	450 MM STEEL FLARED END SECTION	EA	3	1	13.00	$601.00	$7,813.00
		EA	4	1	1.00	$250.00	$250.00
		EA	7	2	5.00	$478.80	$2,394.00
		EA	9	1	21.00	$700.00	$14,700.00
		EA	10	1	1.00	$150.00	$150.00
	Unit Sub Total	**EA**		**6**	**41.00**	**$617.24**	**$25,307.00**
	Item Code 705044 Total No. of Proj.			**6**		**Total Amount**	**$25,307.00**
705045	600 MM STEEL FLARED END SECTION	EA	3	1	20.00	$647.00	$12,940.00
		EA	7	1	1.00	$488.00	$488.00
		EA	9	1	8.00	$900.00	$7,200.00
		EA	10	1	2.00	$220.00	$440.00
		EA	11	1	4.00	$662.00	$2,648.00
	Unit Sub Total	**EA**		**5**	**35.00**	**$677.60**	**$23,716.00**
	Item Code 705045 Total No. of Proj.			**5**		**Total Amount**	**$23,716.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
705047	750 MM STEEL FLARED END SECTION	EA	3	1	2.00	$945.00	$1,890.00
		EA	10	1	1.00	$385.00	$385.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$758.33**	**$2,275.00**
	Item Code 705047 Total No. of Proj.			**2**		**Total Amount**	**$2,275.00**
705048	900 MM STEEL FLARED END SECTION	EA	3	1	1.00	$1,129.00	$1,129.00
		EA	9	1	1.00	$1,000.00	$1,000.00
		EA	10	1	1.00	$600.00	$600.00
	Unit Sub Total	**EA**		**3**	**3.00**	**$909.67**	**$2,729.00**
	Item Code 705048 Total No. of Proj.			**3**		**Total Amount**	**$2,729.00**
705049	1050 MM STEEL FLARED END SECTION	EA	6	1	2.00	$3,000.00	$6,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$3,000.00**	**$6,000.00**
	Item Code 705049 Total No. of Proj.			**1**		**Total Amount**	**$6,000.00**
705050	1200 MM STEEL FLARED END SECTION	EA	3	1	2.00	$1,805.00	$3,610.00
		EA	9	1	1.00	$1,900.00	$1,900.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$1,836.67**	**$5,510.00**
	Item Code 705050 Total No. of Proj.			**2**		**Total Amount**	**$5,510.00**
705069	30" BITUMINOUS COATED STEEL FLARED END SECTION	EA	8	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,000.00**	**$1,000.00**
	Item Code 705069 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
705073	36" BITUMINOUS COATED STEEL FLARED END SECTION	EA	8	1	5.00	$600.00	$3,000.00
	Unit Sub Total	**EA**		**1**	**5.00**	**$600.00**	**$3,000.00**
	Item Code 705073 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
705081	48" BITUMINOUS COATED STEEL FLARED END SECTION	EA	8	2	2.00	$1,450.00	$2,900.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$1,450.00**	**$2,900.00**
	Item Code 705081 Total No. of Proj.			**2**		**Total Amount**	**$2,900.00**
705201	12" CONCRETE FLARED END SECTION	EA	1	1	2.00	$693.00	$1,386.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
705201	12" CONCRETE FLARED END SECTION	EA	12	1	1.00	$270.00	$270.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$552.00**	**$1,656.00**
	Item Code 705201 Total No. of Proj.			**2**		**Total Amount**	**$1,656.00**
705204	18" CONCRETE FLARED END SECTION	EA	3	1	10.00	$700.00	$7,000.00
		EA	10	2	8.00	$800.00	$6,400.00
	Unit Sub Total	**EA**		**3**	**18.00**	**$744.44**	**$13,400.00**
	Item Code 705204 Total No. of Proj.			**3**		**Total Amount**	**$13,400.00**
705206	24" CONCRETE FLARED END SECTION	EA	2	1	2.00	$750.00	$1,500.00
		EA	3	2	14.00	$764.29	$10,700.00
		EA	4	1	2.00	$800.00	$1,600.00
		EA	5	1	1.00	$1,000.00	$1,000.00
		EA	7	2	2.00	$1,000.00	$2,000.00
		EA	8	1	1.00	$1,401.00	$1,401.00
	Unit Sub Total	**EA**		**8**	**22.00**	**$827.32**	**$18,201.00**
	Item Code 705206 Total No. of Proj.			**8**		**Total Amount**	**$18,201.00**
705222	450 MM CONCRETE FLARED END SECTION	EA	3	2	9.00	$848.00	$7,632.00
		EA	4	1	4.00	$500.00	$2,000.00
		EA	6	1	4.00	$1,500.00	$6,000.00
		EA	10	4	21.00	$650.48	$13,660.00
		EA	11	1	4.00	$860.00	$3,440.00
	Unit Sub Total	**EA**		**9**	**42.00**	**$779.33**	**$32,732.00**
	Item Code 705222 Total No. of Proj.			**9**		**Total Amount**	**$32,732.00**
705224	600 MM CONCRETE FLARED END SECTION	EA	3	3	14.00	$952.29	$13,332.00
		EA	6	1	1.00	$2,000.00	$2,000.00
		EA	10	3	18.00	$583.89	$10,510.00
		EA	11	2	24.00	$891.67	$21,400.00
	Unit Sub Total	**EA**		**9**	**57.00**	**$828.81**	**$47,242.00**
	Item Code 705224 Total No. of Proj.			**9**		**Total Amount**	**$47,242.00**
705226	750 MM CONCRETE FLARED END SECTION	EA	3	1	1.00	$800.00	$800.00
		EA	11	2	2.00	$865.00	$1,730.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**3**	**3.00**	**$843.33**	**$2,530.00**
	Item Code 705226 Total No. of Proj.			**3**		**Total Amount**	**$2,530.00**
705227	900 MM CONCRETE FLARED END SECTION	EA	10	1	2.00	$1,000.00	$2,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,000.00**	**$2,000.00**
	Item Code 705227 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
705307	12" ALTERNATIVE FLARED END SECTION	EA	4	1	1.00	$250.00	$250.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$250.00**	**$250.00**
	Item Code 705307 Total No. of Proj.			**1**		**Total Amount**	**$250.00**
705311	18" ALTERNATIVE FLARED END SECTION	EA	2	1	2.00	$295.00	$590.00
		EA	3	1	76.00	$350.00	$26,600.00
		EA	5	1	10.00	$1,500.00	$15,000.00
		EA	10	1	1.00	$1,100.00	$1,100.00
	Unit Sub Total	**EA**		**4**	**89.00**	**$486.40**	**$43,290.00**
	Item Code 705311 Total No. of Proj.			**4**		**Total Amount**	**$43,290.00**
705315	24" ALTERNATIVE FLARED END SECTION	EA	1	1	1.00	$2,500.00	$2,500.00
		EA	2	2	19.00	$403.95	$7,675.00
		EA	3	1	5.00	$350.00	$1,750.00
		EA	5	1	1.00	$1,500.00	$1,500.00
		EA	6	1	62.00	$450.00	$27,900.00
		EA	7	1	1.00	$400.00	$400.00
		EA	11	1	2.00	$1,100.00	$2,200.00
	Unit Sub Total	**EA**		**8**	**91.00**	**$482.69**	**$43,925.00**
	Item Code 705315 Total No. of Proj.			**8**		**Total Amount**	**$43,925.00**
705334	300 MM ALTERNATIVE FLARED END SECTION	EA	3	1	9.00	$950.00	$8,550.00
		EA	4	2	4.00	$111.25	$445.00
		EA	6	1	2.00	$300.00	$600.00
	Unit Sub Total	**EA**		**4**	**15.00**	**$639.67**	**$9,595.00**
	Item Code 705334 Total No. of Proj.			**4**		**Total Amount**	**$9,595.00**
705335	375 MM ALTERNATIVE FLARED END SECTION	EA	8	1	15.00	$360.00	$5,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**15.00**	**$360.00**	**$5,400.00**
	Item Code 705335	**Total No. of Proj.**			**1**		**Total Amount**	**$5,400.00**
705336	450 MM ALTERNATIVE FLARED END SECTION		EA	3	4	47.00	$662.98	$31,160.00
			EA	4	7	44.00	$281.59	$12,390.00
			EA	5	2	4.00	$475.00	$1,900.00
			EA	6	2	32.00	$228.13	$7,300.00
			EA	8	3	24.00	$528.88	$12,693.00
			EA	10	2	26.00	$588.46	$15,300.00
			EA	11	2	2.00	$400.00	$800.00
		Unit Sub Total	**EA**		**22**	**179.00**	**$455.55**	**$81,543.00**
	Item Code 705336	**Total No. of Proj.**			**22**		**Total Amount**	**$81,543.00**
705337	600 MM ALTERNATIVE FLARED END SECTION		EA	1	2	8.00	$456.25	$3,650.00
			EA	2	1	3.00	$140.00	$420.00
			EA	3	4	26.00	$586.54	$15,250.00
			EA	4	4	18.00	$272.22	$4,900.00
			EA	5	1	25.00	$500.00	$12,500.00
			EA	6	3	122.00	$478.36	$58,360.00
			EA	8	2	7.00	$653.57	$4,575.00
			EA	9	1	2.00	$475.00	$950.00
			EA	10	1	4.00	$500.00	$2,000.00
			EA	11	1	8.00	$330.00	$2,640.00
		Unit Sub Total	**EA**		**20**	**223.00**	**$471.95**	**$105,245.00**
	Item Code 705337	**Total No. of Proj.**			**20**		**Total Amount**	**$105,245.00**
705338	750 MM ALTERNATIVE FLARED END SECTION		EA	3	2	11.00	$555.45	$6,110.00
			EA	4	2	2.00	$582.50	$1,165.00
			EA	6	1	37.00	$1,000.00	$37,000.00
			EA	8	1	1.00	$786.00	$786.00
			EA	11	1	1.00	$470.00	$470.00
		Unit Sub Total	**EA**		**7**	**52.00**	**$875.60**	**$45,531.00**
	Item Code 705338	**Total No. of Proj.**			**7**		**Total Amount**	**$45,531.00**
705339	900 MM ALTERNATIVE FLARED END SECTION		EA	4	3	4.00	$561.25	$2,245.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
705339	900 MM ALTERNATIVE FLARED END SECTION	EA	5	1	3.00	$700.00	$2,100.00
		EA	6	1	2.00	$350.00	$700.00
		EA	8	2	4.00	$818.75	$3,275.00
		EA	10	1	2.00	$750.00	$1,500.00
	Unit Sub Total	**EA**		**8**	**15.00**	**$654.67**	**$9,820.00**
	Item Code 705339 Total No. of Proj.			**8**		**Total Amount**	**$9,820.00**
705340	1050 MM ALTERNATIVE FLARED END SECTION	EA	4	1	1.00	$1,530.00	$1,530.00
		EA	8	1	1.00	$1,050.00	$1,050.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$1,290.00**	**$2,580.00**
	Item Code 705340 Total No. of Proj.			**2**		**Total Amount**	**$2,580.00**
705342	1350 MM ALTERNATIVE FLARED END SECTION	EA	8	1	1.00	$1,325.00	$1,325.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,325.00**	**$1,325.00**
	Item Code 705342 Total No. of Proj.			**1**		**Total Amount**	**$1,325.00**
705346	525 MM X 375 MM ALTERNATIVE FLARED END PIPE ARCH SECTION	EA	3	1	4.00	$310.00	$1,240.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$310.00**	**$1,240.00**
	Item Code 705346 Total No. of Proj.			**1**		**Total Amount**	**$1,240.00**
705348	875 MM X 600 MM ALTERNATIVE FLARED END PIPE ARCH SECTION	EA	3	1	2.00	$520.00	$1,040.00
		EA	5	1	2.00	$1,500.00	$3,000.00
	Unit Sub Total	**EA**		**2**	**4.00**	**$1,010.00**	**$4,040.00**
	Item Code 705348 Total No. of Proj.			**2**		**Total Amount**	**$4,040.00**
705349	1050 MM X 725 MM ALTERNATIVE FLARED END PIPE ARCH SECTION	EA	3	1	6.00	$590.00	$3,540.00
	Unit Sub Total	**EA**		**1**	**6.00**	**$590.00**	**$3,540.00**
	Item Code 705349 Total No. of Proj.			**1**		**Total Amount**	**$3,540.00**
705403	21" X 15" STEEL FLARED END PIPE ARCH SECTION	EA	2	1	2.00	$200.00	$400.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$200.00**	**$400.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 705403 Total No. of Proj.			**1**		**Total Amount**	**$400.00**
705477	875 MM X 600 MM STEEL FLARED END PIPE ARCH SECTION	EA	9	1	1.00	$930.00	$930.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$930.00**	**$930.00**
	Item Code 705477 Total No. of Proj.			**1**		**Total Amount**	**$930.00**
705648	450 MM SLIDE HEADGATE	EA	3	1	2.00	$3,600.00	$7,200.00
		EA	4	1	2.00	$5,000.00	$10,000.00
	Unit Sub Total	**EA**		**2**	**4.00**	**$4,300.00**	**$17,200.00**
	Item Code 705648 Total No. of Proj.			**2**		**Total Amount**	**$17,200.00**
705954	300 MM GATE VALVE	EA	11	1	8.00	$1,500.00	$12,000.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$1,500.00**	**$12,000.00**
	Item Code 705954 Total No. of Proj.			**1**		**Total Amount**	**$12,000.00**
706500	DEBRIS RACK	EA	2	1	2.00	$1,500.00	$3,000.00
		EA	8	1	1.00	$3,000.00	$3,000.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$2,000.00**	**$6,000.00**
	Item Code 706500 Total No. of Proj.			**2**		**Total Amount**	**$6,000.00**
706605	36" DEBRIS RACK CAGE (H=4')	EA	5	1	1.00	$2,400.00	$2,400.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$2,400.00**	**$2,400.00**
	Item Code 706605 Total No. of Proj.			**1**		**Total Amount**	**$2,400.00**
706607	48" DEBRIS RACK CAGE (H=4')	EA	4	1	1.00	$4,000.00	$4,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$4,000.00**	**$4,000.00**
	Item Code 706607 Total No. of Proj.			**1**		**Total Amount**	**$4,000.00**
706652	900 MM DEBRIS RACK CAGE (H = 1.8 M)	KG	2	1	126.40	$100.00	$12,640.00
	Unit Sub Total	**KG**		**1**	**126.40**	**$100.00**	**$12,640.00**
	Item Code 706652 Total No. of Proj.			**1**		**Total Amount**	**$12,640.00**
707117	36" PRECAST CONCRETE PIPE INLET	LF	1	3	40.50	$170.74	$6,915.00
		LF	2	2	57.00	$392.89	$22,395.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
707117	36" PRECAST CONCRETE PIPE INLET	LF	3	1	320.00	$550.00	$176,000.00
		LF	5	1	6.00	$75.00	$450.00
	Unit Sub Total	**LF**		**7**	**423.50**	**$485.86**	**$205,760.00**
	Item Code 707117 Total No. of Proj.			**7**		**Total Amount**	**$205,760.00**
707125	48" PRECAST CONCRETE PIPE INLET	LF	3	1	7.00	$650.00	$4,550.00
	Unit Sub Total	**LF**		**1**	**7.00**	**$650.00**	**$4,550.00**
	Item Code 707125 Total No. of Proj.			**1**		**Total Amount**	**$4,550.00**
707133	900 MM PRECAST CONCRETE PIPE INLET	M	3	1	10.00	$1,000.00	$10,000.00
		M	4	2	6.00	$708.33	$4,250.00
		M	5	1	1.00	$2,000.00	$2,000.00
		M	6	1	2.70	$1,700.00	$4,590.00
		M	8	1	9.00	$652.00	$5,868.00
		M	10	2	7.20	$1,171.67	$8,436.00
		M	11	1	11.00	$510.00	$5,610.00
	Unit Sub Total	**M**		**9**	**46.90**	**$868.96**	**$40,754.00**
	Item Code 707133 Total No. of Proj.			**9**		**Total Amount**	**$40,754.00**
707217	36" PRECAST CONCRETE PIPE MANHOLE	LF	12	2	15.00	$560.00	$8,400.00
	Unit Sub Total	**LF**		**2**	**15.00**	**$560.00**	**$8,400.00**
	Item Code 707217 Total No. of Proj.			**2**		**Total Amount**	**$8,400.00**
707244	900 MM PRECAST CONCRETE PIPE MANHOLE	M	7	3	7.10	$1,228.17	$8,720.00
		M	8	1	1.60	$1,255.00	$2,008.00
	Unit Sub Total	**M**		**4**	**8.70**	**$1,233.10**	**$10,728.00**
	Item Code 707244 Total No. of Proj.			**4**		**Total Amount**	**$10,728.00**
707247	1200 MM PRECAST CONCRETE PIPE MANHOLE	EA	10	1	9.00	$3,000.00	$27,000.00
	Unit Sub Total	**EA**		**1**	**9.00**	**$3,000.00**	**$27,000.00**
	Item Code 707247 Total No. of Proj.			**1**		**Total Amount**	**$27,000.00**
707249	1500 MM PRECAST CONCRETE PIPE MANHOLE	EA	10	1	8.00	$5,000.00	$40,000.00
		EA	11	1	2.00	$62,000.00	$124,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**2**	**10.00**	**$16,400.00**	**$164,000.00**
	Item Code 707249 Total No. of Proj.			**2**		**Total Amount**	**$164,000.00**
707252	1800 MM PRECAST CONCRETE PIPE MANHOLE	M	1	1	2.00	$3,500.00	$7,000.00
		M	4	1	10.60	$4,500.00	$47,700.00
	Unit Sub Total	**M**		**2**	**12.60**	**$4,341.27**	**$54,700.00**
	Item Code 707252 Total No. of Proj.			**2**		**Total Amount**	**$54,700.00**
707417	36" PRECAST CONCRETE PIPE RISER	LF	11	1	5.00	$420.00	$2,100.00
	Unit Sub Total	**LF**		**1**	**5.00**	**$420.00**	**$2,100.00**
	Item Code 707417 Total No. of Proj.			**1**		**Total Amount**	**$2,100.00**
707467	36" REINFORCED CONCRETE PIPE RISER	LF	11	1	5.00	$600.00	$3,000.00
	Unit Sub Total	**LF**		**1**	**5.00**	**$600.00**	**$3,000.00**
	Item Code 707467 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
707471	900 MM PRECAST CONCRETE PIPE RISER	M	7	1	1.30	$1,250.00	$1,625.00
	Unit Sub Total	**M**		**1**	**1.30**	**$1,250.00**	**$1,625.00**
	Item Code 707471 Total No. of Proj.			**1**		**Total Amount**	**$1,625.00**
707479	900 MM REINFORCED CONCRETE PIPE RISER	M	11	2	46.00	$716.09	$32,940.00
	Unit Sub Total	**M**		**2**	**46.00**	**$716.09**	**$32,940.00**
	Item Code 707479 Total No. of Proj.			**2**		**Total Amount**	**$32,940.00**
708050	36" ALTERNATIVE PIPE RISER	LF	5	1	10.00	$700.00	$7,000.00
	Unit Sub Total	**LF**		**1**	**10.00**	**$700.00**	**$7,000.00**
	Item Code 708050 Total No. of Proj.			**1**		**Total Amount**	**$7,000.00**
717001	4" POLYVINYL CHLORIDE SEWER PIPE	LF	4	1	40.00	$135.00	$5,400.00
	Unit Sub Total	**LF**		**1**	**40.00**	**$135.00**	**$5,400.00**
	Item Code 717001 Total No. of Proj.			**1**		**Total Amount**	**$5,400.00**
717073	150 MM SEWER PIPE	M	4	1	26.00	$100.00	$2,600.00
	Unit Sub Total	**M**		**1**	**26.00**	**$100.00**	**$2,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 717073 Total No. of Proj.			**1**		**Total Amount**	**$2,600.00**
719110	SEWER TERMINAL CLEANOUT	EA	4	2	4.00	$812.50	$3,250.00
	Unit Sub Total	**EA**		**2**	**4.00**	**$812.50**	**$3,250.00**
	Item Code 719110 Total No. of Proj.			**2**		**Total Amount**	**$3,250.00**
719190	SEWER MANHOLE FRAME AND COVER	EA	4	1	2.00	$500.00	$1,000.00
		EA	11	1	5.00	$7,300.00	$36,500.00
	Unit Sub Total	**EA**		**2**	**7.00**	**$5,357.14**	**$37,500.00**
	Item Code 719190 Total No. of Proj.			**2**		**Total Amount**	**$37,500.00**
719200	SEWER MANHOLE	EA	4	1	2.00	$2,500.00	$5,000.00
		EA	11	1	5.00	$7,500.00	$37,500.00
	Unit Sub Total	**EA**		**2**	**7.00**	**$6,071.43**	**$42,500.00**
	Item Code 719200 Total No. of Proj.			**2**		**Total Amount**	**$42,500.00**
719210	CONCRETE SEWER MANHOLE	EA	7	1	21.00	$7,700.00	$161,700.00
	Unit Sub Total	**EA**		**1**	**21.00**	**$7,700.00**	**$161,700.00**
	Item Code 719210 Total No. of Proj.			**1**		**Total Amount**	**$161,700.00**
719305	MANHOLE (TYPE A)	EA	5	1	2.00	$2,500.00	$5,000.00
		EA	6	1	3.00	$3,000.00	$9,000.00
	Unit Sub Total	**EA**		**2**	**5.00**	**$2,800.00**	**$14,000.00**
	Item Code 719305 Total No. of Proj.			**2**		**Total Amount**	**$14,000.00**
719569	MINOR CONCRETE (PIPE ENCASEMENT)	CY	7	1	22.00	$155.00	$3,410.00
	Unit Sub Total	**CY**		**1**	**22.00**	**$155.00**	**$3,410.00**
719569	MINOR CONCRETE (PIPE ENCASEMENT)	M3	11	2	915.00	$330.23	$302,160.00
	Unit Sub Total	**M3**		**2**	**915.00**	**$330.23**	**$302,160.00**
	Item Code 719569 Total No. of Proj.			**3**		**Total Amount**	**$305,570.00**
719589	MINOR CONCRETE (BACKFILL)	CY	5	1	130.00	$200.00	$26,000.00
		CY	6	1	13.00	$171.00	$2,223.00
	Unit Sub Total	**CY**		**2**	**143.00**	**$197.36**	**$28,223.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
719589	MINOR CONCRETE (BACKFILL)	M3	4	1	110.00	$250.00	$27,500.00
		M3	5	1	5.60	$300.00	$1,680.00
		M3	6	1	30.00	$180.00	$5,400.00
		M3	10	1	14.00	$125.00	$1,750.00
	Unit Sub Total	**M3**		**4**	**159.60**	**$227.63**	**$36,330.00**
	Item Code 719589 Total No. of Proj.			**6**		**Total Amount**	**$64,553.00**
719598	CLASS 4 CONCRETE (BACKFILL)	CY	8	1	17.00	$150.00	$2,550.00
	Unit Sub Total	**CY**		**1**	**17.00**	**$150.00**	**$2,550.00**
719598	CLASS 4 CONCRETE (BACKFILL)	M3	3	1	45.00	$250.00	$11,250.00
	Unit Sub Total	**M3**		**1**	**45.00**	**$250.00**	**$11,250.00**
	Item Code 719598 Total No. of Proj.			**2**		**Total Amount**	**$13,800.00**
720103	ROCK SLOPE PROTECTION (2 TON, METHOD A)	CY	6	1	3,580.00	$76.00	$272,080.00
		CY	8	1	110.00	$66.00	$7,260.00
	Unit Sub Total	**CY**		**2**	**3,690.00**	**$75.70**	**$279,340.00**
	Item Code 720103 Total No. of Proj.			**2**		**Total Amount**	**$279,340.00**
720104	ROCK SLOPE PROTECTION (1 TON, METHOD A)	TON	1	1	100.00	$151.50	$15,150.00
	Unit Sub Total	**TON**		**1**	**100.00**	**$151.50**	**$15,150.00**
	Item Code 720104 Total No. of Proj.			**1**		**Total Amount**	**$15,150.00**
720106	ROCK SLOPE PROTECTION (1/2 TON, METHOD A)	CY	1	3	112.40	$136.27	$15,317.00
		CY	2	2	90.00	$86.67	$7,800.00
		CY	4	1	460.00	$75.00	$34,500.00
		CY	10	1	700.00	$45.00	$31,500.00
	Unit Sub Total	**CY**		**7**	**1,362.40**	**$65.41**	**$89,117.00**
	Item Code 720106 Total No. of Proj.			**7**		**Total Amount**	**$89,117.00**
720117	ROCK SLOPE PROTECTION (4T, METHOD A)	M3	11	1	170.00	$54.00	$9,180.00
	Unit Sub Total	**M3**		**1**	**170.00**	**$54.00**	**$9,180.00**
	Item Code 720117 Total No. of Proj.			**1**		**Total Amount**	**$9,180.00**
720118	ROCK SLOPE PROTECTION (2T, METHOD A)	M3	1	1	2.30	$110.00	$253.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M3**		**1**	**2.30**	**$110.00**	**$253.00**
	Item Code 720118 Total No. of Proj.			**1**		**Total Amount**	**$253.00**
720119	ROCK SLOPE PROTECTION (1T, METHOD A)	M3	1	1	5.30	$110.00	$583.00
	Unit Sub Total	**M3**		**1**	**5.30**	**$110.00**	**$583.00**
	Item Code 720119 Total No. of Proj.			**1**		**Total Amount**	**$583.00**
720120	ROCK SLOPE PROTECTION (1/2T, METHOD A)	M3	1	1	5.30	$110.00	$583.00
		M3	7	1	890.00	$108.00	$96,120.00
		M3	10	1	76.00	$188.00	$14,288.00
	Unit Sub Total	**M3**		**3**	**971.30**	**$114.27**	**$110,991.00**
	Item Code 720120 Total No. of Proj.			**3**		**Total Amount**	**$110,991.00**
721004	ROCK SLOPE PROTECTION (1 TON, METHOD B)	CY	8	1	200.00	$66.00	$13,200.00
	Unit Sub Total	**CY**		**1**	**200.00**	**$66.00**	**$13,200.00**
	Item Code 721004 Total No. of Proj.			**1**		**Total Amount**	**$13,200.00**
721006	ROCK SLOPE PROTECTION (1/2 TON, METHOD B)	CY	1	1	230.00	$72.00	$16,560.00
		CY	12	1	450.00	$60.00	$27,000.00
	Unit Sub Total	**CY**		**2**	**680.00**	**$64.06**	**$43,560.00**
	Item Code 721006 Total No. of Proj.			**2**		**Total Amount**	**$43,560.00**
721007	ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	CY	1	4	16,185.00	$47.88	$774,965.00
		CY	2	2	156.00	$89.45	$13,954.00
		CY	3	2	1,140.00	$103.93	$118,485.80
		CY	4	1	14.00	$100.00	$1,400.00
		CY	5	1	1,410.00	$90.00	$126,900.00
		CY	6	1	750.00	$87.00	$65,250.00
		CY	7	2	850.00	$87.76	$74,600.00
		CY	8	3	1,412.00	$80.72	$113,969.68
		CY	11	1	12.00	$450.00	$5,400.00
	Unit Sub Total	**CY**		**17**	**21,929.00**	**$59.05**	**$1,294,924.48**
721007	ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	M3	1	1	69.00	$110.00	$7,590.00
		M3	6	1	1,020.00	$170.00	$173,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M3**		**2**	**1,089.00**	**$166.20**	**$180,990.00**
721007	ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	TON	1	1	74.00	$53.00	$3,922.00
	Unit Sub Total	**TON**		**1**	**74.00**	**$53.00**	**$3,922.00**
721007	ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	TONN	2	2	172.00	$124.75	$21,457.00
	Unit Sub Total	**TONN**		**2**	**172.00**	**$124.75**	**$21,457.00**
	Item Code 721007 Total No. of Proj.			**22**		**Total Amount**	**$1,501,293.48**
721008	ROCK SLOPE PROTECTION (LIGHT, METHOD B)	CY	1	7	1,137.50	$76.53	$87,055.75
		CY	2	3	23.50	$269.77	$6,339.50
		CY	3	3	1,826.00	$83.47	$152,420.00
		CY	4	2	100.00	$146.00	$14,600.00
		CY	5	2	95.00	$110.42	$10,490.00
		CY	6	2	65.00	$268.58	$17,458.00
		CY	7	2	28.00	$106.61	$2,985.00
		CY	8	2	242.00	$73.31	$17,740.00
		CY	10	1	4.00	$400.00	$1,600.00
	Unit Sub Total	**CY**		**24**	**3,521.00**	**$88.24**	**$310,688.25**
721008	ROCK SLOPE PROTECTION (LIGHT, METHOD B)	M3	1	2	80.00	$149.88	$11,990.00
		M3	2	1	240.00	$143.00	$34,320.00
		M3	3	2	91.00	$176.15	$16,030.00
		M3	4	5	1,334.00	$119.60	$159,540.00
		M3	6	1	6.00	$500.00	$3,000.00
		M3	8	1	110.00	$300.00	$33,000.00
		M3	10	3	178.00	$162.83	$28,984.00
		M3	11	2	22,031.00	$49.28	$1,085,750.00
	Unit Sub Total	**M3**		**17**	**24,070.00**	**$57.03**	**$1,372,614.00**
	Item Code 721008 Total No. of Proj.			**41**		**Total Amount**	**$1,683,302.25**
721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	CF	8	1	480.00	$12.20	$5,856.00
	Unit Sub Total	**CF**		**1**	**480.00**	**$12.20**	**$5,856.00**
721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	CY	1	3	71.00	$54.07	$3,839.00
		CY	2	3	73.00	$109.11	$7,965.00
		CY	3	2	11.00	$179.09	$1,970.00
		CY	4	2	80.00	$141.88	$11,350.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	CY	5	2	22.00	$1,000.00	$22,000.00
		CY	6	2	683.00	$91.31	$62,362.00
		CY	7	2	21.00	$428.57	$9,000.00
		CY	9	1	16.00	$110.00	$1,760.00
		CY	10	1	2.00	$700.00	$1,400.00
		CY	11	1	5.00	$225.00	$1,125.00
		CY	12	1	70.00	$60.00	$4,200.00
	Unit Sub Total	**CY**		**20**	**1,054.00**	**$120.47**	**$126,971.00**
721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	M3	3	2	147.00	$151.69	$22,298.00
		M3	4	6	265.60	$186.33	$49,490.00
		M3	6	1	420.00	$190.00	$79,800.00
		M3	7	2	220.00	$323.64	$71,200.00
		M3	8	1	51.00	$115.00	$5,865.00
		M3	9	2	194.00	$307.22	$59,600.00
		M3	10	2	1,128.00	$63.49	$71,616.00
		M3	11	1	280.00	$84.00	$23,520.00
	Unit Sub Total	**M3**		**17**	**2,705.60**	**$141.70**	**$383,389.00**
721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	TON	2	3	162.00	$79.41	$12,864.00
	Unit Sub Total	**TON**		**3**	**162.00**	**$79.41**	**$12,864.00**
	Item Code 721009 Total No. of Proj.			**41**		**Total Amount**	**$529,080.00**
721010	ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B)	CY	1	1	12.00	$380.00	$4,560.00
		CY	2	1	27.00	$80.00	$2,160.00
		CY	3	2	1,355.00	$80.44	$109,000.00
		CY	4	1	9.00	$120.00	$1,080.00
		CY	5	2	406.00	$81.77	$33,200.00
		CY	8	3	93.00	$128.09	$11,912.00
		CY	10	1	370.00	$39.50	$14,615.00
		CY	11	1	8.00	$340.00	$2,720.00
		CY	12	1	20.00	$100.00	$2,000.00
	Unit Sub Total	**CY**		**13**	**2,300.00**	**$78.80**	**$181,247.00**
721010	ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B)	M3	1	1	370.00	$102.00	$37,740.00
		M3	3	1	66.00	$170.00	$11,220.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
721010	ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B)	M3	5	1	450.00	$100.00	$45,000.00
		M3	8	1	2.40	$425.00	$1,020.00
		M3	11	2	113.00	$134.40	$15,187.00
	Unit Sub Total	**M3**		**6**	**1,001.40**	**$110.01**	**$110,167.00**
721010	ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B)	TONN	2	2	18.00	$193.33	$3,479.94
	Unit Sub Total	**TONN**		**2**	**18.00**	**$193.33**	**$3,479.94**
	Item Code 721010 Total No. of Proj.			**21**		**Total Amount**	**$294,893.94**
721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	CY	1	2	39.00	$94.36	$3,680.00
		CY	2	4	259.10	$73.74	$19,105.00
		CY	3	1	5.00	$400.00	$2,000.00
		CY	4	2	126.00	$111.26	$14,019.00
		CY	5	2	8.00	$355.00	$2,840.00
		CY	6	1	23.00	$240.00	$5,520.00
		CY	8	2	2,180.00	$110.39	$240,640.00
		CY	10	3	17.00	$311.76	$5,300.00
		CY	11	1	2.60	$250.00	$650.00
	Unit Sub Total	**CY**		**18**	**2,659.70**	**$110.45**	**$293,754.00**
721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	M3	1	1	24.00	$150.00	$3,600.00
		M3	2	1	1.40	$600.00	$840.00
		M3	3	3	735.00	$94.21	$69,242.00
		M3	4	2	74.50	$171.81	$12,800.00
		M3	5	3	444.00	$223.48	$99,226.08
		M3	6	2	810.00	$138.15	$111,900.00
		M3	8	1	10.00	$125.00	$1,250.00
		M3	10	2	48.00	$206.88	$9,930.00
		M3	11	1	130.00	$254.00	$33,020.00
	Unit Sub Total	**M3**		**16**	**2,276.90**	**$150.12**	**$341,808.08**
721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	TON	2	1	5.00	$180.00	$900.00
	Unit Sub Total	**TON**		**1**	**5.00**	**$180.00**	**$900.00**
721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	TONN	2	2	220.00	$104.90	$23,076.90

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**TONN**		**2**	**220.00**	**$104.90**	**$23,076.90**
	Item Code 721011 Total No. of Proj.			**37**		**Total Amount**	**$659,538.98**
721012	ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B)	CY	1	1	170.00	$116.00	$19,720.00
		CY	2	1	15.00	$302.00	$4,530.00
		CY	3	3	386.00	$151.55	$58,500.00
		CY	4	4	169.50	$74.27	$12,589.00
		CY	5	1	290.00	$90.00	$26,100.00
		CY	6	1	690.00	$110.00	$75,900.00
		CY	7	2	4.40	$409.09	$1,800.00
	Unit Sub Total	**CY**		**13**	**1,724.90**	**$115.45**	**$199,139.00**
721012	ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B)	M3	4	1	400.00	$161.00	$64,400.00
		M3	8	1	18.00	$129.00	$2,322.00
		M3	10	1	6.00	$280.00	$1,680.00
	Unit Sub Total	**M3**		**3**	**424.00**	**$161.33**	**$68,402.00**
721012	ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B)	TON	1	1	55.00	$62.00	$3,410.00
		TON	2	1	26.00	$91.00	$2,366.00
	Unit Sub Total	**TON**		**2**	**81.00**	**$71.31**	**$5,776.00**
	Item Code 721012 Total No. of Proj.			**18**		**Total Amount**	**$273,317.00**
721022	ROCK SLOPE PROTECTION (1T, METHOD B)	M3	1	1	66.00	$110.00	$7,260.00
	Unit Sub Total	**M3**		**1**	**66.00**	**$110.00**	**$7,260.00**
	Item Code 721022 Total No. of Proj.			**1**		**Total Amount**	**$7,260.00**
721023	ROCK SLOPE PROTECTION (1/2T, METHOD B)	M3	1	1	270.00	$92.00	$24,840.00
		M3	11	1	3,310.00	$65.00	$215,150.00
	Unit Sub Total	**M3**		**2**	**3,580.00**	**$67.04**	**$239,990.00**
	Item Code 721023 Total No. of Proj.			**2**		**Total Amount**	**$239,990.00**
721024	ROCK SLOPE PROTECTION (1/4T, METHOD B)	CY	1	1	320.00	$87.00	$27,840.00
		CY	4	1	620.00	$115.00	$71,300.00
		CY	8	1	150.00	$71.00	$10,650.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**CY**		**3**	**1,090.00**	**$100.72**	**$109,790.00**
721024	ROCK SLOPE PROTECTION (1/4T, METHOD B)	M3	1	4	1,090.00	$79.18	$86,305.00
		M3	4	2	1,068.00	$93.84	$100,224.00
		M3	5	1	85.00	$160.00	$13,600.00
		M3	8	2	179.00	$162.39	$29,068.00
		M3	11	1	60.00	$90.00	$5,400.00
	Unit Sub Total	**M3**		**10**	**2,482.00**	**$94.52**	**$234,597.00**
	Item Code 721024 Total No. of Proj.			**13**		**Total Amount**	**$344,387.00**
721025	ROCK SLOPE PROTECTION (2T, METHOD B)	M3	1	1	66.00	$110.00	$7,260.00
	Unit Sub Total	**M3**		**1**	**66.00**	**$110.00**	**$7,260.00**
	Item Code 721025 Total No. of Proj.			**1**		**Total Amount**	**$7,260.00**
721400	CONCRETE (SLOPE PROTECTION)	CY	3	1	6.00	$300.00	$1,800.00
		CY	11	2	75.00	$486.00	$36,450.00
	Unit Sub Total	**CY**		**3**	**81.00**	**$472.22**	**$38,250.00**
	Item Code 721400 Total No. of Proj.			**3**		**Total Amount**	**$38,250.00**
721420	CONCRETE (DITCH LINING)	CY	8	1	70.00	$284.00	$19,880.00
	Unit Sub Total	**CY**		**1**	**70.00**	**$284.00**	**$19,880.00**
721420	CONCRETE (DITCH LINING)	M3	3	1	0.10	$9,100.00	$910.00
		M3	4	1	4.00	$1,200.00	$4,800.00
		M3	10	1	18.00	$1,220.00	$21,960.00
	Unit Sub Total	**M3**		**3**	**22.10**	**$1,252.04**	**$27,670.00**
	Item Code 721420 Total No. of Proj.			**4**		**Total Amount**	**$47,550.00**
721430	CONCRETE (CHANNEL LINING)	CY	7	1	1,160.00	$410.00	$475,600.00
		CY	8	1	290.00	$189.65	$54,998.50
	Unit Sub Total	**CY**		**2**	**1,450.00**	**$365.93**	**$530,598.50**
721430	CONCRETE (CHANNEL LINING)	M3	4	1	73.00	$907.00	$66,211.00
	Unit Sub Total	**M3**		**1**	**73.00**	**$907.00**	**$66,211.00**
	Item Code 721430 Total No. of Proj.			**3**		**Total Amount**	**$596,809.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
721501	CONCRETE (CONCRETED-ROCK SLOPE PROTECTION)	CY	8	2	660.00	$225.45	$148,800.00
		CY	12	1	3.00	$250.00	$750.00
	Unit Sub Total	**CY**		**3**	**663.00**	**$225.57**	**$149,550.00**
	Item Code 721501 Total No. of Proj.			**3**		**Total Amount**	**$149,550.00**
721509	CONCRETED-ROCK SLOPE PROTECTION (FACING, METHOD A)	CY	3	1	66.00	$300.00	$19,800.00
	Unit Sub Total	**CY**		**1**	**66.00**	**$300.00**	**$19,800.00**
	Item Code 721509 Total No. of Proj.			**1**		**Total Amount**	**$19,800.00**
721518	CONCRETED-ROCK SLOPE PROTECTION (1T, METHOD A)	CY	8	1	200.00	$76.00	$15,200.00
	Unit Sub Total	**CY**		**1**	**200.00**	**$76.00**	**$15,200.00**
	Item Code 721518 Total No. of Proj.			**1**		**Total Amount**	**$15,200.00**
721607	CONCRETED-ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	CY	8	1	3,980.00	$125.00	$497,500.00
	Unit Sub Total	**CY**		**1**	**3,980.00**	**$125.00**	**$497,500.00**
	Item Code 721607 Total No. of Proj.			**1**		**Total Amount**	**$497,500.00**
721616	CONCRETED-ROCK SLOPE PROTECTION (COBBLE, METHOD B)	CY	12	1	9.00	$250.00	$2,250.00
	Unit Sub Total	**CY**		**1**	**9.00**	**$250.00**	**$2,250.00**
	Item Code 721616 Total No. of Proj.			**1**		**Total Amount**	**$2,250.00**
721810	SLOPE PAVING (CONCRETE)	CY	3	2	111.00	$747.93	$83,020.00
		CY	4	1	15.00	$500.00	$7,500.00
		CY	7	5	1,182.00	$285.62	$337,600.00
		CY	11	1	20.00	$775.00	$15,500.00
		CY	12	2	210.00	$477.14	$100,200.00
	Unit Sub Total	**CY**		**11**	**1,538.00**	**$353.59**	**$543,820.00**
721810	SLOPE PAVING (CONCRETE)	M3	3	2	92.00	$930.11	$85,570.00
		M3	4	2	95.00	$1,129.22	$107,276.00
		M3	5	1	38.00	$6,000.00	$228,000.00
		M3	7	2	158.00	$560.32	$88,530.00
		M3	8	2	292.00	$660.02	$192,725.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**9**	**675.00**	**$1,040.15**	**$702,101.00**
721810	SLOPE PAVING (CONCRETE)		SQFT	12	3	19,360.00	$19.21	$372,000.00
		Unit Sub Total	**SQFT**		**3**	**19,360.00**	**$19.21**	**$372,000.00**
	Item Code 721810	**Total No. of Proj.**			**23**		**Total Amount**	**$1,617,921.00**
722002	BROKEN CONCRETE SLOPE PROTECTION		CY	7	1	0.60	$1,000.00	$600.00
		Unit Sub Total	**CY**		**1**	**0.60**	**$1,000.00**	**$600.00**
	Item Code 722002	**Total No. of Proj.**			**1**		**Total Amount**	**$600.00**
722020	GABION		CY	2	3	395.00	$166.27	$65,675.00
			CY	3	1	54.00	$250.00	$13,500.00
			CY	5	1	180.00	$480.00	$86,400.00
			CY	7	2	80.00	$432.69	$34,615.00
		Unit Sub Total	**CY**		**7**	**709.00**	**$282.36**	**$200,190.00**
722020	GABION		M3	3	1	410.00	$180.00	$73,800.00
			M3	7	2	780.00	$275.68	$215,030.00
		Unit Sub Total	**M3**		**3**	**1,190.00**	**$242.71**	**$288,830.00**
	Item Code 722020	**Total No. of Proj.**			**10**		**Total Amount**	**$489,020.00**
727901	MINOR CONCRETE (DITCH LINING)		CF	12	1	100.00	$27.50	$2,750.00
		Unit Sub Total	**CF**		**1**	**100.00**	**$27.50**	**$2,750.00**
727901	MINOR CONCRETE (DITCH LINING)		CY	1	1	10.00	$500.00	$5,000.00
			CY	3	1	210.00	$345.00	$72,450.00
			CY	4	4	135.20	$357.55	$48,341.40
			CY	7	1	1.50	$800.00	$1,200.00
			CY	12	2	20.00	$616.50	$12,330.00
		Unit Sub Total	**CY**		**9**	**376.70**	**$369.85**	**$139,321.40**
727901	MINOR CONCRETE (DITCH LINING)		M3	4	1	70.00	$570.00	$39,900.00
			M3	7	2	5.30	$423.40	$2,244.00
			M3	8	2	112.00	$246.43	$27,600.00
			M3	11	1	140.00	$530.00	$74,200.00
		Unit Sub Total	**M3**		**6**	**327.30**	**$439.79**	**$143,944.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 727901 Total No. of Proj.			**16**		**Total Amount**	**$286,015.40**
727902	MINOR CONCRETE (SLOPE PROTECTION)	M3	11	1	820.00	$367.00	$300,940.00
	Unit Sub Total	**M3**		**1**	**820.00**	**$367.00**	**$300,940.00**
	Item Code 727902 Total No. of Proj.			**1**		**Total Amount**	**$300,940.00**
727905	MINOR CONCRETE (CHANNEL LINING)	CY	7	1	3.00	$800.00	$2,400.00
		CY	11	1	9.00	$800.00	$7,200.00
		CY	12	1	53.00	$445.00	$23,585.00
	Unit Sub Total	**CY**		**3**	**65.00**	**$510.54**	**$33,185.00**
727905	MINOR CONCRETE (CHANNEL LINING)	M3	8	1	140.00	$190.00	$26,600.00
	Unit Sub Total	**M3**		**1**	**140.00**	**$190.00**	**$26,600.00**
	Item Code 727905 Total No. of Proj.			**4**		**Total Amount**	**$59,785.00**
727906	MINOR CONCRETE (GUTTER LINING)	CY	7	1	3.00	$800.00	$2,400.00
	Unit Sub Total	**CY**		**1**	**3.00**	**$800.00**	**$2,400.00**
	Item Code 727906 Total No. of Proj.			**1**		**Total Amount**	**$2,400.00**
729000	FILTER FABRIC	SQYD	2	1	7.00	$70.00	$490.00
	Unit Sub Total	**SQYD**		**1**	**7.00**	**$70.00**	**$490.00**
	Item Code 729000 Total No. of Proj.			**1**		**Total Amount**	**$490.00**
729002	FILTER FABRIC (GABION)	M2	7	1	2,350.00	$2.32	$5,452.00
	Unit Sub Total	**M2**		**1**	**2,350.00**	**$2.32**	**$5,452.00**
	Item Code 729002 Total No. of Proj.			**1**		**Total Amount**	**$5,452.00**
729010	ROCK SLOPE PROTECTION FABRIC	LF	1	1	180.00	$1.75	$315.00
	Unit Sub Total	**LF**		**1**	**180.00**	**$1.75**	**$315.00**
729010	ROCK SLOPE PROTECTION FABRIC	M2	1	4	1,670.00	$5.62	$9,390.00
		M2	2	3	638.00	$10.94	$6,982.36
		M2	3	5	3,089.00	$3.94	$12,182.00
		M2	4	10	6,347.50	$4.15	$26,340.00
		M2	5	3	2,119.00	$3.21	$6,799.88
		M2	6	3	3,650.00	$5.82	$21,230.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
729010	ROCK SLOPE PROTECTION FABRIC		M2	7	2	630.00	$9.00	$5,670.00
			M2	8	3	940.00	$5.64	$5,302.50
			M2	9	2	670.00	$2.78	$1,860.00
			M2	10	7	3,278.00	$3.30	$10,827.00
			M2	11	3	1,670.00	$5.65	$9,435.00
		Unit Sub Total	**M2**		**45**	**24,701.50**	**$4.70**	**$116,018.74**
729010	ROCK SLOPE PROTECTION FABRIC		M3	1	1	105.00	$2.50	$262.50
		Unit Sub Total	**M3**		**1**	**105.00**	**$2.50**	**$262.50**
729010	ROCK SLOPE PROTECTION FABRIC		SQFT	1	1	1,730.00	$0.50	$865.00
			SQFT	2	1	810.00	$0.50	$405.00
			SQFT	6	1	7,760.00	$0.20	$1,552.00
			SQFT	8	2	1,010.00	$0.89	$899.90
			SQFT	10	1	140.00	$3.00	$420.00
		Unit Sub Total	**SQFT**		**6**	**11,450.00**	**$0.36**	**$4,141.90**
729010	ROCK SLOPE PROTECTION FABRIC		SQYD	1	12	11,122.00	$1.25	$13,862.00
			SQYD	2	8	2,008.00	$3.69	$7,406.00
			SQYD	3	8	6,532.00	$5.56	$36,336.40
			SQYD	4	7	2,354.00	$4.42	$10,413.50
			SQYD	5	4	2,989.00	$1.47	$4,380.00
			SQYD	6	5	3,437.00	$4.47	$15,350.00
			SQYD	7	5	6,139.00	$1.09	$6,672.00
			SQYD	8	6	6,685.00	$5.30	$35,425.00
			SQYD	9	1	39.00	$4.00	$156.00
			SQYD	10	4	670.00	$3.88	$2,600.00
			SQYD	11	3	70.00	$25.69	$1,798.00
			SQYD	12	1	32.00	$20.00	$640.00
		Unit Sub Total	**SQYD**		**64**	**42,077.00**	**$3.21**	**$135,038.90**
	Item Code 729010	**Total No. of Proj.**			**117**		**Total Amount**	**$255,777.04**
731501	MINOR CONCRETE (CURB)		CY	2	1	18.00	$450.00	$8,100.00
			CY	3	1	1.00	$3,000.00	$3,000.00
			CY	4	4	354.00	$396.81	$140,470.00
			CY	6	1	8.00	$620.00	$4,960.00
			CY	8	1	7.00	$900.00	$6,300.00
			CY	10	1	3.20	$1,000.00	$3,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
731501	MINOR CONCRETE (CURB)		CY	11	1	6.00	$195.51	$1,173.06
		Unit Sub Total	**CY**		**10**	**397.20**	**$420.95**	**$167,203.06**
731501	MINOR CONCRETE (CURB)		LF	2	1	110.00	$17.50	$1,925.00
			LF	7	2	370.00	$28.76	$10,640.00
			LF	9	2	720.00	$26.42	$19,020.00
		Unit Sub Total	**LF**		**5**	**1,200.00**	**$26.32**	**$31,585.00**
731501	MINOR CONCRETE (CURB)		M3	4	1	79.00	$440.00	$34,760.00
			M3	5	1	22.00	$1,041.18	$22,905.96
			M3	6	1	29.00	$1,200.00	$34,800.00
		Unit Sub Total	**M3**		**3**	**130.00**	**$711.28**	**$92,465.96**
	Item Code 731501	**Total No. of Proj.**			**18**		**Total Amount**	**$291,254.02**
731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)		CY	1	1	56.00	$1,000.00	$56,000.00
			CY	2	3	47.00	$621.91	$29,230.00
			CY	3	3	498.00	$266.75	$132,840.00
			CY	4	5	708.00	$413.30	$292,619.00
			CY	5	2	242.00	$740.18	$179,124.00
			CY	6	5	216.00	$478.44	$103,342.00
			CY	7	2	40.10	$405.24	$16,250.00
			CY	8	5	482.00	$412.49	$198,820.00
			CY	9	2	292.00	$390.55	$114,040.00
			CY	10	2	40.50	$598.77	$24,250.00
			CY	11	4	81.00	$650.99	$52,730.00
			CY	12	9	1,156.50	$443.55	$512,960.00
		Unit Sub Total	**CY**		**43**	**3,859.10**	**$443.68**	**$1,712,205.00**
731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)		M3	3	3	79.20	$360.60	$28,559.20
			M3	4	7	2,733.00	$490.93	$1,341,710.00
			M3	5	1	52.00	$500.00	$26,000.00
			M3	6	2	343.00	$366.76	$125,800.00
			M3	7	3	1,556.20	$461.95	$718,890.00
			M3	8	2	1,530.00	$330.56	$505,750.00
			M3	9	1	130.00	$850.00	$110,500.00
			M3	10	1	460.00	$700.00	$322,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	M3	11	3	946.00	$515.59	$487,750.00
	Unit Sub Total	**M3**		**23**	**7,829.40**	**$468.36**	**$3,666,959.20**
	Item Code 731502 Total No. of Proj.			**66**		**Total Amount**	**$5,379,164.20**
731504	MINOR CONCRETE (CURB AND GUTTER)	CY	2	2	50.00	$582.80	$29,140.00
		CY	3	3	3,343.00	$283.58	$948,000.00
		CY	4	1	20.00	$500.00	$10,000.00
		CY	7	4	21.00	$616.62	$12,949.00
		CY	8	3	30.00	$724.30	$21,729.00
	Unit Sub Total	**CY**		**13**	**3,464.00**	**$294.98**	**$1,021,818.00**
731504	MINOR CONCRETE (CURB AND GUTTER)	LF	2	1	110.00	$58.99	$6,488.90
	Unit Sub Total	**LF**		**1**	**110.00**	**$58.99**	**$6,488.90**
731504	MINOR CONCRETE (CURB AND GUTTER)	M3	3	1	18.00	$700.00	$12,600.00
		M3	4	1	220.00	$365.00	$80,300.00
		M3	5	1	97.00	$500.00	$48,500.00
		M3	8	1	210.00	$243.00	$51,030.00
	Unit Sub Total	**M3**		**4**	**545.00**	**$353.08**	**$192,430.00**
	Item Code 731504 Total No. of Proj.			**18**		**Total Amount**	**$1,220,736.90**
731505	MINOR CONCRETE (CURB AND SIDEWALK)	CY	5	1	39.00	$1,190.00	$46,410.00
	Unit Sub Total	**CY**		**1**	**39.00**	**$1,190.00**	**$46,410.00**
731505	MINOR CONCRETE (CURB AND SIDEWALK)	M3	4	1	1,290.00	$600.00	$774,000.00
	Unit Sub Total	**M3**		**1**	**1,290.00**	**$600.00**	**$774,000.00**
	Item Code 731505 Total No. of Proj.			**2**		**Total Amount**	**$820,410.00**
731507	MINOR CONCRETE (GUTTER DEPRESSION)	CY	2	1	2.40	$750.00	$1,800.00
		CY	4	2	8.00	$903.75	$7,230.00
		CY	8	1	0.90	$1,400.00	$1,260.00
	Unit Sub Total	**CY**		**4**	**11.30**	**$910.62**	**$10,290.00**
731507	MINOR CONCRETE (GUTTER DEPRESSION)	M3	4	1	65.00	$540.00	$35,100.00
		M3	8	1	3.50	$500.00	$1,750.00
		M3	10	1	12.00	$630.00	$7,560.00
	Unit Sub Total	**M3**		**3**	**80.50**	**$551.68**	**$44,410.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 731507 Total No. of Proj.			**7**		**Total Amount**	**$54,700.00**
731509	MINOR CONCRETE (CONCRETE MOW STRIP)	M3	4	1	8.00	$700.00	$5,600.00
	Unit Sub Total	**M3**		**1**	**8.00**	**$700.00**	**$5,600.00**
	Item Code 731509 Total No. of Proj.			**1**		**Total Amount**	**$5,600.00**
731510	MINOR CONCRETE (CURB, GUTTER, SIDEWALK AND DRIVEWAY)	CY	9	1	47.00	$500.00	$23,500.00
	Unit Sub Total	**CY**		**1**	**47.00**	**$500.00**	**$23,500.00**
	Item Code 731510 Total No. of Proj.			**1**		**Total Amount**	**$23,500.00**
731511	MINOR CONCRETE (ISLAND PAVING)	CY	2	1	12.00	$232.00	$2,784.00
		CY	4	1	6.00	$300.00	$1,800.00
		CY	7	1	2.00	$985.00	$1,970.00
	Unit Sub Total	**CY**		**3**	**20.00**	**$327.70**	**$6,554.00**
731511	MINOR CONCRETE (ISLAND PAVING)	M3	4	1	55.00	$265.00	$14,575.00
	Unit Sub Total	**M3**		**1**	**55.00**	**$265.00**	**$14,575.00**
	Item Code 731511 Total No. of Proj.			**4**		**Total Amount**	**$21,129.00**
731512	MINOR CONCRETE (EXPOSED AGGREGATE SIDEWALK)	SQFT	6	1	1,330.00	$8.99	$11,956.70
	Unit Sub Total	**SQFT**		**1**	**1,330.00**	**$8.99**	**$11,956.70**
	Item Code 731512 Total No. of Proj.			**1**		**Total Amount**	**$11,956.70**
731516	MINOR CONCRETE (DRIVEWAY)	CY	7	1	19.00	$500.00	$9,500.00
	Unit Sub Total	**CY**		**1**	**19.00**	**$500.00**	**$9,500.00**
731516	MINOR CONCRETE (DRIVEWAY)	M3	4	1	7.00	$328.00	$2,296.00
		M3	6	1	12.00	$520.00	$6,240.00
		M3	8	1	120.00	$190.00	$22,800.00
	Unit Sub Total	**M3**		**3**	**139.00**	**$225.44**	**$31,336.00**
	Item Code 731516 Total No. of Proj.			**4**		**Total Amount**	**$40,836.00**
731517	MINOR CONCRETE (GUTTER)	CY	1	1	6.00	$465.00	$2,790.00
		CY	3	1	0.10	$4,000.00	$400.00
		CY	4	1	0.80	$364.50	$291.60

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
731517	MINOR CONCRETE (GUTTER)	CY	7	3	85.00	$571.29	$48,560.00
		CY	9	1	5.00	$500.00	$2,500.00
		CY	12	1	1.00	$500.00	$500.00
	Unit Sub Total	**CY**		**8**	**97.90**	**$562.22**	**$55,041.60**
731517	MINOR CONCRETE (GUTTER)	LF	1	1	489.00	$36.00	$17,604.00
		LF	3	1	2,513.00	$20.00	$50,260.00
		LF	4	1	663.00	$35.00	$23,205.00
		LF	7	2	461.00	$30.41	$14,020.00
	Unit Sub Total	**LF**		**5**	**4,126.00**	**$25.47**	**$105,089.00**
731517	MINOR CONCRETE (GUTTER)	M	3	1	562.00	$80.00	$44,960.00
		M	4	3	1,358.00	$68.65	$93,220.00
		M	7	3	145.00	$124.31	$18,025.00
		M	8	1	16.00	$200.00	$3,200.00
	Unit Sub Total	**M**		**8**	**2,081.00**	**$76.60**	**$159,405.00**
731517	MINOR CONCRETE (GUTTER)	M3	4	3	123.50	$731.17	$90,300.00
		M3	6	1	6.00	$550.00	$3,300.00
		M3	8	1	9.00	$388.00	$3,492.00
	Unit Sub Total	**M3**		**5**	**138.50**	**$701.03**	**$97,092.00**
	Item Code 731517 Total No. of Proj.			**26**		**Total Amount**	**$416,627.60**
731518	MINOR CONCRETE (BRUSHED CONCRETE)	M2	3	1	1,380.00	$86.00	$118,680.00
	Unit Sub Total	**M2**		**1**	**1,380.00**	**$86.00**	**$118,680.00**
	Item Code 731518 Total No. of Proj.			**1**		**Total Amount**	**$118,680.00**
731519	MINOR CONCRETE (STAMPED CONCRETE)	CY	11	1	57.00	$550.00	$31,350.00
	Unit Sub Total	**CY**		**1**	**57.00**	**$550.00**	**$31,350.00**
731519	MINOR CONCRETE (STAMPED CONCRETE)	M2	3	1	1,440.00	$106.00	$152,640.00
		M2	7	1	12,000.00	$82.00	$984,000.00
		M2	11	1	270.00	$86.00	$23,220.00
	Unit Sub Total	**M2**		**3**	**13,710.00**	**$84.60**	**$1,159,860.00**
731519	MINOR CONCRETE (STAMPED CONCRETE)	M3	8	1	87.00	$758.00	$65,946.00
	Unit Sub Total	**M3**		**1**	**87.00**	**$758.00**	**$65,946.00**
731519	MINOR CONCRETE (STAMPED CONCRETE)	SQFT	2	1	48.00	$18.62	$893.76

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
731519	MINOR CONCRETE (STAMPED CONCRETE)	SQFT	7	3	141,800.00	$5.80	$823,000.00
	Unit Sub Total	**SQFT**		**4**	**141,848.00**	**$5.81**	**$823,893.76**
731519	MINOR CONCRETE (STAMPED CONCRETE)	SQYD	12	1	8.00	$120.00	$960.00
	Unit Sub Total	**SQYD**		**1**	**8.00**	**$120.00**	**$960.00**
	Item Code 731519 Total No. of Proj.			**10**		**Total Amount**	**$2,082,009.76**
731521	MINOR CONCRETE (SIDEWALK)	CY	2	3	129.00	$632.78	$81,628.42
		CY	3	1	96.00	$250.00	$24,000.00
		CY	4	2	333.00	$378.38	$126,000.00
		CY	6	1	340.00	$323.14	$109,867.60
		CY	7	1	0.40	$1,000.00	$400.00
		CY	8	1	15.00	$600.00	$9,000.00
	Unit Sub Total	**CY**		**9**	**913.40**	**$384.16**	**$350,896.02**
731521	MINOR CONCRETE (SIDEWALK)	M3	2	1	190.00	$341.00	$64,790.00
		M3	3	1	7.00	$700.00	$4,900.00
		M3	4	1	280.00	$283.00	$79,240.00
		M3	5	1	45.00	$500.00	$22,500.00
		M3	7	1	13.00	$500.00	$6,500.00
		M3	8	1	270.00	$277.00	$74,790.00
	Unit Sub Total	**M3**		**6**	**805.00**	**$313.94**	**$252,720.00**
	Item Code 731521 Total No. of Proj.			**15**		**Total Amount**	**$603,616.02**
731524	MINOR CONCRETE (COBBLESTONE TEXTURED PAVING)	M2	10	1	83.00	$122.00	$10,126.00
	Unit Sub Total	**M2**		**1**	**83.00**	**$122.00**	**$10,126.00**
	Item Code 731524 Total No. of Proj.			**1**		**Total Amount**	**$10,126.00**
731530	MINOR CONCRETE (TEXTURED PAVING)	CY	4	1	49.00	$560.00	$27,440.00
		CY	11	1	11.00	$3,181.00	$34,991.00
	Unit Sub Total	**CY**		**2**	**60.00**	**$1,040.52**	**$62,431.00**
731530	MINOR CONCRETE (TEXTURED PAVING)	M2	4	2	1,870.00	$63.72	$119,150.00
		M2	7	1	610.00	$100.00	$61,000.00
		M2	11	1	2,680.00	$64.00	$171,520.00
	Unit Sub Total	**M2**		**4**	**5,160.00**	**$68.15**	**$351,670.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
731530	MINOR CONCRETE (TEXTURED PAVING)	M3	3	1	350.00	$499.00	$174,650.00
	Unit Sub Total	**M3**		**1**	**350.00**	**$499.00**	**$174,650.00**
731530	MINOR CONCRETE (TEXTURED PAVING)	SQFT	2	1	400.00	$9.00	$3,600.00
		SQFT	3	1	41,600.00	$5.00	$208,000.00
		SQFT	4	1	520.00	$12.00	$6,240.00
		SQFT	6	3	17,520.00	$6.72	$117,673.00
		SQFT	11	1	5,670.00	$4.00	$22,680.00
	Unit Sub Total	**SQFT**		**7**	**65,710.00**	**$5.45**	**$358,193.00**
731530	MINOR CONCRETE (TEXTURED PAVING)	SQYD	2	1	420.00	$78.75	$33,075.00
	Unit Sub Total	**SQYD**		**1**	**420.00**	**$78.75**	**$33,075.00**
	Item Code 731530	**Total No. of Proj.**		**15**		**Total Amount**	**$980,019.00**
731623	MINOR CONCRETE (CURB RAMP)	CY	2	1	2.00	$1,250.00	$2,500.00
		CY	4	2	41.00	$693.41	$28,430.00
		CY	7	1	2.90	$1,850.00	$5,365.00
		CY	8	2	14.00	$868.86	$12,164.00
		CY	12	1	8.00	$560.00	$4,480.00
	Unit Sub Total	**CY**		**7**	**67.90**	**$779.66**	**$52,939.00**
731623	MINOR CONCRETE (CURB RAMP)	M3	2	1	5.00	$676.00	$3,380.00
		M3	3	1	8.00	$700.00	$5,600.00
		M3	4	1	10.00	$900.00	$9,000.00
		M3	5	1	1.30	$1,200.00	$1,560.00
		M3	6	1	52.00	$480.00	$24,960.00
		M3	8	1	21.00	$825.00	$17,325.00
	Unit Sub Total	**M3**		**6**	**97.30**	**$635.41**	**$61,825.00**
	Item Code 731623	**Total No. of Proj.**		**13**		**Total Amount**	**$114,764.00**
731626	MINOR CONCRETE (CURB AND CURB RAMP)	CY	8	1	22.00	$250.00	$5,500.00
	Unit Sub Total	**CY**		**1**	**22.00**	**$250.00**	**$5,500.00**
	Item Code 731626	**Total No. of Proj.**		**1**		**Total Amount**	**$5,500.00**
731627	MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP)	CY	3	3	305.00	$766.85	$233,890.00
		CY	4	2	120.00	$557.29	$66,875.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
731627	MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP)	CY	7	4	91.00	$780.44	$71,020.00
		CY	10	1	26.00	$1,000.00	$26,000.00
		CY	11	2	109.00	$347.25	$37,850.00
		CY	12	1	43.00	$350.00	$15,050.00
	Unit Sub Total	**CY**		**13**	**694.00**	**$649.40**	**$450,685.00**
731627	MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP)	M3	4	2	71.00	$656.34	$46,600.00
	Unit Sub Total	**M3**		**2**	**71.00**	**$656.34**	**$46,600.00**
	Item Code 731627 **Total No. of Proj.**			**15**		**Total Amount**	**$497,285.00**
731656	CURB RAMP DETECTABLE WARNING SURFACE	EA	12	1	3.00	$600.00	$1,800.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$600.00**	**$1,800.00**
731656	CURB RAMP DETECTABLE WARNING SURFACE	SQFT	1	1	84.00	$42.00	$3,528.00
		SQFT	4	1	36.00	$50.00	$1,800.00
		SQFT	11	2	167.00	$30.00	$5,010.00
		SQFT	12	1	170.00	$28.00	$4,760.00
	Unit Sub Total	**SQFT**		**5**	**457.00**	**$33.04**	**$15,098.00**
731656	CURB RAMP DETECTABLE WARNING SURFACE	SQYD	3	1	9.00	$275.00	$2,475.00
	Unit Sub Total	**SQYD**		**1**	**9.00**	**$275.00**	**$2,475.00**
	Item Code 731656 **Total No. of Proj.**			**7**		**Total Amount**	**$19,373.00**
740500	DRAINAGE PUMPING EQUIPMENT	LS	4	1	1.00	$50,000.00	$50,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$50,000.00**	**$50,000.00**
	Item Code 740500 **Total No. of Proj.**			**1**		**Total Amount**	**$50,000.00**
741001	PUMPING PLANT ELECTRICAL EQUIPMENT	LS	4	1	1.00	$170,000.00	$170,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$170,000.00**	**$170,000.00**
	Item Code 741001 **Total No. of Proj.**			**1**		**Total Amount**	**$170,000.00**
750001	MISCELLANEOUS IRON AND STEEL	KG	1	3	4,237.00	$8.18	$34,638.00
		KG	2	1	5,230.00	$7.00	$36,610.00
		KG	3	5	23,117.00	$3.03	$70,101.00
		KG	4	11	127,225.00	$3.08	$392,264.00
		KG	5	3	5,243.00	$3.97	$20,821.20

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
750001	MISCELLANEOUS IRON AND STEEL	KG	6	4	14,288.00	$2.94	$41,987.00
		KG	7	4	42,942.00	$3.34	$143,375.00
		KG	8	3	52,583.00	$3.22	$169,557.00
		KG	9	3	907.00	$14.24	$12,914.50
		KG	10	4	13,030.00	$2.50	$32,541.00
		KG	11	3	41,288.00	$4.53	$187,093.40
	Unit Sub Total	**KG**		**44**	**330,090.00**	**$3.46**	**$1,141,902.10**
750001	MISCELLANEOUS IRON AND STEEL	LB	1	13	22,985.00	$1.10	$25,193.70
		LB	2	14	31,607.00	$3.78	$119,612.43
		LB	3	8	139,825.00	$2.58	$360,677.50
		LB	4	12	58,624.00	$1.96	$114,728.73
		LB	5	8	24,133.00	$2.70	$65,154.50
		LB	6	4	8,478.00	$1.67	$14,181.00
		LB	7	10	141,758.00	$1.37	$193,903.57
		LB	8	3	2,650.00	$2.45	$6,480.00
		LB	10	5	15,336.00	$1.25	$19,163.50
		LB	11	5	8,843.00	$3.97	$35,146.50
		LB	12	6	59,005.00	$2.47	$145,696.60
	Unit Sub Total	**LB**		**88**	**513,244.00**	**$2.14**	**$1,099,938.03**
	Item Code 750001 **Total No. of Proj.**			**132**		**Total Amount**	**$2,241,840.13**
750002	MISCELLANEOUS IRON AND STEEL (SEWER SYSTEM)	KG	7	1	3,486.00	$3.50	$12,201.00
	Unit Sub Total	**KG**		**1**	**3,486.00**	**$3.50**	**$12,201.00**
	Item Code 750002 **Total No. of Proj.**			**1**		**Total Amount**	**$12,201.00**
750005	STEEL COVER	EA	10	1	1.00	$3,780.00	$3,780.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$3,780.00**	**$3,780.00**
	Item Code 750005 **Total No. of Proj.**			**1**		**Total Amount**	**$3,780.00**
750007	FRAME AND GRATE	EA	6	1	4.00	$112.35	$449.40
		EA	9	1	1.00	$600.00	$600.00
		EA	10	1	1.00	$390.00	$390.00
	Unit Sub Total	**EA**		**3**	**6.00**	**$239.90**	**$1,439.40**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 750007 Total No. of Proj.			**3**		**Total Amount**	**$1,439.40**
750008	FRAME AND COVER	EA	2	1	3.00	$265.00	$795.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$265.00**	**$795.00**
	Item Code 750008 Total No. of Proj.			**1**		**Total Amount**	**$795.00**
750010	MANHOLE FRAME AND COVER	EA	6	1	3.00	$1,000.00	$3,000.00
		EA	10	1	21.00	$250.00	$5,250.00
	Unit Sub Total	**EA**		**2**	**24.00**	**$343.75**	**$8,250.00**
	Item Code 750010 Total No. of Proj.			**2**		**Total Amount**	**$8,250.00**
750030	INLET FRAME AND GRATE	EA	5	1	7.00	$612.00	$4,284.00
		EA	6	1	2.00	$680.00	$1,360.00
		EA	10	1	43.00	$350.00	$15,050.00
	Unit Sub Total	**EA**		**3**	**52.00**	**$397.96**	**$20,694.00**
	Item Code 750030 Total No. of Proj.			**3**		**Total Amount**	**$20,694.00**
750041	ISOLATION CASING	KG	4	3	77,344.00	$6.42	$496,653.00
		KG	7	1	21,090.00	$3.00	$63,270.00
		KG	8	1	21,805.00	$7.00	$152,635.00
	Unit Sub Total	**KG**		**5**	**120,239.00**	**$5.93**	**$712,558.00**
750041	ISOLATION CASING	LB	4	3	49,500.00	$6.12	$303,000.00
	Unit Sub Total	**LB**		**3**	**49,500.00**	**$6.12**	**$303,000.00**
	Item Code 750041 Total No. of Proj.			**8**		**Total Amount**	**$1,015,558.00**
750050	INLET GRATE	EA	10	1	6.00	$630.00	$3,780.00
	Unit Sub Total	**EA**		**1**	**6.00**	**$630.00**	**$3,780.00**
	Item Code 750050 Total No. of Proj.			**1**		**Total Amount**	**$3,780.00**
750496	MISCELLANEOUS METAL (RESTRAINER - PIPE TYPE)	KG	4	1	14,500.00	$15.00	$217,500.00
		KG	7	1	15,707.00	$15.00	$235,605.00
		KG	10	1	4,700.00	$10.50	$49,350.00
	Unit Sub Total	**KG**		**3**	**34,907.00**	**$14.39**	**$502,455.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 750496 Total No. of Proj.			**3**		**Total Amount**	**$502,455.00**
750497	MISCELLANEOUS METAL (RESTRAINER - BAR TYPE)	KG	11	1	2,410.00	$11.00	$26,510.00
	Unit Sub Total	**KG**		**1**	**2,410.00**	**$11.00**	**$26,510.00**
	Item Code 750497 Total No. of Proj.			**1**		**Total Amount**	**$26,510.00**
750498	MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE)	KG	4	3	5,096.00	$14.57	$74,240.00
		KG	6	1	950.00	$24.00	$22,800.00
		KG	7	1	1,333.00	$16.00	$21,328.00
		KG	8	1	5,750.00	$5.00	$28,750.00
	Unit Sub Total	**KG**		**6**	**13,129.00**	**$11.21**	**$147,118.00**
750498	MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE)	LB	10	1	298.00	$50.00	$14,900.00
		LB	12	1	420.00	$15.00	$6,300.00
	Unit Sub Total	**LB**		**2**	**718.00**	**$29.53**	**$21,200.00**
	Item Code 750498 Total No. of Proj.			**8**		**Total Amount**	**$168,318.00**
750501	MISCELLANEOUS METAL (BRIDGE)	KG	2	1	68,800.00	$6.00	$412,800.00
		KG	4	5	2,875.00	$33.15	$95,300.00
		KG	5	1	490.00	$8.00	$3,920.00
		KG	6	1	500.00	$35.00	$17,500.00
		KG	7	2	3,250.00	$13.66	$44,400.00
		KG	8	2	1,888.00	$6.65	$12,560.00
		KG	11	2	4,590.00	$13.76	$63,180.00
	Unit Sub Total	**KG**		**14**	**82,393.00**	**$7.88**	**$649,660.00**
750501	MISCELLANEOUS METAL (BRIDGE)	LB	1	2	658.00	$28.11	$18,494.00
		LB	2	1	2,160.00	$8.00	$17,280.00
		LB	3	4	27,439.00	$7.08	$194,356.05
		LB	4	4	38,820.00	$3.87	$150,300.00
		LB	5	1	550.00	$23.00	$12,650.00
		LB	7	2	700.00	$7.50	$5,250.00
		LB	10	1	4,760.00	$31.00	$147,560.00
	Unit Sub Total	**LB**		**15**	**75,087.00**	**$7.27**	**$545,890.05**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 750501	**Total No. of Proj.**			**29**		**Total Amount**	**$1,195,550.05**
750505	BRIDGE DECK DRAINAGE SYSTEM		KG	1	1	260.00	$15.00	$3,900.00
			KG	2	1	1,100.00	$22.00	$24,200.00
			KG	4	4	46,386.00	$14.37	$666,547.00
			KG	5	1	3,455.00	$20.00	$69,100.00
			KG	6	1	2,600.00	$12.00	$31,200.00
			KG	7	3	7,136.00	$16.89	$120,534.00
			KG	8	2	7,772.00	$6.22	$48,360.00
			KG	10	1	2,400.00	$20.00	$48,000.00
			KG	11	2	21,700.00	$10.72	$232,600.00
		Unit Sub Total	**KG**		**16**	**92,809.00**	**$13.41**	**$1,244,441.00**
750505	BRIDGE DECK DRAINAGE SYSTEM		LB	4	4	73,440.00	$4.27	$313,910.00
			LB	5	1	830.00	$5.00	$4,150.00
			LB	7	1	775.00	$25.00	$19,375.00
			LB	12	1	180.00	$19.00	$3,420.00
		Unit Sub Total	**LB**		**7**	**75,225.00**	**$4.53**	**$340,855.00**
	Item Code 750505	**Total No. of Proj.**			**23**		**Total Amount**	**$1,585,296.00**
750520	PUMPING PLANT METAL WORK		KG	4	1	5,348.00	$10.00	$53,480.00
			KG	6	1	185.00	$15.00	$2,775.00
		Unit Sub Total	**KG**		**2**	**5,533.00**	**$10.17**	**$56,255.00**
	Item Code 750520	**Total No. of Proj.**			**2**		**Total Amount**	**$56,255.00**
760011	WELL DEVELOPMENT		LS	2	1	1.00	$5,892.00	$5,892.00
			LS	6	1	1.00	$21,250.00	$21,250.00
		Unit Sub Total	**LS**		**2**	**2.00**	**$13,571.00**	**$27,142.00**
	Item Code 760011	**Total No. of Proj.**			**2**		**Total Amount**	**$27,142.00**
760012	TESTING WELL		HR	2	1	30.00	$6.70	$201.00
			HR	6	1	8.00	$312.00	$2,496.00
		Unit Sub Total	**HR**		**2**	**38.00**	**$70.97**	**$2,697.00**
	Item Code 760012	**Total No. of Proj.**			**2**		**Total Amount**	**$2,697.00**
760021	DRILL PILOT HOLE		LF	2	1	400.00	$0.21	$84.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
760021	DRILL PILOT HOLE	LF	6	1	300.00	$54.50	$16,350.00
	Unit Sub Total	**LF**		**2**	**700.00**	**$23.48**	**$16,434.00**
	Item Code 760021 Total No. of Proj.			**2**		**Total Amount**	**$16,434.00**
760022	REAMING WATER WELL	LF	2	1	400.00	$0.34	$135.00
		LF	6	1	300.00	$54.50	$16,350.00
	Unit Sub Total	**LF**		**2**	**700.00**	**$23.55**	**$16,485.00**
	Item Code 760022 Total No. of Proj.			**2**		**Total Amount**	**$16,485.00**
760025	CONDUCTOR CASING	LF	2	1	50.00	$11.98	$599.00
		LF	6	1	50.00	$237.00	$11,850.00
	Unit Sub Total	**LF**		**2**	**100.00**	**$124.49**	**$12,449.00**
	Item Code 760025 Total No. of Proj.			**2**		**Total Amount**	**$12,449.00**
760030	BLANK WELL CASING	LF	2	1	310.00	$0.15	$47.99
		LF	6	1	290.00	$77.30	$22,417.00
	Unit Sub Total	**LF**		**2**	**600.00**	**$37.44**	**$22,464.99**
	Item Code 760030 Total No. of Proj.			**2**		**Total Amount**	**$22,464.99**
760035	WELL SCREEN	LF	2	1	90.00	$0.98	$87.99
		LF	6	1	15.00	$131.00	$1,965.00
	Unit Sub Total	**LF**		**2**	**105.00**	**$19.55**	**$2,052.99**
	Item Code 760035 Total No. of Proj.			**2**		**Total Amount**	**$2,052.99**
760080	WATER SUPPLY SYSTEM	LS	6	1	1.00	$21,262.00	$21,262.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$21,262.00**	**$21,262.00**
	Item Code 760080 Total No. of Proj.			**1**		**Total Amount**	**$21,262.00**
760090	MOBILIZATION, DEMOBILIZATION, AND FINAL CLEANUP	LS	2	1	1.00	$45,275.00	$45,275.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$45,275.00**	**$45,275.00**
	Item Code 760090 Total No. of Proj.			**1**		**Total Amount**	**$45,275.00**
800001	FENCE (TYPE BW, METAL POST)	LF	5	1	80.00	$15.00	$1,200.00
		LF	6	1	390.00	$12.00	$4,680.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
800001	FENCE (TYPE BW, METAL POST)	LF	10	1	140.00	$20.00	$2,800.00
	Unit Sub Total	**LF**		**3**	**610.00**	**$14.23**	**$8,680.00**
800001	FENCE (TYPE BW, METAL POST)	M	5	1	6,260.00	$9.00	$56,340.00
		M	10	1	2,040.00	$12.50	$25,500.00
	Unit Sub Total	**M**		**2**	**8,300.00**	**$9.86**	**$81,840.00**
	Item Code 800001 Total No. of Proj.			**5**		**Total Amount**	**$90,520.00**
800002	FENCE (TYPE BW, WOOD POST)	M	3	1	210.00	$32.00	$6,720.00
		M	4	1	45.00	$18.40	$828.00
	Unit Sub Total	**M**		**2**	**255.00**	**$29.60**	**$7,548.00**
	Item Code 800002 Total No. of Proj.			**2**		**Total Amount**	**$7,548.00**
800007	FENCE (TYPE BW, 5 STRAND, METAL POST)	LF	1	1	950.00	$12.50	$11,875.00
		LF	2	2	1,060.00	$5.68	$6,020.00
		LF	3	1	160.00	$11.49	$1,838.40
		LF	6	1	93,200.00	$2.75	$256,300.00
	Unit Sub Total	**LF**		**5**	**95,370.00**	**$2.89**	**$276,033.40**
800007	FENCE (TYPE BW, 5 STRAND, METAL POST)	M	9	2	1,320.00	$15.96	$21,067.50
	Unit Sub Total	**M**		**2**	**1,320.00**	**$15.96**	**$21,067.50**
	Item Code 800007 Total No. of Proj.			**7**		**Total Amount**	**$297,100.90**
800008	FENCE (TYPE BW, 4-STRAND, METAL POST)	M	6	1	25,800.00	$11.00	$283,800.00
	Unit Sub Total	**M**		**1**	**25,800.00**	**$11.00**	**$283,800.00**
	Item Code 800008 Total No. of Proj.			**1**		**Total Amount**	**$283,800.00**
800051	FENCE (TYPE WM, METAL POST)	LF	2	1	4,410.00	$4.45	$19,624.50
		LF	6	1	24,000.00	$5.46	$131,040.00
	Unit Sub Total	**LF**		**2**	**28,410.00**	**$5.30**	**$150,664.50**
800051	FENCE (TYPE WM, METAL POST)	M	1	1	22.00	$140.00	$3,080.00
		M	3	2	6,360.00	$15.02	$95,535.00
		M	10	1	20.00	$213.00	$4,260.00
	Unit Sub Total	**M**		**4**	**6,402.00**	**$16.07**	**$102,875.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 800051 Total No. of Proj.			**6**		**Total Amount**	**$253,539.50**
800302	CHAIN LINK FENCE (TYPE CL-3, VINYL-CLAD)	LF	11	1	881.00	$18.00	$15,858.00
	Unit Sub Total	**LF**		**1**	**881.00**	**$18.00**	**$15,858.00**
	Item Code 800302 Total No. of Proj.			**1**		**Total Amount**	**$15,858.00**
800360	CHAIN LINK FENCE (TYPE CL-6)	LF	2	1	1,390.00	$11.75	$16,332.50
		LF	3	1	740.00	$15.00	$11,100.00
		LF	4	3	1,834.00	$14.22	$26,075.12
		LF	5	1	330.00	$18.04	$5,953.20
		LF	6	2	890.00	$14.97	$13,320.00
		LF	7	5	2,850.00	$26.16	$74,570.00
		LF	8	2	4,880.00	$12.21	$59,584.00
		LF	10	2	2,900.00	$11.79	$34,180.00
		LF	11	3	990.00	$17.75	$17,570.00
		LF	12	2	2,880.00	$12.12	$34,910.00
	Unit Sub Total	**LF**		**22**	**19,684.00**	**$14.92**	**$293,594.82**
	Item Code 800360 Total No. of Proj.			**22**		**Total Amount**	**$293,594.82**
800361	CHAIN LINK FENCE (TYPE CL-6, VINYL-CLAD)	LF	4	2	372.00	$30.00	$11,160.00
	Unit Sub Total	**LF**		**2**	**372.00**	**$30.00**	**$11,160.00**
	Item Code 800361 Total No. of Proj.			**2**		**Total Amount**	**$11,160.00**
800363	CHAIN LINK FENCE (TYPE CL-6, EXTENSION ARM)	LF	8	1	40.00	$49.05	$1,962.00
	Unit Sub Total	**LF**		**1**	**40.00**	**$49.05**	**$1,962.00**
	Item Code 800363 Total No. of Proj.			**1**		**Total Amount**	**$1,962.00**
800365	CHAIN LINK FENCE (TYPE CL-6, SLATTED)	LF	5	1	80.00	$39.00	$3,120.00
	Unit Sub Total	**LF**		**1**	**80.00**	**$39.00**	**$3,120.00**
	Item Code 800365 Total No. of Proj.			**1**		**Total Amount**	**$3,120.00**
800381	CHAIN LINK FENCE (TYPE CL-0.9)	M	4	2	1,330.00	$33.25	$44,219.00
	Unit Sub Total	**M**		**2**	**1,330.00**	**$33.25**	**$44,219.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 800381 Total No. of Proj.			**2**		**Total Amount**	**$44,219.00**
800382	CHAIN LINK FENCE (TYPE CL-0.9, VINYL-CLAD)	M	4	2	1,800.00	$39.20	$70,560.00
	Unit Sub Total	**M**		**2**	**1,800.00**	**$39.20**	**$70,560.00**
	Item Code 800382 Total No. of Proj.			**2**		**Total Amount**	**$70,560.00**
800385	CHAIN LINK FENCE (TYPE CL-1.2)	M	3	1	170.00	$44.00	$7,480.00
	Unit Sub Total	**M**		**1**	**170.00**	**$44.00**	**$7,480.00**
	Item Code 800385 Total No. of Proj.			**1**		**Total Amount**	**$7,480.00**
800386	CHAIN LINK FENCE (TYPE CL-1.2, VINYL-CLAD)	M	4	4	2,262.00	$52.00	$117,620.00
	Unit Sub Total	**M**		**4**	**2,262.00**	**$52.00**	**$117,620.00**
	Item Code 800386 Total No. of Proj.			**4**		**Total Amount**	**$117,620.00**
800391	CHAIN LINK FENCE (TYPE CL-1.8)	M	2	2	12.00	$169.92	$2,038.98
		M	3	2	2,060.00	$47.87	$98,620.00
		M	4	7	6,840.00	$52.77	$360,971.50
		M	5	2	740.00	$56.24	$41,620.00
		M	6	2	19,310.00	$20.20	$389,980.00
		M	7	3	680.00	$61.60	$41,890.00
		M	8	2	3,640.00	$44.45	$161,800.00
		M	10	1	550.00	$36.00	$19,800.00
		M	11	2	7,920.00	$64.32	$509,410.00
	Unit Sub Total	**M**		**23**	**41,752.00**	**$38.95**	**$1,626,130.48**
	Item Code 800391 Total No. of Proj.			**23**		**Total Amount**	**$1,626,130.48**
800392	CHAIN LINK FENCE (TYPE CL-1.8, VINYL-CLAD)	M	4	2	2,434.00	$59.70	$145,316.00
	Unit Sub Total	**M**		**2**	**2,434.00**	**$59.70**	**$145,316.00**
	Item Code 800392 Total No. of Proj.			**2**		**Total Amount**	**$145,316.00**
800395	CHAIN LINK FENCE (TYPE CL-1.8, SLATTED)	M	2	1	40.00	$64.75	$2,590.00
	Unit Sub Total	**M**		**1**	**40.00**	**$64.75**	**$2,590.00**
	Item Code 800395 Total No. of Proj.			**1**		**Total Amount**	**$2,590.00**
800423	CHAIN LINK FENCE (TYPE CL-2.4)	M	2	1	2,450.00	$60.00	$147,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**1**	**2,450.00**	**$60.00**	**$147,000.00**
	Item Code 800423 Total No. of Proj.			**1**		**Total Amount**	**$147,000.00**
800428	CHAIN LINK FENCE (TYPE CL-3.0, VINYL-CLAD)	M	7	1	151.00	$445.00	$67,195.00
	Unit Sub Total	**M**		**1**	**151.00**	**$445.00**	**$67,195.00**
	Item Code 800428 Total No. of Proj.			**1**		**Total Amount**	**$67,195.00**
800701	WOOD FENCE	LF	3	1	730.00	$50.00	$36,500.00
	Unit Sub Total	**LF**		**1**	**730.00**	**$50.00**	**$36,500.00**
800701	WOOD FENCE	M	9	1	11.00	$200.00	$2,200.00
	Unit Sub Total	**M**		**1**	**11.00**	**$200.00**	**$2,200.00**
	Item Code 800701 Total No. of Proj.			**2**		**Total Amount**	**$38,700.00**
800705	WIRE MESH AND WOOD FENCE	LF	4	1	1,700.00	$40.00	$68,000.00
	Unit Sub Total	**LF**		**1**	**1,700.00**	**$40.00**	**$68,000.00**
	Item Code 800705 Total No. of Proj.			**1**		**Total Amount**	**$68,000.00**
801194	2.4 M WIRE MESH GATE	EA	5	1	5.00	$1,000.00	$5,000.00
	Unit Sub Total	**EA**		**1**	**5.00**	**$1,000.00**	**$5,000.00**
	Item Code 801194 Total No. of Proj.			**1**		**Total Amount**	**$5,000.00**
801230	16' WIRE MESH GATE	EA	6	1	3.00	$2,913.00	$8,739.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$2,913.00**	**$8,739.00**
	Item Code 801230 Total No. of Proj.			**1**		**Total Amount**	**$8,739.00**
801340	METAL GATE	EA	9	1	1.00	$7,861.00	$7,861.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$7,861.00**	**$7,861.00**
	Item Code 801340 Total No. of Proj.			**1**		**Total Amount**	**$7,861.00**
801365	1.8 M METAL GATE	EA	9	1	1.00	$500.00	$500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$500.00**	**$500.00**
	Item Code 801365 Total No. of Proj.			**1**		**Total Amount**	**$500.00**
801901	4' CHAIN LINK GATE (TYPE CL-3)	EA	3	1	2.00	$700.00	$1,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**2.00**	**$700.00**	**$1,400.00**
	Item Code 801901	**Total No. of Proj.**			**1**		**Total Amount**	**$1,400.00**
802180	12' CHAIN LINK GATE (TYPE CL-4)		EA	2	1	2.00	$1,247.50	$2,495.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$1,247.50**	**$2,495.00**
	Item Code 802180	**Total No. of Proj.**			**1**		**Total Amount**	**$2,495.00**
802501	4' CHAIN LINK GATE (TYPE CL-6)		EA	4	2	2.00	$992.00	$1,984.00
			EA	5	2	4.00	$1,026.20	$4,104.80
			EA	7	3	9.00	$958.89	$8,630.00
			EA	11	2	10.00	$976.94	$9,769.43
		Unit Sub Total	**EA**		**9**	**25.00**	**$979.53**	**$24,488.23**
	Item Code 802501	**Total No. of Proj.**			**9**		**Total Amount**	**$24,488.23**
802510	5' CHAIN LINK GATE (TYPE CL-6)		EA	4	1	2.00	$2,000.00	$4,000.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$2,000.00**	**$4,000.00**
	Item Code 802510	**Total No. of Proj.**			**1**		**Total Amount**	**$4,000.00**
802520	6' CHAIN LINK GATE (TYPE CL-6)		EA	4	1	3.00	$650.00	$1,950.00
			EA	10	1	1.00	$1,000.00	$1,000.00
			EA	11	1	2.00	$666.00	$1,332.00
		Unit Sub Total	**EA**		**3**	**6.00**	**$713.67**	**$4,282.00**
	Item Code 802520	**Total No. of Proj.**			**3**		**Total Amount**	**$4,282.00**
802540	8' CHAIN LINK GATE (TYPE CL-6)		EA	4	2	4.00	$1,410.00	$5,640.00
		Unit Sub Total	**EA**		**2**	**4.00**	**$1,410.00**	**$5,640.00**
	Item Code 802540	**Total No. of Proj.**			**2**		**Total Amount**	**$5,640.00**
802560	10' CHAIN LINK GATE (TYPE CL-6)		EA	3	1	2.00	$1,500.00	$3,000.00
			EA	7	1	1.00	$1,640.00	$1,640.00
			EA	11	1	1.00	$1,625.00	$1,625.00
		Unit Sub Total	**EA**		**3**	**4.00**	**$1,566.25**	**$6,265.00**
	Item Code 802560	**Total No. of Proj.**			**3**		**Total Amount**	**$6,265.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
802580	12' CHAIN LINK GATE (TYPE CL-6)	EA	10	1	1.00	$1,000.00	$1,000.00
		EA	11	2	3.00	$925.63	$2,776.90
		EA	12	1	1.00	$1,600.00	$1,600.00
	Unit Sub Total	**EA**		**4**	**5.00**	**$1,075.38**	**$5,376.90**
	Item Code 802580 Total No. of Proj.			**4**		**Total Amount**	**$5,376.90**
802584	0.9 M CHAIN LINK GATE (TYPE CL-1.8)	EA	3	1	2.00	$800.00	$1,600.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$800.00**	**$1,600.00**
	Item Code 802584 Total No. of Proj.			**1**		**Total Amount**	**$1,600.00**
802585	1.2 M CHAIN LINK GATE (TYPE CL-1.8)	EA	4	2	5.00	$1,000.00	$5,000.00
		EA	5	1	2.00	$725.00	$1,450.00
		EA	7	1	1.00	$1,500.00	$1,500.00
		EA	8	1	2.00	$700.00	$1,400.00
		EA	11	2	18.00	$1,006.11	$18,110.00
	Unit Sub Total	**EA**		**7**	**28.00**	**$980.71**	**$27,460.00**
	Item Code 802585 Total No. of Proj.			**7**		**Total Amount**	**$27,460.00**
802586	1.2 M CHAIN LINK GATE (TYPE CL-1.8, VINYL-CLAD)	EA	4	1	2.00	$1,500.00	$3,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,500.00**	**$3,000.00**
	Item Code 802586 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
802589	1.5 M CHAIN LINK GATE (TYPE CL-1.8)	EA	7	1	10.00	$900.00	$9,000.00
	Unit Sub Total	**EA**		**1**	**10.00**	**$900.00**	**$9,000.00**
	Item Code 802589 Total No. of Proj.			**1**		**Total Amount**	**$9,000.00**
802590	1.8 M CHAIN LINK GATE (TYPE CL-1.8)	EA	11	1	6.00	$745.00	$4,470.00
	Unit Sub Total	**EA**		**1**	**6.00**	**$745.00**	**$4,470.00**
	Item Code 802590 Total No. of Proj.			**1**		**Total Amount**	**$4,470.00**
802592	2.4 M CHAIN LINK GATE (TYPE CL-1.8)	EA	3	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,000.00**	**$1,000.00**
	Item Code 802592 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
802595	3.0 M CHAIN LINK GATE (TYPE CL-1.8)	EA	4	1	4.00	$1,350.00	$5,400.00
		EA	11	1	1.00	$3,000.00	$3,000.00
	Unit Sub Total	**EA**		**2**	**5.00**	**$1,680.00**	**$8,400.00**
	Item Code 802595 Total No. of Proj.			**2**		**Total Amount**	**$8,400.00**
802596	3.7 M CHAIN LINK GATE (TYPE CL-1.8)	EA	4	2	10.00	$1,500.00	$15,000.00
		EA	11	1	2.00	$5,000.00	$10,000.00
	Unit Sub Total	**EA**		**3**	**12.00**	**$2,083.33**	**$25,000.00**
	Item Code 802596 Total No. of Proj.			**3**		**Total Amount**	**$25,000.00**
802601	14' CHAIN LINK GATE (TYPE CL-6)	EA	7	2	6.00	$1,333.33	$8,000.00
	Unit Sub Total	**EA**		**2**	**6.00**	**$1,333.33**	**$8,000.00**
	Item Code 802601 Total No. of Proj.			**2**		**Total Amount**	**$8,000.00**
802620	16' CHAIN LINK GATE (TYPE CL-6)	EA	6	1	1.00	$3,200.00	$3,200.00
		EA	7	1	1.00	$1,500.00	$1,500.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$2,350.00**	**$4,700.00**
	Item Code 802620 Total No. of Proj.			**2**		**Total Amount**	**$4,700.00**
802671	4.3 M CHAIN LINK GATE (TYPE CL-1.8)	EA	7	1	2.00	$1,800.00	$3,600.00
		EA	8	1	4.00	$1,000.00	$4,000.00
	Unit Sub Total	**EA**		**2**	**6.00**	**$1,266.67**	**$7,600.00**
	Item Code 802671 Total No. of Proj.			**2**		**Total Amount**	**$7,600.00**
802672	4.9 M CHAIN LINK GATE (TYPE CL-1.8)	EA	3	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,000.00**	**$1,000.00**
	Item Code 802672 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
802675	6.1 M CHAIN LINK GATE (TYPE CL-1.8)	EA	5	1	1.00	$2,000.00	$2,000.00
		EA	8	1	1.00	$1,400.00	$1,400.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$1,700.00**	**$3,400.00**
	Item Code 802675 Total No. of Proj.			**2**		**Total Amount**	**$3,400.00**
802676	7.3 M CHAIN LINK GATE (TYPE CL-1.8)	EA	6	1	1.00	$1,620.00	$1,620.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
802676	7.3 M CHAIN LINK GATE (TYPE CL-1.8)	EA	8	1	1.00	$2,800.00	$2,800.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$2,210.00**	**$4,420.00**
	Item Code 802676 Total No. of Proj.			**2**		**Total Amount**	**$4,420.00**
802841	5.5 M CHAIN LINK GATE (TYPE CL-2.1)	EA	2	1	2.00	$1,100.00	$2,200.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,100.00**	**$2,200.00**
	Item Code 802841 Total No. of Proj.			**1**		**Total Amount**	**$2,200.00**
802943	1.2 M CHAIN LINK GATE (TYPE CL-2.4)	EA	11	1	41.00	$1,000.00	$41,000.00
	Unit Sub Total	**EA**		**1**	**41.00**	**$1,000.00**	**$41,000.00**
	Item Code 802943 Total No. of Proj.			**1**		**Total Amount**	**$41,000.00**
810110	SURVEY MONUMENT	EA	5	1	9.00	$541.00	$4,869.00
		EA	6	1	56.00	$400.00	$22,400.00
		EA	8	5	142.00	$725.28	$102,990.00
	Unit Sub Total	**EA**		**7**	**207.00**	**$629.27**	**$130,259.00**
	Item Code 810110 Total No. of Proj.			**7**		**Total Amount**	**$130,259.00**
810111	SURVEY MONUMENT (TYPE A)	EA	2	1	4.00	$500.00	$2,000.00
		EA	6	1	3.00	$220.00	$660.00
		EA	7	1	8.00	$330.00	$2,640.00
	Unit Sub Total	**EA**		**3**	**15.00**	**$353.33**	**$5,300.00**
	Item Code 810111 Total No. of Proj.			**3**		**Total Amount**	**$5,300.00**
810112	SURVEY MONUMENT (TYPE B)	EA	6	2	93.00	$261.83	$24,350.00
	Unit Sub Total	**EA**		**2**	**93.00**	**$261.83**	**$24,350.00**
	Item Code 810112 Total No. of Proj.			**2**		**Total Amount**	**$24,350.00**
810116	SURVEY MONUMENT (TYPE D)	EA	4	1	4.00	$650.00	$2,600.00
		EA	6	2	12.00	$758.33	$9,100.00
		EA	8	2	27.00	$2,094.44	$56,550.00
		EA	9	1	8.00	$900.00	$7,200.00
	Unit Sub Total	**EA**		**6**	**51.00**	**$1,479.41**	**$75,450.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 810116	**Total No. of Proj.**			**6**		**Total Amount**	**$75,450.00**
820101	MARKER		EA	2	1	9.00	$55.00	$495.00
			EA	9	1	2.00	$35.00	$70.00
		Unit Sub Total	**EA**		**2**	**11.00**	**$51.36**	**$565.00**
	Item Code 820101	**Total No. of Proj.**			**2**		**Total Amount**	**$565.00**
820105	DELINEATOR (SPECIAL)		EA	4	1	140.00	$30.00	$4,200.00
		Unit Sub Total	**EA**		**1**	**140.00**	**$30.00**	**$4,200.00**
	Item Code 820105	**Total No. of Proj.**			**1**		**Total Amount**	**$4,200.00**
820107	DELINEATOR (CLASS 1)		EA	1	4	140.00	$34.24	$4,793.00
			EA	2	4	161.00	$42.07	$6,774.00
			EA	3	14	1,395.00	$31.88	$44,476.20
			EA	4	10	1,556.00	$33.06	$51,434.00
			EA	5	8	795.00	$30.17	$23,987.25
			EA	6	9	985.00	$30.88	$30,412.00
			EA	7	3	85.00	$35.88	$3,050.00
			EA	8	3	339.00	$42.08	$14,265.00
			EA	10	10	500.00	$31.53	$15,764.00
			EA	11	10	1,301.00	$39.75	$51,713.32
			EA	12	3	85.00	$37.41	$3,180.00
		Unit Sub Total	**EA**		**78**	**7,342.00**	**$34.03**	**$249,848.77**
	Item Code 820107	**Total No. of Proj.**			**78**		**Total Amount**	**$249,848.77**
820108	DELINEATOR (CLASS 2)		EA	2	13	2,675.00	$45.08	$120,591.45
			EA	3	1	390.00	$50.00	$19,500.00
			EA	8	2	406.00	$29.80	$12,100.00
			EA	9	3	383.00	$31.02	$11,880.00
			EA	10	2	9.00	$53.11	$478.00
		Unit Sub Total	**EA**		**21**	**3,863.00**	**$42.60**	**$164,549.45**
	Item Code 820108	**Total No. of Proj.**			**21**		**Total Amount**	**$164,549.45**
820110	MILEPOST MARKER		EA	1	2	3.00	$85.00	$255.00
			EA	2	10	54.00	$57.19	$3,088.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
820110	MILEPOST MARKER	EA	3	1	18.00	$50.00	$900.00
		EA	6	1	20.00	$48.00	$960.00
		EA	9	2	17.00	$31.18	$530.00
		EA	10	2	30.00	$43.93	$1,318.00
		EA	11	8	119.00	$56.91	$6,772.78
	Unit Sub Total	**EA**		**26**	**261.00**	**$52.96**	**$13,823.78**
	Item Code 820110 Total No. of Proj.			**26**		**Total Amount**	**$13,823.78**
820111	UNDERDRAIN MARKER	EA	1	1	6.00	$100.00	$600.00
		EA	2	1	24.00	$25.00	$600.00
	Unit Sub Total	**EA**		**2**	**30.00**	**$40.00**	**$1,200.00**
	Item Code 820111 Total No. of Proj.			**2**		**Total Amount**	**$1,200.00**
820112	MARKER (CULVERT)	EA	1	14	142.00	$51.37	$7,295.00
		EA	2	18	187.00	$69.87	$13,066.00
		EA	3	10	640.00	$54.61	$34,950.75
		EA	5	1	3.00	$45.00	$135.00
		EA	9	1	58.00	$30.00	$1,740.00
		EA	10	1	9.00	$52.00	$468.00
	Unit Sub Total	**EA**		**45**	**1,039.00**	**$55.49**	**$57,654.75**
	Item Code 820112 Total No. of Proj.			**45**		**Total Amount**	**$57,654.75**
820118	GUARD RAILING DELINEATOR	EA	1	5	190.00	$21.47	$4,080.00
		EA	2	2	20.00	$21.40	$428.00
		EA	3	1	16.00	$10.90	$174.40
		EA	4	14	2,441.00	$14.93	$36,441.00
		EA	5	6	202.00	$18.43	$3,722.00
		EA	6	1	370.00	$10.50	$3,885.00
		EA	7	2	160.00	$14.88	$2,380.00
		EA	8	2	24.00	$30.30	$727.20
		EA	10	6	135.00	$13.96	$1,885.25
		EA	11	6	412.00	$19.34	$7,969.00
		EA	12	4	343.00	$17.50	$6,004.00
	Unit Sub Total	**EA**		**49**	**4,313.00**	**$15.70**	**$67,695.85**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 820118	**Total No. of Proj.**			**49**		**Total Amount**	**$67,695.85**
820130	OBJECT MARKER		EA	4	4	20.00	$44.20	$884.00
			EA	5	3	99.00	$30.89	$3,058.00
			EA	6	2	30.00	$33.80	$1,014.00
			EA	8	3	46.00	$55.54	$2,555.00
			EA	9	1	75.00	$30.00	$2,250.00
			EA	11	1	10.00	$30.00	$300.00
			EA	12	1	3.00	$50.00	$150.00
		Unit Sub Total	**EA**		**15**	**283.00**	**$36.08**	**$10,211.00**
	Item Code 820130	**Total No. of Proj.**			**15**		**Total Amount**	**$10,211.00**
820131	OBJECT MARKER (TYPE K)		EA	4	1	3.00	$45.00	$135.00
			EA	5	2	13.00	$62.70	$815.12
			EA	6	1	19.00	$30.00	$570.00
			EA	10	1	1.00	$45.00	$45.00
		Unit Sub Total	**EA**		**5**	**36.00**	**$43.48**	**$1,565.12**
	Item Code 820131	**Total No. of Proj.**			**5**		**Total Amount**	**$1,565.12**
820132	OBJECT MARKER (TYPE L)		EA	4	1	5.00	$30.00	$150.00
			EA	5	3	21.00	$50.80	$1,066.79
			EA	10	7	24.00	$76.83	$1,844.00
		Unit Sub Total	**EA**		**11**	**50.00**	**$61.22**	**$3,060.79**
	Item Code 820132	**Total No. of Proj.**			**11**		**Total Amount**	**$3,060.79**
820133	OBJECT MARKER (TYPE N)		EA	5	1	2.00	$41.20	$82.40
			EA	10	1	1.00	$175.00	$175.00
			EA	11	1	4.00	$50.00	$200.00
			EA	12	1	34.00	$200.00	$6,800.00
		Unit Sub Total	**EA**		**4**	**41.00**	**$177.01**	**$7,257.40**
	Item Code 820133	**Total No. of Proj.**			**4**		**Total Amount**	**$7,257.40**
820134	OBJECT MARKER (TYPE P)		EA	1	1	2.00	$35.00	$70.00
			EA	2	4	15.00	$81.87	$1,228.00
			EA	4	4	44.00	$52.73	$2,320.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
820134	OBJECT MARKER (TYPE P)		EA	5	3	33.00	$108.83	$3,591.35
			EA	6	2	9.00	$50.56	$455.00
			EA	8	1	2.00	$50.00	$100.00
			EA	10	5	35.00	$38.83	$1,359.00
			EA	12	1	1.00	$100.00	$100.00
		Unit Sub Total	**EA**		**21**	**141.00**	**$65.41**	**$9,223.35**
	Item Code 820134	**Total No. of Proj.**			**21**		**Total Amount**	**$9,223.35**
820135	OBJECT MARKER (TYPE R)		EA	12	1	17.00	$100.00	$1,700.00
		Unit Sub Total	**EA**		**1**	**17.00**	**$100.00**	**$1,700.00**
	Item Code 820135	**Total No. of Proj.**			**1**		**Total Amount**	**$1,700.00**
820141	OBJECT MARKER (TYPE K-1)		EA	3	2	7.00	$41.43	$290.00
			EA	4	3	14.00	$27.86	$390.00
			EA	5	1	24.00	$35.00	$840.00
			EA	8	1	52.00	$20.00	$1,040.00
			EA	12	2	10.00	$194.20	$1,942.00
		Unit Sub Total	**EA**		**9**	**107.00**	**$42.07**	**$4,502.00**
	Item Code 820141	**Total No. of Proj.**			**9**		**Total Amount**	**$4,502.00**
820143	OBJECT MARKER (TYPE K-2)		EA	4	1	1.00	$35.00	$35.00
			EA	10	1	2.00	$200.00	$400.00
		Unit Sub Total	**EA**		**2**	**3.00**	**$145.00**	**$435.00**
	Item Code 820143	**Total No. of Proj.**			**2**		**Total Amount**	**$435.00**
820151	OBJECT MARKER (TYPE L-1)		EA	1	1	3.00	$40.00	$120.00
			EA	2	4	31.00	$50.03	$1,551.00
			EA	3	11	288.00	$30.68	$8,836.24
			EA	4	11	697.00	$34.33	$23,928.00
			EA	6	3	31.00	$62.74	$1,945.00
			EA	9	1	3.00	$35.00	$105.00
			EA	10	2	29.00	$37.55	$1,089.00
		Unit Sub Total	**EA**		**33**	**1,082.00**	**$34.73**	**$37,574.24**
	Item Code 820151	**Total No. of Proj.**			**33**		**Total Amount**	**$37,574.24**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
820152	OBJECT MARKER (TYPE L-2)	EA	2	1	13.00	$50.00	$650.00
		EA	9	1	4.00	$35.00	$140.00
	Unit Sub Total	**EA**		**2**	**17.00**	**$46.47**	**$790.00**
	Item Code 820152 Total No. of Proj.			**2**		**Total Amount**	**$790.00**
820180	INSTALL MEDIAN MILEAGE PANEL	EA	7	3	116.00	$89.14	$10,340.00
	Unit Sub Total	**EA**		**3**	**116.00**	**$89.14**	**$10,340.00**
	Item Code 820180 Total No. of Proj.			**3**		**Total Amount**	**$10,340.00**
832001	METAL BEAM GUARD RAILING	LF	1	2	2,240.00	$21.44	$48,020.00
		LF	2	7	6,663.00	$21.11	$140,635.00
		LF	3	5	20,250.00	$17.23	$348,855.00
		LF	4	4	2,930.00	$24.09	$70,570.00
		LF	7	4	1,538.00	$26.31	$40,468.00
		LF	8	3	395.00	$33.07	$13,064.00
		LF	10	1	1,000.00	$17.00	$17,000.00
		LF	11	2	1,133.00	$20.83	$23,605.00
	Unit Sub Total	**LF**		**28**	**36,149.00**	**$19.43**	**$702,217.00**
832001	METAL BEAM GUARD RAILING	M	1	2	154.00	$80.82	$12,446.00
		M	2	1	180.00	$100.00	$18,000.00
		M	3	1	170.00	$100.00	$17,000.00
		M	4	1	86.00	$80.00	$6,880.00
		M	7	2	710.00	$63.23	$44,890.00
		M	8	1	980.00	$79.00	$77,420.00
		M	11	3	1,240.00	$72.64	$90,070.00
	Unit Sub Total	**M**		**11**	**3,520.00**	**$75.77**	**$266,706.00**
	Item Code 832001 Total No. of Proj.			**39**		**Total Amount**	**$968,923.00**
832002	METAL BEAM GUARD RAILING (STEEL POST)	LF	1	3	2,248.00	$25.38	$57,047.50
		LF	2	3	2,187.00	$23.52	$51,441.50
		LF	3	2	193.00	$40.19	$7,757.11
		LF	4	2	16,700.00	$22.68	$378,800.00
		LF	5	6	21,790.00	$20.89	$455,130.00
		LF	6	6	10,826.00	$25.89	$280,292.00
		LF	7	2	760.00	$32.37	$24,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
832002	METAL BEAM GUARD RAILING (STEEL POST)	LF	8	5	11,280.00	$21.93	$247,405.60
		LF	10	3	1,095.00	$36.01	$39,430.00
	Unit Sub Total	**LF**		**32**	**67,079.00**	**$22.99**	**$1,541,903.71**
832002	METAL BEAM GUARD RAILING (STEEL POST)	M	3	1	460.00	$38.00	$17,480.00
		M	4	3	3,053.00	$65.38	$199,616.00
		M	5	3	2,850.00	$72.33	$206,140.80
		M	6	4	103.80	$174.33	$18,095.00
		M	9	1	24.00	$86.00	$2,064.00
		M	10	1	320.00	$63.00	$20,160.00
	Unit Sub Total	**M**		**13**	**6,810.80**	**$68.06**	**$463,555.80**
	Item Code 832002 Total No. of Proj.			**45**		**Total Amount**	**$2,005,459.51**
832003	METAL BEAM GUARD RAILING (WOOD POST)	LF	2	2	1,213.00	$22.64	$27,465.00
		LF	3	2	4,270.00	$17.00	$72,590.00
		LF	4	9	19,245.00	$24.10	$463,775.00
		LF	5	3	830.00	$60.24	$50,000.00
		LF	7	3	1,313.00	$24.73	$32,464.00
		LF	8	5	2,605.00	$24.04	$62,621.20
		LF	11	1	120.00	$28.00	$3,360.00
		LF	12	8	10,168.00	$24.39	$247,988.00
	Unit Sub Total	**LF**		**33**	**39,764.00**	**$24.15**	**$960,263.20**
832003	METAL BEAM GUARD RAILING (WOOD POST)	M	3	3	1,374.00	$70.85	$97,345.00
		M	4	7	7,804.00	$64.48	$503,230.00
		M	7	3	699.00	$81.40	$56,899.00
		M	8	2	2,650.00	$65.03	$172,320.00
		M	10	2	20.00	$129.00	$2,580.00
	Unit Sub Total	**M**		**17**	**12,547.00**	**$66.34**	**$832,374.00**
	Item Code 832003 Total No. of Proj.			**50**		**Total Amount**	**$1,792,637.20**
832004	METAL BEAM GUARD RAILING (SPECIAL)	LF	1	2	1,010.00	$272.67	$275,400.00
	Unit Sub Total	**LF**		**2**	**1,010.00**	**$272.67**	**$275,400.00**
	Item Code 832004 Total No. of Proj.			**2**		**Total Amount**	**$275,400.00**
832012	METAL BEAM GUARD RAILING (7' WOOD POST)	LF	1	2	90.00	$45.33	$4,080.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
832012	METAL BEAM GUARD RAILING (7' WOOD POST)	LF	7	1	200.00	$27.00	$5,400.00
	Unit Sub Total	**LF**		**3**	**290.00**	**$32.69**	**$9,480.00**
	Item Code 832012 Total No. of Proj.			**3**		**Total Amount**	**$9,480.00**
832070	VEGETATION CONTROL (MINOR CONCRETE)	M2	1	1	2,600.00	$51.00	$132,600.00
		M2	2	1	490.00	$52.00	$25,480.00
		M2	3	2	1,480.00	$71.01	$105,100.00
		M2	4	1	1,650.00	$51.00	$84,150.00
		M2	8	1	360.00	$94.00	$33,840.00
	Unit Sub Total	**M2**		**6**	**6,580.00**	**$57.93**	**$381,170.00**
832070	VEGETATION CONTROL (MINOR CONCRETE)	SQYD	1	5	2,357.00	$66.94	$157,770.00
		SQYD	2	6	19,565.00	$29.15	$570,412.50
		SQYD	3	2	3,100.00	$39.48	$122,400.00
		SQYD	5	1	6,350.00	$42.00	$266,700.00
		SQYD	7	2	630.00	$59.21	$37,300.00
		SQYD	8	2	3,720.00	$36.50	$135,780.00
		SQYD	12	2	265.00	$39.62	$10,500.00
	Unit Sub Total	**SQYD**		**20**	**35,987.00**	**$36.15**	**$1,300,862.50**
	Item Code 832070 Total No. of Proj.			**26**		**Total Amount**	**$1,682,032.50**
833020	CHAIN LINK RAILING	LF	2	1	70.00	$73.00	$5,110.00
		LF	4	1	502.00	$50.00	$25,100.00
	Unit Sub Total	**LF**		**2**	**572.00**	**$52.81**	**$30,210.00**
	Item Code 833020 Total No. of Proj.			**2**		**Total Amount**	**$30,210.00**
833032	CHAIN LINK RAILING (TYPE 7)	LF	5	1	84.00	$82.00	$6,888.00
		LF	12	1	106.00	$76.25	$8,082.50
	Unit Sub Total	**LF**		**2**	**190.00**	**$78.79**	**$14,970.50**
833032	CHAIN LINK RAILING (TYPE 7)	M	3	1	387.00	$164.00	$63,468.00
		M	4	1	245.00	$150.00	$36,750.00
		M	6	1	167.00	$170.00	$28,390.00
		M	7	1	863.00	$260.00	$224,380.00
		M	8	1	503.00	$128.00	$64,384.00
		M	10	1	368.00	$143.00	$52,624.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
833032	CHAIN LINK RAILING (TYPE 7)	M	11	1	169.00	$225.00	$38,025.00
	Unit Sub Total	**M**		**7**	**2,702.00**	**$188.02**	**$508,021.00**
	Item Code 833032 Total No. of Proj.			**9**		**Total Amount**	**$522,991.50**
833033	CHAIN LINK RAILING (TYPE 7 MODIFIED)	LF	4	2	475.00	$72.21	$34,300.00
		LF	7	1	14,943.00	$34.00	$508,062.00
		LF	12	1	477.00	$90.00	$42,930.00
	Unit Sub Total	**LF**		**4**	**15,895.00**	**$36.82**	**$585,292.00**
833033	CHAIN LINK RAILING (TYPE 7 MODIFIED)	M	4	1	105.00	$275.00	$28,875.00
		M	5	1	202.00	$235.00	$47,470.00
		M	8	1	356.00	$245.00	$87,220.00
	Unit Sub Total	**M**		**3**	**663.00**	**$246.70**	**$163,565.00**
	Item Code 833033 Total No. of Proj.			**7**		**Total Amount**	**$748,857.00**
833034	CHAIN LINK RAILING (TYPE 7L)	M	8	1	117.00	$239.00	$27,963.00
	Unit Sub Total	**M**		**1**	**117.00**	**$239.00**	**$27,963.00**
	Item Code 833034 Total No. of Proj.			**1**		**Total Amount**	**$27,963.00**
833072	WILDLIFE PASSAGE WAY (TYPE S)	EA	5	1	91.00	$100.00	$9,100.00
	Unit Sub Total	**EA**		**1**	**91.00**	**$100.00**	**$9,100.00**
	Item Code 833072 Total No. of Proj.			**1**		**Total Amount**	**$9,100.00**
833077	PEDESTRIAN BARRICADE	EA	4	1	2.00	$600.00	$1,200.00
		EA	10	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$733.33**	**$2,200.00**
833077	PEDESTRIAN BARRICADE	LF	8	1	39.00	$330.00	$12,870.00
	Unit Sub Total	**LF**		**1**	**39.00**	**$330.00**	**$12,870.00**
	Item Code 833077 Total No. of Proj.			**3**		**Total Amount**	**$15,070.00**
833080	CONCRETE BARRIER (TYPE K)	M	4	1	310.00	$11.00	$3,410.00
		M	7	1	160.00	$66.00	$10,560.00
		M	11	1	1,350.00	$11.00	$14,850.00
	Unit Sub Total	**M**		**3**	**1,820.00**	**$15.84**	**$28,820.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 833080 Total No. of Proj.			**3**		**Total Amount**	**$28,820.00**
833085	PIPE HANDRAILING	M	7	1	369.00	$76.00	$28,044.00
		M	8	1	610.00	$55.00	$33,550.00
	Unit Sub Total	**M**		**2**	**979.00**	**$62.92**	**$61,594.00**
	Item Code 833085 Total No. of Proj.			**2**		**Total Amount**	**$61,594.00**
833088	TUBULAR HANDRAILING	LF	1	1	165.00	$79.00	$13,035.00
		LF	8	1	230.00	$180.00	$41,400.00
	Unit Sub Total	**LF**		**2**	**395.00**	**$137.81**	**$54,435.00**
833088	TUBULAR HANDRAILING	M	7	1	51.00	$285.00	$14,535.00
		M	8	1	208.00	$117.00	$24,336.00
		M	11	1	738.00	$200.00	$147,600.00
	Unit Sub Total	**M**		**3**	**997.00**	**$187.03**	**$186,471.00**
	Item Code 833088 Total No. of Proj.			**5**		**Total Amount**	**$240,906.00**
833092	METAL TUBE BRIDGE RAILING	LF	7	2	568.00	$65.00	$36,920.00
	Unit Sub Total	**LF**		**2**	**568.00**	**$65.00**	**$36,920.00**
	Item Code 833092 Total No. of Proj.			**2**		**Total Amount**	**$36,920.00**
833125	CONCRETE BARRIER (TYPE 25)	LF	6	1	1,228.00	$85.00	$104,380.00
	Unit Sub Total	**LF**		**1**	**1,228.00**	**$85.00**	**$104,380.00**
833125	CONCRETE BARRIER (TYPE 25)	M	3	1	166.00	$145.00	$24,070.00
	Unit Sub Total	**M**		**1**	**166.00**	**$145.00**	**$24,070.00**
	Item Code 833125 Total No. of Proj.			**2**		**Total Amount**	**$128,450.00**
833127	CONCRETE BARRIER (TYPE 25B)	LF	4	1	120.00	$400.00	$48,000.00
	Unit Sub Total	**LF**		**1**	**120.00**	**$400.00**	**$48,000.00**
	Item Code 833127 Total No. of Proj.			**1**		**Total Amount**	**$48,000.00**
833128	CONCRETE BARRIER (TYPE 25 MODIFIED)	LF	8	1	364.00	$210.00	$76,440.00
	Unit Sub Total	**LF**		**1**	**364.00**	**$210.00**	**$76,440.00**
	Item Code 833128 Total No. of Proj.			**1**		**Total Amount**	**$76,440.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
833129	CONCRETE BARRIER (TYPE 25A MODIFIED)	M	11	1	2.00	$290.00	$580.00
	Unit Sub Total	**M**		**1**	**2.00**	**$290.00**	**$580.00**
	Item Code 833129 Total No. of Proj.			**1**		**Total Amount**	**$580.00**
833138	CONCRETE BARRIER (TYPE 25R)	LF	2	1	14.00	$110.00	$1,540.00
	Unit Sub Total	**LF**		**1**	**14.00**	**$110.00**	**$1,540.00**
	Item Code 833138 Total No. of Proj.			**1**		**Total Amount**	**$1,540.00**
833140	CONCRETE BARRIER (TYPE 26)	M	7	1	423.00	$535.00	$226,305.00
		M	8	2	428.00	$184.07	$78,780.00
	Unit Sub Total	**M**		**3**	**851.00**	**$358.50**	**$305,085.00**
	Item Code 833140 Total No. of Proj.			**3**		**Total Amount**	**$305,085.00**
833141	CONCRETE BARRIER (TYPE 26A)	LF	5	1	44.00	$300.00	$13,200.00
	Unit Sub Total	**LF**		**1**	**44.00**	**$300.00**	**$13,200.00**
833141	CONCRETE BARRIER (TYPE 26A)	M	7	1	67.00	$470.00	$31,490.00
		M	8	1	28.00	$150.00	$4,200.00
	Unit Sub Total	**M**		**2**	**95.00**	**$375.68**	**$35,690.00**
	Item Code 833141 Total No. of Proj.			**3**		**Total Amount**	**$48,890.00**
833142	CONCRETE BARRIER (TYPE 26 MODIFIED)	LF	5	1	66.00	$265.00	$17,490.00
		LF	12	1	86.00	$140.00	$12,040.00
	Unit Sub Total	**LF**		**2**	**152.00**	**$194.28**	**$29,530.00**
833142	CONCRETE BARRIER (TYPE 26 MODIFIED)	M	3	1	197.00	$400.00	$78,800.00
		M	4	1	393.00	$500.00	$196,500.00
		M	6	1	167.00	$300.00	$50,100.00
		M	8	1	937.00	$155.00	$145,235.00
		M	11	1	169.00	$715.00	$120,835.00
	Unit Sub Total	**M**		**5**	**1,863.00**	**$317.48**	**$591,470.00**
	Item Code 833142 Total No. of Proj.			**7**		**Total Amount**	**$621,000.00**
833143	CONCRETE BARRIER (TYPE 26A MODIFIED)	M	4	1	210.00	$450.00	$94,500.00
		M	8	1	136.00	$160.00	$21,760.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**2**	**346.00**	**$336.01**	**$116,260.00**
	Item Code 833143	**Total No. of Proj.**			**2**		**Total Amount**	**$116,260.00**
833165	CONCRETE BARRIER (TYPE 27B MODIFIED)		LF	7	1	5,170.00	$63.00	$325,710.00
		Unit Sub Total	**LF**		**1**	**5,170.00**	**$63.00**	**$325,710.00**
	Item Code 833165	**Total No. of Proj.**			**1**		**Total Amount**	**$325,710.00**
839220	DOUBLE METAL BEAM GUARD RAILING (WOOD POST)		LF	2	2	1,900.00	$28.64	$54,410.00
			LF	3	1	13,900.00	$21.00	$291,900.00
			LF	4	1	1,000.00	$41.00	$41,000.00
			LF	11	1	250.00	$33.00	$8,250.00
		Unit Sub Total	**LF**		**5**	**17,050.00**	**$23.20**	**$395,560.00**
	Item Code 839220	**Total No. of Proj.**			**5**		**Total Amount**	**$395,560.00**
839301	SINGLE THRIE BEAM BARRIER		M	3	1	680.00	$60.00	$40,800.00
			M	11	1	1,350.00	$75.00	$101,250.00
		Unit Sub Total	**M**		**2**	**2,030.00**	**$69.98**	**$142,050.00**
	Item Code 839301	**Total No. of Proj.**			**2**		**Total Amount**	**$142,050.00**
839303	SINGLE THRIE BEAM BARRIER (STEEL POST)		LF	4	1	240.00	$27.00	$6,480.00
			LF	6	1	10,400.00	$20.00	$208,000.00
		Unit Sub Total	**LF**		**2**	**10,640.00**	**$20.16**	**$214,480.00**
839303	SINGLE THRIE BEAM BARRIER (STEEL POST)		M	5	2	239.00	$116.58	$27,863.36
			M	10	1	45.00	$115.00	$5,175.00
		Unit Sub Total	**M**		**3**	**284.00**	**$116.33**	**$33,038.36**
	Item Code 839303	**Total No. of Proj.**			**5**		**Total Amount**	**$247,518.36**
839310	DOUBLE THRIE BEAM BARRIER		M	4	1	8.00	$175.00	$1,400.00
			M	11	1	3,780.00	$123.00	$464,940.00
		Unit Sub Total	**M**		**2**	**3,788.00**	**$123.11**	**$466,340.00**
	Item Code 839310	**Total No. of Proj.**			**2**		**Total Amount**	**$466,340.00**
839311	DOUBLE THRIE BEAM BARRIER (WOOD POST)		LF	2	1	50.00	$50.00	$2,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**1**	**50.00**	**$50.00**	**$2,500.00**
839311	DOUBLE THRIE BEAM BARRIER (WOOD POST)	M	8	2	372.00	$98.39	$36,600.00
	Unit Sub Total	**M**		**2**	**372.00**	**$98.39**	**$36,600.00**
	Item Code 839311 Total No. of Proj.			**3**		**Total Amount**	**$39,100.00**
839312	DOUBLE THRIE BEAM BARRIER (STEEL POST)	LF	6	1	7,130.00	$33.60	$239,568.00
	Unit Sub Total	**LF**		**1**	**7,130.00**	**$33.60**	**$239,568.00**
839312	DOUBLE THRIE BEAM BARRIER (STEEL POST)	M	5	1	990.00	$100.00	$99,000.00
		M	10	1	98.00	$190.00	$18,620.00
	Unit Sub Total	**M**		**2**	**1,088.00**	**$108.11**	**$117,620.00**
	Item Code 839312 Total No. of Proj.			**3**		**Total Amount**	**$357,188.00**
839402	CONCRETE BARRIER (SPECIAL)	LS	3	1	1.00	$35,600.00	$35,600.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$35,600.00**	**$35,600.00**
	Item Code 839402 Total No. of Proj.			**1**		**Total Amount**	**$35,600.00**
839481	CONCRETE BARRIER (TYPE 50)	LF	3	1	1,410.00	$80.00	$112,800.00
		LF	4	1	472.00	$55.00	$25,960.00
	Unit Sub Total	**LF**		**2**	**1,882.00**	**$73.73**	**$138,760.00**
	Item Code 839481 Total No. of Proj.			**2**		**Total Amount**	**$138,760.00**
839514	HANDRAILING	LF	1	1	40.00	$165.00	$6,600.00
		LF	4	1	42.00	$85.00	$3,570.00
		LF	7	1	160.00	$60.50	$9,680.00
	Unit Sub Total	**LF**		**3**	**242.00**	**$82.02**	**$19,850.00**
	Item Code 839514 Total No. of Proj.			**3**		**Total Amount**	**$19,850.00**
839521	CABLE RAILING	LF	1	4	1,434.00	$23.54	$33,763.00
		LF	2	6	759.00	$45.47	$34,515.00
		LF	3	1	2,490.00	$15.00	$37,350.00
		LF	4	2	113.00	$49.78	$5,625.00
		LF	5	1	318.00	$25.00	$7,950.00
		LF	7	11	5,931.00	$22.65	$134,323.00
		LF	8	3	250.00	$28.96	$7,240.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839521	CABLE RAILING		LF	9	1	20.00	$100.00	$2,000.00
			LF	10	1	151.00	$25.00	$3,775.00
			LF	11	1	20.00	$140.00	$2,800.00
			LF	12	2	7,550.00	$10.46	$79,000.00
		Unit Sub Total	**LF**		**33**	**19,036.00**	**$18.30**	**$348,341.00**
839521	CABLE RAILING		M	1	1	23.20	$270.00	$6,264.00
			M	2	3	65.00	$262.05	$17,033.52
			M	3	4	824.00	$64.26	$52,952.00
			M	4	2	1,271.00	$56.18	$71,401.00
			M	7	3	1,017.00	$70.54	$71,740.00
			M	8	2	219.00	$72.72	$15,925.00
			M	9	1	8.00	$200.00	$1,600.00
			M	11	3	1,055.70	$64.99	$68,608.60
		Unit Sub Total	**M**		**19**	**4,482.90**	**$68.15**	**$305,524.12**
	Item Code 839521	**Total No. of Proj.**			**52**		**Total Amount**	**$653,865.12**
839522	REMOVABLE BARRIER POST		EA	3	1	6.00	$300.00	$1,800.00
		Unit Sub Total	**EA**		**1**	**6.00**	**$300.00**	**$1,800.00**
	Item Code 839522	**Total No. of Proj.**			**1**		**Total Amount**	**$1,800.00**
839527	CABLE RAILING (MODIFIED)		M	7	1	7.00	$75.00	$525.00
		Unit Sub Total	**M**		**1**	**7.00**	**$75.00**	**$525.00**
	Item Code 839527	**Total No. of Proj.**			**1**		**Total Amount**	**$525.00**
839528	BURIED POST ANCHOR		EA	4	1	2.00	$714.00	$1,428.00
			EA	6	1	1.00	$600.00	$600.00
			EA	8	1	2.00	$600.00	$1,200.00
		Unit Sub Total	**EA**		**3**	**5.00**	**$645.60**	**$3,228.00**
	Item Code 839528	**Total No. of Proj.**			**3**		**Total Amount**	**$3,228.00**
839539	TERMINAL SYSTEM (TYPE SKT)		EA	4	1	1.00	$3,000.00	$3,000.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$3,000.00**	**$3,000.00**
	Item Code 839539	**Total No. of Proj.**			**1**		**Total Amount**	**$3,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839540	TRANSITION RAILING (TYPE STB)	EA	4	1	4.00	$3,000.00	$12,000.00
		EA	5	1	2.00	$2,900.00	$5,800.00
		EA	6	1	3.00	$2,000.00	$6,000.00
		EA	8	1	6.00	$3,400.00	$20,400.00
		EA	11	1	2.00	$3,300.00	$6,600.00
	Unit Sub Total	**EA**		**5**	**17.00**	**$2,988.24**	**$50,800.00**
	Item Code 839540 Total No. of Proj.			**5**		**Total Amount**	**$50,800.00**
839541	TRANSITION RAILING (TYPE WB)	EA	1	9	37.00	$3,982.97	$147,370.00
		EA	2	11	134.00	$3,104.85	$416,050.00
		EA	3	10	251.00	$2,665.48	$669,036.09
		EA	4	15	166.00	$2,746.39	$455,900.00
		EA	5	8	94.00	$2,819.32	$265,016.00
		EA	6	6	17.00	$3,829.41	$65,100.00
		EA	7	8	42.00	$4,098.81	$172,150.00
		EA	8	8	114.00	$3,273.54	$373,184.00
		EA	10	4	17.00	$3,200.00	$54,400.00
		EA	11	7	38.00	$3,278.95	$124,600.00
		EA	12	4	19.00	$3,456.84	$65,680.00
	Unit Sub Total	**EA**		**90**	**929.00**	**$3,023.13**	**$2,808,486.09**
	Item Code 839541 Total No. of Proj.			**90**		**Total Amount**	**$2,808,486.09**
839542	TRANSITION RAILING (TYPE DTB)	EA	5	2	7.00	$3,171.43	$22,200.00
		EA	6	1	1.00	$3,000.00	$3,000.00
		EA	7	1	1.00	$5,300.00	$5,300.00
		EA	8	1	2.00	$3,200.00	$6,400.00
		EA	10	1	1.00	$5,600.00	$5,600.00
		EA	11	1	4.00	$3,600.00	$14,400.00
	Unit Sub Total	**EA**		**7**	**16.00**	**$3,556.25**	**$56,900.00**
	Item Code 839542 Total No. of Proj.			**7**		**Total Amount**	**$56,900.00**
839547	TERMINAL CONNECTOR (THRIE BEAM BARRIER)	EA	10	1	1.00	$150.00	$150.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$150.00**	**$150.00**
	Item Code 839547 Total No. of Proj.			**1**		**Total Amount**	**$150.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839553	END SECTION		EA	3	1	7.00	$30.33	$212.31
			EA	4	2	20.00	$100.00	$2,000.00
		Unit Sub Total	**EA**		**3**	**27.00**	**$81.94**	**$2,212.31**
	Item Code 839553	**Total No. of Proj.**			**3**		**Total Amount**	**$2,212.31**
839555	END CAP		EA	3	1	6.00	$65.00	$390.00
			EA	4	1	2.00	$1,000.00	$2,000.00
			EA	8	1	1.00	$385.00	$385.00
			EA	12	1	3.00	$400.00	$1,200.00
		Unit Sub Total	**EA**		**4**	**12.00**	**$331.25**	**$3,975.00**
	Item Code 839555	**Total No. of Proj.**			**4**		**Total Amount**	**$3,975.00**
839559	TERMINAL SYSTEM (TYPE ET)		EA	4	1	1.00	$3,000.00	$3,000.00
			EA	8	1	1.00	$3,300.00	$3,300.00
		Unit Sub Total	**EA**		**2**	**2.00**	**$3,150.00**	**$6,300.00**
	Item Code 839559	**Total No. of Proj.**			**2**		**Total Amount**	**$6,300.00**
839561	RAIL TENSIONING ASSEMBLY		EA	3	1	6.00	$550.00	$3,300.00
			EA	4	1	16.00	$736.00	$11,776.00
			EA	5	1	7.00	$750.00	$5,250.00
		Unit Sub Total	**EA**		**3**	**29.00**	**$700.90**	**$20,326.00**
	Item Code 839561	**Total No. of Proj.**			**3**		**Total Amount**	**$20,326.00**
839565	TERMINAL SYSTEM (TYPE SRT)		EA	1	1	1.00	$2,500.00	$2,500.00
			EA	3	1	6.00	$3,000.00	$18,000.00
			EA	4	1	13.00	$2,500.00	$32,500.00
		Unit Sub Total	**EA**		**3**	**20.00**	**$2,650.00**	**$53,000.00**
	Item Code 839565	**Total No. of Proj.**			**3**		**Total Amount**	**$53,000.00**
839566	TERMINAL SYSTEM (TYPE CAT)		EA	2	1	15.00	$5,000.00	$75,000.00
			EA	3	1	80.00	$4,000.00	$320,000.00
			EA	7	2	4.00	$7,400.00	$29,600.00
			EA	8	1	1.00	$5,000.00	$5,000.00
		Unit Sub Total	**EA**		**5**	**100.00**	**$4,296.00**	**$429,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 839566 Total No. of Proj.			**5**		**Total Amount**	**$429,600.00**
839567	TERMINAL SYSTEM (TYPE CAT) BACKUP	EA	2	1	15.00	$500.00	$7,500.00
		EA	3	1	80.00	$150.00	$12,000.00
		EA	7	2	4.00	$437.50	$1,750.00
		EA	8	1	1.00	$600.00	$600.00
	Unit Sub Total	**EA**		**5**	**100.00**	**$218.50**	**$21,850.00**
	Item Code 839567 Total No. of Proj.			**5**		**Total Amount**	**$21,850.00**
839568	TERMINAL ANCHOR ASSEMBLY (TYPE SFT)	EA	1	1	5.00	$860.00	$4,300.00
		EA	2	1	5.00	$750.00	$3,750.00
		EA	3	3	28.00	$508.93	$14,250.00
		EA	4	3	22.00	$829.77	$18,255.00
		EA	5	1	5.00	$865.00	$4,325.00
		EA	7	2	3.00	$666.67	$2,000.00
		EA	8	4	7.00	$1,000.00	$7,000.00
		EA	11	1	4.00	$800.00	$3,200.00
		EA	12	2	3.00	$680.00	$2,040.00
	Unit Sub Total	**EA**		**18**	**82.00**	**$720.98**	**$59,120.00**
	Item Code 839568 Total No. of Proj.			**18**		**Total Amount**	**$59,120.00**
839571	RETURN CAP	EA	4	1	16.00	$180.00	$2,880.00
	Unit Sub Total	**EA**		**1**	**16.00**	**$180.00**	**$2,880.00**
	Item Code 839571 Total No. of Proj.			**1**		**Total Amount**	**$2,880.00**
839572	RETURN CAP (TYPE TA)	EA	11	1	2.00	$220.00	$440.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$220.00**	**$440.00**
	Item Code 839572 Total No. of Proj.			**1**		**Total Amount**	**$440.00**
839576	END CAP (TYPE A)	EA	3	4	15.00	$79.13	$1,187.00
		EA	4	4	10.00	$140.00	$1,400.00
		EA	5	1	1.00	$175.00	$175.00
		EA	7	1	2.00	$400.00	$800.00
		EA	12	1	6.00	$170.00	$1,020.00
	Unit Sub Total	**EA**		**11**	**34.00**	**$134.76**	**$4,582.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 839576 Total No. of Proj.			**11**		**Total Amount**	**$4,582.00**
839577	END CAP (TYPE TA)	EA	4	1	8.00	$150.00	$1,200.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$150.00**	**$1,200.00**
	Item Code 839577 Total No. of Proj.			**1**		**Total Amount**	**$1,200.00**
839578	END CAP (TYPE TC)	EA	1	2	7.00	$212.14	$1,485.00
		EA	3	2	8.00	$92.95	$743.61
		EA	4	2	4.00	$88.75	$355.00
		EA	7	2	5.00	$215.40	$1,077.00
	Unit Sub Total	**EA**		**8**	**24.00**	**$152.53**	**$3,660.61**
	Item Code 839578 Total No. of Proj.			**8**		**Total Amount**	**$3,660.61**
839581	END ANCHOR ASSEMBLY (TYPE SFT)	EA	1	2	5.00	$820.00	$4,100.00
		EA	2	2	14.00	$657.14	$9,200.00
		EA	3	9	73.00	$765.82	$55,904.89
		EA	4	18	220.00	$690.68	$151,949.00
		EA	5	7	45.00	$696.15	$31,326.90
		EA	6	6	22.00	$690.91	$15,200.00
		EA	7	7	16.00	$885.31	$14,165.00
		EA	8	5	38.00	$654.39	$24,867.00
		EA	9	1	23.00	$575.00	$13,225.00
		EA	10	3	23.00	$581.52	$13,375.00
		EA	11	2	11.00	$813.64	$8,950.00
		EA	12	6	18.00	$754.17	$13,575.00
	Unit Sub Total	**EA**		**68**	**508.00**	**$700.47**	**$355,837.79**
	Item Code 839581 Total No. of Proj.			**68**		**Total Amount**	**$355,837.79**
839582	END ANCHOR ASSEMBLY (TYPE CA)	EA	4	2	17.00	$1,502.94	$25,550.00
		EA	11	1	2.00	$1,500.00	$3,000.00
	Unit Sub Total	**EA**		**3**	**19.00**	**$1,502.63**	**$28,550.00**
	Item Code 839582 Total No. of Proj.			**3**		**Total Amount**	**$28,550.00**
839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	1	5	11.00	$3,401.82	$37,420.00
		EA	2	5	13.00	$3,103.08	$40,340.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	3	9	51.00	$2,586.75	$131,924.10
		EA	4	11	80.00	$2,355.50	$188,440.00
		EA	5	6	29.00	$2,678.33	$77,671.60
		EA	6	3	3.00	$2,948.33	$8,845.00
		EA	7	6	26.00	$3,180.77	$82,700.00
		EA	8	9	41.00	$2,987.80	$122,500.00
		EA	10	5	14.00	$2,778.57	$38,900.00
		EA	11	5	13.00	$3,190.77	$41,480.00
		EA	12	2	3.00	$3,233.33	$9,700.00
	Unit Sub Total	**EA**		**66**	**284.00**	**$2,746.20**	**$779,920.70**
	Item Code 839584 Total No. of Proj.			**66**		**Total Amount**	**$779,920.70**
839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	1	9	26.00	$2,892.31	$75,200.00
		EA	2	16	125.00	$2,392.48	$299,059.50
		EA	3	13	168.00	$1,677.17	$281,764.64
		EA	4	20	705.00	$1,852.73	$1,306,175.00
		EA	5	9	36.00	$2,106.56	$75,836.00
		EA	6	8	55.00	$2,199.91	$120,995.00
		EA	7	9	40.00	$2,618.50	$104,740.00
		EA	8	12	85.00	$2,389.88	$203,140.00
		EA	9	2	21.00	$2,395.24	$50,300.00
		EA	10	4	25.00	$2,187.60	$54,690.00
		EA	11	8	26.00	$2,475.00	$64,350.00
		EA	12	6	29.00	$2,315.17	$67,140.00
	Unit Sub Total	**EA**		**116**	**1,341.00**	**$2,015.95**	**$2,703,390.14**
	Item Code 839585 Total No. of Proj.			**116**		**Total Amount**	**$2,703,390.14**
839591	CRASH CUSHION, SAND FILLED	EA	4	3	29.00	$1,355.17	$39,300.00
		EA	5	1	1.00	$5,000.00	$5,000.00
		EA	6	1	2.00	$6,200.00	$12,400.00
		EA	7	2	24.00	$816.67	$19,600.00
		EA	12	2	67.00	$373.88	$25,050.00
	Unit Sub Total	**EA**		**9**	**123.00**	**$823.98**	**$101,350.00**
	Item Code 839591 Total No. of Proj.			**9**		**Total Amount**	**$101,350.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839601	CRASH CUSHION (TYPE CAT)	EA	4	4	4.00	$6,625.00	$26,500.00
		EA	5	1	1.00	$5,000.00	$5,000.00
		EA	6	1	3.00	$5,300.00	$15,900.00
		EA	7	1	1.00	$6,100.00	$6,100.00
		EA	8	1	1.00	$5,000.00	$5,000.00
		EA	11	2	3.00	$5,100.00	$15,300.00
	Unit Sub Total	**EA**		**10**	**13.00**	**$5,676.92**	**$73,800.00**
	Item Code 839601 Total No. of Proj.			**10**		**Total Amount**	**$73,800.00**
839602	CRASH CUSHION (TYPE CAT) BACKUP	EA	4	3	3.00	$831.67	$2,495.00
		EA	5	1	1.00	$500.00	$500.00
		EA	6	1	3.00	$350.00	$1,050.00
		EA	7	1	1.00	$6,500.00	$6,500.00
		EA	8	1	1.00	$600.00	$600.00
		EA	11	2	3.00	$766.67	$2,300.00
	Unit Sub Total	**EA**		**9**	**12.00**	**$1,120.42**	**$13,445.00**
	Item Code 839602 Total No. of Proj.			**9**		**Total Amount**	**$13,445.00**
839603	CRASH CUSHION (ADIEM)	EA	1	1	6.00	$3,200.00	$19,200.00
		EA	3	1	1.00	$16,000.00	$16,000.00
		EA	4	1	4.00	$15,000.00	$60,000.00
		EA	5	1	1.00	$23,000.00	$23,000.00
		EA	7	1	2.00	$22,600.00	$45,200.00
	Unit Sub Total	**EA**		**5**	**14.00**	**$11,671.43**	**$163,400.00**
	Item Code 839603 Total No. of Proj.			**5**		**Total Amount**	**$163,400.00**
839604	CRASH CUSHION (REACT 9CBB)	EA	3	1	1.00	$50,000.00	$50,000.00
		EA	4	3	11.00	$52,700.00	$579,700.00
		EA	7	4	6.00	$56,500.00	$339,000.00
		EA	11	4	40.00	$40,400.00	$1,616,000.00
		EA	12	1	17.00	$40,000.00	$680,000.00
	Unit Sub Total	**EA**		**13**	**75.00**	**$43,529.33**	**$3,264,700.00**
	Item Code 839604 Total No. of Proj.			**13**		**Total Amount**	**$3,264,700.00**
839605	CRASH CUSHION (REACT 9SCBS)	EA	2	1	1.00	$40,000.00	$40,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839605	CRASH CUSHION (REACT 9SCBS)	EA	4	2	2.00	$55,500.00	$111,000.00
		EA	7	2	7.00	$59,428.57	$416,000.00
	Unit Sub Total	**EA**		**5**	**10.00**	**$56,700.00**	**$567,000.00**
	Item Code 839605 Total No. of Proj.			**5**		**Total Amount**	**$567,000.00**
839631	CRASH CUSHION MODULE, SAND FILLED	EA	4	2	42.00	$400.00	$16,800.00
	Unit Sub Total	**EA**		**2**	**42.00**	**$400.00**	**$16,800.00**
	Item Code 839631 Total No. of Proj.			**2**		**Total Amount**	**$16,800.00**
839701	CONCRETE BARRIER (TYPE 60)	LF	2	2	260.00	$73.08	$19,000.00
		LF	4	1	260.00	$95.00	$24,700.00
		LF	5	5	17,860.00	$39.20	$700,025.00
		LF	6	3	7,450.00	$40.55	$302,130.00
		LF	7	2	11,342.00	$48.78	$553,220.00
		LF	10	2	5,840.00	$32.33	$188,820.00
		LF	11	3	11,010.00	$67.25	$740,470.00
		LF	12	4	7,285.00	$55.69	$405,700.00
	Unit Sub Total	**LF**		**22**	**61,307.00**	**$47.86**	**$2,934,065.00**
839701	CONCRETE BARRIER (TYPE 60)	M	2	1	1,120.00	$277.00	$310,240.00
		M	3	2	1,530.00	$134.31	$205,500.00
		M	4	8	6,087.00	$175.48	$1,068,154.00
		M	5	1	320.00	$80.00	$25,600.00
		M	7	4	782.00	$148.26	$115,940.00
		M	8	3	4,770.00	$121.18	$578,050.00
		M	10	1	840.00	$165.00	$138,600.00
		M	11	2	8,070.00	$143.94	$1,161,600.00
	Unit Sub Total	**M**		**22**	**23,519.00**	**$153.22**	**$3,603,684.00**
	Item Code 839701 Total No. of Proj.			**44**		**Total Amount**	**$6,537,749.00**
839702	CONCRETE BARRIER (TYPE 60A)	LF	3	1	870.00	$40.00	$34,800.00
	Unit Sub Total	**LF**		**1**	**870.00**	**$40.00**	**$34,800.00**
839702	CONCRETE BARRIER (TYPE 60A)	M	2	1	612.00	$277.00	$169,524.00
		M	4	3	501.00	$190.30	$95,340.00
		M	8	1	53.00	$181.00	$9,593.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839702	CONCRETE BARRIER (TYPE 60A)		M	10	1	189.00	$200.00	$37,800.00
			M	11	1	67.00	$167.00	$11,189.00
		Unit Sub Total	**M**		**7**	**1,422.00**	**$227.46**	**$323,446.00**
	Item Code 839702	**Total No. of Proj.**			**8**		**Total Amount**	**$358,246.00**
839703	CONCRETE BARRIER (TYPE 60C)		LF	2	2	590.00	$114.24	$67,400.00
			LF	4	2	1,270.00	$88.50	$112,400.00
			LF	5	2	3,690.00	$62.41	$230,310.00
			LF	7	2	8,130.00	$84.36	$685,860.00
			LF	10	1	8,510.00	$39.00	$331,890.00
			LF	11	1	2,220.00	$145.00	$321,900.00
			LF	12	3	14,130.00	$84.96	$1,200,450.00
		Unit Sub Total	**LF**		**13**	**38,540.00**	**$76.55**	**$2,950,210.00**
839703	CONCRETE BARRIER (TYPE 60C)		M	2	1	350.00	$305.00	$106,750.00
			M	3	2	2,140.00	$144.95	$310,200.00
			M	4	8	19,852.00	$210.61	$4,181,000.00
			M	7	2	1,020.00	$192.65	$196,500.00
			M	8	3	3,370.00	$170.00	$572,890.00
			M	11	2	1,000.00	$245.70	$245,700.00
		Unit Sub Total	**M**		**18**	**27,732.00**	**$202.40**	**$5,613,040.00**
	Item Code 839703	**Total No. of Proj.**			**31**		**Total Amount**	**$8,563,250.00**
839704	CONCRETE BARRIER (TYPE 60D)		LF	4	1	1,365.00	$50.00	$68,250.00
			LF	12	1	160.00	$75.00	$12,000.00
		Unit Sub Total	**LF**		**2**	**1,525.00**	**$52.62**	**$80,250.00**
839704	CONCRETE BARRIER (TYPE 60D)		M	2	1	27.00	$288.00	$7,776.00
			M	3	1	344.00	$180.00	$61,920.00
			M	4	6	1,715.00	$173.12	$296,896.00
			M	7	1	1,540.00	$130.00	$200,200.00
			M	8	1	200.00	$252.00	$50,400.00
			M	11	1	71.00	$250.00	$17,750.00
		Unit Sub Total	**M**		**11**	**3,897.00**	**$162.93**	**$634,942.00**
	Item Code 839704	**Total No. of Proj.**			**13**		**Total Amount**	**$715,192.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839705	CONCRETE BARRIER (TYPE 60E)	LF	7	1	1,640.00	$235.00	$385,400.00
		LF	10	1	450.00	$175.00	$78,750.00
		LF	12	2	3,390.00	$148.38	$503,000.00
	Unit Sub Total	**LF**		**4**	**5,480.00**	**$176.49**	**$967,150.00**
839705	CONCRETE BARRIER (TYPE 60E)	M	2	1	48.00	$326.00	$15,648.00
		M	3	1	450.00	$50.00	$22,500.00
		M	4	3	520.00	$668.27	$347,500.00
		M	6	1	62.00	$495.00	$30,690.00
		M	7	1	40.00	$470.00	$18,800.00
		M	8	2	156.00	$525.19	$81,930.00
	Unit Sub Total	**M**		**9**	**1,276.00**	**$405.23**	**$517,068.00**
	Item Code 839705 Total No. of Proj.			**13**		**Total Amount**	**$1,484,218.00**
839706	CONCRETE BARRIER (TYPE 60G)	LF	5	1	260.00	$125.00	$32,500.00
		LF	7	1	1,450.00	$53.00	$76,850.00
	Unit Sub Total	**LF**		**2**	**1,710.00**	**$63.95**	**$109,350.00**
839706	CONCRETE BARRIER (TYPE 60G)	M	7	1	3,140.00	$280.00	$879,200.00
		M	8	1	2,780.00	$131.00	$364,180.00
	Unit Sub Total	**M**		**2**	**5,920.00**	**$210.03**	**$1,243,380.00**
	Item Code 839706 Total No. of Proj.			**4**		**Total Amount**	**$1,352,730.00**
839708	CONCRETE BARRIER (TYPE 60GC)	M	7	1	260.00	$270.00	$70,200.00
		M	8	1	1,250.00	$170.00	$212,500.00
	Unit Sub Total	**M**		**2**	**1,510.00**	**$187.22**	**$282,700.00**
	Item Code 839708 Total No. of Proj.			**2**		**Total Amount**	**$282,700.00**
839709	CONCRETE BARRIER (TYPE 60GE)	M	8	1	130.00	$673.00	$87,490.00
	Unit Sub Total	**M**		**1**	**130.00**	**$673.00**	**$87,490.00**
	Item Code 839709 Total No. of Proj.			**1**		**Total Amount**	**$87,490.00**
839710	CONCRETE BARRIER (TYPE 60S)	LF	5	2	1,430.00	$51.89	$74,200.00
		LF	11	1	1,990.00	$47.00	$93,530.00
	Unit Sub Total	**LF**		**3**	**3,420.00**	**$49.04**	**$167,730.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 839710 Total No. of Proj.			**3**		**Total Amount**	**$167,730.00**
839712	CONCRETE BARRIER (TYPE 60SC)	LF	5	1	1,200.00	$70.00	$84,000.00
		LF	6	1	198.00	$218.00	$43,164.00
		LF	11	1	300.00	$58.00	$17,400.00
		LF	12	1	1,330.00	$70.00	$93,100.00
	Unit Sub Total	**LF**		**4**	**3,028.00**	**$78.49**	**$237,664.00**
	Item Code 839712 Total No. of Proj.			**4**		**Total Amount**	**$237,664.00**
839713	CONCRETE BARRIER (TYPE 60SE)	LF	6	1	1,562.00	$71.00	$110,902.00
	Unit Sub Total	**LF**		**1**	**1,562.00**	**$71.00**	**$110,902.00**
	Item Code 839713 Total No. of Proj.			**1**		**Total Amount**	**$110,902.00**
839714	CONCRETE BARRIER (TYPE 80)	M	1	1	346.00	$350.00	$121,100.00
		M	11	1	369.00	$540.00	$199,260.00
	Unit Sub Total	**M**		**2**	**715.00**	**$448.06**	**$320,360.00**
	Item Code 839714 Total No. of Proj.			**2**		**Total Amount**	**$320,360.00**
839717	CONCRETE BARRIER (TYPE 732 MODIFIED)	LF	1	1	165.00	$147.00	$24,255.00
		LF	4	1	2,976.00	$60.00	$178,560.00
		LF	5	1	3,780.00	$45.00	$170,100.00
		LF	6	1	2,270.00	$71.00	$161,170.00
	Unit Sub Total	**LF**		**4**	**9,191.00**	**$58.11**	**$534,085.00**
839717	CONCRETE BARRIER (TYPE 732 MODIFIED)	M	4	3	975.00	$288.55	$281,340.00
		M	5	1	135.00	$300.00	$40,500.00
		M	8	1	984.00	$100.00	$98,400.00
		M	10	1	369.00	$175.00	$64,575.00
	Unit Sub Total	**M**		**6**	**2,463.00**	**$196.84**	**$484,815.00**
	Item Code 839717 Total No. of Proj.			**10**		**Total Amount**	**$1,018,900.00**
839718	CONCRETE BARRIER (TYPE 732R)	M	8	1	542.00	$369.00	$199,998.00
	Unit Sub Total	**M**		**1**	**542.00**	**$369.00**	**$199,998.00**
	Item Code 839718 Total No. of Proj.			**1**		**Total Amount**	**$199,998.00**
839720	CONCRETE BARRIER (TYPE 732)	LF	1	1	191.00	$120.00	$22,920.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839720	CONCRETE BARRIER (TYPE 732)	LF	8	1	181.00	$182.00	$32,942.00
		LF	12	1	1,338.00	$75.00	$100,350.00
	Unit Sub Total	**LF**		**3**	**1,710.00**	**$91.35**	**$156,212.00**
839720	CONCRETE BARRIER (TYPE 732)	M	4	5	1,934.00	$205.56	$397,547.00
		M	5	1	161.00	$150.00	$24,150.00
		M	6	1	82.00	$500.00	$41,000.00
		M	7	1	113.00	$240.00	$27,120.00
		M	8	1	187.00	$136.00	$25,432.00
	Unit Sub Total	**M**		**9**	**2,477.00**	**$208.01**	**$515,249.00**
	Item Code 839720 **Total No. of Proj.**			**12**		**Total Amount**	**$671,461.00**
839721	CONCRETE BARRIER (TYPE 732A)	LF	12	1	1,492.00	$78.00	$116,376.00
	Unit Sub Total	**LF**		**1**	**1,492.00**	**$78.00**	**$116,376.00**
839721	CONCRETE BARRIER (TYPE 732A)	M	4	5	921.00	$200.37	$184,540.00
		M	8	1	6.00	$100.00	$600.00
		M	10	1	1,520.00	$182.00	$276,640.00
	Unit Sub Total	**M**		**7**	**2,447.00**	**$188.71**	**$461,780.00**
	Item Code 839721 **Total No. of Proj.**			**8**		**Total Amount**	**$578,156.00**
839723	CONCRETE BARRIER (TYPE 732B)	LF	5	1	2,440.00	$45.00	$109,800.00
		LF	7	2	380.00	$143.42	$54,500.00
	Unit Sub Total	**LF**		**3**	**2,820.00**	**$58.26**	**$164,300.00**
839723	CONCRETE BARRIER (TYPE 732B)	M	8	1	160.00	$160.00	$25,600.00
	Unit Sub Total	**M**		**1**	**160.00**	**$160.00**	**$25,600.00**
	Item Code 839723 **Total No. of Proj.**			**4**		**Total Amount**	**$189,900.00**
839725	CONCRETE BARRIER (TYPE 736)	LF	2	1	395.00	$80.00	$31,600.00
		LF	4	1	329.00	$52.00	$17,108.00
		LF	5	1	171.00	$86.00	$14,706.00
		LF	11	1	365.00	$69.00	$25,185.00
	Unit Sub Total	**LF**		**4**	**1,260.00**	**$70.32**	**$88,599.00**
839725	CONCRETE BARRIER (TYPE 736)	M	4	2	2,388.00	$166.77	$398,250.00
		M	7	1	258.00	$235.00	$60,630.00
		M	11	3	1,742.00	$179.69	$313,014.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**6**	**4,388.00**	**$175.91**	**$771,894.00**
	Item Code 839725	**Total No. of Proj.**			**10**		**Total Amount**	**$860,493.00**
839726	CONCRETE BARRIER (TYPE 736A)		LF	3	1	2,420.00	$60.00	$145,200.00
			LF	4	1	1,371.00	$55.00	$75,405.00
			LF	6	1	800.00	$54.00	$43,200.00
			LF	11	2	1,238.00	$69.15	$85,606.00
		Unit Sub Total	**LF**		**5**	**5,829.00**	**$59.94**	**$349,411.00**
839726	CONCRETE BARRIER (TYPE 736A)		M	3	1	990.00	$170.00	$168,300.00
			M	4	4	1,263.00	$276.46	$349,170.00
			M	7	2	2,379.00	$7.47	$17,770.00
			M	8	1	1,050.00	$100.00	$105,000.00
		Unit Sub Total	**M**		**8**	**5,682.00**	**$112.68**	**$640,240.00**
	Item Code 839726	**Total No. of Proj.**			**13**		**Total Amount**	**$989,651.00**
839727	CONCRETE BARRIER (TYPE 736 MODIFIED)		LF	1	1	391.00	$123.00	$48,093.00
			LF	2	3	653.00	$122.85	$80,223.00
			LF	3	1	700.00	$80.00	$56,000.00
			LF	5	1	760.00	$45.00	$34,200.00
		Unit Sub Total	**LF**		**6**	**2,504.00**	**$87.27**	**$218,516.00**
839727	CONCRETE BARRIER (TYPE 736 MODIFIED)		M	4	3	1,522.00	$356.30	$542,290.00
			M	5	1	135.00	$400.00	$54,000.00
			M	7	3	1,828.00	$171.54	$313,578.00
			M	8	1	174.00	$100.00	$17,400.00
			M	11	1	175.00	$280.00	$49,000.00
		Unit Sub Total	**M**		**9**	**3,834.00**	**$254.63**	**$976,268.00**
	Item Code 839727	**Total No. of Proj.**			**15**		**Total Amount**	**$1,194,784.00**
839728	CONCRETE BARRIER (TYPE 736R)		M	7	1	226.00	$150.00	$33,900.00
			M	11	1	79.00	$180.00	$14,220.00
		Unit Sub Total	**M**		**2**	**305.00**	**$157.77**	**$48,120.00**
	Item Code 839728	**Total No. of Proj.**			**2**		**Total Amount**	**$48,120.00**
839731	CONCRETE BARRIER (TYPE 736B)		LF	4	1	420.00	$110.00	$46,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839731	CONCRETE BARRIER (TYPE 736B)	LF	5	2	387.00	$54.28	$21,006.00
		LF	7	1	2,940.00	$103.00	$302,820.00
		LF	11	2	570.00	$153.51	$87,500.00
	Unit Sub Total	**LF**		**6**	**4,317.00**	**$105.98**	**$457,526.00**
839731	CONCRETE BARRIER (TYPE 736B)	M	4	2	44.00	$847.73	$37,300.00
		M	7	2	960.00	$362.22	$347,730.00
		M	8	1	250.00	$160.00	$40,000.00
		M	11	1	1,039.00	$250.00	$259,750.00
	Unit Sub Total	**M**		**6**	**2,293.00**	**$298.64**	**$684,780.00**
	Item Code 839731 Total No. of Proj.			**12**		**Total Amount**	**$1,142,306.00**
839734	CONCRETE BARRIER (TYPE 736SV)	LF	3	1	14,600.00	$90.00	$1,314,000.00
		LF	7	1	660.00	$170.00	$112,200.00
	Unit Sub Total	**LF**		**2**	**15,260.00**	**$93.46**	**$1,426,200.00**
839734	CONCRETE BARRIER (TYPE 736SV)	M	3	1	540.00	$420.00	$226,800.00
		M	4	2	2,029.00	$397.91	$807,360.00
		M	7	3	4,720.00	$336.63	$1,588,900.00
		M	8	2	358.00	$295.08	$105,640.00
	Unit Sub Total	**M**		**8**	**7,647.00**	**$356.83**	**$2,728,700.00**
	Item Code 839734 Total No. of Proj.			**10**		**Total Amount**	**$4,154,900.00**
839735	CONCRETE BARRIER (TYPE 742)	LF	8	1	226.00	$100.00	$22,600.00
	Unit Sub Total	**LF**		**1**	**226.00**	**$100.00**	**$22,600.00**
	Item Code 839735 Total No. of Proj.			**1**		**Total Amount**	**$22,600.00**
839736	CONCRETE BARRIER (TYPE 742A)	M	8	1	95.00	$100.00	$9,500.00
	Unit Sub Total	**M**		**1**	**95.00**	**$100.00**	**$9,500.00**
	Item Code 839736 Total No. of Proj.			**1**		**Total Amount**	**$9,500.00**
839737	CONCRETE BARRIER (TYPE 742B)	M	8	1	160.00	$160.00	$25,600.00
	Unit Sub Total	**M**		**1**	**160.00**	**$160.00**	**$25,600.00**
	Item Code 839737 Total No. of Proj.			**1**		**Total Amount**	**$25,600.00**
840501	THERMOPLASTIC TRAFFIC STRIPE	LF	1	1	130.00	$7.00	$910.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840501	THERMOPLASTIC TRAFFIC STRIPE	LF	4	1	320.00	$4.00	$1,280.00
		LF	6	1	14,500.00	$0.50	$7,250.00
		LF	8	4	14,460.00	$0.59	$8,576.60
	Unit Sub Total	**LF**		**7**	**29,410.00**	**$0.61**	**$18,016.60**
840501	THERMOPLASTIC TRAFFIC STRIPE	M	6	1	16,300.00	$0.80	$13,040.00
	Unit Sub Total	**M**		**1**	**16,300.00**	**$0.80**	**$13,040.00**
	Item Code 840501 Total No. of Proj.			**8**		**Total Amount**	**$31,056.60**
840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	1	29	1,084,270.00	$0.34	$373,961.30
		LF	2	3	176,260.00	$0.28	$49,300.00
		LF	3	20	1,156,480.00	$0.25	$291,667.40
		LF	4	52	2,105,075.00	$0.33	$692,374.25
		LF	5	12	1,005,600.00	$0.28	$280,481.00
		LF	6	28	3,622,070.00	$0.24	$870,140.70
		LF	7	55	1,755,603.00	$0.31	$549,996.85
		LF	8	1	530.00	$1.00	$530.00
		LF	10	4	36,490.00	$0.29	$10,552.00
		LF	11	8	75,270.00	$0.54	$40,274.50
		LF	12	25	1,121,050.00	$0.30	$332,745.26
	Unit Sub Total	**LF**		**237**	**12,138,698.00**	**$0.29**	**$3,492,023.26**
	Item Code 840504 Total No. of Proj.			**237**		**Total Amount**	**$3,492,023.26**
840505	6" THERMOPLASTIC TRAFFIC STRIPE	LF	4	7	51,180.00	$0.30	$15,140.00
		LF	5	1	490.00	$0.58	$284.20
		LF	12	2	17,560.00	$0.36	$6,369.60
	Unit Sub Total	**LF**		**10**	**69,230.00**	**$0.31**	**$21,793.80**
	Item Code 840505 Total No. of Proj.			**10**		**Total Amount**	**$21,793.80**
840506	8" THERMOPLASTIC TRAFFIC STRIPE	LF	1	5	4,310.00	$1.21	$5,199.00
		LF	2	3	10,550.00	$1.17	$12,310.00
		LF	3	17	78,241.00	$0.51	$39,866.30
		LF	4	33	135,935.00	$0.66	$90,207.40
		LF	5	11	63,330.00	$0.67	$42,116.20
		LF	6	20	138,720.00	$0.60	$83,212.20
		LF	7	37	136,902.00	$0.58	$79,948.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840506	8" THERMOPLASTIC TRAFFIC STRIPE	LF	8	3	203.00	$1.68	$340.60
		LF	11	18	59,220.00	$0.96	$56,834.80
		LF	12	23	137,310.00	$0.64	$87,512.80
	Unit Sub Total	**LF**		**170**	**764,721.00**	**$0.65**	**$497,547.30**
	Item Code 840506 Total No. of Proj.			**170**		**Total Amount**	**$497,547.30**
840508	8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	LF	2	2	3,190.00	$0.65	$2,070.00
		LF	3	7	33,140.00	$0.31	$10,246.90
		LF	4	13	47,050.00	$0.57	$26,663.20
		LF	6	4	12,660.00	$0.48	$6,029.50
		LF	7	14	32,430.00	$0.59	$19,029.80
		LF	11	9	17,140.00	$1.07	$18,313.50
		LF	12	11	34,075.00	$0.48	$16,433.90
	Unit Sub Total	**LF**		**60**	**179,685.00**	**$0.55**	**$98,786.80**
	Item Code 840508 Total No. of Proj.			**60**		**Total Amount**	**$98,786.80**
840511	4" THERMOPLASTIC TRAFFIC STRIPE (DASHED WHITE)	LF	1	1	530.00	$1.00	$530.00
	Unit Sub Total	**LF**		**1**	**530.00**	**$1.00**	**$530.00**
	Item Code 840511 Total No. of Proj.			**1**		**Total Amount**	**$530.00**
840515	THERMOPLASTIC PAVEMENT MARKING	M2	1	1	2.20	$170.00	$374.00
		M2	3	5	879.00	$32.60	$28,658.80
		M2	4	11	3,393.00	$36.98	$125,475.00
		M2	5	2	730.00	$29.73	$21,700.00
		M2	6	6	2,956.00	$32.52	$96,137.00
		M2	7	4	2,320.00	$30.79	$71,440.00
		M2	8	3	1,250.00	$18.56	$23,200.00
		M2	9	1	100.00	$25.00	$2,500.00
		M2	10	8	1,877.00	$37.22	$69,870.00
		M2	11	3	2,030.00	$34.13	$69,280.00
	Unit Sub Total	**M2**		**44**	**15,537.20**	**$32.74**	**$508,634.80**
840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	1	8	4,042.00	$6.06	$24,495.50
		SQFT	2	18	19,204.00	$5.13	$98,456.59
		SQFT	3	17	24,959.00	$3.44	$85,930.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	4	30	57,022.00	$3.08	$175,859.40
		SQFT	5	17	23,220.00	$2.93	$68,005.30
		SQFT	6	26	55,963.00	$2.68	$150,162.50
		SQFT	7	36	98,467.00	$2.48	$243,769.20
		SQFT	8	27	25,644.00	$3.65	$93,645.12
		SQFT	9	2	4,770.00	$2.77	$13,200.00
		SQFT	10	15	19,303.00	$3.14	$60,595.90
		SQFT	11	19	26,334.00	$3.36	$88,507.55
		SQFT	12	23	75,950.00	$2.45	$185,746.00
	Unit Sub Total	**SQFT**		**238**	**434,878.00**	**$2.96**	**$1,288,373.56**
840515	THERMOPLASTIC PAVEMENT MARKING	SQYD	3	1	10.00	$325.60	$3,256.00
		SQYD	8	1	1,820.00	$2.00	$3,640.00
	Unit Sub Total	**SQYD**		**2**	**1,830.00**	**$3.77**	**$6,896.00**
	Item Code 840515 Total No. of Proj.			**284**		**Total Amount**	**$1,803,904.36**
840519	THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING	SQFT	4	3	23,196.00	$1.89	$43,839.00
		SQFT	7	1	310.00	$2.58	$799.80
	Unit Sub Total	**SQFT**		**4**	**23,506.00**	**$1.90**	**$44,638.80**
	Item Code 840519 Total No. of Proj.			**4**		**Total Amount**	**$44,638.80**
840521	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 6-1)	LF	3	2	1,060.00	$0.39	$410.00
		LF	4	2	1,500.00	$0.12	$178.30
		LF	7	2	790.00	$0.47	$370.90
		LF	11	1	630.00	$0.75	$472.50
		LF	12	6	4,300.00	$0.55	$2,353.60
	Unit Sub Total	**LF**		**13**	**8,280.00**	**$0.46**	**$3,785.30**
	Item Code 840521 Total No. of Proj.			**13**		**Total Amount**	**$3,785.30**
840523	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	LF	1	2	2,660.00	$0.93	$2,471.00
		LF	2	2	750.00	$1.20	$902.50
		LF	3	3	6,730.00	$0.15	$1,030.60
		LF	4	3	1,390.00	$0.35	$488.50
		LF	5	4	3,900.00	$0.32	$1,262.60

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840523	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	LF	6	15	31,470.00	$0.19	$5,969.10
	Unit Sub Total	**LF**		**29**	**46,900.00**	**$0.26**	**$12,124.30**
	Item Code 840523 Total No. of Proj.			**29**		**Total Amount**	**$12,124.30**
840525	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	LF	1	10	32,150.00	$0.45	$14,385.00
		LF	2	2	71,340.00	$0.13	$9,019.00
		LF	3	16	792,930.00	$0.14	$108,658.70
		LF	4	22	642,190.00	$0.23	$145,074.90
		LF	5	9	300,270.00	$0.16	$47,865.20
		LF	6	25	2,064,320.00	$0.15	$310,071.80
		LF	7	43	1,036,615.00	$0.21	$222,800.25
		LF	11	3	32,340.00	$0.51	$16,586.00
		LF	12	16	739,380.00	$0.18	$135,604.40
	Unit Sub Total	**LF**		**146**	**5,711,535.00**	**$0.18**	**$1,010,065.25**
	Item Code 840525 Total No. of Proj.			**146**		**Total Amount**	**$1,010,065.25**
840526	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 17-7)	LF	1	1	73.00	$3.00	$219.00
		LF	2	2	5,180.00	$0.27	$1,380.50
		LF	3	11	29,478.00	$0.30	$8,912.80
		LF	4	25	135,660.00	$0.19	$25,721.10
		LF	5	4	1,890.00	$0.58	$1,090.00
		LF	6	9	30,090.00	$0.25	$7,582.50
		LF	7	20	192,540.00	$0.22	$41,835.20
		LF	11	6	4,970.00	$0.91	$4,508.50
		LF	12	14	106,240.00	$0.21	$22,708.30
	Unit Sub Total	**LF**		**92**	**506,121.00**	**$0.23**	**$113,957.90**
	Item Code 840526 Total No. of Proj.			**92**		**Total Amount**	**$113,957.90**
840545	4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED, BROKEN 36-12)	LF	3	4	128,800.00	$1.06	$136,130.00
	Unit Sub Total	**LF**		**4**	**128,800.00**	**$1.06**	**$136,130.00**
	Item Code 840545 Total No. of Proj.			**4**		**Total Amount**	**$136,130.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840550	8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	LF	7	3	8,170.00	$0.63	$5,112.20
		LF	12	3	10,060.00	$0.66	$6,673.20
	Unit Sub Total	**LF**		**6**	**18,230.00**	**$0.65**	**$11,785.40**
	Item Code 840550 Total No. of Proj.			**6**		**Total Amount**	**$11,785.40**
840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	LF	1	5	22,540.00	$0.88	$19,825.00
		LF	2	27	2,018,705.00	$0.17	$349,818.93
		LF	3	2	1,210.00	$5.21	$6,303.00
		LF	5	9	114,410.00	$0.48	$54,520.30
		LF	6	4	670,400.00	$0.18	$118,340.00
		LF	8	44	5,565,430.00	$0.14	$771,502.50
		LF	10	21	1,633,320.00	$0.20	$324,610.50
	Unit Sub Total	**LF**		**112**	**10,026,015.00**	**$0.16**	**$1,644,920.23**
840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	M	2	2	142.00	$24.32	$3,453.44
		M	5	2	31,160.00	$0.54	$16,945.00
		M	6	5	73,510.00	$0.50	$37,065.00
		M	8	3	242,900.00	$0.53	$128,510.00
		M	10	9	56,240.00	$1.44	$80,835.50
	Unit Sub Total	**M**		**21**	**403,952.00**	**$0.66**	**$266,808.94**
	Item Code 840560 Total No. of Proj.			**133**		**Total Amount**	**$1,911,729.17**
840561	100 MM THERMOPLASTIC TRAFFIC STRIPE	M	1	3	24,360.00	$1.05	$25,610.00
		M	3	5	81,300.00	$0.94	$76,690.00
		M	4	13	226,070.00	$1.08	$245,225.50
		M	6	4	92,590.00	$1.02	$94,243.00
		M	7	5	93,280.00	$1.18	$109,970.00
		M	10	3	26,670.00	$1.17	$31,204.00
		M	11	1	41.00	$5.00	$205.00
	Unit Sub Total	**M**		**34**	**544,311.00**	**$1.07**	**$583,147.50**
	Item Code 840561 Total No. of Proj.			**34**		**Total Amount**	**$583,147.50**
840562	150 MM THERMOPLASTIC TRAFFIC STRIPE	M	3	1	740.00	$1.25	$925.00
		M	4	3	6,160.00	$1.33	$8,183.50
	Unit Sub Total	**M**		**4**	**6,900.00**	**$1.32**	**$9,108.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 840562 Total No. of Proj.			**4**		**Total Amount**	**$9,108.50**
840563	200 MM THERMOPLASTIC TRAFFIC STRIPE	M	3	4	7,100.00	$1.68	$11,915.00
		M	4	10	21,150.00	$2.17	$45,877.50
		M	6	4	13,010.00	$2.10	$27,287.00
		M	7	4	6,300.00	$2.88	$18,115.20
		M	10	1	60.00	$2.00	$120.00
		M	11	3	9,710.00	$2.82	$27,360.00
	Unit Sub Total	**M**		**26**	**57,330.00**	**$2.28**	**$130,674.70**
	Item Code 840563 Total No. of Proj.			**26**		**Total Amount**	**$130,674.70**
840564	200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M)	M	3	2	4,400.00	$1.53	$6,730.00
		M	4	7	7,340.00	$1.54	$11,301.00
		M	7	4	3,700.00	$2.03	$7,502.00
		M	11	2	1,690.00	$1.80	$3,034.00
	Unit Sub Total	**M**		**15**	**17,130.00**	**$1.67**	**$28,567.00**
	Item Code 840564 Total No. of Proj.			**15**		**Total Amount**	**$28,567.00**
840567	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 1.83 M - 0.30 M)	M	3	2	198.00	$0.95	$189.00
		M	6	2	290.00	$1.45	$421.00
		M	11	1	220.00	$3.00	$660.00
	Unit Sub Total	**M**		**5**	**708.00**	**$1.79**	**$1,270.00**
	Item Code 840567 Total No. of Proj.			**5**		**Total Amount**	**$1,270.00**
840568	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M)	M	3	1	260.00	$0.85	$221.00
		M	6	2	590.00	$0.62	$363.00
		M	10	2	860.00	$1.17	$1,002.00
	Unit Sub Total	**M**		**5**	**1,710.00**	**$0.93**	**$1,586.00**
	Item Code 840568 Total No. of Proj.			**5**		**Total Amount**	**$1,586.00**
840570	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	M	1	1	10,200.00	$0.50	$5,100.00
		M	3	4	53,660.00	$0.68	$36,427.00
		M	4	3	3,610.00	$0.98	$3,535.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840570	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	M	6	3	45,380.00	$0.64	$29,058.00
		M	7	4	78,750.00	$0.67	$52,861.00
	Unit Sub Total	**M**		**15**	**191,600.00**	**$0.66**	**$126,981.00**
	Item Code 840570 Total No. of Proj.			**15**		**Total Amount**	**$126,981.00**
840571	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 5.18 M - 2.14 M)	M	3	2	3,530.00	$0.90	$3,180.00
		M	4	6	5,435.00	$0.89	$4,853.50
		M	6	1	800.00	$2.50	$2,000.00
		M	7	4	2,644.00	$0.76	$2,006.40
		M	11	2	494.00	$2.45	$1,208.00
	Unit Sub Total	**M**		**15**	**12,903.00**	**$1.03**	**$13,247.90**
	Item Code 840571 Total No. of Proj.			**15**		**Total Amount**	**$13,247.90**
840574	200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	M	7	1	880.00	$2.00	$1,760.00
	Unit Sub Total	**M**		**1**	**880.00**	**$2.00**	**$1,760.00**
	Item Code 840574 Total No. of Proj.			**1**		**Total Amount**	**$1,760.00**
840575	100 MM TWO-COMPONENT PAINT TRAFFIC STRIPE	M	2	1	15,100.00	$7.00	$105,700.00
	Unit Sub Total	**M**		**1**	**15,100.00**	**$7.00**	**$105,700.00**
	Item Code 840575 Total No. of Proj.			**1**		**Total Amount**	**$105,700.00**
840577	200 MM TWO-COMPONENT PAINT TRAFFIC STRIPE	M	2	1	180.00	$15.00	$2,700.00
	Unit Sub Total	**M**		**1**	**180.00**	**$15.00**	**$2,700.00**
	Item Code 840577 Total No. of Proj.			**1**		**Total Amount**	**$2,700.00**
840580	4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED) (BROKEN 17-7)	LF	3	4	2,500.00	$1.68	$4,210.00
	Unit Sub Total	**LF**		**4**	**2,500.00**	**$1.68**	**$4,210.00**
	Item Code 840580 Total No. of Proj.			**4**		**Total Amount**	**$4,210.00**
840581	4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED)	LF	3	6	305,870.00	$1.17	$357,485.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**6**	**305,870.00**	**$1.17**	**$357,485.00**
	Item Code 840581 Total No. of Proj.			**6**		**Total Amount**	**$357,485.00**
840582	4" TWO-COMPONENT PAINT TRAFFIC STRIPE	LF	3	5	323,150.00	$0.47	$153,290.00
	Unit Sub Total	**LF**		**5**	**323,150.00**	**$0.47**	**$153,290.00**
	Item Code 840582 Total No. of Proj.			**5**		**Total Amount**	**$153,290.00**
840600	PAINTED TRAFFIC STRIPE	M	10	1	5,490.00	$1.00	$5,490.00
	Unit Sub Total	**M**		**1**	**5,490.00**	**$1.00**	**$5,490.00**
	Item Code 840600 Total No. of Proj.			**1**		**Total Amount**	**$5,490.00**
840651	PAINTED STALL LINES AND PAVEMENT MARKINGS	SQFT	1	1	64.00	$18.00	$1,152.00
	Unit Sub Total	**SQFT**		**1**	**64.00**	**$18.00**	**$1,152.00**
	Item Code 840651 Total No. of Proj.			**1**		**Total Amount**	**$1,152.00**
840653	PAINT TRAFFIC STRIPE	LF	2	1	370.00	$5.60	$2,072.00
	Unit Sub Total	**LF**		**1**	**370.00**	**$5.60**	**$2,072.00**
840653	PAINT TRAFFIC STRIPE	M	1	2	240.00	$21.88	$5,250.00
		M	5	1	8,840.00	$2.25	$19,890.00
	Unit Sub Total	**M**		**3**	**9,080.00**	**$2.77**	**$25,140.00**
	Item Code 840653 Total No. of Proj.			**4**		**Total Amount**	**$27,212.00**
840655	PAINT TRAFFIC STRIPE (1-COAT)	LF	1	3	101,140.00	$0.19	$19,190.00
	Unit Sub Total	**LF**		**3**	**101,140.00**	**$0.19**	**$19,190.00**
840655	PAINT TRAFFIC STRIPE (1-COAT)	M	4	1	11,200.00	$1.00	$11,200.00
		M	11	1	38,500.00	$0.50	$19,250.00
	Unit Sub Total	**M**		**2**	**49,700.00**	**$0.61**	**$30,450.00**
	Item Code 840655 Total No. of Proj.			**5**		**Total Amount**	**$49,640.00**
840656	PAINT TRAFFIC STRIPE (2-COAT)	LF	2	2	360.00	$6.58	$2,370.00
		LF	3	2	490.00	$6.79	$3,325.00
		LF	4	2	53,690.00	$0.30	$15,873.00
		LF	6	5	1,195,600.00	$0.08	$98,290.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840656	PAINT TRAFFIC STRIPE (2-COAT)	LF	7	4	510,300.00	$0.11	$57,160.00
		LF	8	2	14,550.00	$0.30	$4,395.00
		LF	9	7	1,164,670.00	$0.10	$110,945.00
		LF	11	21	1,460,835.00	$0.16	$236,675.75
		LF	12	5	413,175.00	$0.13	$54,252.25
	Unit Sub Total	**LF**		**50**	**4,813,670.00**	**$0.12**	**$583,286.00**
840656	PAINT TRAFFIC STRIPE (2-COAT)	M	4	3	36,297.00	$0.69	$25,097.00
		M	5	1	16,900.00	$0.50	$8,450.00
		M	6	1	21,500.00	$0.35	$7,525.00
		M	7	3	181,300.00	$0.61	$110,131.00
		M	8	2	250,300.00	$0.42	$105,275.00
		M	9	3	75,990.00	$0.42	$31,682.50
		M	10	2	2,780.00	$2.36	$6,555.50
		M	11	3	151,000.00	$0.68	$102,250.00
	Unit Sub Total	**M**		**18**	**736,067.00**	**$0.54**	**$396,966.00**
	Item Code 840656 Total No. of Proj.			**68**		**Total Amount**	**$980,252.00**
840660	PAINT PAVEMENT MARKING	M2	5	1	13.00	$15.00	$195.00
		M2	7	1	24.00	$32.10	$770.40
		M2	10	1	5.00	$65.00	$325.00
	Unit Sub Total	**M2**		**3**	**42.00**	**$30.72**	**$1,290.40**
	Item Code 840660 Total No. of Proj.			**3**		**Total Amount**	**$1,290.40**
840661	TWO-COMPONENT PAINT PAVEMENT MARKING	LF	3	1	580.00	$5.00	$2,900.00
	Unit Sub Total	**LF**		**1**	**580.00**	**$5.00**	**$2,900.00**
840661	TWO-COMPONENT PAINT PAVEMENT MARKING	M2	2	1	12.00	$500.00	$6,000.00
	Unit Sub Total	**M2**		**1**	**12.00**	**$500.00**	**$6,000.00**
840661	TWO-COMPONENT PAINT PAVEMENT MARKING	SQFT	3	5	9,520.00	$6.79	$64,675.00
	Unit Sub Total	**SQFT**		**5**	**9,520.00**	**$6.79**	**$64,675.00**
	Item Code 840661 Total No. of Proj.			**7**		**Total Amount**	**$73,575.00**
840666	PAINT PAVEMENT MARKING (2-COAT)	M2	4	3	477.00	$29.25	$13,950.00
		M2	5	1	220.00	$25.00	$5,500.00
		M2	6	1	320.00	$30.00	$9,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840666	PAINT PAVEMENT MARKING (2-COAT)	M2	7	1	150.00	$33.00	$4,950.00
		M2	8	2	232.00	$9.24	$2,144.00
		M2	9	2	361.00	$21.96	$7,928.00
		M2	10	2	70.00	$42.94	$3,006.00
		M2	11	1	6.00	$40.00	$240.00
	Unit Sub Total	**M2**		**13**	**1,836.00**	**$25.77**	**$47,318.00**
840666	PAINT PAVEMENT MARKING (2-COAT)	SQFT	4	1	130.00	$4.00	$520.00
		SQFT	6	3	12,330.00	$1.24	$15,326.00
		SQFT	8	1	53.00	$11.00	$583.00
		SQFT	9	3	5,670.00	$2.27	$12,883.00
		SQFT	12	1	130.00	$3.00	$390.00
	Unit Sub Total	**SQFT**		**9**	**18,313.00**	**$1.62**	**$29,702.00**
	Item Code 840666 Total No. of Proj.			**22**		**Total Amount**	**$77,020.00**
842000	PARKING BUMPER (PRECAST CONCRETE)	EA	4	2	41.00	$88.90	$3,645.00
		EA	5	1	23.00	$50.00	$1,150.00
		EA	6	1	9.00	$90.00	$810.00
		EA	11	2	172.00	$60.17	$10,350.00
		EA	12	1	2.00	$38.50	$77.00
	Unit Sub Total	**EA**		**7**	**247.00**	**$64.91**	**$16,032.00**
	Item Code 842000 Total No. of Proj.			**7**		**Total Amount**	**$16,032.00**
850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	1	4	8,766.00	$3.21	$28,170.00
		EA	3	2	2,720.00	$1.87	$5,080.00
		EA	4	42	161,048.00	$1.60	$256,994.70
		EA	5	8	19,400.00	$1.44	$27,946.50
		EA	6	1	74.00	$3.00	$222.00
		EA	7	38	131,857.00	$1.36	$179,252.90
		EA	8	23	255,424.00	$0.65	$167,273.60
		EA	10	3	878.00	$2.06	$1,812.00
		EA	11	16	34,706.00	$1.45	$50,222.80
		EA	12	18	75,770.00	$1.12	$85,157.60
	Unit Sub Total	**EA**		**155**	**690,643.00**	**$1.16**	**$802,132.10**
	Item Code 850101 Total No. of Proj.			**155**		**Total Amount**	**$802,132.10**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
850102	PAVEMENT MARKER (REFLECTIVE)	EA	4	1	730.00	$8.50	$6,205.00
		EA	8	6	11,110.00	$2.52	$28,014.20
	Unit Sub Total	**EA**		**7**	**11,840.00**	**$2.89**	**$34,219.20**
	Item Code 850102 Total No. of Proj.			**7**		**Total Amount**	**$34,219.20**
850104	PAVEMENT MARKER (REFLECTIVE-SPECIAL TYPE H)	EA	7	1	190.00	$2.00	$380.00
	Unit Sub Total	**EA**		**1**	**190.00**	**$2.00**	**$380.00**
	Item Code 850104 Total No. of Proj.			**1**		**Total Amount**	**$380.00**
850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	1	18	18,289.00	$3.92	$71,723.00
		EA	2	4	25,140.00	$3.52	$88,582.50
		EA	3	26	46,017.00	$3.14	$144,588.16
		EA	4	62	114,130.00	$3.34	$381,531.90
		EA	5	23	38,217.00	$2.40	$91,654.15
		EA	6	35	110,510.00	$2.34	$258,116.00
		EA	7	55	107,960.00	$2.75	$296,416.90
		EA	8	26	83,642.00	$2.61	$218,088.60
		EA	10	26	37,781.00	$3.20	$120,947.50
		EA	11	24	42,823.00	$3.73	$159,925.30
		EA	12	23	55,505.00	$2.69	$149,114.40
	Unit Sub Total	**EA**		**322**	**680,014.00**	**$2.91**	**$1,980,688.41**
	Item Code 850111 Total No. of Proj.			**322**		**Total Amount**	**$1,980,688.41**
850112	PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE G)	EA	1	1	12.00	$8.00	$96.00
		EA	4	2	1,310.00	$3.38	$4,425.00
		EA	7	2	602.00	$2.69	$1,620.00
		EA	12	1	1,710.00	$1.75	$2,992.50
	Unit Sub Total	**EA**		**6**	**3,634.00**	**$2.51**	**$9,133.50**
	Item Code 850112 Total No. of Proj.			**6**		**Total Amount**	**$9,133.50**
850113	PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE H)	EA	4	1	1,250.00	$3.30	$4,125.00
		EA	7	1	52.00	$10.00	$520.00
		EA	12	1	670.00	$1.75	$1,172.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**3**	**1,972.00**	**$2.95**	**$5,817.50**
	Item Code 850113 Total No. of Proj.			**3**		**Total Amount**	**$5,817.50**
850120	PAVEMENT MARKER (REFLECTIVE-RECESSED)	EA	1	1	1,220.00	$8.00	$9,760.00
		EA	8	1	440.00	$8.25	$3,630.00
	Unit Sub Total	**EA**		**2**	**1,660.00**	**$8.07**	**$13,390.00**
	Item Code 850120 Total No. of Proj.			**2**		**Total Amount**	**$13,390.00**
850122	PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	EA	1	17	9,553.00	$9.93	$94,856.50
		EA	2	21	29,460.00	$7.04	$207,466.24
		EA	3	1	3,260.00	$6.00	$19,560.00
		EA	4	3	780.00	$16.89	$13,175.00
		EA	6	3	5,720.00	$9.61	$54,950.00
		EA	7	3	5,770.00	$7.51	$43,350.00
		EA	8	12	31,297.00	$7.61	$238,030.60
	Unit Sub Total	**EA**		**60**	**85,840.00**	**$7.82**	**$671,388.34**
	Item Code 850122 Total No. of Proj.			**60**		**Total Amount**	**$671,388.34**
860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	1	5	5.00	$1,550.00	$7,750.00
		LS	2	11	11.00	$6,531.82	$71,850.00
		LS	3	29	29.00	$1,918.10	$55,625.00
		LS	4	23	23.00	$3,640.39	$83,729.00
		LS	5	12	12.00	$1,942.99	$23,315.88
		LS	6	26	26.00	$2,380.51	$61,893.26
		LS	7	59	59.00	$1,747.80	$103,120.44
		LS	8	26	26.00	$2,496.90	$64,919.45
		LS	9	3	3.00	$1,575.00	$4,725.00
		LS	10	25	25.00	$1,038.86	$25,971.50
		LS	11	33	33.00	$3,879.05	$128,008.64
		LS	12	34	34.00	$1,026.79	$34,911.00
	Unit Sub Total	**LS**		**286**	**286.00**	**$2,328.04**	**$665,819.17**
	Item Code 860090 Total No. of Proj.			**286**		**Total Amount**	**$665,819.17**
860150	SIGNAL AND LIGHTING (TEMPORARY)	LS	7	2	2.00	$19,931.00	$39,862.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LS**		**2**	**2.00**	**$19,931.00**	**$39,862.00**
	Item Code 860150 Total No. of Proj.			**2**		**Total Amount**	**$39,862.00**
860151	SIGNAL AND LIGHTING (TEMPORARY LOCATION 1)	LS	11	1	1.00	$10,500.00	$10,500.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$10,500.00**	**$10,500.00**
	Item Code 860151 Total No. of Proj.			**1**		**Total Amount**	**$10,500.00**
860201	SIGNAL AND LIGHTING	LS	3	3	3.00	$136,516.67	$409,550.00
		LS	4	2	2.00	$102,800.00	$205,600.00
		LS	6	1	1.00	$131,264.00	$131,264.00
		LS	7	1	1.00	$143,000.00	$143,000.00
		LS	8	3	3.00	$112,000.00	$336,000.00
		LS	10	3	3.00	$145,746.67	$437,240.00
		LS	11	2	2.00	$121,092.50	$242,185.00
		LS	12	3	3.00	$93,094.93	$279,284.78
	Unit Sub Total	**LS**		**18**	**18.00**	**$121,340.21**	**$2,184,123.78**
	Item Code 860201 Total No. of Proj.			**18**		**Total Amount**	**$2,184,123.78**
860251	SIGNAL AND LIGHTING (LOCATION 1)	LS	2	1	1.00	$111,375.61	$111,375.61
		LS	4	5	5.00	$94,400.00	$472,000.00
		LS	6	2	2.00	$195,000.00	$390,000.00
		LS	8	3	3.00	$87,666.67	$263,000.00
		LS	10	1	1.00	$88,500.00	$88,500.00
		LS	11	2	2.00	$82,150.00	$164,300.00
		LS	12	1	1.00	$7,000.00	$7,000.00
	Unit Sub Total	**LS**		**15**	**15.00**	**$99,745.04**	**$1,496,175.61**
	Item Code 860251 Total No. of Proj.			**15**		**Total Amount**	**$1,496,175.61**
860252	SIGNAL AND LIGHTING (LOCATION 2)	LS	2	1	1.00	$125,922.65	$125,922.65
		LS	4	4	4.00	$65,250.00	$261,000.00
		LS	6	2	2.00	$135,000.00	$270,000.00
		LS	8	3	3.00	$91,666.67	$275,000.00
		LS	10	1	1.00	$60,000.00	$60,000.00
		LS	11	2	2.00	$192,500.00	$385,000.00
		LS	12	1	1.00	$7,750.00	$7,750.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LS**		**14**	**14.00**	**$98,905.19**	**$1,384,672.65**
	Item Code 860252 Total No. of Proj.			**14**		**Total Amount**	**$1,384,672.65**
860253	SIGNAL AND LIGHTING (LOCATION 3)	LS	4	3	3.00	$107,666.67	$323,000.00
		LS	6	2	2.00	$120,000.00	$240,000.00
		LS	8	1	1.00	$60,000.00	$60,000.00
		LS	11	2	2.00	$123,500.00	$247,000.00
		LS	12	1	1.00	$4,700.00	$4,700.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$97,188.89**	**$874,700.00**
	Item Code 860253 Total No. of Proj.			**9**		**Total Amount**	**$874,700.00**
860254	SIGNAL AND LIGHTING (LOCATION 4)	LS	4	3	3.00	$133,333.33	$400,000.00
		LS	6	1	1.00	$175,000.00	$175,000.00
		LS	11	2	2.00	$74,500.00	$149,000.00
	Unit Sub Total	**LS**		**6**	**6.00**	**$120,666.67**	**$724,000.00**
	Item Code 860254 Total No. of Proj.			**6**		**Total Amount**	**$724,000.00**
860255	SIGNAL AND LIGHTING (LOCATION 5)	LS	4	1	1.00	$125,000.00	$125,000.00
		LS	6	1	1.00	$250,000.00	$250,000.00
		LS	11	2	2.00	$142,000.00	$284,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$164,750.00**	**$659,000.00**
	Item Code 860255 Total No. of Proj.			**4**		**Total Amount**	**$659,000.00**
860256	SIGNAL AND LIGHTING (LOCATION 6)	LS	11	1	1.00	$124,000.00	$124,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$124,000.00**	**$124,000.00**
	Item Code 860256 Total No. of Proj.			**1**		**Total Amount**	**$124,000.00**
860257	SIGNAL AND LIGHTING (LOCATION 7)	LS	4	1	1.00	$85,000.00	$85,000.00
		LS	11	1	1.00	$183,000.00	$183,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$134,000.00**	**$268,000.00**
	Item Code 860257 Total No. of Proj.			**2**		**Total Amount**	**$268,000.00**
860258	SIGNAL AND LIGHTING (LOCATION 8)	LS	11	1	1.00	$127,000.00	$127,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$127,000.00**	**$127,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 860258 Total No. of Proj.			**1**		**Total Amount**	**$127,000.00**
860259	SIGNAL AND LIGHTING (LOCATION 9)	LS	4	1	1.00	$55,000.00	$55,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$55,000.00**	**$55,000.00**
	Item Code 860259 Total No. of Proj.			**1**		**Total Amount**	**$55,000.00**
860297	SIGNAL AND LIGHTING (CITY)	LS	8	1	1.00	$70,000.00	$70,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$70,000.00**	**$70,000.00**
	Item Code 860297 Total No. of Proj.			**1**		**Total Amount**	**$70,000.00**
860298	SIGNAL AND LIGHTING (STAGE CONSTRUCTION)	LS	4	4	4.00	$134,000.00	$536,000.00
		LS	6	1	1.00	$132,000.00	$132,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$133,600.00**	**$668,000.00**
	Item Code 860298 Total No. of Proj.			**5**		**Total Amount**	**$668,000.00**
860301	SIGNAL AND LIGHTING	LS	5	1	1.00	$101,455.00	$101,455.00
		LS	6	3	3.00	$186,333.33	$559,000.00
		LS	11	1	1.00	$177,404.00	$177,404.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$167,571.80**	**$837,859.00**
	Item Code 860301 Total No. of Proj.			**5**		**Total Amount**	**$837,859.00**
860303	SIGNAL AND LIGHTING (CITY STREET LOCATION 3)	LS	2	1	1.00	$155,120.89	$155,120.89
	Unit Sub Total	**LS**		**1**	**1.00**	**$155,120.89**	**$155,120.89**
	Item Code 860303 Total No. of Proj.			**1**		**Total Amount**	**$155,120.89**
860305	SIGNAL AND LIGHTING (CITY STREET LOCATION 5)	LS	4	1	1.00	$90,000.00	$90,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$90,000.00**	**$90,000.00**
	Item Code 860305 Total No. of Proj.			**1**		**Total Amount**	**$90,000.00**
860306	SIGNAL AND LIGHTING (CITY STREET LOCATION 6)	LS	4	1	1.00	$80,000.00	$80,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$80,000.00**	**$80,000.00**
	Item Code 860306 Total No. of Proj.			**1**		**Total Amount**	**$80,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860400	LIGHTING (TEMPORARY)	LS	3	1	1.00	$5,500.00	$5,500.00
		LS	4	1	1.00	$30,000.00	$30,000.00
		LS	7	4	4.00	$80,650.00	$322,600.00
	Unit Sub Total	**LS**		**6**	**6.00**	**$59,683.33**	**$358,100.00**
	Item Code 860400 Total No. of Proj.			**6**		**Total Amount**	**$358,100.00**
860401	LIGHTING	LS	2	3	3.00	$149,745.34	$449,236.02
		LS	3	1	1.00	$24,037.00	$24,037.00
		LS	4	1	1.00	$23,100.00	$23,100.00
		LS	10	1	1.00	$50,000.00	$50,000.00
		LS	11	3	3.00	$82,866.67	$248,600.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$88,330.34**	**$794,973.02**
	Item Code 860401 Total No. of Proj.			**9**		**Total Amount**	**$794,973.02**
860402	LIGHTING (CITY STREET)	LS	4	4	4.00	$70,750.00	$283,000.00
		LS	7	1	1.00	$159,000.00	$159,000.00
		LS	11	2	2.00	$112,500.00	$225,000.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$95,285.71**	**$667,000.00**
	Item Code 860402 Total No. of Proj.			**7**		**Total Amount**	**$667,000.00**
860403	HIGHWAY LIGHTING	LS	1	1	1.00	$33,150.00	$33,150.00
		LS	3	2	2.00	$41,150.00	$82,300.00
		LS	4	1	1.00	$300,000.00	$300,000.00
		LS	5	3	3.00	$55,000.00	$165,000.00
		LS	6	3	3.00	$111,000.00	$333,000.00
		LS	10	2	2.00	$12,450.00	$24,900.00
	Unit Sub Total	**LS**		**12**	**12.00**	**$78,195.83**	**$938,350.00**
	Item Code 860403 Total No. of Proj.			**12**		**Total Amount**	**$938,350.00**
860407	LIGHTING (PARKING LOT)	LS	4	1	1.00	$60,000.00	$60,000.00
		LS	6	1	1.00	$30,000.00	$30,000.00
		LS	11	1	1.00	$58,000.00	$58,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$49,333.33**	**$148,000.00**
	Item Code 860407 Total No. of Proj.			**3**		**Total Amount**	**$148,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860415	LIGHTING (STAGE CONSTRUCTION)	LS	4	2	2.00	$126,000.00	$252,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$126,000.00**	**$252,000.00**
	Item Code 860415 Total No. of Proj.			**2**		**Total Amount**	**$252,000.00**
860420	LIGHTING (TUNNEL)	LS	7	1	1.00	$25,000.00	$25,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$25,000.00**	**$25,000.00**
	Item Code 860420 Total No. of Proj.			**1**		**Total Amount**	**$25,000.00**
860460	LIGHTING AND SIGN ILLUMINATION	LS	2	1	1.00	$60,000.00	$60,000.00
		LS	4	9	9.00	$240,200.00	$2,161,800.00
		LS	8	1	1.00	$800,000.00	$800,000.00
		LS	11	4	4.00	$210,750.00	$843,000.00
		LS	12	1	1.00	$180,000.00	$180,000.00
	Unit Sub Total	**LS**		**16**	**16.00**	**$252,800.00**	**$4,044,800.00**
	Item Code 860460 Total No. of Proj.			**16**		**Total Amount**	**$4,044,800.00**
860501	SIGN ILLUMINATION	LS	3	3	3.00	$15,833.33	$47,500.00
		LS	7	1	1.00	$14,500.00	$14,500.00
		LS	8	1	1.00	$16,000.00	$16,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$15,600.00**	**$78,000.00**
	Item Code 860501 Total No. of Proj.			**5**		**Total Amount**	**$78,000.00**
860503	EXTINGUISHABLE MESSAGE SIGN	LS	3	1	1.00	$25,000.00	$25,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$25,000.00**	**$25,000.00**
	Item Code 860503 Total No. of Proj.			**1**		**Total Amount**	**$25,000.00**
860504	EXTINGUISHABLE MESSAGE SIGN SYSTEM	LS	10	1	1.00	$34,500.00	$34,500.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$34,500.00**	**$34,500.00**
	Item Code 860504 Total No. of Proj.			**1**		**Total Amount**	**$34,500.00**
860508	MODIFY SIGN ILLUMINATION	LS	3	2	2.00	$11,500.00	$23,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$11,500.00**	**$23,000.00**
	Item Code 860508 Total No. of Proj.			**2**		**Total Amount**	**$23,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860520	HIGHWAY ADVISORY RADIO SYSTEM	EA	4	3	3.00	$17,333.33	$52,000.00
	Unit Sub Total	**EA**		**3**	**3.00**	**$17,333.33**	**$52,000.00**
860520	HIGHWAY ADVISORY RADIO SYSTEM	LS	2	2	2.00	$35,000.00	$70,000.00
		LS	4	2	2.00	$30,000.00	$60,000.00
		LS	6	1	1.00	$170,000.00	$170,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$60,000.00**	**$300,000.00**
	Item Code 860520 Total No. of Proj.			**8**		**Total Amount**	**$352,000.00**
860530	CHANGEABLE MESSAGE SIGN SYSTEM	LS	3	1	1.00	$25,000.00	$25,000.00
		LS	6	3	3.00	$25,000.00	$75,000.00
		LS	8	1	1.00	$16,500.00	$16,500.00
		LS	11	2	2.00	$42,000.00	$84,000.00
		LS	12	1	1.00	$30,000.00	$30,000.00
	Unit Sub Total	**LS**		**8**	**8.00**	**$28,812.50**	**$230,500.00**
	Item Code 860530 Total No. of Proj.			**8**		**Total Amount**	**$230,500.00**
860551	LIGHTING AND SIGN ILLUMINATION (LOCATION 1)	LS	4	1	1.00	$75,000.00	$75,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$75,000.00**	**$75,000.00**
	Item Code 860551 Total No. of Proj.			**1**		**Total Amount**	**$75,000.00**
860552	LIGHTING AND SIGN ILLUMINATION (LOCATION 2)	LS	4	1	1.00	$200,000.00	$200,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$200,000.00**	**$200,000.00**
	Item Code 860552 Total No. of Proj.			**1**		**Total Amount**	**$200,000.00**
860553	LIGHTING AND SIGN ILLUMINATION (LOCATION 3)	LS	4	1	1.00	$75,000.00	$75,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$75,000.00**	**$75,000.00**
	Item Code 860553 Total No. of Proj.			**1**		**Total Amount**	**$75,000.00**
860601	FLASHING BEACON	LS	3	2	2.00	$66,000.00	$132,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$66,000.00**	**$132,000.00**
	Item Code 860601 Total No. of Proj.			**2**		**Total Amount**	**$132,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860603	FLASHING BEACON AND LIGHTING	LS	4	1	1.00	$40,000.00	$40,000.00
		LS	6	1	1.00	$53,000.00	$53,000.00
		LS	7	2	2.00	$31,500.00	$63,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$39,000.00**	**$156,000.00**
	Item Code 860603 Total No. of Proj.			**4**		**Total Amount**	**$156,000.00**
860615	MODIFY FLASHING BEACON	LS	5	1	1.00	$16,100.00	$16,100.00
		LS	6	1	1.00	$20,000.00	$20,000.00
		LS	11	1	1.00	$12,000.00	$12,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$16,033.33**	**$48,100.00**
	Item Code 860615 Total No. of Proj.			**3**		**Total Amount**	**$48,100.00**
860701	INTERCONNECTION CONDUIT AND CONDUCTOR	LS	4	1	1.00	$15,000.00	$15,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$15,000.00**	**$15,000.00**
	Item Code 860701 Total No. of Proj.			**1**		**Total Amount**	**$15,000.00**
860703	INTERCONNECTION CONDUIT AND CABLE	LS	8	2	2.00	$25,000.00	$50,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$25,000.00**	**$50,000.00**
	Item Code 860703 Total No. of Proj.			**2**		**Total Amount**	**$50,000.00**
860764	SIZE 53 CONDUIT	M	9	1	30.00	$130.00	$3,900.00
	Unit Sub Total	**M**		**1**	**30.00**	**$130.00**	**$3,900.00**
	Item Code 860764 Total No. of Proj.			**1**		**Total Amount**	**$3,900.00**
860791	COMMUNICATION CONDUIT	LS	4	1	1.00	$30,000.00	$30,000.00
		LS	10	1	1.00	$173,000.00	$173,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$101,500.00**	**$203,000.00**
	Item Code 860791 Total No. of Proj.			**2**		**Total Amount**	**$203,000.00**
860792	COMMUNICATION CONDUIT (BRIDGE)	LF	5	1	1,560.00	$55.00	$85,800.00
	Unit Sub Total	**LF**		**1**	**1,560.00**	**$55.00**	**$85,800.00**
860792	COMMUNICATION CONDUIT (BRIDGE)	LS	4	1	1.00	$15,000.00	$15,000.00
		LS	10	1	1.00	$33,000.00	$33,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$24,000.00**	**$48,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860792	COMMUNICATION CONDUIT (BRIDGE)	M	2	1	2,500.00	$100.00	$250,000.00
		M	4	1	64.00	$110.00	$7,040.00
		M	5	1	744.00	$65.00	$48,360.00
		M	7	1	672.00	$115.00	$77,280.00
		M	8	1	218.00	$24.00	$5,232.00
	Unit Sub Total	**M**		**5**	**4,198.00**	**$92.40**	**$387,912.00**
	Item Code 860792 Total No. of Proj.			**8**		**Total Amount**	**$521,712.00**
860796	SPRINKLER CONTROL CONDUIT (BRIDGE)	LS	7	1	1.00	$2,500.00	$2,500.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$2,500.00**	**$2,500.00**
860796	SPRINKLER CONTROL CONDUIT (BRIDGE)	M	4	2	642.00	$18.62	$11,953.00
		M	5	1	133.00	$65.00	$8,645.00
		M	6	1	100.00	$126.00	$12,600.00
		M	11	2	380.00	$45.95	$17,460.00
	Unit Sub Total	**M**		**6**	**1,255.00**	**$40.36**	**$50,658.00**
	Item Code 860796 Total No. of Proj.			**7**		**Total Amount**	**$53,158.00**
860797	ELECTRIC SERVICE (IRRIGATION)	LS	3	2	2.00	$22,500.00	$45,000.00
		LS	4	4	4.00	$14,625.00	$58,500.00
		LS	5	2	2.00	$16,818.98	$33,637.95
		LS	7	3	3.00	$23,233.33	$69,700.00
		LS	8	2	2.00	$6,000.00	$12,000.00
		LS	10	1	1.00	$1,000.00	$1,000.00
		LS	11	4	4.00	$19,732.75	$78,931.00
	Unit Sub Total	**LS**		**18**	**18.00**	**$16,598.28**	**$298,768.95**
	Item Code 860797 Total No. of Proj.			**18**		**Total Amount**	**$298,768.95**
860798	BOOSTER PUMP ELECTRICAL SYSTEM	LS	3	1	1.00	$25,000.00	$25,000.00
		LS	5	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$13,000.00**	**$26,000.00**
	Item Code 860798 Total No. of Proj.			**2**		**Total Amount**	**$26,000.00**
860810	INDUCTIVE LOOP DETECTOR	EA	7	2	313.00	$305.46	$95,610.00
		EA	8	6	137.00	$417.00	$57,128.92
		EA	12	7	1,434.00	$207.50	$297,555.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**15**	**1,884.00**	**$239.01**	**$450,293.92**
860810	INDUCTIVE LOOP DETECTOR		LS	2	1	1.00	$10,000.00	$10,000.00
			LS	3	3	3.00	$56,666.67	$170,000.00
			LS	4	1	1.00	$30,000.00	$30,000.00
			LS	5	2	2.00	$4,305.00	$8,610.00
			LS	11	4	4.00	$5,575.00	$22,300.00
			LS	12	2	2.00	$21,600.00	$43,200.00
		Unit Sub Total	**LS**		**13**	**13.00**	**$21,854.62**	**$284,110.00**
	Item Code 860810	**Total No. of Proj.**			**28**		**Total Amount**	**$734,403.92**
860811	DETECTOR LOOP		EA	8	3	36.00	$577.78	$20,800.00
			EA	9	1	2.00	$1,300.00	$2,600.00
		Unit Sub Total	**EA**		**4**	**38.00**	**$615.79**	**$23,400.00**
860811	DETECTOR LOOP		LS	2	1	1.00	$2,640.00	$2,640.00
			LS	5	2	2.00	$7,512.50	$15,025.00
			LS	6	1	1.00	$1,860.00	$1,860.00
		Unit Sub Total	**LS**		**4**	**4.00**	**$4,881.25**	**$19,525.00**
	Item Code 860811	**Total No. of Proj.**			**8**		**Total Amount**	**$42,925.00**
860812	MICROWAVE VEHICLE DETECTION SYSTEM		EA	6	2	29.00	$14,502.21	$420,564.00
		Unit Sub Total	**EA**		**2**	**29.00**	**$14,502.21**	**$420,564.00**
860812	MICROWAVE VEHICLE DETECTION SYSTEM		LS	3	2	2.00	$143,143.00	$286,286.00
			LS	5	1	1.00	$20,000.00	$20,000.00
		Unit Sub Total	**LS**		**3**	**3.00**	**$102,095.33**	**$306,286.00**
	Item Code 860812	**Total No. of Proj.**			**5**		**Total Amount**	**$726,850.00**
860889	MODIFY TRAFFIC MONITORING STATION		LS	3	3	3.00	$32,221.67	$96,665.00
			LS	7	14	14.00	$15,472.14	$216,610.00
			LS	8	2	2.00	$68,149.85	$136,299.70
			LS	10	1	1.00	$33,000.00	$33,000.00
			LS	11	2	2.00	$5,500.00	$11,000.00
			LS	12	3	3.00	$15,000.00	$45,000.00
		Unit Sub Total	**LS**		**25**	**25.00**	**$21,542.99**	**$538,574.70**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 860889 Total No. of Proj.			**25**		**Total Amount**	**$538,574.70**
860890	MODIFY TRAFFIC MONITORING STATION (COUNT)	LS	3	3	3.00	$7,166.67	$21,500.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$7,166.67**	**$21,500.00**
	Item Code 860890 Total No. of Proj.			**3**		**Total Amount**	**$21,500.00**
860925	TRAFFIC MONITORING STATION (COUNT)	LS	3	1	1.00	$20,000.00	$20,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$20,000.00**	**$20,000.00**
	Item Code 860925 Total No. of Proj.			**1**		**Total Amount**	**$20,000.00**
860930	TRAFFIC MONITORING STATION	LS	2	4	4.00	$12,056.00	$48,224.00
		LS	3	3	3.00	$196,666.67	$590,000.00
		LS	4	1	1.00	$15,000.00	$15,000.00
		LS	6	4	4.00	$24,365.00	$97,460.00
		LS	8	1	1.00	$32,600.00	$32,600.00
		LS	10	2	2.00	$25,000.00	$50,000.00
		LS	12	1	1.00	$140,000.00	$140,000.00
	Unit Sub Total	**LS**		**16**	**16.00**	**$60,830.25**	**$973,284.00**
	Item Code 860930 Total No. of Proj.			**16**		**Total Amount**	**$973,284.00**
860931	TRAFFIC MONITORING STATION (LOCATION 1)	LS	6	3	3.00	$16,200.00	$48,600.00
		LS	8	1	1.00	$10,000.00	$10,000.00
		LS	11	3	3.00	$24,333.33	$73,000.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$18,800.00**	**$131,600.00**
	Item Code 860931 Total No. of Proj.			**7**		**Total Amount**	**$131,600.00**
860932	TRAFFIC MONITORING STATION (LOCATION 2)	LS	6	3	3.00	$16,200.00	$48,600.00
		LS	8	1	1.00	$15,000.00	$15,000.00
		LS	11	3	3.00	$26,666.67	$80,000.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$20,514.29**	**$143,600.00**
	Item Code 860932 Total No. of Proj.			**7**		**Total Amount**	**$143,600.00**
860933	TRAFFIC MONITORING STATION (LOCATION 3)	LS	6	2	2.00	$3,800.00	$7,600.00
		LS	8	1	1.00	$20,000.00	$20,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860933	TRAFFIC MONITORING STATION (LOCATION 3)	LS	11	1	1.00	$16,000.00	$16,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$10,900.00**	**$43,600.00**
	Item Code 860933 Total No. of Proj.			**4**		**Total Amount**	**$43,600.00**
860934	TRAFFIC MONITORING STATION (LOCATION 4)	LS	6	1	1.00	$10,000.00	$10,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$10,000.00**	**$10,000.00**
	Item Code 860934 Total No. of Proj.			**1**		**Total Amount**	**$10,000.00**
860935	TRAFFIC MONITORING STATION (LOCATION 5)	LS	6	1	1.00	$35,000.00	$35,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$35,000.00**	**$35,000.00**
	Item Code 860935 Total No. of Proj.			**1**		**Total Amount**	**$35,000.00**
860990	CLOSED CIRCUIT TELEVISION SYSTEM	LS	2	1	1.00	$48,000.00	$48,000.00
		LS	3	1	1.00	$25,000.00	$25,000.00
		LS	4	1	1.00	$200,000.00	$200,000.00
		LS	5	1	1.00	$20,000.00	$20,000.00
		LS	6	1	1.00	$25,000.00	$25,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$63,600.00**	**$318,000.00**
	Item Code 860990 Total No. of Proj.			**5**		**Total Amount**	**$318,000.00**
861088	MODIFY RAMP METERING SYSTEM	LS	3	2	2.00	$77,475.00	$154,950.00
		LS	7	11	11.00	$46,706.10	$513,767.05
		LS	8	2	2.00	$47,150.00	$94,300.00
		LS	12	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**LS**		**16**	**16.00**	**$47,813.57**	**$765,017.05**
	Item Code 861088 Total No. of Proj.			**16**		**Total Amount**	**$765,017.05**
861100	RAMP METERING SYSTEM	LS	3	3	3.00	$133,333.33	$400,000.00
		LS	6	1	1.00	$120,000.00	$120,000.00
		LS	11	1	1.00	$16,000.00	$16,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$107,200.00**	**$536,000.00**
	Item Code 861100 Total No. of Proj.			**5**		**Total Amount**	**$536,000.00**
861101	RAMP METERING SYSTEM (LOCATION 1)	LS	4	2	2.00	$90,000.00	$180,000.00
		LS	8	2	2.00	$52,500.00	$105,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
861101	RAMP METERING SYSTEM (LOCATION 1)	LS	11	2	2.00	$67,500.00	$135,000.00
		LS	12	1	1.00	$16,000.00	$16,000.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$62,285.71**	**$436,000.00**
	Item Code 861101 Total No. of Proj.			**7**		**Total Amount**	**$436,000.00**
861102	RAMP METERING SYSTEM (LOCATION 2)	LS	4	2	2.00	$47,500.00	$95,000.00
		LS	8	2	2.00	$67,500.00	$135,000.00
		LS	11	2	2.00	$76,500.00	$153,000.00
		LS	12	1	1.00	$55,000.00	$55,000.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$62,571.43**	**$438,000.00**
	Item Code 861102 Total No. of Proj.			**7**		**Total Amount**	**$438,000.00**
861103	RAMP METERING SYSTEM (LOCATION 3)	LS	4	2	2.00	$71,000.00	$142,000.00
		LS	8	1	1.00	$70,000.00	$70,000.00
		LS	11	2	2.00	$78,500.00	$157,000.00
		LS	12	1	1.00	$14,000.00	$14,000.00
	Unit Sub Total	**LS**		**6**	**6.00**	**$63,833.33**	**$383,000.00**
	Item Code 861103 Total No. of Proj.			**6**		**Total Amount**	**$383,000.00**
861104	RAMP METERING SYSTEM (LOCATION 4)	LS	4	1	1.00	$62,500.00	$62,500.00
		LS	8	1	1.00	$60,000.00	$60,000.00
		LS	12	1	1.00	$16,000.00	$16,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$46,166.67**	**$138,500.00**
	Item Code 861104 Total No. of Proj.			**3**		**Total Amount**	**$138,500.00**
861303	RELOCATE FLASHING BEACON	LS	3	1	1.00	$5,400.00	$5,400.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$5,400.00**	**$5,400.00**
	Item Code 861303 Total No. of Proj.			**1**		**Total Amount**	**$5,400.00**
861349	REMOVE EXISTING SIGNAL SYSTEM	LS	8	2	2.00	$9,000.00	$18,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$9,000.00**	**$18,000.00**
	Item Code 861349 Total No. of Proj.			**2**		**Total Amount**	**$18,000.00**
861491	MODIFY SIGNAL (LOCATION 1)	LS	11	1	1.00	$36,000.00	$36,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LS**		**1**	**1.00**	**$36,000.00**	**$36,000.00**
	Item Code 861491 Total No. of Proj.			**1**		**Total Amount**	**$36,000.00**
861492	MODIFY SIGNAL (LOCATION 2)	LS	11	1	1.00	$36,000.00	$36,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$36,000.00**	**$36,000.00**
	Item Code 861492 Total No. of Proj.			**1**		**Total Amount**	**$36,000.00**
861493	MODIFY SIGNAL (LOCATION 3)	LS	5	1	1.00	$11,000.00	$11,000.00
		LS	11	1	1.00	$36,000.00	$36,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$23,500.00**	**$47,000.00**
	Item Code 861493 Total No. of Proj.			**2**		**Total Amount**	**$47,000.00**
861494	MODIFY SIGNAL (LOCATION 4)	LS	5	1	1.00	$12,000.00	$12,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$12,000.00**	**$12,000.00**
	Item Code 861494 Total No. of Proj.			**1**		**Total Amount**	**$12,000.00**
861495	MODIFY SIGNAL (LOCATION 5)	LS	5	1	1.00	$19,000.00	$19,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$19,000.00**	**$19,000.00**
	Item Code 861495 Total No. of Proj.			**1**		**Total Amount**	**$19,000.00**
861497	MODIFY SIGNAL AND LIGHTING (LOCATION 1)	LS	5	1	1.00	$26,500.00	$26,500.00
		LS	7	2	2.00	$64,050.00	$128,100.00
		LS	10	1	1.00	$80,000.00	$80,000.00
		LS	11	1	1.00	$24,000.00	$24,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$51,720.00**	**$258,600.00**
	Item Code 861497 Total No. of Proj.			**5**		**Total Amount**	**$258,600.00**
861498	MODIFY SIGNAL AND LIGHTING (LOCATION 2)	LS	5	1	1.00	$36,500.00	$36,500.00
		LS	7	2	2.00	$64,500.00	$129,000.00
		LS	10	1	1.00	$50,000.00	$50,000.00
		LS	11	1	1.00	$24,000.00	$24,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$47,900.00**	**$239,500.00**
	Item Code 861498 Total No. of Proj.			**5**		**Total Amount**	**$239,500.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
861499	MODIFY SIGNAL AND LIGHTING (LOCATION 3)	LS	7	2	2.00	$126,203.00	$252,406.00
		LS	10	1	1.00	$10,000.00	$10,000.00
		LS	11	1	1.00	$24,000.00	$24,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$71,601.50**	**$286,406.00**
	Item Code 861499 Total No. of Proj.			**4**		**Total Amount**	**$286,406.00**
861500	MODIFY SIGNAL AND LIGHTING (LOCATION 4)	LS	10	1	1.00	$50,000.00	$50,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$50,000.00**	**$50,000.00**
	Item Code 861500 Total No. of Proj.			**1**		**Total Amount**	**$50,000.00**
861501	MODIFY SIGNAL AND LIGHTING	LS	1	1	1.00	$121,719.00	$121,719.00
		LS	3	4	4.00	$139,560.25	$558,241.00
		LS	6	1	1.00	$50,000.00	$50,000.00
		LS	7	8	8.00	$70,531.19	$564,249.55
		LS	8	4	4.00	$55,250.00	$221,000.00
		LS	9	1	1.00	$45,000.00	$45,000.00
		LS	12	2	2.00	$7,000.00	$14,000.00
	Unit Sub Total	**LS**		**21**	**21.00**	**$74,962.36**	**$1,574,209.55**
	Item Code 861501 Total No. of Proj.			**21**		**Total Amount**	**$1,574,209.55**
861502	MODIFY SIGNAL	LS	3	4	4.00	$26,025.00	$104,100.00
		LS	4	1	1.00	$7,000.00	$7,000.00
		LS	5	1	1.00	$26,364.00	$26,364.00
		LS	10	3	3.00	$22,866.67	$68,600.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$22,896.00**	**$206,064.00**
	Item Code 861502 Total No. of Proj.			**9**		**Total Amount**	**$206,064.00**
861503	MODIFY LIGHTING	LS	2	1	1.00	$2,800.00	$2,800.00
		LS	3	6	6.00	$83,075.00	$498,450.00
		LS	5	2	2.00	$30,545.26	$61,090.51
		LS	6	2	2.00	$74,098.55	$148,197.10
		LS	7	1	1.00	$740,000.00	$740,000.00
		LS	10	3	3.00	$92,366.67	$277,100.00
		LS	12	1	1.00	$50,000.00	$50,000.00
	Unit Sub Total	**LS**		**16**	**16.00**	**$111,102.35**	**$1,777,637.61**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 861503 Total No. of Proj.			**16**		**Total Amount**	**$1,777,637.61**
861504	MODIFY LIGHTING AND SIGN ILLUMINATION	LS	3	5	5.00	$219,150.00	$1,095,750.00
		LS	4	1	1.00	$40,000.00	$40,000.00
		LS	6	1	1.00	$25,000.00	$25,000.00
		LS	7	8	8.00	$242,593.75	$1,940,750.00
		LS	8	5	5.00	$85,740.00	$428,700.00
		LS	11	2	2.00	$44,500.00	$89,000.00
		LS	12	1	1.00	$18,700.00	$18,700.00
	Unit Sub Total	**LS**		**23**	**23.00**	**$158,169.57**	**$3,637,900.00**
	Item Code 861504 Total No. of Proj.			**23**		**Total Amount**	**$3,637,900.00**
861505	MODIFY SIGNAL AND LIGHTING (LOCATION 5)	LS	10	1	1.00	$10,000.00	$10,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$10,000.00**	**$10,000.00**
	Item Code 861505 Total No. of Proj.			**1**		**Total Amount**	**$10,000.00**
861506	MODIFY SIGNAL AND LIGHTING (LOCATION 6)	LS	8	1	1.00	$101,000.00	$101,000.00
		LS	10	1	1.00	$10,000.00	$10,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$55,500.00**	**$111,000.00**
	Item Code 861506 Total No. of Proj.			**2**		**Total Amount**	**$111,000.00**
861507	MODIFY SIGNAL AND LIGHTING (LOCATION 7)	LS	10	1	1.00	$80,000.00	$80,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$80,000.00**	**$80,000.00**
	Item Code 861507 Total No. of Proj.			**1**		**Total Amount**	**$80,000.00**
861508	MODIFY SIGNAL AND LIGHTING (LOCATION 8)	LS	8	1	1.00	$106,000.00	$106,000.00
		LS	10	1	1.00	$80,000.00	$80,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$93,000.00**	**$186,000.00**
	Item Code 861508 Total No. of Proj.			**2**		**Total Amount**	**$186,000.00**
861509	MODIFY SIGNAL AND LIGHTING (LOCATION 9)	LS	8	1	1.00	$110,400.00	$110,400.00
		LS	10	1	1.00	$80,000.00	$80,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$95,200.00**	**$190,400.00**
	Item Code 861509 Total No. of Proj.			**2**		**Total Amount**	**$190,400.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
862065	REPLACE PULL BOX	EA	6	1	1.00	$2,000.00	$2,000.00
		EA	12	1	6.00	$180.00	$1,080.00
	Unit Sub Total	**EA**		**2**	**7.00**	**$440.00**	**$3,080.00**
	Item Code 862065 Total No. of Proj.			**2**		**Total Amount**	**$3,080.00**
867014	12 SINGLEMODE FIBER OPTIC CABLE	M	8	1	870.00	$11.00	$9,570.00
	Unit Sub Total	**M**		**1**	**870.00**	**$11.00**	**$9,570.00**
	Item Code 867014 Total No. of Proj.			**1**		**Total Amount**	**$9,570.00**
867017	48 SINGLEMODE FIBER OPTIC CABLE	M	8	1	4,580.00	$8.00	$36,640.00
	Unit Sub Total	**M**		**1**	**4,580.00**	**$8.00**	**$36,640.00**
	Item Code 867017 Total No. of Proj.			**1**		**Total Amount**	**$36,640.00**
867130	FIBER OPTIC SPLICE CLOSURE	EA	8	1	10.00	$1,700.00	$17,000.00
	Unit Sub Total	**EA**		**1**	**10.00**	**$1,700.00**	**$17,000.00**
	Item Code 867130 Total No. of Proj.			**1**		**Total Amount**	**$17,000.00**
868007	REMOVE LIGHTING STANDARD	EA	9	1	15.00	$200.00	$3,000.00
	Unit Sub Total	**EA**		**1**	**15.00**	**$200.00**	**$3,000.00**
	Item Code 868007 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
869035	NO. 5 PULL BOX	EA	2	1	1.00	$1,175.00	$1,175.00
		EA	9	1	3.00	$650.00	$1,950.00
		EA	12	1	16.00	$620.00	$9,920.00
	Unit Sub Total	**EA**		**3**	**20.00**	**$652.25**	**$13,045.00**
	Item Code 869035 Total No. of Proj.			**3**		**Total Amount**	**$13,045.00**
869040	PULL BOX	EA	11	1	4.00	$267.67	$1,070.68
	Unit Sub Total	**EA**		**1**	**4.00**	**$267.67**	**$1,070.68**
	Item Code 869040 Total No. of Proj.			**1**		**Total Amount**	**$1,070.68**
869042	ADJUST PULL BOX	EA	3	1	3.00	$200.00	$600.00
		EA	4	1	2.00	$2,000.00	$4,000.00
		EA	5	2	14.00	$374.29	$5,240.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
869042	ADJUST PULL BOX	EA	7	1	30.00	$150.00	$4,500.00
		EA	12	1	9.00	$60.00	$540.00
	Unit Sub Total	**EA**		**6**	**58.00**	**$256.55**	**$14,880.00**
	Item Code 869042 Total No. of Proj.			**6**		**Total Amount**	**$14,880.00**
869047	SPLICE VAULT	EA	8	1	10.00	$4,000.00	$40,000.00
	Unit Sub Total	**EA**		**1**	**10.00**	**$4,000.00**	**$40,000.00**
	Item Code 869047 Total No. of Proj.			**1**		**Total Amount**	**$40,000.00**
869070	POWER AND TELEPHONE SERVICE	LS	2	1	1.00	$35,000.00	$35,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$35,000.00**	**$35,000.00**
	Item Code 869070 Total No. of Proj.			**1**		**Total Amount**	**$35,000.00**
869072	SEISMIC MONITORING SYSTEM	LS	2	1	1.00	$250,000.00	$250,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$250,000.00**	**$250,000.00**
	Item Code 869072 Total No. of Proj.			**1**		**Total Amount**	**$250,000.00**
869075	SYSTEM TESTING AND DOCUMENTATION	LS	7	3	3.00	$14,666.67	$44,000.00
		LS	8	1	1.00	$15,000.00	$15,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$14,750.00**	**$59,000.00**
	Item Code 869075 Total No. of Proj.			**4**		**Total Amount**	**$59,000.00**
869080	TRAINING	LS	3	1	1.00	$5,000.00	$5,000.00
		LS	8	1	1.00	$10,000.00	$10,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$7,500.00**	**$15,000.00**
	Item Code 869080 Total No. of Proj.			**2**		**Total Amount**	**$15,000.00**
991061	ELECTRICAL WORK	LS	2	1	1.00	$398,000.00	$398,000.00
		LS	3	1	1.00	$3,500.00	$3,500.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$200,750.00**	**$401,500.00**
	Item Code 991061 Total No. of Proj.			**2**		**Total Amount**	**$401,500.00**
994420	PICNIC TABLE WITH BENCHES	EA	11	1	4.00	$2,000.00	$8,000.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$2,000.00**	**$8,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 994420	**Total No. of Proj.**			**1**		**Total Amount**	**$8,000.00**
994425	BENCH		EA	11	1	6.00	$500.00	$3,000.00
		Unit Sub Total	**EA**		**1**	**6.00**	**$500.00**	**$3,000.00**
	Item Code 994425	**Total No. of Proj.**			**1**		**Total Amount**	**$3,000.00**
994650	BUILDING WORK		LS	1	1	1.00	$434,000.00	$434,000.00
			LS	2	4	4.00	$587,302.25	$2,349,209.00
			LS	3	4	4.00	$1,146,952.00	$4,587,808.00
			LS	4	5	5.00	$1,488,676.14	$7,443,380.70
			LS	5	1	1.00	$2,162,725.00	$2,162,725.00
			LS	6	2	2.00	$1,464,114.00	$2,928,228.00
			LS	7	1	1.00	$403,806.00	$403,806.00
			LS	8	1	1.00	$410,500.00	$410,500.00
			LS	9	2	2.00	$617,753.50	$1,235,507.00
			LS	11	1	1.00	$1,937,177.45	$1,937,177.45
			LS	12	1	1.00	$1,127,610.00	$1,127,610.00
		Unit Sub Total	**LS**		**23**	**23.00**	**$1,087,823.96**	**$25,019,951.15**
	Item Code 994650	**Total No. of Proj.**			**23**		**Total Amount**	**$25,019,951.15**
994900	DRINKING FOUNTAIN		EA	11	1	7.00	$4,950.00	$34,650.00
		Unit Sub Total	**EA**		**1**	**7.00**	**$4,950.00**	**$34,650.00**
	Item Code 994900	**Total No. of Proj.**			**1**		**Total Amount**	**$34,650.00**
994901	TRASH RECEPTACLE		EA	3	1	24.00	$604.00	$14,496.00
			EA	11	1	18.00	$1,026.00	$18,468.00
		Unit Sub Total	**EA**		**2**	**42.00**	**$784.86**	**$32,964.00**
	Item Code 994901	**Total No. of Proj.**			**2**		**Total Amount**	**$32,964.00**
994920	BICYCLE PARKING RACK		EA	11	1	8.00	$400.00	$3,200.00
		Unit Sub Total	**EA**		**1**	**8.00**	**$400.00**	**$3,200.00**
994920	BICYCLE PARKING RACK		LS	6	1	1.00	$1,200.00	$1,200.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$1,200.00**	**$1,200.00**
	Item Code 994920	**Total No. of Proj.**			**2**		**Total Amount**	**$4,400.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
994922	BICYCLE LOCKER		EA	11	1	15.00	$3,400.00	$51,000.00
		Unit Sub Total	**EA**		**1**	**15.00**	**$3,400.00**	**$51,000.00**
	Item Code 994922	**Total No. of Proj.**			**1**		**Total Amount**	**$51,000.00**
995000	BUS SHELTER		EA	5	1	4.00	$30,000.00	$120,000.00
		Unit Sub Total	**EA**		**1**	**4.00**	**$30,000.00**	**$120,000.00**
	Item Code 995000	**Total No. of Proj.**			**1**		**Total Amount**	**$120,000.00**
999990	MOBILIZATION		LS	1	26	26.00	$97,298.31	$2,529,756.00
			LS	2	11	11.00	$1,169,168.36	$12,860,852.00
			LS	3	40	40.00	$323,405.92	$12,936,236.75
			LS	4	57	57.00	$1,012,533.77	$57,714,425.07
			LS	5	19	19.00	$332,642.44	$6,320,206.30
			LS	6	18	18.00	$589,520.76	$10,611,373.60
			LS	7	88	88.00	$160,355.59	$14,111,291.86
			LS	8	30	30.00	$445,916.92	$13,377,507.50
			LS	9	3	3.00	$272,961.83	$818,885.50
			LS	10	23	23.00	$180,822.72	$4,158,922.60
			LS	11	30	30.00	$447,104.27	$13,413,128.19
			LS	12	23	23.00	$190,233.48	$4,375,370.00
		Unit Sub Total	**LS**		**368**	**368.00**	**$416,380.31**	**$153,227,955.37**
	Item Code 999990	**Total No. of Proj.**			**368**		**Total Amount**	**$153,227,955.37**

APPENDIX A

Conversion Factors From English Units to SI Units

Unit	Abbr.	Multiply:	Unit	Abbr.
Acre	ACRE	0.4046856	Hectare	HA
Calendar Day	CDAY	1	Calendar Day	CDAY
Cubic Foot	CF	0.02831685	Cubic Meter	M3
Cubic Yard	CY	0.7645549	Cubic Meter	M3
Each	EA	1	Each	EA
Gallon	GAL	3.785412	Liter	L
Hour	HR	1	Hour	H
Pound	LB	0.4535924	Kilogram	KG
Linear Foot	LF	0.3048	Meter	M
Lane Mile	LNMI	1.609344	Lane Kilometer	LNKM
Lump Sum	LS	1	Lump Sum	LS
Thousand Foot Board Measure	MFBM	2.359737	Cubic Meter	M3
Mile	MI	1.609344	Kilometer	KM
Square Foot	SQFT	0.09290304	Square Meter	M2
Square Yard	SQYD	0.8361274	Square Meter	M2
Station (100 Ft)	STA	0.3048	Station (100 m)	STA
Tablet	TAB	1	Tablet	TAB
Ton	TON	0.9071847	Tonne (1000 kg)	TONN
Track Foot	TF	1	Track Foot	TF
Working Day	WDAY	1	Working Day	WDAY

APPENDIX B

Conversion Factors From SI Units to English Units

Unit	Abbr.	Multiply:	Unit	Abbr.
Hectare	HA	2.471054	Acre	ACRE
Calendar Day	CDAY	1	Calendar Day	CDAY
Cubic Meter	M3	35.31467	Cubic Foot	CF
Cubic Meter	M3	1.307951	Cubic Yard	CY
Each	EA	1	Each	EA
Liter	L	0.2641720	Gallon	GAL
Hour	H	1	Hour	HR
Kilogram	KG	2.204623	Pound	LB
Meter	M	3.280840	Linear Foot	LF
Lane Kilometer	LNKM	0.6213712	Lane Mile	LNMI
Lump Sum	LS	1	Lump Sum	LS
Cubic Meter	M3	0.4237760	Thousand Foot Board Measure	MFBM
Kilometer	KM	0.6213712	Mile	MI
Square Meter	M2	10.76391	Square Foot	SQFT
Square Meter	M2	1.195990	Square Yard	SQYD
Station (100 m)	STA	3.280840	Station (100 Ft)	STA
Tablet	TAB	1	Tablet	TAB
Tonne (1000 kg)	TONN	1.102312	Ton	TON
Track Foot	TF	1	Track Foot	TF
Working Day	WDAY	1	Working Day	WDAY