Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Sis,Mod	89,139	7.0/24.2, R0.2/R6.0	7	13

REGISTERED CIVIL ENGINEER 10-12-09 DATE

10-20-09
PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER MICHAEL A. CONNER No. C73123 Exp. 12/31/10 CIVIL STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)

LOCATION	Co-Rte	TYPE D	TYPE G	TYPE H
		EA	EA	EA
1	Mod-139	981	13	270
TOTAL		1264		

1

TRANSVERSE WHITE STRIPE

LOCATION	Co-Rte	POSTMILE LIMITS	4" THERMOPLASTIC TRAFFIC STRIPE
		PM-PM	LF
1	Mod-139	R0.53 TO R0.59	192

THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE 2-COAT)

LOCATION	Co-Rte	POSTMILE LIMITS	DETAIL 5	DETAIL 6	DETAIL 18	DETAIL 19	DETAIL 21	DETAIL 22	DETAIL 27B	DETAIL 27C	DETAIL 21	DETAIL 29	DETAIL 38A
		PM-PM	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF
1	Mod-139	R0.23 TO R6.00		18,903		6442		5006	61,168	3224		349	286
2	Sis-89	7.00 TO 24.24	27,773		22,979		37,077		173,739	3945	476		412
SUBTOTAL			27,773	18,903	22,979	6442	37,077	5006	234,907	7169	476	349	698
TOTAL			361,799										

1

THERMOPLASTIC PAVEMENT MARKING

LOCATION	Co-Rte	PM	Lt	Mid	Rt	(N) EA	SQFT	REMARKS
1	Mod-139	R0.23	X			3	66.0	STOP
		R0.23	X				60.0	ROAD CONNECTION LIMIT LINE
		R0.23	X	X		2	30.0	TYPE IV ARROW
		R0.29	X	X		2	30.0	TYPE IV ARROW
		R0.50	X			2	44.0	STOP
		R0.50	X			2	62.0	AHEAD
		R0.70	X		X	2	44.0	STOP
		R0.70	X		X		72.0	ROAD CONNECTION LIMIT LINE
		R5.07	X			1	22.0	STOP
		R5.07	X				33.0	ROAD CONNECTION LIMIT LINE
2	Sis-89	8.03			X		47.0	ROAD CONNECTION LIMIT LINE
		8.03				1	22.0	STOP
		8.99	X		X		64.0	ROAD CONNECTION LIMIT LINE
		8.99	X		X	2	44.0	STOP
		11.14	X				35.0	ROAD CONNECTION LIMIT LINE
		11.14	X			1	22.0	STOP
		11.36	X		X		69.0	ROAD CONNECTION LIMIT LINE
		11.36	X		X	2	44.0	STOP
		13.62	X				35.0	ROAD CONNECTION LIMIT LINE
		14.45	X		X		48.0	ROAD CONNECTION LIMIT LINE
		14.45	X		X	2	44.0	STOP
		14.87	X				17.0	ROAD CONNECTION LIMIT LINE
		14.87	X			1	22.0	STOP
		15.42	X				37.0	ROAD CONNECTION LIMIT LINE
		15.42	X			1	22.0	STOP
		16.79			X		29.0	ROAD CONNECTION LIMIT LINE
		16.79			X	1	22.0	STOP
		16.80	X				31.0	ROAD CONNECTION LIMIT LINE
		16.80	X			1	22.0	STOP
		19.02	X				26.0	ROAD CONNECTION LIMIT LINE
		19.02	X			1	22.0	STOP
		21.38	X		X		57.0	ROAD CONNECTION LIMIT LINE
		21.38	X		X	2	44.0	STOP
		24.20	X		X		74.0	ROAD CONNECTION LIMIT LINE
		24.20	X		X	2	44.0	STOP
TOTAL							1406.0	

1 REVISED PER ADDENDUM No. 1, DATED DECEMBER 02, 2009

PAVEMENT DELINEATION QUANTITIES

PDQ-1

REVISED BY | DATE REVISED
MICHAEL CONNER | KARLIE J. SMITH
CALCULATED-DESIGNED BY | CHECKED BY
FUNCTIONAL SUPERVISOR
LANCE BROWN

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans MAINTENANCE

P:\proj2\02\1E860_plans\pse\21e860nc001.dgn

LAST REVISION 10-13-09 | DATE PLOTTED => 01-DEC-2009 | TIME PLOTTED => 15:25