Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
02	Tri	299	26.1/36.9	5	20

REGISTERED CIVIL ENGINEER 02-10-10 DATE

02-11-10
PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER MATTHEW R. GOWAN No. C52309 Exp. 12-31-10 CIVIL STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

NOTES:

1. (N) - NOT A SEPARATE PAY ITEM, FOR INFORMATION ONLY.
2. EXISTING UTILITY FACILITIES HAVE NOT BEEN POSITIVELY IDENTIFIED.

ROADWAY QUANTITY SUMMARY

1

POST MILE LIMITS	(N) LENGTH	(N) WIDTH	HOT IN-PLACE RECYCLING: RECYCLED ASHPHALT PAVEMENT (RECYCLED ASHPHALT PAVEMENT)	HOT IN-PLACE RECYCLING: CORRECTIVE HMA	HOT IN-PLACE RECYCLING: RECYCLING AGENT	ASPHALTIC EMULSION (FOG SEAL COAT)
PM - PM	LF	LF	SQYD	TON	TON	TON
26.16-26.50	1795	26.0				
26.50-27.00	2640	26.0-25.0				
27.00-27.44	2323	25.0				
27.44-27.45	53	25.0-26.0				
27.45-27.50	264	26.0				
27.50-27.55	264	26.0				
27.55-27.59	211	26.0-25.0				
27.59-28.07	2534	25.0	41,925	1,082	51	6
28.07-28.08	53	25.0-26.0				
28.08-28.13	264	26.0				
28.13-28.15	106	26.0-25.0				
28.15-28.50	1848	25.0-26.0				
28.50-28.55	264	26.0-25.0				
28.55-28.59	211	25.0-26.0				
28.59-28.98	2059	26.0				
28.98-29.01	158		*	*	*	*
29.01-29.40	2059	26.0-25.0	5948	154	7	1
29.40-30.22	4330		*	*	*	*
30.22-30.50	1478	25.0				
30.50-30.70	1056	25.0-26.0				
30.70-30.73	158	26.0				
30.73-30.74	53	26.0-25.0				
30.74-30.77	158	25.0				
30.77-30.98	1109	25.0-26.0				
30.98-30.99	53	26.0				
30.99-31.06	370	26.0-25.0				
31.06-31.09	158	25.0				
31.09-31.22	686	25.0-26.0				
31.22-31.23	53	26.0				
31.23-31.32	476	26.0-25.0				
31.32-31.33	53	25.0-26.0				
31.33-31.46	686	26.0				
31.46-31.48	106	26.0-25.0				
31.48-31.49	53	25.0				
31.49-31.50	53	25.0-26.0	87,505	2,260	105	7
31.50-31.98	2534	26.0				
31.98-32.01	158	26.0				
32.01-32.50	2587	26.0-25.0				
32.50-33.00	2640	25.0				
33.00-33.50	2640	25.0-24.0				
33.50-34.00	2640	24.0-25.0				
34.00-34.50	2640	25.0-26.0				
34.50-35.00	2640	26.0				
35.00-35.49	2587	26.0				
35.49-35.55	317	26.0-25.0				
35.55-35.58	158	25.0				
35.58-35.93	1848	25.0-26.0				
35.93-35.97	211	26.0				
35.97-35.98	53	26.0-25.0				
35.98-36.00	106	25.0-26.0				
36.00-36.11	581	26.0				
36.11-36.51	2112		*	*	*	*
36.51-36.89	2006	26.0	5647	146	7	1
TOTAL			141,025	3,642	170	15

*TRAFFIC STRIPE, PAVEMENT MARKERS, AND REPLACE AC SURFACING ONLY.

1 REVISED PER ADDENDUM NO.1 DATED 4/22/10

THERMOPLASTIC PAVEMENT MARKING

PM	L†	R†	EA	SQFT	REMARKS
26.50	X		1	3.0	DETAIL A
27.50	X		1	3.0	DETAIL A
28.50	X		1	3.0	DETAIL A
28.58		X	1	36.0	ROAD CONNECTION LIMIT LINE
28.58		X	1	22.0	STOP
28.64	X		1	12.0	ROAD CONNECTION LIMIT LINE
28.64	X		1	22.0	STOP
29.50	X		1	3.0	DETAIL A
30.50	X		1	3.0	DETAIL A
30.74	X		1	28.0	ROAD CONNECTION LIMIT LINE
30.74	X		1	22.0	STOP
30.98	X		1	43.0	PARKING
30.99	X		1	14.0	NO
31.45	X		1	48.0	ROAD CONNECTION LIMIT LINE
31.45	X		1	22.0	STOP
31.50	X		1	3.0	DETAIL A
32.50	X		1	3.0	DETAIL A
33.50	X		1	3.0	DETAIL A
34.50	X		1	3.0	DETAIL A
35.50	X		1	3.0	DETAIL A
36.50	X		1	3.0	DETAIL A
36.54		X	1	32.0	ROAD CONNECTION LIMIT LINE
36.54		X	1	22.0	STOP
36.87	X		1	28.0	ROAD CONNECTION LIMIT LINE
36.87	X		1	22.0	STOP
TOTAL				406.0	

PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)

POST MILE LIMITS	TYPE D	TYPE G	TYPE H
	EA	EA	EA
26.16-36.89	4240	80	292
TOTAL	4612		

THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)

POST MILE LIMITS	DETAIL 6	DETAIL 12	DETAIL 19	DETAIL 22	DETAIL 27B	DETAIL 27C	DETAIL 38
	LF	LF	LF	LF	LF	LF	LF
26.16-36.89	1796	2218	6970	48,629	113,943	1357	747
TOTAL	175,660						

RECONSTRUCT METAL BEAM GUARD RAILING

POST MILE LIMITS	SIDE	RECONSTRUCT MBGR	RECONSTRUCT TERMINAL SYSTEM
		LF	EA
34.86-35.13	R†	1076	2
35.68-35.78	R†	454	2
35.98-36.08	R†	454	2
TOTAL		1984	6

REPLACE ASPHALT CONCRETE SURFACING

POST MILE LIMITS	LENGTH (N)	WIDTH (N)	DEPTH (N)	REPLACE ASPHALT CONCRETE SURFACING
PM - PM	LF	LF	LF	CY
26.16-26.17	60	26	0.1	6
28.98-29.01	200	26	0.1	20
29.40-29.41	60	26	0.1	6
30.21-30.22	60	26	0.1	6
36.11-36.12	60	26	0.1	6
36.50-36.51	60	26	0.1	6
36.88-36.89	60	26	0.1	6
TOTAL				56

SUMMARY OF QUANTITIES

Q-1

REVISED BY | DATE REVISED
MATT GOWAN | KARLIE SMITH
CALCULATED-DESIGNED BY | CHECKED BY
FUNCTIONAL SUPERVISOR: LANCE BROWN

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans® MAINTENANCE

P:\proj2\02\2E260\maint\OE\AfterSubmittal\22e260pa001_Rev1.dgn

LAST REVISION 02-10-10 | DATE PLOTTED => 21-APR-2010 | TIME PLOTTED => 16:29