

INFORMATION HANDOUT

WATER QUALITY

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
NORTH COAST REGION

BOARD ORDER No. 2003-0017-DWQ
401 CERTIFICATION

PERMITS

STATE OF CALIFORNIA
DEPARTMENT OF FISH AND GAME

NOTIFICATION NO. 1600-2012-0082-R1

UNITED STATES ARMY CORPS OF ENGINEERS
NON-REPORTING NATIONWIDE 404 PERMIT

WATER QUALITY

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
NORTH COAST REGION

BOARD ORDER No. 2003-0017-DWQ
401 CERTIFICATION

North Coast Regional Water Quality Control Board

June 29, 2012

In the Matter of
Water Quality Certification

for the

**California Department of Transportation
Highway 3 – Hayfork Bike Lane Project
WDID No. 1A12021WNTR**

APPLICANT:	California Department of Transportation
RECEIVING WATER:	Drainage ditches and Streams
HYDROLOGIC AREA:	Trinity River Hydrologic Unit No.106.00
COUNTY:	Trinity
FILE NAME:	CDOT – Hwy 3, Hayfork Bike Lane Project
WDID No.	1A12021WNTR

BY THE EXECUTIVE OFFICER:

1. On May 3, 2012, the North Coast Regional Water Quality Control Board (Regional Water Board) received an application from the California Department of Transportation (Caltrans), requesting Federal Clean Water Act (CWA), section 401, Water Quality Certification for activities related to proposed Highway 3 Hayfork Bike Lane Project (Project). Additional information regarding project specifics was received on June 14, 2012. The proposed project will cause disturbances to waters of the United States (U.S.) and waters of the State associated with intermittent and ephemeral watercourses and wetland that are located within the Trinity River Hydrologic Unit No.106.00 (Hayfork Valley Hydrologic Sub-Area 106.25). The Regional Water Board provided public notice of the application pursuant to title 23, California Code of Regulations, section 3858 on June 7, 2012, and posted information describing the project on the Regional Water Board's website. No comments were received.

2. This project will provide a bike route and pedestrian facility on Highway 3, in the town of Hayfork, in Trinity County. To create the bike route, the highway will be widened, as needed, to provide an 8-foot paved shoulder, on both sides of the highway from Post Mile (PM) 7.3 near to Reservoir Road near PM 7.95. Bike route improvements on Highway 3 will require grading (cut and fill) in spot locations, paving in spot locations, drainage improvements, signing and striping. Bike route improvements on Trinity Street will be limited to signage only. There are four (4) drainage locations that require modification in order to construct the bike route that are subject to Clean Water Act jurisdiction. All four locations convey open waters and have connectivity downstream to Hayfork Creek a tributary to the South Fork Trinity River.
3. Caltrans has determined that the proposed project will result in 1,640 feet² of permanent impacts and 2,250 feet² to waters of the U.S. and waters of the State, for a total of approximately 3,889 feet² (0.09 acres) of impacts to waters. Caltrans proposes to off-set direct impacts to waters of the U.S. and State through on-site revegetation measures, including the enhancement of a roadside ditch with an adjacent vegetated earth berm. The project will result in an increase of approximately 0.4 acres of impervious surface (new pavement); therefore Caltrans has incorporated on-site storm water treatment BMPs which promote biofiltration to treat the pollutants and capture the increased volume in highway storm water runoff.
4. The proposed project is anticipated to be during low flow conditions between August and November 5th; however, work within waters will only be conducted in the dry season prior to October 15th. The project will result in less than one acre disturbed soil area. Caltrans will utilize Best Management Practices (BMPs) to provide erosion control and pollution prevention throughout the project area during construction. All graded areas within the project affected by the construction activities will be appropriately stabilized and/or replanted with appropriate native vegetation.
5. The applicant has applied for authorization from the U.S. Army Corps of Engineers to perform the project under their Nationwide Permits No. 14 (linear transportation projects) pursuant to Clean Water Act, section 404. Caltrans has also applied for a California Department of Fish and Game Streambed Alteration Agreement. Caltrans has determined that this project is categorically exempt from California Environmental Quality Act (CEQA) review (Statutory Exemption). In addition, Regional Water Board staff has determined that this project is categorically exempt from CEQA review (Class 1 Categorical Exemption) and anticipates filing a Notice of Exemption

6. The South Fork Trinity River is listed on the Clean Water Act section 303(d) list as impaired for sediment and temperature. In December, 1998, the U.S. EPA established sediment total maximum daily loads (TMDLs) for the South Fork Eel River and tributaries. Roads are a significant source of sediment in the watershed (directly, from surface erosion, and, indirectly, by triggering landslides. In addition, activities that impact stream bed, banks, and floodplains and reduce riparian vegetation are identified as sources contributing to increased stream temperatures. Such projects may involve removal of vegetation and/or channel alteration, and also have potential to increase sediment loads. A focus on measures to reduce sediment discharges to surface waters from roads in the watershed, and measures to avoid, minimize, and mitigate impacts on riparian zones is essential for achieving Basin Plan and CEQA compliance. Accordingly, this Order is consistent with, and implements portions of the South Fork Trinity River TMDL.
7. Pursuant to Regional Water Board Resolution R1-2004-0087, *Total Maximum Daily Load Implementation Policy Statement for Sediment-Impaired Receiving Waters within the North Coast Region* (Sediment TMDL Implementation Policy), the Executive Officer is directed to “rely on the use of all available authorities, including existing regulatory standards, and permitting and enforcement tools to more effectively and efficaciously pursue compliance with sediment-related standards by all dischargers of sediment waste.”
8. Pursuant to Regional Water Board Resolution R1-2012-0013, *Implementation of the Water Quality Objective for Temperature in the North Coast Region* (Temperature Implementation Policy), Regional Water Board staff is directed to address factors that contribute to elevated water temperatures when issuing 401 certifications or WDRs (permits) for individual projects. Any permit should be consistent with the assumptions and requirements of temperature shade load allocations in areas subject to existing temperature TMDLs, including EPA- established temperature TMDLs, as appropriate. If applicable, any permit or order should implement similar shade controls in areas listed as impaired for temperature but lacking a TMDL and region-wide as appropriate and necessary to prevent future impairments and to comply with the intrastate temperature objective.
9. The federal antidegradation policy requires that state water quality standards include an antidegradation policy consistent with the federal policy. The State Water Board established California’s antidegradation policy in State Water Board Resolution No. 68-16. Resolution No. 68-16 incorporates the federal antidegradation policy where the federal policy applies under federal law. Resolution No. 68-16 requires that existing quality of waters be maintained unless degradation is justified based on specific findings. The Regional Water Board’s Basin Plan implements, and incorporates by reference, both the State and federal antidegradation policies. This Order is consistent with applicable federal and State antidegradation policies, as it

does not authorize the discharge of increased concentrations of pollutants or increased volumes of treated wastewater, and does not otherwise authorize degradation of the waters affected by this project.

10. To ensure compliance with Water Quality Objectives within the Basin Plan, adequate wetland and riparian protection and stringent requirements to avoid, minimize, and mitigate the sediment and temperature impacts associated with the proposed project will be incorporated as enforceable conditions in this Water Quality Certification. In addition, Caltrans will be required to conduct surface water monitoring, sampling, and analysis in accordance with the conditions of the Water Quality Certification. Additionally, storm water runoff monitoring, sampling, and analysis will be conducted as required by the State Water Resources Control Board (SWRCB) National Pollutant Discharge Elimination System (NPDES) Permit for Storm Water Discharges from the State of California, Department of Transportation (Caltrans) Properties, Facilities and Activities Order No. 99 – 06 - DWQ. The surface water data collected will be utilized to assess the adequacy of BMPs during construction as well as site specific mitigation measures proposed to minimize impacts to the environment, including sediment and temperature impacts.
11. This discharge is also regulated under State Water Resources Control Board Order No. 2003-0017-DWQ, "General Waste Discharge Requirements for Dredge and Fill Discharges That Have Received State Water Quality Certification," which requires compliance with all conditions of this certification.

Receiving Waters:	Roadside ditches and streams Trinity River Hydrologic Unit No.106.00 Hayfork Valley Hydrologic Sub-Area 106.25
Filled and/or Excavated Areas:	Permanent – streams (Waters of U.S.): 0.04 acres (1,640 feet ²) Temporary – streams (Waters of U.S.): 0.051 acres (2,250 feet ²)
Total Linear Impacts:	Permanent – streams (Waters of U.S.): 147 linear feet Temporary – streams (Waters of U.S.): 375 linear feet
Dredge Volume :	None
Fill Volume :	279 cubic yards

Mitigation proposed: On-site: Restoration / enhancement of 0.051 acres (2,250 feet²) of ditches / streams (waters of U.S.)

Latitude/Longitude: 40.500 N / 123.125 W

Accordingly, based on its independent review of the record, the Regional Water Board certifies that the Caltrans – Highway 3 Hayfork Bike Lane Project (WDID No. 1A12021WNTR), as described in the application will comply with sections 301, 302, 303, 306 and 307 of the Clean Water Act, and with applicable provisions of state law, provided that the Caltrans complies with the following terms and conditions:

All conditions of this order apply to Caltrans (and all its employees) and all contractors (and their employees), sub-contractors (and their employees), and any other entity or agency that performs activities or work on the project (including the off-site mitigation lands) as related to this Water Quality Certification.

1. This certification action is subject to modification or revocation upon administrative or judicial review; including review and amendment pursuant to Water Code section 13330 and title 23, California Code of Regulations, section 3867.
2. This certification action is not intended and shall not be construed to apply to any discharge from any activity involving a hydroelectric facility requiring a Federal Energy Regulatory Commission (FERC) license or an amendment to a FERC license unless the pertinent certification application was filed pursuant to title 23, California Code of Regulations, section 3855, subdivision (b) and the application specifically identified that a FERC license or amendment to a FERC license for a hydroelectric facility was being sought.
3. The validity this certification is conditioned upon total payment of any fee required under title 23, California Code of Regulations, section 3833, and owed by the applicant.
4. All conditions required by this Order shall be included in the Plans and Specifications prepared by Caltrans for the Contractor. In addition, Caltrans shall require compliance with all conditions included in this Order in the bid contract for this project.
5. Caltrans shall provide a copy of this order and State Water Resources Control Board (SWRCB) Order No. 2003-0017-DWQ (web link referenced below) to the contractor and all subcontractors conducting the work, and require that copies remain in their possession at the work site. Caltrans shall be responsible for work conducted by its contractor or subcontractors.

6. The Regional Water Board shall be notified in writing each year at least five working days (working days are Monday – Friday) prior to the commencement of ground disturbing activities, water diversion activities or construction activities with details regarding the construction schedule, in order to allow Regional Water Board staff to be present on-site during installation and removal activities, and to answer any public inquiries that may arise regarding the project. Caltrans shall provide Regional Water Board staff access to the project site to document compliance with this order.
7. The Resident Engineer (or appropriately authorized agent) shall hold on-site water quality permit compliance meetings (similar to tailgate safety meetings) to discuss permit compliance, including instructions on how to avoid violations and procedures for reporting violations. The meetings shall be held at least every other week, before forecasted storm events, and when a new contractor or subcontractor arrives to begin work at the site. The contractors, subcontractors and their employees, as well as any inspectors or monitors assigned to the project, shall be present at the meetings. Caltrans shall maintain dated sign-in sheets for attendees at these meetings, and shall make them available to the Regional Water Board on request.
8. All activities and best management practices (BMPs) shall be implemented according to the submitted application and the conditions in this certification. BMPs for erosion, sediment, turbidity and pollutant control shall be implemented and in place at commencement of, during, and after any ground clearing activities, construction activities, or any other project activities that could result in erosion, sediment, or other pollutant discharges to waters of the State. The BMPs shall be implemented in accordance with the Caltrans Construction Site Best Management Practice Manual (CCSBMPM) and all contractors and subcontractors shall comply with the CCSBMPM. In addition, BMPs for erosion and sediment control shall be utilized year round, regardless of season or time of year. Caltrans shall stage erosion and sediment control materials at the work site. All BMPs shall be installed properly and in accordance with the manufacturer's specifications. If the project Resident Engineer elects to install alternative BMPs for use on the project, Caltrans shall submit a proposal to Regional Water Board staff for review and concurrence.
9. Caltrans shall prioritize the use of wildlife-friendly biodegradable (not photo-degradable) erosion control products wherever feasible. Caltrans shall not use or allow the use of erosion control products that contain synthetic netting for permanent erosion control (i.e. erosion control materials to be left in place for two years or after the completion date of the project). If Caltrans finds that erosion control netting or products have entrapped or harmed wildlife, personnel shall remove the netting or product and replace it with wildlife-friendly biodegradable products. Caltrans shall not use or allow the use of erosion control products that contain synthetic materials within waters of the United States or waters of the State at any time. Caltrans shall request approval from the Regional Water Board if an exception from this requirement is needed for a specific location.

10. Herbicides and pesticides shall not be used within the project. If Caltrans has a compelling case as to why herbicides and pesticides should be used, they may submit a request along with a BMP plan to the Executive Officer of the Regional Water Board for review, consideration, and concurrence.
11. Work in flowing or standing surface waters, unless otherwise proposed in the project description and approved by the Regional Water Board, is prohibited. If construction dewatering of groundwater is found to be necessary, Caltrans shall use a method of water disposal other than disposal to surface waters (such as land disposal) or Caltrans shall apply for coverage under the Low Threat Discharge Permit or an individual National Pollutant Discharge Elimination System (NPDES) Permit and receive notification of coverage to discharge to surface waters, prior to the discharge.
12. Caltrans is prohibited from discharging waste to waters of the State, unless explicitly authorized by this Order. For example, no debris, soil, silt, sand, bark, slash, sawdust, rubbish, cement or concrete or concrete washings, welding slag, oil or petroleum products, or other organic or earthen material from any construction or associated activity of whatever nature, other than that authorized by this Order, shall be allowed to enter into waters of the State. In addition, none of the materials listed above shall be placed within 150 linear feet of waters of the State or where the materials may be washed by rainfall into waters of the State.
13. Caltrans shall submit, subject to review and concurrence by the Regional Water Board staff, a dewatering and/or diversion plan that appropriately describe the dewatered or diverted areas and how those areas will be handled during construction. The diversion/dewatering plans shall be submitted no later than 30 days prior to conducting the proposed activity. Information submitted shall include the area or work to be diverted or dewatered and method of the proposed activity. All diversion or dewatering activities shall be designed to minimize the impact to waters of the State and maintain natural flows upstream and downstream. All dewatering or diversion structures shall be installed in a manner that does not cause sedimentation, siltation or erosion upstream or downstream. All dewatering or diversion structures shall be removed immediately upon completion of project activities. The in-channel work will only be conducted between May 15 and October 15. This Order does not authorize Caltrans to draft surface waters.
14. Fueling, lubrication, maintenance, storage and staging of vehicles and equipment shall be outside of waters of the U.S. and the State. Fueling, lubrication, maintenance, storage and staging of vehicles and equipment shall not result in a discharge or a threatened discharge to any waters of the State or the U.S. At no time shall Caltrans use any vehicle or equipment which leaks any substance that may impact water quality.

15. Caltrans shall implement appropriate BMPs to prevent the discharge of equipment fluids to the stream channel. The minimum requirements will include: storing hazardous materials at least 150 linear feet outside of the stream banks; checking equipment for leaks and preventing the use of equipment with leaks; pressure washing or steam cleaning equipment to remove fluid residue on any of its surfaces prior to its entering any stream channel in a manner that does not result in a discharge to waters of the State.
16. If, at any time, an unauthorized discharge to surface water (including wetlands, rivers or streams) occurs, or any water quality problem arises, the associated project activities shall cease immediately until adequate BMPs are implemented. The Regional Water Board shall be notified promptly and in no case more than 24 hours after the unauthorized discharge or water quality problem arises.
17. Caltrans and their contractor are not authorized to discharge wastewater (e.g., water that has contacted uncured concrete or cement, or asphalt) to surface waters, ground waters, or land. Wastewater may only be disposed of to a sanitary waste water collection system/facility (with authorization from the facility's owner or operator) or a properly-licensed disposal or reuse facility. If Caltrans or their contractor proposes an alternate disposal method, Caltrans or their contractor shall request authorization from the Regional Water Board. Plans to reuse or recycle wastewater require written approval from Regional Water Board staff.
18. Caltrans shall provide analysis and verification that placing non-hazardous waste or inert materials (which may include discarded product or recycled materials) will not result in degradation of water quality, human health, or the environment. All project-generated waste shall be handled, transported, and disposed in strict compliance with all applicable State and Federal laws and regulations. When operations are complete, any excess material or debris shall be removed from the work area and disposed of properly and in accordance with the Special Provisions for the project and/or Standard Specification 7-1.13, Disposal of Material Outside the Highway Right of Way. Within 30 days of disposing of materials off-site Caltrans shall submit to the Regional Water Board the satisfactory evidence provided to the Caltrans Engineer by the Contractor referenced in Standard Specification 7-1.13. In accordance with State and Federal laws and regulations, Caltrans is liable and responsible for the proper disposal of waste generated by their project.
19. All imported fill material shall be clean and free of pollutants. All fill material shall be imported from a source that has the appropriate environmental clearances and permits. The reuse of low-level contaminated solids as fill on-site shall be performed in accordance with all State and Federal policies and established guidelines and must be submitted to the Regional Water Board for review and concurrence.

20. Only clean washed spawning gravel (0.25" – 6") with a cleanliness value of at least 85, using the Cleanliness Value Test Method for California Test No. 227 will be placed in the streams. Gravel bag fabric shall be nonwoven polypropylene geotextile (or comparable polymer) and shall conform to the following requirements:
- Mass per unit area, grams per square meter, min ASTM Designation: D 5261 – 270
 - Grab tensile strength (25-mm grip), kilonewtons, min. ASTM Designation: D4632* 0.89
 - Ultraviolet stability, percent tensile strength retained after 500 hours, ASTM Designation: D4355, xenon arc lamp method 70 or appropriate test method for specific polymer
 - Gravel bags shall be between 600 mm and 800 mm in length, and between 400 mm and 500 mm in width.
 - Yarn used in construction of the gravel bags shall be as recommended by the manufacturer or bag supplier and shall be of a contrasting color. Gravel shall be between 0.5" – 4" in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials. The opening of gravel-filled bags shall be secured to prevent gravel from escaping. Gravel-filled bags shall be between 13 kg and 22 kg in mass.
 - Caltrans shall request approval from the Regional Water Board if an exception from this requirement is needed for a specific location.
21. In order to demonstrate compliance with receiving water limitations and water quality objectives surface water monitoring shall be conducted. When conducting surface water monitoring Caltrans shall establish discharge, upstream (background) and downstream monitoring locations to demonstrate compliance with applicable water quality objectives. The downstream location shall be no more than 100 feet from the discharge location.
- A. Surface water monitoring shall be conducted whenever a project activity is conducted within waters of the State (e.g. including but not limited to the installation, use or removal of stream diversions, pile installations, and cofferdams). Measurements and observations shall be collected from each sampling location four times daily.
 - B. Surface water monitoring shall be conducted immediately when any project activity has mobilized sediment or other pollutants resulting in a discharge and/or has the potential to alter background conditions within waters of the State (including but not limited to storm water runoff, concrete discharges, leaks, and spills.). The continuing frequency is contingent upon results of field measurements and applicable water quality objectives.

Surface water monitoring field measurements shall be taken for pH and turbidity. In addition, visual observations of each location shall be documented daily for each established monitoring location and monitoring event and include the estimate of flow, appearance of the discharge including color, floating or suspended matter or debris, appearance of the receiving water at the point of discharge (occurrence of erosion and scouring, turbidity, solids deposition, unusual aquatic growth, etc), and observations about the receiving water, such as the presence of aquatic life. If a project activity has reached a steady state and is stable then Caltrans may request a temporary reprieve from this condition from the Regional Water Board until an activity or discharge triggers the monitoring again.

22. Whenever, as a result of project activities (in-stream work or a discharge to receiving waters), downstream measurements exceed any water quality objective 100 feet downstream of the source(s) all necessary steps shall be taken to install, repair, and/or modify BMPs to control the source(s). The frequency of surface water monitoring shall increase to hourly and shall continue until measurements demonstrate compliance with water quality objectives for each parameter listed below and measured levels are no longer increasing as a result of project activities. In addition, the overall distance from the source(s) to the downstream extent of the exceedence of water quality objectives shall be measured.

Monitoring results shall be reported to appropriate Regional Water Board staff person by telephone within 24 hours of taking any measurements that exceed the limits detailed below (only report turbidity if it is higher than 20 NTU).

pH	<6.5 or >8.5 (any changes >0.5 units)
turbidity	20% above natural background

Monitoring results and upstream and downstream pictures within the working and/or disturbed area and discharge location shall be taken and submitted to the appropriate Regional Water Board staff within 24 hours of the incident. All other monitoring data documenting compliance with water quality objectives shall be reported on a monthly basis and is due to the Regional Water Board by the 15th of the following month.

23. Post Storm Event Reports:

- Once the project has begun ground-disturbing activities, and subsequent to a qualifying rain event that exceeds 0.5-inches of precipitation, Caltrans shall inspect the project within 24 hours and take photos of all discharge locations, and disturbed areas, including all excess materials disposal areas, in order to demonstrate that erosion control and revegetation measures are present and have been installed appropriately and are functioning effectively. A brief report containing these photos, corrective actions (if necessary), and any surface water monitoring results collected pursuant to this Order or the Construction General

Permit (SWRCB Order 2009-009 DWQ) shall be submitted to the Regional Water Board within 10 days after the end of the qualifying rain event. Inspections are required daily during extended rain events. Once the project site is stable, in a steady state (channel- ground- or vegetation-disturbing activities have ceased), and has demonstrated sufficient and effective erosion and sediment control, Caltrans may request a reprieve from this condition from the Regional Water Board. At least one post-construction inspection is required to demonstrate sufficient and effective erosion and sediment control and compliance with the Basin Plan.

- Rain events are periods of precipitation that that are separated by more than 48-hours of dry weather. Rainfall amounts may be taken from on-site rain gauges, from the nearest California Data Exchange Center station (<http://cdec.water.ca.gov>), or by a custom method or station approved by Regional Water Board staff.

24. Caltrans shall conduct enhancement and revegetation measures to 0.051 acres (2,250 feet²) of waters of the U.S. in accordance with the application for certification. Planting and enhancement actions shall be completed in the immediate fall or early winter following the completion of the construction project. Monitoring shall be conducted twice annually for at least five years to verify success criteria including 60% survival of plantings in the enhancement area. Monitoring reports must be submitted annually to the Regional Water Board on December 31st, with the first report due in 2012.

25. In the event of any violation or threatened violation of the conditions of this Order, the violation or threatened violation shall be subject to any remedies, penalties, process or sanctions as provided for under applicable state or federal law. For the purposes of section 401(d) of the Clean Water Act, the applicability of any state law authorizing remedies, penalties, process or sanctions for the violation or threatened violation constitutes a limitation necessary to assure compliance with the water quality standards and other pertinent requirements incorporated into this Order. In response to a suspected violation of any condition of this certification, the State Water Board may require the holder of any federal permit or license subject to this Order to furnish, under penalty of perjury, any technical or monitoring reports the State Water Board deems appropriate, provided that the burden, including costs, of the reports shall bear a reasonable relationship to the need for the reports and the benefits to be obtained from the reports. In response to any violation of the conditions of this Order, the Regional Water Board may add to or modify the conditions of this Order as appropriate to ensure compliance.

26. The Regional Water Board may add to or modify the conditions of this Order, as appropriate, to implement any new or revised water quality standards and implementation plans adopted or approved pursuant to the Porter-Cologne Water Quality Control Act or section 303 of the Clean Water Act.

27. This Order is not transferable. In the event of any change in control of ownership of land presently owned or controlled by the Applicant, the Applicant shall notify the successor-in-interest of the existence of this Order by letter and shall forward a copy of the letter to the Regional Water Board. The successor-in-interest must send to the Regional Water Board Executive Officer a written request for transfer of this Order to discharge dredged or fill material under this Order. The request must contain the following:
- a. requesting entity's full legal name
 - b. the state of incorporation, if a corporation
 - c. address and phone number of contact person
 - d. description of any changes to the project or confirmation that the successor-in-interest intends to implement the project as described in this Order.
28. Except as may be modified by any preceding conditions, all certification actions are contingent on: a) the discharge being limited, and all proposed revegetation, avoidance, minimization, and mitigation measures being completed, in strict compliance with Caltrans' project description and CEQA documentation, as approved herein, b) Caltrans shall construct the project in accordance with the project described in the application and the findings above, and c) compliance with all applicable water quality requirements and water quality control plans including the requirements of the Water Quality Control Plan for the North Coast Region (Basin Plan), and amendments thereto. Any change in the design or implementation of the project that would have a significant or material effect on the findings, conclusions, or conditions of this Order must be submitted to the Executive Officer of the Regional Water Board for prior review, consideration, and written concurrence. If the Regional Water Board is not notified of a significant alteration to the project, it will be considered a violation of this Order, and Caltrans may be subject to Regional Water Board enforcement actions.
29. The authorization of this certification for any dredge and fill activities expires on June 29, 2017. Conditions and monitoring requirements outlined in this Order are not subject to the expiration date outlined above, and remain in full effect and are enforceable.

30. Please contact our staff Environmental Specialist / Caltrans Liaison Jeremiah Puget of at (707) 576-2835 or jpuget@waterboards.ca.gov if you have any questions.

Original Signed By

Matthias St. John
Executive Officer

120629_JJP_ef_CDOT_Hwy3_Hayfork_BikeLane_401Cert

Web link: State Water Resources Control Board Order No. 2003-0017 -DWQ, General Waste Discharge Requirements for Dredge and Fill Discharges That Have Received State Water Quality Certification can be found at: http://www.waterboards.ca.gov/board_decisions/adopted_orders/water_quality/2003/wqo/wqo2003-0017.pdf

Original to: Mr. Andre Benoist, Caltrans – District 2, 1031 Butte Street MS 30, Redding, CA 96001

Copies to: Mr. Steve Rodgers, Caltrans – District 2, 1031 Butte Street MS 30, Redding, CA 96001

Electronic

Copies to: U.S. Army Corps of Engineers, Regulatory Functions - San Francisco District

PERMITS

STATE OF CALIFORNIA
DEPARTMENT OF FISH AND GAME

NOTIFICATION NO. 1600-2012-0082-R1

CALIFORNIA DEPARTMENT OF FISH AND GAME
NORTHERN REGION
601 LOCUST STREET
REDDING, CA 96001



STREAMBED ALTERATION AGREEMENT
NOTIFICATION No. 1600-2012-0082-R1
Ewing Gulch

CALIFORNIA DEPARTMENT OF TRANSPORTATION
HAYFORK BIKE LANE

This Streambed Alteration Agreement (Agreement) is entered into between the California Department of Fish and Game (DFG) and the California Department of Transportation (Permittee) as represented by Mr. Steve Rogers.

RECITALS

WHEREAS, pursuant to Fish and Game Code (FGC) section 1602, Permittee notified DFG on April 4, 2012 that Permittee intends to complete the project described herein.

WHEREAS, pursuant to FGC section 1603, DFG has determined that the project could substantially adversely affect existing fish or wildlife resources and has included measures in the Agreement necessary to protect those resources.

WHEREAS, Permittee has reviewed the Agreement and accepts its terms and conditions, including the measures to protect fish and wildlife resources.

NOW THEREFORE, Permittee agrees to complete the project in accordance with the Agreement.

PROJECT LOCATION

The project is located at the State Route (SR) 3 crossing of Ewing Gulch, tributary to Hayfork Creek, in the County of Trinity, State of California; Latitude 40.554341° North, Longitude 123.174006° West.

PROJECT DESCRIPTION

The project is limited to the extension of two existing 42-inch diameter corrugated metal pipe (CMP) culverts at the SR 3 crossing of Ewing Gulch (Post Mile 7.59) to accommodate construction of bicycle lanes. The culverts will be extended a total of 16 feet on the upstream side of the highway and 52 feet on the downstream side of the highway. Concrete headwalls and wingwalls will be constructed at each end of the extended pipes.

PROJECT IMPACTS

Existing fish or wildlife resources the project could substantially adversely affect include: western pond turtle (*Emys marmorata*) and foothill yellow-legged frog (*Rana boylei*), as well as other aquatic and riparian species.

The adverse effects the project could have on the fish or wildlife resources identified above include: physical disturbance of the stream channel and adjacent habitat, as well as temporary adverse effects on fish and downstream benthic invertebrate communities through sediment deposition or spills of deleterious materials.

MEASURES TO PROTECT FISH AND WILDLIFE RESOURCES

1 Administrative Measures

Permittee shall meet each administrative requirement described below.

- 1.1 Documentation at Project Site. Permittee shall make the Agreement, any extensions and amendments to the Agreement, and all related notification materials and California Environmental Quality Act (CEQA) documents, readily available at the project site at all times and shall be presented to DFG personnel, or personnel from another state, federal, or local agency upon request.
- 1.2 Providing Agreement to Persons at Project Site. Permittee shall provide copies of the Agreement and any extensions and amendments to the Agreement to all persons who will be working on the project at the project site on behalf of Permittee, including but not limited to contractors, subcontractors, inspectors, and monitors.
- 1.3 Notification of Conflicting Provisions. Permittee shall notify DFG if Permittee determines or learns that a provision in the Agreement might conflict with a provision imposed on the project by another local, state, or federal agency. In that event, DFG shall contact Permittee to resolve any conflict.
- 1.4 Project Site Entry. Permittee agrees that DFG personnel may enter the project site at any time to verify compliance with the Agreement.

2 Avoidance and Minimization Measures

To avoid or minimize adverse impacts to fish and wildlife resources identified above, Permittee shall implement each measure listed below.

PROJECT TIMING

- 2.1 All work on the stream banks or within the stream channel, shall be confined to the period commencing May 15, and ending October 15, of any year in which this

Agreement is valid, provided the stream is dry. If weather conditions permit and the stream remains dry, the Permittee may perform work within the stream channel or on the banks after October 15, provided a written request is made to the Department at least 5 days before the proposed work period variance. Written approval from the Department for the proposed work period variance must be received by the Permittee prior to the start or continuation of work after October 15.

- 2.2 If work is performed within the stream channel or on the banks after October 15, the Permittee shall do all of the following:
- a. Stage erosion and sediment control materials at the work site.
 - b. Monitor the seventy-two (72) hour forecast from the National Weather Service.
 - c. When the 72-hour forecast indicates a probability of precipitation of 60% or greater, or at the onset of any precipitation, ground disturbing activities shall cease and erosion control measures shall be implemented to stabilize exposed soils and prevent the mobilization of sediment into the stream channel or adjacent wetland or riparian areas.

HABITAT AND SPECIES PROTECTION

- 2.3 This Agreement does not authorize the take of any State threatened or endangered species. If the project could result in the "take" of a state listed threatened or endangered species, the Permittee has the responsibility to obtain from the Department, a California Endangered Species Act Permit (CESA 2081 Permit). The Department may formulate a management plan that will avoid or mitigate take. If appropriate, contact the Department CESA coordinator at (530) 225-2300.
- 2.4 Removal of existing vegetation shall not exceed the minimum necessary to complete operations. No woody riparian vegetation shall be removed from the stream channel or banks.
- 2.5 Construction equipment and personnel shall be restricted to the limits of the work area as shown on the project plans. No construction activities or habitat disturbance is authorized beyond this area.
- 2.6 Take of migratory birds will be avoided during construction activities. In no case shall active nests with eggs or young be removed during construction.

PETROLEUM, CHEMICAL AND OTHER POLLUTANTS

- 2.7 All construction-related materials and equipment shall be stored in designated staging areas located outside of the floodplain unless approved in writing by DFG.

- 2.8 Refueling and vehicle maintenance shall be performed at least 100 feet from streams or other water bodies unless approved in writing by DFG.
- 2.9 No equipment or machinery shall be operated within any flowing stream.
- 2.10 Any equipment or vehicles driven and/or operated within or adjacent to the stream channel shall be checked and maintained daily to prevent leaks of materials that, if introduced to water, could be deleterious to aquatic life, wildlife, or riparian habitat.
- 2.11 Stationary equipment such as motors, pumps, generators, and welders that contain deleterious materials, located adjacent to the stream channel shall be positioned over drip pans.
- 2.12 No debris, soil, silt, sand, bark, slash, sawdust, rubbish, cement or concrete or washings thereof, asphalt, paint or other coating material, oil or petroleum products or other organic or earthen material from any construction, or associated activity of whatever nature shall be allowed to enter into, or placed where it may be washed by rainfall or runoff into, waters of the State. When operations are completed, any excess materials or debris shall be removed from the work area. No rubbish shall be deposited within 150 feet of the high water mark of any stream or lake.

EROSION AND SEDIMENT CONTROL

- 2.13 The project shall at all time feature adequate erosion and sediment control devices to prevent the degradation of water quality.
- 2.14 Soils exposed by project operations shall be treated to prevent sediment runoff and transport. Erosion control measures shall include the proper installation and maintenance of approved Best Management Practices (BMPs) and may include applications of seed, certified weed-free straw, compost, fiber, commercial fertilizer, stabilizing emulsion and mulch, or combinations thereof.
- 2.15 Soils adjacent to the stream channel that are exposed by project operations shall be adequately stabilized when rainfall is reasonably expected during construction, and immediately upon completion of construction, to prevent the mobilization of such sediment into the stream channel or adjacent riparian areas. National Weather Service forecasts shall be monitored by the Permittee to determine the chance of precipitation.
- 2.16 Following construction, all disturbed upland areas shall be stabilized and reseeded with an erosion control mix consisting of regionally appropriate, native grass and forb species.

CONTACT INFORMATION

Any communication that Permittee or DFG submits to the other shall be in writing and any communication or documentation shall be delivered to the address below by U.S. mail, fax, or email, or to such other address as Permittee or DFG specifies by written notice to the other.

To Permittee:

Mr. Steve Rogers
Department of Transportation
Post Office Box 496073
Redding, CA 96049-6073
Fax: (530) 225-2455
Email: steve.rogers@dot.ca.gov

To DFG:

Department of Fish and Game
Northern Region
601 Locust Street
Redding, CA 96001
Attn: Lake and Streambed Alteration Program – Craig Martz
Notification #1600-2012-0082-R1
Fax: (530) 225-2267
Email: cmartz@dfg.ca.gov

LIABILITY

Permittee shall be solely liable for any violations of the Agreement, whether committed by Permittee or any person acting on behalf of Permittee, including its officers, employees, representatives, agents or contractors and subcontractors, to complete the project or any activity related to it that the Agreement authorizes.

This Agreement does not constitute DFG's endorsement of, or require Permittee to proceed with the project. The decision to proceed with the project is Permittee's alone.

SUSPENSION AND REVOCATION

DFG may suspend or revoke in its entirety the Agreement if it determines that Permittee or any person acting on behalf of Permittee, including its officers, employees, representatives, agents, or contractors and subcontractors, is not in compliance with the Agreement.

Before DFG suspends or revokes the Agreement, it shall provide Permittee written notice by certified or registered mail that it intends to suspend or revoke. The notice shall state the reason(s) for the proposed suspension or revocation, provide Permittee an opportunity to correct any deficiency before DFG suspends or revokes the Agreement, and include instructions to Permittee, if necessary, including but not limited to a directive to immediately cease the specific activity or activities that caused DFG to issue the notice.

ENFORCEMENT

Nothing in the Agreement precludes DFG from pursuing an enforcement action against Permittee instead of, or in addition to, suspending or revoking the Agreement.

Nothing in the Agreement limits or otherwise affects DFG's enforcement authority or that of its enforcement personnel.

OTHER LEGAL OBLIGATIONS

This Agreement does not relieve Permittee or any person acting on behalf of Permittee, including its officers, employees, representatives, agents, or contractors and subcontractors, from obtaining any other permits or authorizations that might be required under other federal, state, or local laws or regulations before beginning the project or an activity related to it.

This Agreement does not relieve Permittee or any person acting on behalf of Permittee, including its officers, employees, representatives, agents, or contractors and subcontractors, from complying with other applicable statutes in the FGC including, but not limited to, FGC sections 2050 et seq. (threatened and endangered species), 3503 (bird nests and eggs), 3503.5 (birds of prey), 5650 (water pollution), 5652 (refuse disposal into water), 5901 (fish passage), 5937 (sufficient water for fish), and 5948 (obstruction of stream).

Nothing in the Agreement authorizes Permittee or any person acting on behalf of Permittee, including its officers, employees, representatives, agents, or contractors and subcontractors, to trespass.

AMENDMENT

DFG may amend the Agreement at any time during its term if DFG determines the amendment is necessary to protect an existing fish or wildlife resource.

Permittee may amend the Agreement at any time during its term, provided the amendment is mutually agreed to in writing by DFG and Permittee. To request an amendment, Permittee shall submit to DFG a completed DFG "Request to Amend Lake or Streambed Alteration" form and include with the completed form payment of the

corresponding amendment fee identified in DFG's current fee schedule (see Cal. Code Regs., tit. 14, § 699.5).

TRANSFER AND ASSIGNMENT

This Agreement may not be transferred or assigned to another entity, and any purported transfer or assignment of the Agreement to another entity shall not be valid or effective, unless the transfer or assignment is requested by Permittee in writing, as specified below, and thereafter DFG approves the transfer or assignment in writing.

The transfer or assignment of the Agreement to another entity shall constitute a minor amendment, and therefore to request a transfer or assignment, Permittee shall submit to DFG a completed DFG "Request to Amend Lake or Streambed Alteration" form and include with the completed form payment of the minor amendment fee identified in DFG's current fee schedule (see Cal. Code Regs., tit. 14, § 699.5).

EXTENSIONS

In accordance with FGC section 1605(b), Permittee may request one extension of the Agreement, provided the request is made prior to the expiration of the Agreement's term. To request an extension, Permittee shall submit to DFG a completed DFG "Request to Extend Lake or Streambed Alteration" form and include with the completed form payment of the extension fee identified in DFG's current fee schedule (see Cal. Code Regs., tit. 14, § 699.5). DFG shall process the extension request in accordance with FGC 1605(b) through (e).

If Permittee fails to submit a request to extend the Agreement prior to its expiration, Permittee must submit a new notification and notification fee before beginning or continuing the project the Agreement covers (Fish & G. Code, § 1605, subd. (f)).

EFFECTIVE DATE

The Agreement becomes effective on the date of DFG's signature, which shall be: 1) after Permittee's signature; 2) after DFG complies with all applicable requirements under the California Environmental Quality Act (CEQA); and 3) after payment of the applicable FGC section 711.4 filing fee listed at

http://www.dfg.ca.gov/habcon/ceqa/ceqa_changes.html.

TERM

This Agreement shall expire on December 31, 2014, unless it is terminated or extended before then. All provisions in the Agreement shall remain in force throughout its term. Permittee shall remain responsible for implementing any provisions specified herein to

protect fish and wildlife resources after the Agreement expires or is terminated, as FGC section 1605(a) (2) requires.

AUTHORITY

If the person signing the Agreement (signatory) is doing so as a representative of Permittee, the signatory hereby acknowledges that he or she is doing so on Permittee's behalf and represents and warrants that he or she has the authority to legally bind Permittee to the provisions herein.

AUTHORIZATION

This Agreement authorizes only the project described herein. If Permittee begins or completes a project different from the project the Agreement authorizes, Permittee may be subject to civil or criminal prosecution for failing to notify DFG in accordance with FGC section 1602.

CONCURRENCE

The undersigned accepts and agrees to comply with all provisions contained herein.

FOR DEPARTMENT OF TRANSPORTATION



Steve Rogers
Project Manager

5-21-12

Date

FOR DEPARTMENT OF FISH AND GAME



Curt Babcock
Habitat Conservation Program Manager

5/22/12

Date

PERMITS

UNITED STATES ARMY CORPS OF ENGINEERS
NON-REPORTING NATIONWIDE 14 404 PERMIT



U S Army Corps of
Engineers
Sacramento District

Nationwide Permit Summary

33 CFR Part 330; Issuance of Nationwide Permits - March 19, 2007 includes corrections of May 8, 2007 and addition of regional conditions December 2007

14. Linear Transportation Projects. Activities required for the construction, expansion, modification, or improvement of linear transportation projects (e.g., roads, highways, railways, trails, airport runways, and taxiways) in waters of the United States. For linear transportation projects in non-tidal waters, the discharge cannot cause the loss of greater than 1/2-acre of waters of the United States. ~~For linear transportation projects in tidal waters, the discharge cannot cause the loss of greater than 1/3-acre of waters of the United States.~~ Any stream channel modification, including bank stabilization, is limited to the minimum necessary to construct or protect the linear transportation project; such modifications must be in the immediate vicinity of the project.

This NWP also authorizes temporary structures, fills, and work necessary to construct the linear transportation project. Appropriate measures must be taken to maintain normal downstream flows and minimize flooding to the maximum extent practicable, when temporary structures, work, and discharges, including cofferdams, are necessary for construction activities, access fills, or dewatering of construction sites. Temporary fills must consist of materials, and be placed in a manner, that will not be eroded by expected high flows. Temporary fills must be removed in their entirety and the affected areas returned to pre-construction elevations. The areas affected by temporary fills must be revegetated, as appropriate.

This NWP cannot be used to authorize non-linear features commonly associated with transportation projects, such as vehicle maintenance or storage buildings, parking lots, train stations, or aircraft hangars.

Notification: The permittee must submit a pre-construction notification to the district engineer prior to commencing the activity if: (1) the loss of waters of the United States exceeds 1/10 acre; or (2) there is a discharge in a special aquatic site, including wetlands. (See general condition 27.) (Sections 10 and 404)

Note: ~~Some discharges for the construction of farm roads or forest roads, or temporary roads for moving mining equipment, may qualify for an exemption under Section 404(f) of the Clean Water Act (see 33 CFR 323.4)~~

A. Nationwide Permit General Conditions

Note: To qualify for NWP authorization, the prospective permittee must comply with the following general conditions, as appropriate, in addition to any regional or case-specific conditions imposed by the division engineer or district engineer. Prospective permittees should contact the appropriate Corps district office to determine if regional conditions have been imposed on an NWP. Prospective permittees should also contact

the appropriate Corps district office to determine the status of Clean Water Act Section 401 water quality certification and/or Coastal Zone Management Act consistency for an NWP.

1. ~~Navigation.~~

~~(a) No activity may cause more than a minimal adverse effect on navigation.~~

~~(b) Any safety lights and signals prescribed by the U.S. Coast Guard, through regulations or otherwise, must be installed and maintained at the permittee's expense on authorized facilities in navigable waters of the United States.~~

~~(c) The permittee understands and agrees that, if future operations by the United States require the removal, relocation, or other alteration, of the structure or work herein authorized, or if, in the opinion of the Secretary of the Army or his authorized representative, said structure or work shall cause unreasonable obstruction to the free navigation of the navigable waters, the permittee will be required, upon due notice from the Corps of Engineers, to remove, relocate, or alter the structural work or obstructions caused thereby, without expense to the United States. No claim shall be made against the United States on account of any such removal or alteration.~~

2. Aquatic Life Movements. No activity may substantially disrupt the necessary life cycle movements of those species of aquatic life indigenous to the waterbody, including those species that normally migrate through the area, unless the activity's primary purpose is to impound water. Culverts placed in streams must be installed to maintain low flow conditions.

~~3. Spawning Areas.~~ Activities in spawning areas during spawning seasons must be avoided to the maximum extent practicable. ~~Activities that result in the physical destruction (e.g., through excavation, fill, or downstream smothering by substantial turbidity) of an important spawning area are not authorized.~~

~~4. Migratory Bird Breeding Areas.~~ Activities in waters of the United States that serve as breeding areas for migratory birds must be avoided to the maximum extent practicable.

~~5. Shellfish Beds.~~ No activity may occur in areas of concentrated shellfish populations, unless the activity is directly related to a shellfish harvesting activity authorized by NWPs 4 and 48.

6. Suitable Material. No activity may use unsuitable material (e.g., trash, debris, car bodies, asphalt, etc.). Material used for construction or discharged must be free from toxic pollutants in toxic amounts (see Section 307 of the Clean Water Act).

~~7. Water Supply Intakes.~~ No activity may occur in the proximity of a public water supply intake, except where the activity is for the repair or improvement of public water supply intake structures or adjacent bank stabilization.

8. Adverse Effects From Impoundments. If the activity creates an impoundment of water, adverse effects to the aquatic system due to accelerating the passage of water, and/or

restricting its flow must be minimized to the maximum extent practicable.

9. Management of Water Flows. To the maximum extent practicable, the pre-construction course, condition, capacity, and location of open waters must be maintained for each activity, including stream channelization and storm water management activities, except as provided below. The activity must be constructed to withstand expected high flows. The activity must not restrict or impede the passage of normal or high flows, unless the primary purpose of the activity is to impound water or manage high flows. The activity may alter the pre-construction course, condition, capacity, and location of open waters if it benefits the aquatic environment (e.g., stream restoration or relocation activities).

10. Fills Within 100-Year Floodplains. The activity must comply with applicable FEMA approved state or local floodplain management requirements.

11. Equipment. Heavy equipment working in wetlands or mudflats must be placed on mats, or other measures must be taken to minimize soil disturbance.

12. Soil Erosion and Sediment Controls. Appropriate soil erosion and sediment controls must be used and maintained in effective operating condition during construction, and all exposed soil and other fills, as well as any work below the ordinary high water mark or high tide line, must be permanently stabilized at the earliest practicable date. Permittees are encouraged to perform work within waters of the United States during periods of low-flow or no-flow.

13. Removal of Temporary Fills. Temporary fills must be removed in their entirety and the affected areas returned to pre-construction elevations. The affected areas must be revegetated, as appropriate.

14. Proper Maintenance. Any authorized structure or fill shall be properly maintained, including maintenance to ensure public safety.

15. Wild and Scenic Rivers. No activity may occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a "study river" for possible inclusion in the system while the river is in an official study status, unless the appropriate Federal agency with direct management responsibility for such river, has determined in writing that the proposed activity will not adversely affect the Wild and Scenic River designation or study status. Information on Wild and Scenic Rivers may be obtained from the appropriate Federal land management agency in the area (e.g., National Park Service, U.S. Forest Service, Bureau of Land Management, U.S. Fish and Wildlife Service).

16. Tribal Rights. No activity or its operation may impair reserved tribal rights, including, but not limited to, reserved water rights and treaty fishing and hunting rights.

17. Endangered Species.

(a) No activity is authorized under any NWP which is likely to jeopardize the continued existence of a threatened or endangered species or a species proposed for such designation, as identified under the Federal Endangered Species Act (ESA), or which will destroy or adversely modify the critical habitat of such species. No

~~activity is authorized under any NWP which "may affect" a listed species or critical habitat, unless Section 7 consultation addressing the effects of the proposed activity has been completed.~~

(b) ~~Federal agencies should follow their own procedures for complying with the requirements of the ESA. Federal permittees must provide the district engineer with the appropriate documentation to demonstrate compliance with those requirements.~~

(c) ~~Non-federal permittees shall notify the district engineer if any listed species or designated critical habitat might be affected or is in the vicinity of the project, or if the project is located in designated critical habitat, and shall not begin work on the activity until notified by the district engineer that the requirements of the ESA have been satisfied and that the activity is authorized. For activities that might affect Federally-listed endangered or threatened species or designated critical habitat, the pre-construction notification must include the name(s) of the endangered or threatened species that may be affected by the proposed work or that utilize the designated critical habitat that may be affected by the proposed work. The district engineer will determine whether the proposed activity "may affect" or will have "no effect" to listed species and designated critical habitat and will notify the non-Federal applicant of the Corps' determination within 45 days of receipt of a complete pre-construction notification. In cases where the non-Federal applicant has identified listed species or critical habitat that might be affected or is in the vicinity of the project, and has so notified the Corps, the applicant shall not begin work until the Corps has provided notification the proposed activities will have "no effect" on listed species or critical habitat, or until Section 7 consultation has been completed.~~

(d) ~~As a result of formal or informal consultation with the FWS or NMFS the district engineer may add species-specific regional endangered species conditions to the NWPs.~~

(e) ~~Authorization of an activity by a NWP does not authorize the "take" of a threatened or endangered species as defined under the ESA. In the absence of separate authorization (e.g., an ESA Section 10 Permit, a Biological Opinion with "incidental take" provisions, etc.) from the U.S. FWS or the NMFS, both lethal and non-lethal "takes" of protected species are in violation of the ESA. Information on the location of threatened and endangered species and their critical habitat can be obtained directly from the offices of the U.S. FWS and NMFS or their world wide Web pages at <http://www.fws.gov/> and <http://www.noaa.gov/fisheries.html> respectively.~~

18. Historic Properties.

(a) ~~In cases where the district engineer determines that the activity may affect properties listed, or eligible for listing, in the National Register of Historic Places, the activity is not authorized, until the requirements of Section 106 of the National Historic Preservation Act (NHPA) have been satisfied.~~

~~□ (b) Federal permittees should follow their own procedures for complying with the requirements of Section 106 of the National Historic Preservation Act. Federal permittees must provide the district engineer with the appropriate documentation to demonstrate compliance with those requirements.~~

~~□ (c) Non federal permittees must submit a pre-construction notification to the district engineer if the authorized activity may have the potential to cause effects to any historic properties listed, determined to be eligible for listing on, or potentially eligible for listing on the National Register of Historic Places, including previously unidentified properties. For such activities, the pre-construction notification must state which historic properties may be affected by the proposed work or include a vicinity map indicating the location of the historic properties or the potential for the presence of historic properties. Assistance regarding information on the location of or potential for the presence of historic resources can be sought from the State Historic Preservation Officer or Tribal Historic Preservation Officer, as appropriate, and the National Register of Historic Places (see 33 CFR 330.4(g)). The district engineer shall make a reasonable and good faith effort to carry out appropriate identification efforts, which may include background research, consultation, oral history interviews, sample field investigation, and field survey. Based on the information submitted and these efforts, the district engineer shall determine whether the proposed activity has the potential to cause an effect on the historic properties. Where the non-Federal applicant has identified historic properties which the activity may have the potential to cause effects and so notified the Corps, the non-Federal applicant shall not begin the activity until notified by the district engineer either that the activity has no potential to cause effects or that consultation under Section 106 of the NHPA has been completed.~~

~~□ (d) The district engineer will notify the prospective permittee within 45 days of receipt of a complete pre-construction notification whether NHPA Section 106 consultation is required. Section 106 consultation is not required when the Corps determines that the activity does not have the potential to cause effects on historic properties (see 36 CFR §800.3(a)). If NHPA section 106 consultation is required and will occur, the district engineer will notify the non-Federal applicant that he or she cannot begin work until Section 106 consultation is completed.~~

~~□ (e) Prospective permittees should be aware that section 110k of the NHPA (16 U.S.C. 470h-2(k)) prevents the Corps from granting a permit or other assistance to an applicant who, with intent to avoid the requirements of Section 106 of the NHPA, has intentionally significantly adversely affected a historic property to which the permit would relate, or having legal power to prevent it, allowed such significant adverse effect to occur, unless the Corps, after consultation with the Advisory Council on Historic Preservation (ACHP), determines that circumstances justify granting such assistance despite the adverse effect created or permitted by the applicant. If circumstances justify granting the assistance, the Corps is required to~~

~~notify the ACHP and provide documentation specifying the circumstances, explaining the degree of damage to the integrity of any historic properties affected, and proposed mitigation. This documentation must include any views obtained from the applicant, SHPO/THPO, appropriate Indian tribes if the undertaking occurs on or affects historic properties on tribal lands or affects properties of interest to those tribes, and other parties known to have a legitimate interest in the impacts to the permitted activity on historic properties.~~

~~□ 19. Designated Critical Resource Waters. Critical resource waters include, NOAA designated marine sanctuaries, National Estuarine Research Reserves, state natural heritage sites, and outstanding national resource waters or other waters officially designated by a state as having particular environmental or ecological significance and identified by the district engineer after notice and opportunity for public comment. The district engineer may also designate additional critical resource waters after notice and opportunity for comment.~~

~~□ (a) Discharges of dredged or fill material into waters of the United States are not authorized by NWP's 7, 12, 14, 16, 17, 21, 29, 31, 35, 39, 40, 42, 43, 44, 49, and 50 for any activity within, or directly affecting, critical resource waters, including wetlands adjacent to such waters.~~

~~□ (b) For NWP's 3, 8, 10, 13, 15, 18, 19, 22, 23, 25, 27, 28, 30, 33, 34, 36, 37, and 38, notification is required in accordance with general condition 27, for any activity proposed in the designated critical resource waters including wetlands adjacent to those waters. The district engineer may authorize activities under these NWP's only after it is determined that the impacts to the critical resource waters will be no more than minimal.~~

~~□ 20 Mitigation. The district engineer will consider the following factors when determining appropriate and practicable mitigation necessary to ensure that adverse effects on the aquatic environment are minimal:~~

~~□ (a) The activity must be designed and constructed to avoid and minimize adverse effects, both temporary and permanent, to waters of the United States to the maximum extent practicable at the project site (i.e., on-site).~~

~~□ (b) Mitigation in all its forms (avoiding, minimizing, rectifying, reducing, or compensating) will be required to the extent necessary to ensure that the adverse effects to the aquatic environment are minimal.~~

~~□ (c) Compensatory mitigation at a minimum one-for-one ratio will be required for all wetland losses that exceed 1/10 acre and require pre-construction notification, unless the district engineer determines in writing that some other form of mitigation would be more environmentally appropriate and provides a project-specific waiver of this requirement. For wetland losses of 1/10 acre or less that require pre-construction notification, the district engineer may determine on a case-by-case basis that compensatory mitigation is required to ensure that the activity results in minimal adverse effects on the~~

~~aquatic environment. Since the likelihood of success is greater and the impacts to potentially valuable uplands are reduced, wetland restoration should be the first compensatory mitigation option considered.~~

~~□ (d) For losses of streams or other open waters that require pre-construction notification, the district engineer may require compensatory mitigation, such as stream restoration, to ensure that the activity results in minimal adverse effects on the aquatic environment.~~

~~□ (e) Compensatory mitigation will not be used to increase the acreage losses allowed by the acreage limits of the NWP. For example, if an NWP has an acreage limit of 1/2 acre, it cannot be used to authorize any project resulting in the loss of greater than 1/2 acre of waters of the United States, even if compensatory mitigation is provided that replaces or restores some of the lost waters. However, compensatory mitigation can and should be used, as necessary, to ensure that a project already meeting the established acreage limits also satisfies the minimal impact requirement associated with the NWP.~~

~~□ (f) Compensatory mitigation plans for projects in or near streams or other open waters will normally include a requirement for the establishment, maintenance, and legal protection (e.g., conservation easements) of riparian areas next to open waters. In some cases, riparian areas may be the only compensatory mitigation required. Riparian areas should consist of native species. The width of the required riparian area will address documented water quality or aquatic habitat loss concerns. Normally, the riparian area will be 25 to 50 feet wide on each side of the stream, but the district engineer may require slightly wider riparian areas to address documented water quality or habitat loss concerns. Where both wetlands and open waters exist on the project site, the district engineer will determine the appropriate compensatory mitigation (e.g., riparian areas and/or wetlands compensation) based on what is best for the aquatic environment on a watershed basis. In cases where riparian areas are determined to be the most appropriate form of compensatory mitigation, the district engineer may waive or reduce the requirement to provide wetland compensatory mitigation for wetland losses.~~

~~□ (g) Permittees may propose the use of mitigation banks, in-lieu fee arrangements or separate activity-specific compensatory mitigation. In all cases, the mitigation provisions will specify the party responsible for accomplishing and/or complying with the mitigation plan.~~

~~□ (h) Where certain functions and services of waters of the United States are permanently adversely affected, such as the conversion of a forested or scrub-shrub wetland to a herbaceous wetland in a permanently maintained utility line right-of-way, mitigation may be required to reduce the adverse effects of the project to the minimal level.~~

~~□ **21. Water Quality.** Where States and authorized Tribes, or EPA where applicable, have not previously certified compliance of an NWP with CWA Section 401, individual 401 Water Quality Certification must be obtained or waived (see 33 CFR~~

~~330.4(e)). The district engineer or State or Tribe may require additional water quality management measures to ensure that the authorized activity does not result in more than minimal degradation of water quality.~~

~~□ **22. Coastal Zone Management.** In coastal states where an NWP has not previously received a state coastal zone management consistency concurrence, an individual state coastal zone management consistency concurrence must be obtained, or a presumption of concurrence must occur (see 33 CFR 330.4(d)). The district engineer or a State may require additional measures to ensure that the authorized activity is consistent with state coastal zone management requirements.~~

~~□ **23. Regional and Case-By-Case Conditions.** The activity must comply with any regional conditions that may have been added by the Division Engineer (see 33 CFR 330.4(e)) and with any case-specific conditions added by the Corps or by the state, Indian Tribe, or U.S. EPA in its section 401 Water Quality Certification, or by the state in its Coastal Zone Management Act consistency determination.~~

~~□ **24. Use of Multiple Nationwide Permits.** The use of more than one NWP for a single and complete project is prohibited, except when the acreage loss of waters of the United States authorized by the NWP does not exceed the acreage limit of the NWP with the highest specified acreage limit. For example, if a road crossing over tidal waters is constructed under NWP 14, with associated bank stabilization authorized by NWP 13, the maximum acreage loss of waters of the United States for the total project cannot exceed 1/3 acre.~~

~~□ **25. Transfer of Nationwide Permit Verifications.** If the permittee sells the property associated with a nationwide permit verification, the permittee may transfer the nationwide permit verification to the new owner by submitting a letter to the appropriate Corps district office to validate the transfer. A copy of the nationwide permit verification must be attached to the letter, and the letter must contain the following statement and signature:~~

~~“When the structures or work authorized by this nationwide permit are still in existence at the time the property is transferred, the terms and conditions of this nationwide permit, including any special conditions, will continue to be binding on the new owner(s) of the property. To validate the transfer of this nationwide permit and the associated liabilities associated with compliance with its terms and conditions, have the transferee sign and date below.”~~

~~_____~~
(Transferee)

~~_____~~
(Date)

~~□ **26. Compliance Certification.** Each permittee who received an NWP verification from the Corps must submit a signed certification regarding the completed work and any required mitigation. The certification form must be forwarded by the Corps with the NWP verification letter and will include:~~

(a) ~~A statement that the authorized work was done in accordance with the NWP authorization, including any general or specific conditions;~~

(b) ~~A statement that any required mitigation was completed in accordance with the permit conditions; and~~

(c) ~~The signature of the permittee certifying the completion of the work and mitigation.~~

27. ~~Pre-Construction Notification.~~

(a) ~~**Timing.** Where required by the terms of the NWP, the prospective permittee must notify the district engineer by submitting a pre-construction notification (PCN) as early as possible. The district engineer must determine if the PCN is complete within 30 calendar days of the date of receipt and, as a general rule, will request additional information necessary to make the PCN complete only once. However, if the prospective permittee does not provide all of the requested information, then the district engineer will notify the prospective permittee that the PCN is still incomplete and the PCN review process will not commence until all of the requested information has been received by the district engineer. The prospective permittee shall not begin the activity until either:~~

(1) ~~He or she is notified in writing by the district engineer that the activity may proceed under the NWP with any special conditions imposed by the district or division engineer; or~~

(2) ~~Forty-five calendar days have passed from the district engineer's receipt of the complete PCN and the prospective permittee has not received written notice from the district or division engineer. However, if the permittee was required to notify the Corps pursuant to general condition 17 that listed species or critical habitat might be affected or in the vicinity of the project, or to notify the Corps pursuant to general condition 18 that the activity may have the potential to cause effects to historic properties, the permittee cannot begin the activity until receiving written notification from the Corps that is "no effect" on listed species or "no potential to cause effects" on historic properties, or that any consultation required under Section 7 of the Endangered Species Act (see 33 CFR 330.4(f)) and/or Section 106 of the National Historic Preservation (see 33 CFR 330.4(g)) is completed. Also, work cannot begin under NWPs 21, 49, or 50 until the permittee has received written approval from the Corps. If the proposed activity requires a written waiver to exceed specified limits of an NWP, the permittee cannot begin the activity until the district engineer issues the waiver. If the district or division engineer notifies the permittee in writing that an individual permit is required within 45 calendar days of receipt of a complete PCN, the permittee cannot begin the activity until an individual permit has been obtained. Subsequently, the permittee's right to proceed under the NWP may be modified, suspended, or revoked only in accordance with the procedure set forth in 33 CFR 330.5(d)(2).~~

(b) ~~**Contents of Pre-Construction Notification:** The PCN must be in writing and include the following information:~~

(1) ~~Name, address and telephone numbers of the prospective permittee;~~

(2) ~~Location of the proposed project;~~

(3) ~~A description of the proposed project; the project's purpose; direct and indirect adverse environmental effects the project would cause; any other NWP(s), regional general permit(s), or individual permit(s) used or intended to be used to authorize any part of the proposed project or any related activity. The description should be sufficiently detailed to allow the district engineer to determine that the adverse effects of the project will be minimal and to determine the need for compensatory mitigation. Sketches should be provided when necessary to show that the activity complies with the terms of the NWP. (Sketches usually clarify the project and when provided result in a quicker decision.);~~

(4) ~~The PCN must include a delineation of special aquatic sites and other waters of the United States on the project site. Wetland delineations must be prepared in accordance with the current method required by the Corps. The permittee may ask the Corps to delineate the special aquatic sites and other waters of the United States, but there may be a delay if the Corps does the delineation, especially if the project site is large or contains many waters of the United States. Furthermore, the 45-day period will not start until the delineation has been submitted to or completed by the Corps, where appropriate;~~

(5) ~~If the proposed activity will result in the loss of greater than 1/10 acre of wetlands and a PCN is required, the prospective permittee must submit a statement describing how the mitigation requirement will be satisfied. As an alternative, the prospective permittee may submit a conceptual or detailed mitigation plan.~~

(6) ~~If any listed species or designated critical habitat might be affected or is in the vicinity of the project, or if the project is located in designated critical habitat, for non-Federal applicants the PCN must include the name(s) of those endangered or threatened species that might be affected by the proposed work or utilize the designated critical habitat that may be affected by the proposed work. Federal applicants must provide documentation demonstrating compliance with the Endangered Species Act; and~~

(7) ~~For an activity that may affect a historic property listed on, determined to be eligible for listing on, or potentially eligible for listing on, the National Register of Historic Places, for non-Federal applicants the PCN must state which historic property may be affected by the proposed work or include a vicinity map indicating the location of the historic~~

~~property. Federal applicants must provide documentation demonstrating compliance with Section 106 of the National Historic Preservation Act.~~

~~□ (c) Form of Pre-Construction Notification: The standard individual permit application form (Form ENG 4345) may be used, but the completed application form must clearly indicate that it is a PCN and must include all of the information required in paragraphs (b)(1) through (7) of this general condition. A letter containing the required information may also be used.~~

~~□ (d) Agency Coordination:~~

~~□ (1) The district engineer will consider any comments from Federal and state agencies concerning the proposed activity's compliance with the terms and conditions of the NWP and the need for mitigation to reduce the project's adverse environmental effects to a minimal level.~~

~~□ (2) For all NWP 48 activities requiring pre-construction notification and for other NWP activities requiring pre-construction notification to the district engineer that result in the loss of greater than 1/2 acre of waters of the United States, the district engineer will immediately provide (e.g., via facsimile transmission, overnight mail, or other expeditious manner) a copy of the PCN to the appropriate Federal or state offices (U.S. FWS, state natural resource or water quality agency, EPA, State Historic Preservation Officer (SHPO) or Tribal Historic Preservation Office (THPO), and, if appropriate, the NMFS). With the exception of NWP 37, these agencies will then have 10 calendar days from the date the material is transmitted to telephone or fax the district engineer notice that they intend to provide substantive, site-specific comments. If so contacted by an agency, the district engineer will wait an additional 15 calendar days before making a decision on the pre-construction notification. The district engineer will fully consider agency comments received within the specified time frame, but will provide no response to the resource agency, except as provided below. The district engineer will indicate in the administrative record associated with each pre-construction notification that the resource agencies' concerns were considered. For NWP 37, the emergency watershed protection and rehabilitation activity may proceed immediately in cases where there is an unacceptable hazard to life or a significant loss of property or economic hardship will occur. The district engineer will consider any comments received to decide whether the NWP 37 authorization should be modified, suspended, or revoked in accordance with the procedures at 33 CFR 330.5.~~

~~□ (3) In cases of where the prospective permittee is not a Federal agency, the district engineer will provide a response to NMFS within 30 calendar days of receipt of any Essential Fish Habitat conservation recommendations, as required by Section 305(b)(4)(B) of the Magnuson-Stevens Fishery Conservation and Management Act.~~

~~□ (4) Applicants are encouraged to provide the Corps multiple copies of pre-construction notifications to expedite agency coordination.~~

~~□ (5) For NWP 48 activities that require reporting, the district engineer will provide a copy of each report within 10 calendar days of receipt to the appropriate regional office of the NMFS.~~

~~□ (e) In reviewing the PCN for the proposed activity, the district engineer will determine whether the activity authorized by the NWP will result in more than minimal individual or cumulative adverse environmental effects or may be contrary to the public interest. If the proposed activity requires a PCN and will result in a loss of greater than 1/10 acre of wetlands, the prospective permittee should submit a mitigation proposal with the PCN. Applicants may also propose compensatory mitigation for projects with smaller impacts. The district engineer will consider any proposed compensatory mitigation the applicant has included in the proposal in determining whether the net adverse environmental effects to the aquatic environment of the proposed work are minimal. The compensatory mitigation proposal may be either conceptual or detailed. If the district engineer determines that the activity complies with the terms and conditions of the NWP and that the adverse effects on the aquatic environment are minimal, after considering mitigation, the district engineer will notify the permittee and include any conditions the district engineer deems necessary. The district engineer must approve any compensatory mitigation proposal before the permittee commences work. If the prospective permittee elects to submit a compensatory mitigation plan with the PCN, the district engineer will expeditiously review the proposed compensatory mitigation plan. The district engineer must review the plan within 45 calendar days of receiving a complete PCN and determine whether the proposed mitigation would ensure no more than minimal adverse effects on the aquatic environment. If the net adverse effects of the project on the aquatic environment (after consideration of the compensatory mitigation proposal) are determined by the district engineer to be minimal, the district engineer will provide a timely written response to the applicant. The response will state that the project can proceed under the terms and conditions of the NWP.~~

~~If the district engineer determines that the adverse effects of the proposed work are more than minimal, then the district engineer will notify the applicant either: (1) That the project does not qualify for authorization under the NWP and instruct the applicant on the procedures to seek authorization under an individual permit; (2) that the project is authorized under the NWP subject to the applicant's submission of a mitigation plan that would reduce the adverse effects on the aquatic environment to the minimal level; or (3) that the project is authorized under the NWP with specific modifications or conditions. Where the district engineer determines that mitigation is required to ensure no more than minimal adverse effects occur to the aquatic environment, the activity will be authorized within the 45-day PCN period. The authorization will include the necessary conceptual or specific mitigation or a requirement that the applicant~~

~~submit a mitigation plan that would reduce the adverse effects on the aquatic environment to the minimal level. When mitigation is required, no work in waters of the United States may occur until the district engineer has approved a specific mitigation plan.~~

(a) 28. Single and Complete Project. The activity must be a single and complete project. The same NWP cannot be used more than once for the same single and complete project.

B. Regional Conditions:

I. Sacramento District (All States, except Colorado)

~~1. When pre-construction notification (PCN) is required, the prospective permittee shall notify the Sacramento District in accordance with General Condition 27 using either the South Pacific Division Preconstruction Notification (PCN) Checklist or a completed application form (ENG Form 4345). In addition, the PCN shall include:~~

~~a. A written statement explaining how the activity has been designed to avoid and minimize adverse effects, both temporary and permanent, to waters of the United States;~~

~~b. Drawings, including plan and cross-section views, clearly depicting the location, size and dimensions of the proposed activity. The drawings shall contain a title block, legend and scale, amount (in cubic yards) and size (in acreage) of fill in Corps jurisdiction, including both permanent and temporary fills/structures. The ordinary high water mark or, if tidal waters, the high tide line should be shown (in feet), based on National Geodetic Vertical Datum (NGVD) or other appropriate referenced elevation; and~~

~~c. Pre-project color photographs of the project site taken from designated locations documented on the plan drawing.~~

~~2. The permittee shall complete compensatory mitigation required by special conditions of the NWP verification before or concurrent with construction of the authorized activity, except when specifically determined to be impracticable by the Sacramento District. When project mitigation involves use of a mitigation bank or in-lieu fee program, payment shall be made before commencing construction.~~

~~3. The permittee shall record the NWP verification with the Registrar of Deeds or other appropriate official charged with the responsibility for maintaining records of title to or interest in real property against areas (1) designated to be preserved as part of mitigation for authorized impacts, including any associated covenants or restrictions, or (2) where structures such as boat ramps or docks, marinas, piers, and permanently moored vessels will be constructed in or adjacent to navigable waters (Section 10 and Section 404). The recordation shall also include a map showing the surveyed location of the authorized structure and any associated areas preserved to minimize or compensate for project impacts.~~

~~4. The permittee shall place wetlands, other aquatic areas, and any vegetative buffers preserved as part of mitigation for impacts into a separate "preserve" parcel prior to discharging~~

~~dredged or fill material into waters of the United States, except where specifically determined to be impracticable by the Sacramento District. Permanent legal protection shall be established for all preserve parcels, following Sacramento District approval of the legal instrument.~~

~~5. The permittee shall allow Corps representatives to inspect the authorized activity and any mitigation areas at any time deemed necessary to determine compliance with the terms and conditions of the NWP verification. The permittee will be notified in advance of an inspection.~~

~~6. For NWPs 29, 39, 40, 42, 43, 44, and 46, requests to waive the 300 linear foot limitation for intermittent or ephemeral waters of the U.S. shall include an evaluation of functions and services provided by the waterbody taking into account the watershed, measures to be implemented to avoid and minimize impacts, other measures to avoid and minimize that were found to be impracticable, and a mitigation plan for offsetting impacts.~~

~~7. Road crossings shall be designed to ensure fish passage, especially for anadromous fisheries. Permittees shall employ bridge designs that span the stream or river, utilize pier or pile supported structures, or involve large bottomless culverts with a natural streambed, where the substrate and streamflow conditions approximate existing channel conditions. Approach fills in waters of the United States below the ordinary high water mark are not authorized under the NWPs, except where avoidance has specifically been determined to be impracticable by the Sacramento District.~~

~~8. For NWP 12, clay blocks, bentonite, or other suitable material shall be used to seal the trench to prevent the utility line from draining waters of the United States, including wetlands.~~

~~9. For NWP 13, bank stabilization shall include the use of vegetation or other biotechnical design to the maximum extent practicable. Activities involving hard armoring of the bank toe or slope requires submission of a PCN per General Condition 27.~~

~~10. For NWP 23, the PCN shall include a copy of the signed Categorical Exclusion document and final agency determinations regarding compliance with Section 7 of the Endangered Species Act, Essential Fish Habitat under the Magnussen-Stevens Act, and Section 106 of the National Historic Preservation Act.~~

~~11. For NWP 44, the discharge shall not cause the loss of more than 300 linear feet of streambed. For intermittent and ephemeral streams, the 300 linear foot limit may be waived in writing by the Sacramento District. This NWP does not authorize discharges in waters of the United States supporting anadromous fisheries.~~

~~12. For NWPs 29 and 39, channelization or relocation of intermittent or perennial drainage, is not authorized, except when, as determined by the Sacramento District, the relocation would result in a net increase in functions of the aquatic ecosystem within the watershed.~~

~~13. For NWP 33, temporary fills for construction access in waters of the United States supporting fisheries shall be accomplished with clean, washed spawning quality gravels where practicable as determined by the Sacramento District, in consultation with appropriate federal and state wildlife agencies.~~

~~14. For NWP 46, the discharge shall not cause the loss of greater than 0.5 acres of waters of the United States or the loss of more than 300 linear feet of ditch, unless this 300-foot linear foot limit is waived in writing by the Sacramento District.~~

~~15. For NWPs 29, 39, 40, 42, and 43, upland vegetated buffers shall be established and maintained in perpetuity, to the maximum extent practicable, next to all preserved open waters, streams and wetlands including created, restored, enhanced or preserved waters of the U.S., consistent with General Condition 20. Except in unusual circumstances, vegetated buffers shall be at least 50 feet in width.~~

~~16. All NWPs except 3, 6, 20, 27, 32, 38, and 47, are revoked for activities in histosols and fens and in wetlands contiguous with fens. Fens are defined as slope wetlands with a histie epipedon that are hydrologically supported by groundwater. Fens are normally saturated throughout the growing season, although they may not be during drought conditions. For NWPs 3, 6, 20, 27, 32, and 38, prospective permittees shall submit a PCN to the Sacramento District in accordance with General Condition 27.~~

~~17. For all NWPs, when activities are proposed within 100 feet of the point of groundwater discharge of a natural spring, prospective permittees shall submit a PCN to the Sacramento District in accordance with General Condition 27. A spring source is defined as any location where ground water emanates from a point in the ground. For purposes of this condition, springs do not include seeps or other discharges which lack a defined channel.~~

~~H. California Only~~

~~1. In the Lake Tahoe Basin, all NWPs are revoked. Activities in this area shall be authorized under Regional General Permit 16 or through an individual permit.~~

~~2. In the Primary and Secondary Zones of the Legal Delta, NWPs 29 and 39 are revoked. New development activities in the Legal Delta will be reviewed through the Corps' standard permit process.~~

~~III. Nevada Only~~

~~1. In the Lake Tahoe Basin, all NWPs are revoked. Activities in this area shall be authorized under Regional General Permit 16 or through an individual permit.~~

~~IV. Utah Only~~

~~1. For all NWPs, except NWP 47, prospective permittees shall submit a PCN in accordance with General Condition 27 for any activity, in waters of the United States, below 4217 feet mean sea level (msl) adjacent to the Great Salt Lake and below 4500 feet msl adjacent to Utah Lake.~~

~~2. A PCN is required for all bank stabilization activities in a perennial stream that would affect more than 100 linear feet of stream~~

~~3. For NWP 27, facilities for controlling stormwater runoff, construction of water parks such as kayak courses, and use of grout or concrete to construct in-stream structures are not authorized. A PCN is required for all projects exceeding 1500 linear feet as measured on the stream thalweg, using in-stream structures exceeding 50 cubic yards per structure and/or incorporating grade control structures exceeding 1-foot vertical~~

~~drop. For any stream restoration project, the post-project stream sinuosity shall be appropriate to the geomorphology of the surrounding area and shall be equal to, or greater than, pre-project sinuosity. Sinuosity is defined as the ratio of stream length to project reach length. Structures shall allow the passage of aquatic organisms, recreational water craft or other navigational activities unless specifically waived in writing by the District Engineer.~~

~~V. Colorado Only~~

~~1. Final Regional Conditions Applicable to Specific Nationwide Permits within Colorado.~~

~~a. Nationwide Permit Nos. 12 and 14, Utility Line Activities and Linear Transportation Projects. In the Colorado River Basin, utility line and road activities crossing perennial water or special aquatic sites require notification to the District Engineer in accordance with General Condition 27 (Pre-Construction Notification).~~

~~b. Nationwide Permit No. 13 Bank Stabilization. In Colorado, bank stabilization activities necessary for erosion prevention in streams that average less than 20 feet in width (measured between the ordinary high water marks) are limited to the placement of no more than 1/4 cubic yard of suitable fill* material per running foot below the plane of the ordinary high water mark. Activities greater than 1/4 cubic yard may be authorized if the permittee notifies the District Engineer in accordance with General Condition 27 (Pre-Construction Notification) and the Corps determines the adverse environmental effects are minimal. [* See (g) for definition of Suitable Fill]~~

~~e. Nationwide Permit No. 27 Aquatic Habitat Restoration, Establishment, and Enhancement Activities.~~

~~(1) For activities that include a fishery enhancement component, the Corps will send the Pre-Construction Notification to the Colorado Division of Wildlife (CDOW) for review. In accordance with General Condition 27 (Pre-Construction Notification), CDOW will have 10 days from the receipt of Corps notification to indicate that they will be commenting on the proposed project. CDOW will then have an additional 15 days after the initial 10-day period to provide those comments. If CDOW raises concerns, the applicant may either modify their plan, in coordination with CDOW, or apply for a standard individual permit.~~

~~(2) For activities involving the length of a stream, the post-project stream sinuosity will not be significantly reduced, unless it is demonstrated that the reduction in sinuosity is consistent with the natural morphological evolution of the stream (sinuosity is the ratio of stream length to project reach length).~~

~~(3) Structures will allow the upstream and downstream passage of aquatic organisms, including fish native to the reach, as well as recreational water craft or other navigational activities, unless specifically waived in writing by the District Engineer. The use of grout and/or concrete in~~

~~building structures is not authorized by this nationwide permit.~~

~~(4) The construction of water parks (i.e., kayak courses) and flood control projects are not authorized by this nationwide permit.~~

~~d. Nationwide Permits Nos. 29 and 39; Residential Developments and Commercial and Institutional Developments. A copy of the existing FEMA/locally approved floodplain map must be submitted with the Pre-Construction Notification. When reviewing proposed developments, the Corps will utilize the most accurate and reliable FEMA/locally approved pre-project floodplain mapping, not post-project floodplain mapping based on a CLOMR or LOMR. However, the Corps will accept revisions to existing floodplain mapping if the revisions resolve inaccuracies in the original floodplain mapping and if the revisions accurately reflect pre-project conditions.~~

~~2. Final Regional Conditions Applicable to All Nationwide Permits within Colorado~~

~~e. Removal of Temporary Fills. General Condition 13 (Removal of Temporary Fills) is amended by adding the following: When temporary fills are placed in wetlands in Colorado, a horizontal marker (i.e. fabric, certified weed-free straw, etc.) must be used to delineate the existing ground elevation of wetlands that will be temporarily filled during construction.~~

~~f. Spawning Areas. General Condition 3 (Spawning Areas) is amended by adding the following: In Colorado, all Designated Critical Resource Waters (see enclosure 1) are considered important spawning areas. Therefore, in accordance with General Condition 19 (Designated Critical Resource Waters), the discharge of dredged or fill material is not authorized by the following nationwide permits in these waters: NWP 7, 12, 14, 16, 17, 21, 29, 31, 35, 39, 40, 42, 43, 44, 49, and 50. In addition, in accordance with General Condition 27 (Pre-Construction Notification), notification to the District Engineer is required for use of the following nationwide permits in these waters: NWP 3, 8, 10, 13, 15, 18, 19, 22, 23, 25, 27, 28, 30, 33, 34, 36, 37 and 38".~~

~~g. Suitable Fill. In Colorado, use of broken concrete as fill material requires notification to the District Engineer in accordance with General Condition 27 (Pre-Construction Notification). Permittees must demonstrate that soft engineering methods utilizing native or non-manmade materials are not practicable (with respect to cost, existing technology, and logistics), before broken concrete is allowed as suitable fill. Use of broken concrete with exposed rebar is prohibited in perennial waters and special aquatic sites.~~

~~h. Invasive Aquatic Species. General Condition 11 is amended by adding the following condition for work in perennial or intermittent waters of the United States: If heavy equipment is used for the subject project that was previously working in another stream, river, lake, pond, or wetland within 10 days of initiating work, one the~~

~~following procedures is necessary to prevent the spread of New Zealand Mud Snails and other aquatic hitchhikers:~~

~~(1) Remove all mud and debris from equipment (tracks, turrets, buckets, drags, teeth, etc.) and keep the equipment dry for 10 days. OR~~

~~(2) Remove all mud and debris from Equipment (tracks, turrets, buckets, drags, teeth, etc.) and spray/soak equipment with either a 1:1 solution of Formula 409 Household Cleaner and water, or a solution of Sparquat 256 (5 ounces Sparquat per gallon of water). Treated equipment must be kept moist for at least 10 minutes. OR~~

~~(3) Remove all mud and debris from equipment (tracks, turrets, buckets, drags, teeth, etc.) and spray/soak equipment with water greater than 120 degrees F for at least 10 minutes.~~

~~3. Final Regional Conditions for Revocation/Special Notification Specific to Certain Geographic Areas~~

~~i. Fens: All Nationwide permits, except permit Nos. 3, 6, 20, 27, 32, 38 and 47, are revoked in fens and wetlands adjacent to fens. Use of nationwide permit Nos. 3, 20, 27 and 38, requires notification to the District Engineer, in accordance with General Condition 27 (Pre-Construction Notification), and the permittee may not begin the activity until the Corps determines the adverse environmental effects are minimal. The following defines a fen:~~

~~Fen soils (histosols) are normally saturated throughout the growing season, although they may not be during drought conditions. The primary source of hydrology for fens is groundwater. Histosols are defined in accordance with the U.S. Department of Agriculture, Natural Resources Conservation Service publications on Keys to Soil Taxonomy and Field Indicators of Hydric Soils in the United States (<http://soils.usda.gov/technical/classification/taxonomy>).~~

~~j. Springs: Within the state of Colorado, all NWP, except permit 47 (original 'C'), require preconstruction notification pursuant to General Condition 27 for discharges of dredged or fill material within 100 feet of the point of groundwater discharge of natural springs. A spring source is defined as any location where groundwater emanates from a point in the ground. For purposes of this regional condition, springs do not include seeps or other discharges which do not have a defined channel.~~

~~4. Additional Information~~

~~The following provides additional information regarding minimization of impacts and compliance with existing general Conditions:~~

~~a. Permittees are reminded of the existing General Condition No. 6 which prohibits the use of unsuitable material. Organic debris, building waste, asphalt, car bodies, and trash are not suitable material. Also, General Condition 12 requires appropriate erosion and sediment controls (i.e. all fills must be permanently stabilized to~~

~~prevent erosion and siltation into waters and wetlands at the earliest practicable date). Streambed material or other small aggregate material placed along a bank as stabilization will not meet General Condition 12. Also, use of erosion control mats that contain plastic netting may not meet General Condition 12 if deemed harmful to wildlife.~~

~~b. Designated Critical Resource Waters in Colorado. In Colorado, a list of designated Critical Resource Waters has been published in accordance with General Condition 19 (Designated Critical Resource Waters). This list will be published on the Albuquerque District Regulatory home page (<http://www.spa.usace.army.mil/reg/>)~~

~~e. Federally Listed Threatened and Endangered Species. General condition 17 requires that not federal permittees notify the District Engineer if any listed species or designated critical habitat might be affected or is in the vicinity of the project. Information on such species, to include occurrence by county in Colorado, may be found at the following U.S. Fish and Wildlife Service website: http://www.fws.gov/mountain%2Dprairie/endspp/name%20county_search.htm~~

C. Further Information

1. District Engineers have authority to determine if an activity complies with the terms and conditions of an NWP.
2. NWPs do not obviate the need to obtain other federal, state, or local permits, approvals, or authorizations required by law.
3. NWPs do not grant any property rights or exclusive privileges.
4. NWPs do not authorize any injury to the property or rights of others.
5. NWPs do not authorize interference with any existing or proposed Federal project.

D. Definitions

Best management practices (BMPs): Policies, practices, procedures, or structures implemented to mitigate the adverse environmental effects on surface water quality resulting from development. BMPs are categorized as structural or non-structural.

Compensatory mitigation: The restoration, establishment (creation), enhancement, or preservation of aquatic resources for the purpose of compensating for unavoidable adverse impacts which remain after all appropriate and practicable avoidance and minimization has been achieved.

Currently serviceable: Useable as is or with some maintenance, but not so degraded as to essentially require reconstruction.

Discharge: The term “discharge” means any discharge of dredged or fill material.

Enhancement: The manipulation of the physical, chemical, or biological characteristics of an aquatic resource to heighten, intensify, or improve a specific aquatic resource function(s). Enhancement results in the gain of selected aquatic resource function(s), but may also lead to a decline in other aquatic

resource function(s). Enhancement does not result in a gain in aquatic resource area.

Ephemeral stream: An ephemeral stream has flowing water only during, and for a short duration after, precipitation events in a typical year. Ephemeral stream beds are located above the water table year-round. Groundwater is not a source of water for the stream. Runoff from rainfall is the primary source of water for stream flow.

Establishment (creation): The manipulation of the physical, chemical, or biological characteristics present to develop an aquatic resource that did not previously exist at an upland site. Establishment results in a gain in aquatic resource area.

Historic Property: Any prehistoric or historic district, site (including archaeological site), building, structure, or other object included in, or eligible for inclusion in, the National Register of Historic Places maintained by the Secretary of the Interior. This term includes artifacts, records, and remains that are related to and located within such properties. The term includes properties of traditional religious and cultural importance to an Indian tribe or Native Hawaiian organization and that meet the National Register criteria (36 CFR part 60).

Independent utility: A test to determine what constitutes a single and complete project in the Corps regulatory program. A project is considered to have independent utility if it would be constructed absent the construction of other projects in the project area. Portions of a multi-phase project that depend upon other phases of the project do not have independent utility. Phases of a project that would be constructed even if the other phases were not built can be considered as separate single and complete projects with independent utility.

Intermittent stream: An intermittent stream has flowing water during certain times of the year, when groundwater provides water for stream flow. During dry periods, intermittent streams may not have flowing water. Runoff from rainfall is a supplemental source of water for stream flow.

Loss of waters of the United States: Waters of the United States that are permanently adversely affected by filling, flooding, excavation, or drainage because of the regulated activity. Permanent adverse effects include permanent discharges of dredged or fill material that change an aquatic area to dry land, increase the bottom elevation of a waterbody, or change the use of a waterbody. The acreage of loss of waters of the United States is a threshold measurement of the impact to jurisdictional waters for determining whether a project may qualify for an NWP; it is not a net threshold that is calculated after considering compensatory mitigation that may be used to offset losses of aquatic functions and services. The loss of stream bed includes the linear feet of stream bed that is filled or excavated. Waters of the United States temporarily filled, flooded, excavated, or drained, but restored to pre-construction contours and elevations after construction, are not included in the measurement of loss of waters of the United States. Impacts resulting from activities eligible for exemptions under Section 404(f) of the Clean Water Act are not considered when calculating the loss of waters of the United States.

Non-tidal wetland: A non-tidal wetland is a wetland that is not subject to the ebb and flow of tidal waters. The definition of a wetland can be found at 33 CFR 328.3(b). Non-tidal wetlands

contiguous to tidal waters are located landward of the high tide line (i.e., spring high tide line).

Open water: For purposes of the NWP, an open water is any area that in a year with normal patterns of precipitation has water flowing or standing above ground to the extent that an ordinary high water mark can be determined. Aquatic vegetation within the area of standing or flowing water is either non-emergent, sparse, or absent. Vegetated shallows are considered to be open waters. Examples of “open waters” include rivers, streams, lakes, and ponds.

Ordinary High Water Mark: An ordinary high water mark is a line on the shore established by the fluctuations of water and indicated by physical characteristics, or by other appropriate means that consider the characteristics of the surrounding areas (see 33 CFR 328.3(e)).

Perennial stream: A perennial stream has flowing water year-round during a typical year. The water table is located above the stream bed for most of the year. Groundwater is the primary source of water for stream flow. Runoff from rainfall is a supplemental source of water for stream flow.

Practicable: Available and capable of being done after taking into consideration cost, existing technology, and logistics in light of overall project purposes.

Pre-construction notification: A request submitted by the project proponent to the Corps for confirmation that a particular activity is authorized by nationwide permit. The request may be a permit application, letter, or similar document that includes information about the proposed work and its anticipated environmental effects. Pre-construction notification may be required by the terms and conditions of a nationwide permit, or by regional conditions. A pre-construction notification may be voluntarily submitted in cases where pre-construction notification is not required and the project proponent wants confirmation that the activity is authorized by nationwide permit.

Preservation: The removal of a threat to, or preventing the decline of, aquatic resources by an action in or near those aquatic resources. This term includes activities commonly associated with the protection and maintenance of aquatic resources through the implementation of appropriate legal and physical mechanisms. Preservation does not result in a gain of aquatic resource area or functions.

Re-establishment: The manipulation of the physical, chemical, or biological characteristics of a site with the goal of returning natural/historic functions to a former aquatic resource. Re-establishment results in rebuilding a former aquatic resource and results in a gain in aquatic resource area.

Rehabilitation: The manipulation of the physical, chemical, or biological characteristics of a site with the goal of repairing natural/historic functions to a degraded aquatic resource. Rehabilitation results in a gain in aquatic resource function, but does not result in a gain in aquatic resource area.

Restoration: The manipulation of the physical, chemical, or biological characteristics of a site with the goal of returning natural/historic functions to a former or degraded aquatic resource. For the purpose of tracking net gains in aquatic resource area, restoration is divided into two categories: re-establishment and rehabilitation.

Riffle and pool complex: Riffle and pool complexes are special aquatic sites under the 404(b)(1) Guidelines. Riffle and pool complexes sometimes characterize steep gradient sections of streams. Such stream sections are recognizable by their hydraulic characteristics. The rapid movement of water over a coarse substrate in riffles results in a rough flow, a turbulent surface, and high dissolved oxygen levels in the water. Pools are deeper areas associated with riffles. A slower stream velocity, a streaming flow, a smooth surface, and a finer substrate characterize pools.

Riparian areas: Riparian areas are lands adjacent to streams, lakes, and estuarine-marine shorelines. Riparian areas are transitional between terrestrial and aquatic ecosystems, through which surface and subsurface hydrology connects waterbodies with their adjacent uplands. Riparian areas provide a variety of ecological functions and services and help improve or maintain local water quality. (See general condition 20.)

Shellfish seeding: The placement of shellfish seed and/or suitable substrate to increase shellfish production. Shellfish seed consists of immature individual shellfish or individual shellfish attached to shells or shell fragments (i.e., spat on shell). Suitable substrate may consist of shellfish shells, shell fragments, or other appropriate materials placed into waters for shellfish habitat.

Single and complete project: The term “single and complete project” is defined at 33 CFR 330.2(i) as the total project proposed or accomplished by one owner/developer or partnership or other association of owners/developers. A single and complete project must have independent utility (see definition). For linear projects, a “single and complete project” is all crossings of a single water of the United States (i.e., a single waterbody) at a specific location. For linear projects crossing a single waterbody several times at separate and distant locations, each crossing is considered a single and complete project. However, individual channels in a braided stream or river, or individual arms of a large, irregularly shaped wetland or lake, etc., are not separate waterbodies, and crossings of such features cannot be considered separately.

Stormwater management: Stormwater management is the mechanism for controlling stormwater runoff for the purposes of reducing downstream erosion, water quality degradation, and flooding and mitigating the adverse effects of changes in land use on the aquatic environment.

Stormwater management facilities: Stormwater management facilities are those facilities, including but not limited to, stormwater retention and detention ponds and best management practices, which retain water for a period of time to control runoff and/or improve the quality (i.e., by reducing the concentration of nutrients, sediments, hazardous substances and other pollutants) of stormwater runoff.

Stream bed: The substrate of the stream channel between the ordinary high water marks. The substrate may be bedrock or inorganic particles that range in size from clay to boulders. Wetlands contiguous to the stream bed, but outside of the ordinary high water marks, are not considered part of the stream bed.

Stream channelization: The manipulation of a stream’s course, condition, capacity, or location that causes more than minimal

interruption of normal stream processes. A channelized stream remains a water of the United States.

Structure: An object that is arranged in a definite pattern of organization. Examples of structures include, without limitation, any pier, boat dock, boat ramp, wharf, dolphin, weir, boom, breakwater, bulkhead, revetment, riprap, jetty, artificial island, artificial reef, permanent mooring structure, power transmission line, permanently moored floating vessel, piling, aid to navigation, or any other manmade obstacle or obstruction.

Tidal wetland: A tidal wetland is a wetland (i.e., water of the United States) that is inundated by tidal waters. The definitions of a wetland and tidal waters can be found at 33 CFR 328.3(b) and 33 CFR 328.3(f), respectively. Tidal waters rise and fall in a predictable and measurable rhythm or cycle due to the gravitational pulls of the moon and sun. Tidal waters end where the rise and fall of the water surface can no longer be practically measured in a predictable rhythm due to masking by other waters, wind, or other effects. Tidal wetlands are located channelward of the high tide line, which is defined at 33 CFR 328.3(d).

Vegetated shallows: Vegetated shallows are special aquatic sites under the 404(b)(1) Guidelines. They are areas that are permanently inundated and under normal circumstances have rooted aquatic vegetation, such as seagrasses in marine and estuarine systems and a variety of vascular rooted plants in freshwater systems.

Waterbody: For purposes of the NWPs, a waterbody is a jurisdictional water of the United States that, during a year with normal patterns of precipitation, has water flowing or standing above ground to the extent that an ordinary high water mark (OHWM) or other indicators of jurisdiction can be determined, as well as any wetland area (see 33 CFR 328.3(b)). If a jurisdictional wetland is adjacent--meaning bordering, contiguous, or neighboring--to a jurisdictional waterbody displaying an OHWM or other indicators of jurisdiction, that waterbody and its adjacent wetlands are considered together as a single aquatic unit (see 33 CFR 328.4(c)(2)). Examples of "waterbodies" include streams, rivers, lakes, ponds, and wetlands.