

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER
1727 30th Street MS-43
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
TTY 711



*Flex your power!
Be energy efficient!*

December 6, 2011

03-Yub-20, 70-0.8/R2.0, 14.4/15.0
03-0A5804
Project ID 0300020139
NH-X115(010)E

Addendum No. 4

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN YUBA COUNTY IN MARYSVILLE ON ROUTE 20 FROM F STREET TO BUCHANAN STREET AND ON ROUTE 70 FROM 6TH STREET TO 0.2 MILE SOUTH OF BINNEY JUNCTION UNDERPASS.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Tuesday, December 13, 2011.

This addendum is being issued to revise the Notice to Bidders and Special Provisions.

In the Special Provisions, Section 4, "BEGINNING OF WORK, TIME OF COMPLETION, AND LIQUIDATED DAMAGES," is revised as attached.

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the third paragraph is revised as follows:

"One-time extended directional closures, conducted continuously and consecutively as shown in the plans, shall be allowed on State Route (SR) 70 and SR-20 within the project limits for no more than the number of days outlined in the table below during the life of this contract to perform all the work that is in Stage 1 to Stage 13, as shown on the plans. Construction operations shall be performed on a 24/7 basis. The traffic shall be detoured in accordance with the detour plans, traffic handling plans, and these special provisions. No more than one extended closure shall be allowed at any given time."

03-Yub-20, 70-0.8/R2.0, 14.4/15.0
03-0A5804
Project ID 0300020139
NH-X115(010)E

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the table after the third paragraph is revised as follows:

"

Stages	Number of days for the Closure	Begin of closures	End of closures
Stage 1	34	6:00 am	6:00 am on the thirty fifth day
Stage 2	17	6:00 am	6:00 am on the eighteenth day
Stage 3	24	6:00 am	6:00 am on the twenty fifth day
Stage 4	22	6:00 am	6:00 am on the twenty third day
Stage 5	21	6:00 am	6:00 am on the twenty second day
Stage 6	27	6:00 am	6:00 am on the twenty eighth day
Stage 7	22	6:00 am	6:00 am on the twenty third day
Stage 8	19	6:00 am	6:00 am on the twentieth day
Stage 9	20	6:00 am	6:00 am on the twenty first day
Stage 10	17	6:00 am	6:00 am on the eighteenth day
Stage 11	15	6:00 am	6:00 am on the sixteenth day
Stage 12	15	6:00 am	6:00 am on the sixteenth day
Stage 13	16	6:00 am	6:00 am on the seventeenth day

"

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the seventh paragraph is revised as follows:

"Attention is directed to "Archaeological Monitoring Area" and to "Earthwork" of these special provisions and the Standard Specification, Section 14-2, "CULTURAL RESOURCES."

In the Special Provisions, Section 10-1.14, "MAINTAINING TRAFFIC," Chart No. 8 is revised as attached.

In the Special Provisions, Section 10-1.28, "EARTHWORK," the following paragraphs are added after the third paragraph:

"During the excavation of a numbered drainage system, be prepared to provide three soil samples upon the request of the Department's assigned AMA Monitor, of approximately 1 cubic-foot each. The exact location and depth of the sample to be taken within the excavation envelope of a numbered drainage system will be determined in the field by the AMA Monitor. The sample, when requested, shall be placed and spread about, at a safe location near to the excavation operation, such that, inspection of the sample can occur without delay to your excavation operation of the drainage system. The sample when spread shall be done so by the use of hand tools, such that, the depth of the sample is approximately 3 inches in depth. When the AMA Monitor completes the inspection of the soil sample, dispose of the soil sample in accordance with the provisions that governed the excavation work. If archaeological resources are discovered, the AMA Monitor will notify you to comply with Section 14-2.02, "Archaeological Resources," of the Standard Specifications.

Full compensation for providing three soil samples per numbered drainage system shall be considered as included in the contract prices paid for the various item of work involved and no additional compensation will be allowed therefor."

Addendum No. 4
Page 3
December 6, 2011

03-Yub-20, 70-0.8/R2.0, 14.4/15.0
03-0A5804
Project ID 0300020139
NH-X115(010)E

To Bid book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This addendum and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/03/03-0A5804

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



REBECCA D. HARNAGEL
Chief, Office of Plans, Specifications & Estimates
Office Engineer
Division of Engineering Services

Attachments

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION, AND LIQUIDATED DAMAGES

The 1st working day is the 120th day after contract approval.

Do not start work at the job site until the Engineer approves your submittal for:

1. Storm Water Pollution Prevention Plan (SWPPP)
2. Notification of Dispute Resolution Advisor (DRA) or Dispute Review Board (DRB) nominee and disclosure statement as specified in Section 5-1.15, "Dispute Resolution," of the Standard Specifications

You may enter the job site only to measure controlling field dimensions and locating utilities. Do not start other work activities until all the submittals from the above list are approved and the following information is submitted:

1. Notice of Materials To Be Used.
2. Contingency plan for reopening closures to public traffic.
3. Written statement from the vendor that the order for the sign panels has been received and accepted by the vendor. The statement must show the dates that the materials will be shipped.
4. Written statement from the vendor that the order for electrical material has been received and accepted by the vendor. The statement must show the dates that the materials will be shipped.
5. Written statement from the vendor that the order for structural steel has been received and accepted by the vendor. The statement must show the dates that the materials will be shipped.

You may start work at the job site before the 120th day after contract approval if:

1. You obtain required approval for each submittal before the 120th day
2. The Engineer authorizes it in writing

The Department grants a time extension if a delay is beyond your control and prevents you from starting work at the job site on the 1st working day.

Complete the work, except plant establishment work, within 640 working days.

Complete the work, including plant establishment work, within 760 working days.

Chart 8

County: Yub	Route: 20 & 70	PM: Var																								
Closure Limits: Route 20 EB/WB Route 70 NB/SB Route 20 & 70 EB/WB Route 20 & 70 NB/SB 9 th & E Street I/S																										
FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	
Mondays through Thursdays	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	
Fridays	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	
Saturdays	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	
Sundays	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	
Legend: <input type="checkbox"/> C Lanes may be closed completely.																										
REMARKS: 1- This chart applies to the work in Stage 1 to Stage 13. 2- See Stage Construction Plan and Detour Plan shown on the plans. 3- Detour must be in place during the work for Stage 1 to Stage 13. 4- Designated legal holidays for Stage 1 to Stage 13 are: January 1st, the third Monday in February, November 11th, Thanksgiving Day, and December 25th. When a designated legal holiday falls on a Sunday, the following Monday shall be a designated legal holiday. When November 11th falls on a Saturday, the preceding Friday shall be a designated legal holiday.																										