

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



Serious Drought.
Help save water!

June 26, 2015

03-1A8434

Project ID 0300000224

ACSTP-P089(112)

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN EL DORADO COUNTY NEAR SOUTH LAKE TAHOE FROM CASCADE ROAD TO UPPER EMERALD BAY ROAD.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Tuesday, June 30, 2015.

This addendum is being issued to revise the project plans, the *Notice to Bidders and Special Provisions*, and the *Bid* book.

Project plan sheets 151, 152 and 153 are replaced and attached for substitution for the like-numbered sheets.

In the *Special Provisions*, Section 12-4.05G is replaced as attached.

In the *Bid* book, in the "Bid Item List," Items 54, 55, 56, 57, 59, 60, 61 and 62 are replaced as attached.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html

Inform subcontractors and suppliers as necessary.

Addendum No. 3
Page 2
June 26, 2015

03-1A8434
Project ID 0300000224
ACSTP-P089(112)

This addendum, EBS addendum file and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/03/03-1A8434

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



For

AMARJEET BENIPAL
District Director

Attachments

Replace "Reserved" in section 12-4.05G with:

Chart no. 3 Complete Conventional Highway Closure Hours																									
County: El Dorado							Route/Direction: SR 89 NB/SB							Sta. "A3" 224+70 to Sta. "A3" 304+00											
Closure limits: Sta. "A3" 224+70 to Sta. "A3" 304+00																									
Hour	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon-Thu	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C						C	C	C	C
Fri	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C									
Sat																									
Sun																						C	C	C	C

Legend:

C Conventional highway may be closed completely

No complete conventional highway closure is allowed

REMARKS:

- This chart is to be used for Cold Planning, HMA Paving and Drainage Work only.
- The complete closure is allowed as shown in this chart for maximum of two weeks only during the off peak season (Labor Day to Memorial Day) with 5 consecutive days in each week.
- A detour shall be in effect to reroute traffic, see detour plan /motorist Information plan sheets for details.

**BID ITEM LIST
03-1A8434**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41	150821	REMOVE HEADWALL	EA	2		
42	152320	RESET ROADSIDE SIGN	EA	42		
43	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	63,300		
44	153121	REMOVE CONCRETE (CY)	CY	0.1		
45	155213	CLEANING, INSPECTING, AND PREPARING CULVERT (LF)	LF	450		
46	155232	SAND BACKFILL	CY	5		
47	155314	18" CURED-IN-PLACE PIPELINER	LF	370		
48	155316	24" CURED-IN-PLACE PIPELINER	LF	80		
49	160102	CLEARING AND GRUBBING (LS)	LS	LUMP SUM	LUMP SUM	
50	190101	ROADWAY EXCAVATION	CY	2,040		
51	194001	DITCH EXCAVATION	CY	19		
52	210010	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	3		
53	027919	IMPORTED TOPSOIL (MODIFIED)	CY	420		
54	027920	BONDED FIBER MATRIX (TYPE 1)	SQFT	259,000		
55	027921	BONDED FIBER MATRIX (TYPE 2)	SQFT	3,570		
56	210270	ROLLED EROSION CONTROL PRODUCT (NETTING)	SQFT	33,000		
57	210290	ROLLED EROSION CONTROL PRODUCT (TRM)	SQFT	39,400		
58	027922	ROLLED EROSION CONTROL PRODUCT (TURF REINFORCEMENT MAT) TYPE D	SQFT	16,400		
59	210420	STRAW	SQFT	33,100		
60	027923	COMPOST (TYPE 1)	SQFT	76,000		

**BID ITEM LIST
03-1A8434**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	027924	COMPOST (TYPE 2)	SQFT	39,400		
62	210630	INCORPORATE MATERIALS	SQFT	51,000		
63	027925	CORING	EA	4,760		
64	260203	CLASS 2 AGGREGATE BASE (CY)	CY	700		
65	374207	CRACK TREATMENT	LNMI	8		
66	390095	REPLACE ASPHALT CONCRETE SURFACING	CY	740		
67	390132	HOT MIX ASPHALT (TYPE A)	TON	9,000		
68	394060	DATA CORE	LS	LUMP SUM	LUMP SUM	
69	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	30		
70	397005	TACK COAT	TON	19		
71 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	CY	17		
72	560248	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	SQFT	120		
73	566011	ROADSIDE SIGN - ONE POST	EA	11		
74	591200	ROCK STAIN	SQFT	8,870		
75	027926	CONCRETE STAIN	SQFT	10,400		
76	620100	18" ALTERNATIVE PIPE CULVERT	LF	740		
77	620140	24" ALTERNATIVE PIPE CULVERT	LF	84		
78 (F)	620800	CONCRETE BACKFILL (PIPE TRENCH)	CY	8		
79	667030	49" X 33" CORRUGATED STEEL PIPE ARCH (.138" THICK)	LF	55		
80	027927	CLASS 4 PERMEABLE MATERIAL (CY)	CY	210		