Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
08	SBd	10,210	Var	5	27

REGISTERED CIVIL ENGINEER 3-03-14 DATE

3-03-14
PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER OSCAR ALEJANDRE No. C70863 Exp. 6-30-15 CIVIL STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

2 PAVEMENT DELINEATION QUANTITIES

LOCATION						REMOVE THERMOPLASTIC PAVEMENT MARKING	REMOVE PAVEMENT MARKERS	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	REMOVE THERMOPLASTIC TRAFFIC STRIPE	PAVEMENT MARKERS				THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)										THERMOPLASTIC PAVEMENT MARKING
										NON-REFLECTIVE	RETROREFLECTIVE			4" YELLOW				4" WHITE			8" WHITE			
										TYPE	TYPE													
Rte	PM	BRIDGE NAME	BRIDGE No.	BRIDGE TYPE	DIRECTION					A	C	G	H	DETAIL 21	DETAIL 25	DETAIL 25A	DETAIL M-10	DETAIL 12	DETAIL 13M	DETAIL 27B	DETAIL 37	DETAIL 38A	DETAIL M-10	
						SQFT	EA	LF	LF	EA	EA	EA	EA	LF				LF						SQFT
10	0.32	SAN ANTONIO WASH	54-0451	BRIDGE	EB		57	384	730	36		9	12		128		128		384	256				
					WB		57	384	730	36		9	12		128		128		384	256				
10	0.68	MONTE VISTA AVENUE UC	54-0450	UC	EB		24	255	487	12		3	9		85		85		254	169				
					WB		24	255	487	12		3	9		85		85		254	169				
10	1.75	BENSON AVENUE UC	54-0448	UC	EB		52	91	298	28	8	13	3		91				273	91	91		91	
					WB		44	91	264	28		13	3		91				273	81			91	
10	4.88	GROVE AVENUE UC	54-0441	UC	EB		57	309	593	36		9	12		103		103		310	207				
					WB		57	309	593	36		9	12		103		103		310	207				
10	19.90	RIALTO CHANNEL	54-1116	BRIDGE	EB		27	50	137	20		5	2		50				150	50				
					WB		27	50	137	20		5	2		50				150	50				
10	20.97	PEPPER AVENUE OC	54-0531	OC	EB	84		750	1075					375						440		130		84
					WB	118			1185											450		180		118
10	R22.38	COLTON OH	54-0464L	OH	WB		150	382	1450	112		28	10		382				1145	622		80		
10	R23.25	MOUNT VERNON AVENUE OC	54-0459	OC	NB	138	10	760	476			10		380				340						138
					SB	84	10		476			10						340						84
10	R24.19	E10-N215 CONNECTOR OC.	54-0823G	CONNECTOR	NB		216	2560	5780			108	108			2560		2560		2560				
10	R24.30	W10-S215 CONNECTOR	54-0822F	CONNECTOR	SB		228	2560	6012			114	114			2670		2670		2670				
10	25.54	SAN TIMOTEO CREEK	54-0599	BRIDGE	WB		80	207	569	60		15	5		207				621	207				
10	29.82	TENNESSEE ST. OC	54-0592	OC	NB	70	12	1000	644			12		500				500				100		70
					SB	80	12		644			12						500				100		80
SUBTOTAL						574	1144	10397	22767	436	8	387	313	1255	1503	5230	632	6910	4508	8485	91	590	182	574
TOTAL						574	-	10397	22767	-	-			29386										574

2 REPLACED PER ADDENDUM No. 2 DATED APRIL 28, 2014

PAVEMENT DELINEATION QUANTITIES

PDQ-2

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans® TRAFFIC DESIGN

FUNCTIONAL SUPERVISOR: BILL WASSER
CALCULATED-DESIGNED BY: OSCAR ALEJANDRE
CHECKED BY: DARYUSH NAMI
REVISED BY
DATE REVISED

LAST REVISION 03-03-14 DATE PLOTTED => 24-APR-2014 TIME PLOTTED => 10:18