

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

TTY 711

*Flex your power!
Be energy efficient!*

January 13, 2011

08-Riv-60,91,215-11.5/12.2,20.3/21.6,43.1/43.9

08-334864

Project ID 0800000603

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN RIVERSIDE COUNTY IN RIVERSIDE ON ROUTE 215 FROM DOWN STREET OVERHEAD TO COLOMBIA AVENUE OVERCROSSING ON ROUTE 60 FROM 0.2 MILE WEST OF MAIN STREET OVERCROSSING TO 215/60/91 SEPARATION ON ROUTE 91 FROM 0.2 MILE SOUTH OF UNIVERSITY AVENUE UNDERCROSSING TO 215/60/91 SEPARATION.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, January 27, 2011.

This addendum is being issued to revise the Project Plans, and the Notice to Bidders and Special Provisions.

Project Plan Sheets 16, 17, 31, 32, 33, 34, 35, and 67 are revised. Copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Notice to Bidders and Special Provisions, in the "NOTICE TO BIDDERS," the twelfth paragraph is revised as follows:

"Complete the work, including plant establishment work, within 1000 working days."

In the Special Provisions, Section 4, "BEGINNING OF WORK, TIME OF COMPLETION, AND LIQUIDATED DAMAGES," the sixth and seventh paragraphs are revised as follows:

"Complete the work, except plant establishment work, within 250 working days.
Complete the work, including plant establishment work, within 1000 working days."

In the Special Provisions, Section 10-1.21, "TYPE 6B RETAINING WALL," subsection "TEST PANEL," is revised as follows:

"A test panel at least 9' X 4' in size shall be successfully completed at a location approved by the Engineer before beginning work on architectural textures. The test panel shall be constructed and finished with the materials, tools, equipment, and methods to be used in constructing the architectural texture, including placement of expansion joints, weakened plane joints and joints between form liner units. If ordered by the Engineer, additional test panels shall be constructed and finished until the specified finished texture and color are obtained as determined by the Engineer.

Addendum No. 1
Page 2
January 13, 2011

08-Riv-60,91,215-11.5/12.2,20.3/21.6,43.1/43.9
08-334864
Project ID 0800000603

The test panel approved by the Engineer shall be used as the standard of comparison in determining acceptability of architectural texture for concrete surfaces. Approved test panels shall not be destroyed without the permission of the Engineer."

In the Special Provisions, Section 10-2.04, "HIGHWAY PLANTING," subsection "GRAVEL (MISCELLANEOUS AREAS)," is revised as attached.

To Bid book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This addendum and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/08/08-334864

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY H.MEHRSHAHI FOR:

REBECCA D. HARNAGEL
Chief, Office of Plans, Specifications & Estimates
Office Engineer
Division of Engineering Services

Attachments

GRAVEL (MISCELLANEOUS AREAS)

GENERAL

Summary

This work consists of installing gravel in miscellaneous areas.

Submittals

Submit the following items for approval:

- 1. Samples: Submit a 5 pound sample of each color gravel for approval before delivery of materials to the site.

MATERIALS

Edging

Edging must be minor concrete (curb) as described in "miscellaneous concrete construction," of these special provisions.

Soil Sterilant

Soil sterilant must be dichlobenil and must comply with Section 20-4.026, "Pesticides," of the Standard Specification, except recommendations from a Pest Control Adviser will not be required.

Gravel

Gravel must consist of crushed rock and must comply with the following:

Size Requirements for 3/4" crushed rock

Size	Percent (Min)
3/4-inch	80

Gravel must consist of crushed rock and comply with the following:

Size Requirements for 1 1/2" crushed rock

Size	Percent (Min)
2 1/2-inch	80

The color of gravel must be Burgundy or Gray/Green. Lava type rock shall not be used.

CONSTRUCTION

Clearing

Prior to beginning gravel work, areas to receive the gravel shall be cleared in conformance with the provisions in "Roadside Clearing" of these special provisions.

Earthwork

Earthwork must comply with Section 19, "Earthwork," of the Standard Specifications and these special provisions.

Prior to placement of gravel, soil shall be scarified to a minimum depth of 0.125 foot.

Immediately prior to placement of gravel, scarified material shall be watered. Gravel shall be placed, watered, and rolled with a double drum smooth steel roller weighing approximately 2 tons to form a uniform, compacted surface. No soil shall be exposed to view on the finished surface. Watering shall conform to the provisions in Section 17, "Watering," of Standard Specifications.

Gravel shall not be compacted within a 6-foot diameter area centered at each plant location.

Treatment of Soil

After compaction, the areas shall be sterilized with dichlobenil. The soil sterilant shall be applied at the maximum label rate and shall not be applied more than 12 inches beyond the gravel limits. Soil sterilant shall not be applied within a 3-foot diameter area centered at each plant location. Soil sterilant shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specifications, except recommendations from a licensed Pest Control Adviser will not be required.

Edging

Install edging to delineate the limits of the gravel areas. Edging will not be required between the adjacent face of walls, pavement edges, curbs, dikes or rock blanket areas.

When work is complete, the surface must be smooth compact and uniform.

MEASUREMENT AND PAYMENT

Gravel (miscellaneous areas) will be measured by the square yard as determined from actual measurements made parallel to the ground slope.

The contract unit price paid per square yard for the various sizes and colors of gravel (miscellaneous areas) includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in gravel (miscellaneous areas), complete in place, including site preparation, earthwork, and soil treatment, aggregate base, landscape fabric, and edging, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.