

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

TTY 711

*Flex your power!
Be energy efficient!*

February 8, 2011

08-Riv-60, 91, 215-11.5/12.2, 20.3/21.6, 43.1/43.9

08-334864

Project ID 0800000603

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN RIVERSIDE COUNTY IN RIVERSIDE ON ROUTE 215 FROM DOWN STREET OVERHEAD TO COLOMBIA AVENUE OVERCROSSING ON ROUTE 60 FROM 0.2 MILE WEST OF MAIN STREET OVERCROSSING TO 215/60/91 SEPARATION ON ROUTE 91 FROM 0.2 MILE SOUTH OF UNIVERSITY AVENUE UNDERCROSSING TO 215/60/91 SEPARATION.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on February 17, 2011. The original bid opening date was previously postponed indefinitely under Addendum No. 2 dated January 26, 2011.

This addendum is being issued to set a new bid opening date as shown herein and revise the Project Plans, the Notice to Bidders and Special Provisions, and the Bid book.

Project Plan Sheet 36 is revised. A copy of the revised sheet is attached for substitution for the like-numbered sheet.

In the Special Provisions, Section 10-1.20, "ROCK BLANKET," subsection "MEASUREMENT AND PAYMENT," the second paragraph is revised as follows:

"The contract price paid per square yard for rock blanket shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in placing rock blanket, complete in place, including site preparation, earthwork, and furnishing and applying soil sterilant, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer."

In the Special Provisions, Section 10-1.21, "TYPE 6B RETAINING WALL," the third paragraph is revised as follows:

"The contract price paid per linear foot for retaining wall (Type 6B) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the reinforced concrete retaining wall, including concrete footing, reinforcement, and backfill, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer."

In the Special Provisions, Section 10-2.04, "HIGHWAY PLANTING," subsection "GRAVEL (MISCELLANEOUS AREAS)," is revised as attached.

Addendum No. 3
Page 2
February 8, 2011

08-Riv-60, 91, 215-11.5/12.2, 20.3/21.6, 43.1/43.9
08-334864
Project ID 0800000603

In the Bid book, in the "Bid Item List," Items 14, 16 and 17 are revised as attached.

To Bid book holders:

Replace page 3 of the "Bid Item List" in the Bid book with the attached revised page 3 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.


Inform subcontractors and suppliers as necessary.

This addendum and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/08/08-334864

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



REBECCA D. HARNAGEL
Chief, Office of Plans, Specifications & Estimates
Office Engineer
Division of Engineering Services

Attachments

GRAVEL (MISCELLANEOUS AREAS)

GENERAL

Summary

This work consists of installing gravel in miscellaneous areas.

Submittals

Submit the following items for approval:

1. Samples: Submit a 5 pound sample of each color gravel for approval before delivery of materials to the site.

MATERIALS

Edging

Edging must be minor concrete (curb) as described in "miscellaneous concrete construction," of these special provisions.

Soil Sterilant

Soil sterilant must be dichlobenil and must comply with Section 20-4.026, "Pesticides," of the Standard Specification, except recommendations from a Pest Control Adviser will not be required.

Gravel

Gravel must consist of crushed rock and must comply with the following:

Size Requirements for ¾" crushed rock

Size	Percent (Min)
¾-inch	80

Gravel must consist of crushed rock and comply with the following:

Size Requirements for 1 ½" crushed rock

Size	Percent (Min)
1 ½-inch	80

The color of gravel must be Burgundy or Gray/Green. Lava type rock shall not be used.

CONSTRUCTION

Clearing

Prior to beginning gravel work, areas to receive the gravel shall be cleared in conformance with the provisions in "Roadside Clearing" of these special provisions.

Earthwork

Earthwork must comply with Section 19, "Earthwork," of the Standard Specifications and these special provisions.

After clearing, excavate areas to receive gravel. Where gravel is to be placed adjacent to an existing curb, dike, pavement, sidewalk or soundwall, excavate so that the finished gravel elevation adjacent to those items will maintain planned flow lines, slope gradient and contours of the project site. After excavation, grade areas to receive gravel to a smooth, uniform surface and compact to not less than 80 percent relative compaction.

08-334864

REVISED PER ADDENDUM NO 3 DATED FEBRUARY 8, 2011

Prior to placement of gravel, soil shall be scarified to a minimum depth of 0.125 foot.

Immediately prior to placement of gravel, scarified material shall be watered. Gravel shall be placed, watered, and rolled with a double drum smooth steel roller weighing approximately 2 tons to form a uniform, compacted surface. No soil shall be exposed to view on the finished surface. Watering shall conform to the provisions in Section 17, "Watering," of Standard Specifications.

Gravel shall not be compacted within a 6-foot diameter area centered at each plant location.

Treatment of Soil

After compaction, the areas shall be sterilized with dichlobenil. The soil sterilant shall be applied at the maximum label rate and shall not be applied more than 12 inches beyond the gravel limits. Soil sterilant shall not be applied within a 3-foot diameter area centered at each plant location. Soil sterilant shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specifications, except recommendations from a licensed Pest Control Adviser will not be required.

Edging

Install edging to delineate the limits of the gravel areas. Edging will not be required between the adjacent face of walls, pavement edges, curbs, dikes or rock blanket areas.

When work is complete, the surface must be smooth, compact, and uniform.

MEASUREMENT AND PAYMENT

Gravel (miscellaneous areas) will be measured by the square yard as determined from actual measurements made parallel to the ground slope.

The contract unit price paid per square yard for the various sizes and colors of gravel (miscellaneous areas) includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in gravel (miscellaneous areas), complete in place, including site preparation, earthwork, and soil treatment, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

08-334864

REVISED PER ADDENDUM NO 3 DATED FEBRUARY 8, 2011

BID ITEM LIST
08-334864

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070013	SMALL BUSINESS UTILIZATION REPORT	EA	7	250.00	1,750.00
2	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
3	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM	LUMP SUM	
4	074028	TEMPORARY FIBER ROLL	LF	22,900		
5	074033	TEMPORARY CONSTRUCTION ENTRANCE	EA	6		
6	074034	TEMPORARY COVER	SQYD	300		
7	074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	12		
8	074041	STREET SWEEPING	LS	LUMP SUM	LUMP SUM	
9	074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	LUMP SUM	LUMP SUM	
10	074057	STORM WATER ANNUAL REPORT	EA	1		
11	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
12	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
13	128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	4		
14	190101	ROADWAY EXCAVATION	CY	1,200		
15	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
16	192001	STRUCTURE EXCAVATION	CY	930		
17	198001	IMPORTED BORROW	CY	24,700		
18	200002	ROADSIDE CLEARING	LS	LUMP SUM	LUMP SUM	
19	018909	GRAVEL (MISCELLANEOUS AREAS) (3/4" BURGUNDY)	SQYD	27,100		
20	018910	GRAVEL (MISCELLANEOUS AREAS) (2 1/2" BURGUNDY)	SQYD	19,100		